



Oregon

Ted Kulongoski, Governor

Department of Corrections

Purchasing Section

3601 State Street, Suite 280

Salem, OR 97301-5780

(503) 378-3798 x 22496, 371-3161 FAX

www.scott.petterson@doc.state.or.us

04/09/2007

Addendum # 1

To

Drive In Storage Racking for Central Distribution Warehouse, Bid # 228870-07



Below you will find Revisions, clarifications, deletions and/or additions to the bid specifications. This addendum modifies the related Invitation to Bid only to the extent specifically indicated herein. All other areas not specifically mentioned or affected by this addendum shall remain in full force and effect.

This addendum shall be added to and become part of the original Invitation to Bid.

A. Answers and clarifications to the bid specifications

- Site plan will be provided to the winning bidder.
- 110 volt A.C. power supply will be provided.
- Lift equipment provided by winning bidder.
- Normal working hours are from 7:00 A.M to 5:00 P.M. Monday through Friday. With three day notice will provide access until 10:00 P.M.
- 2500 Average Load 100% utilization.
- Isle way in new freezer for access to install site is 143". Door from ambient room to new freezer door is 96" wide and the door from Old freezer to the new freezer is 100" wide.
- Evaporator measurements and clearance in attachment.
- Floor is 6" thick 3000 PSI concrete with #4 Rebar on 18" centers each way. Under this concrete is 5" Polyurethane insulation then the Glycol lines, installed over existing concrete slab.
- Contractor removes all construction debris
- Egress and lighting is DOC responsibility.
- Sprinkler system is DOC responsibility.
- Sprinkler system is a Dry System double actuating from Reliable.
- Racking drawing on page 70 is revised by moving the new installed racking 6' off the north wall. All Racking on drawing will be moved 6' north.
- All racking will be 1' from existing evaporators. Drawing of the location of the evaporator provided.

B. The following Brand/Product substitutions have been approved:

- a) Mecalux Drive in Pallet Rack System
- b) Lodi Metal Tech Inc. Drive-In Storage System

C. Evaporator location drawing is attached and hereby incorporated by reference.

D. Bid closing date remains unchanged.

This addendum represents a material change to the ITB and is required to be signed and returned by the Bid Closing Date and Time. Failure to do so may result in bid rejection.

Company Name: _____

Authorized Signature: _____

Date: _____