



# Oregon

Theodore R. Kulongoski, Governor

**Department of Transportation**  
Technical Services  
Roadway Engineering Section  
355 Capitol Street NE, Room 222  
Salem, OR 97301-3871  
Telephone 503-986-3714  
FAX 503-986-3749

**DATE:** January 25, 2007

## Addenda No. 3

**TO:** PLAN HOLDERS

**PREPARED BY:** Original Signed by Dennis Hart

**APPROVED BY:** Original Signed by Laurence Beskow, P.E.

**SUBJECT:** OAK ST- MCANDREWS TO TAFT  
OAK STREET  
JACKSON COUNTY  
(Bids to be opened and read February 1, 2007)

### The following changes are made to the Project Bid Booklet:

1. The following changes are made to the Project Bid Items:

a. Name Changes:

<u>Number</u>	<u>Item</u>
0160	Concrete Manholes, 48" Storm Sewer

b. Quantity and Unit changes:

<u>Number</u>	<u>Item</u>	<u>Unit</u>		<u>Quantity</u>	
		<u>Original</u>	<u>New</u>	<u>Original</u>	<u>New</u>
0230	¾ inch – 0 Aggregate base	CUYD	TON	950	1900
0240	4 inch – 0 Aggregate base	CUYD	TON	160	350

**The following changes are made to the Project Special Provisions:**

1. Subsection 00330.41 (a-13) Petroleum Contaminated Soil Excavation and Removal –

This subsection is replaced with the following subsection:

**00330.41 (a-13) Petroleum Contaminated Soil Excavation and Removal** – This item shall include all labor, equipment, certified testing, and materials necessary to excavate, stockpile and cover, and dispose of petroleum contaminated soil at a certified landfill as shown on the plans or as directed in the field by the engineer. Historical records show that a Unocal bulk petroleum plant operated until 1991 east of the improvement area, near the north end of Oak St. In the event soil excavated near this area, as part of the improvement project, smells or looks as if it contains petroleum, the contractor shall segregate the excavated material, stockpile on site, and cover. Contaminated soil shall be disposed of at a certified landfill. All work on this item shall comply with Section 00290 of the Standard Specifications.

2. Section 00470– Manholes, Catch Basins and Inlets - This Section is replaced with the following Section:

Comply with Section 00470 of the Standard Specifications

Make a copy of and use the new attached Bid Sheets. A Bid **not** including these new Bid Sheets **will be rejected as non-responsive**.

These changes will be included in the Contract for this Project. It is understood that your Bid will be submitted accordingly.

Make copies of the new Bid Sheets to replace the Special Provisions Bid Schedule Sheets.

Attachments: New Bid Sheets

BID SCHEDULE

REVISED:

CONTRACT ID: 13321

PROJECT: OAK ST - MCANDREWS TO TAFT

PROJECT KEY: 13357

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
---------	------------------	--------------------	-------------------------	-------------------------

SECTION 0001 TEMPORARY FEATURES AND APPURTENANCES

0010	MOBILIZATION	LS	ALL	
0020	TEMPORARY WORK ZONE TRAFFIC CONTROL, COMPLETE	LS	ALL	
0030	FLAGGERS	HOUR	100.00	
0040	EROSION CONTROL	LS	ALL	
0050	CONSTRUCTION ENTRANCES	EACH	1.00	
0060	INLET PROTECTION	EACH	8.00	

SECTION 0002 ROADWORK

0070	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	ALL	
0080	REMOVAL OF PIPES	FOOT	210.00	
0090	REMOVAL OF RAILROAD TRACK AND TIES	LS	ALL	
0100	CLEARING AND GRUBBING	LS	ALL	
0110	GENERAL EXCAVATION	CUYD	1,800.00	

BID SCHEDULE

CONTRACT ID: 13321

PROJECT: OAK ST - MCANDREWS TO TAFT

PROJECT KEY: 13357

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0120	PETROLEUM CONTAMINATED SOIL EXCAVATION AND REMOVAL	100.00 CUYD		
0130	SUBGRADE GEOTEXTILE	4,100.00 SQYD		

SECTION 0003 DRAINAGE AND SEWERS

0140	12 INCH STORM SEWER PIPE, 5 FT DEPTH	418.00 FOOT		
0150	12 INCH STORM SEWER PIPE, 10 FT DEPTH	130.00 FOOT		
0160	CONCRETE MANHOLES, 48" STORM SEWER	3.00 EACH		
0170	CONCRETE MANHOLES, WITH INLET	2.00 EACH		
0180	CONCRETE INLETS, TYPE 4A	5.00 EACH		
0190	CATCH BASINS, STEEL, MODIFIED	1.00 EACH		
0200	ADJUSTING BOXES	6.00 EACH		
0210	CONNECTION TO EXISTING STRUCTURES	3.00 EACH		
0220	MINOR ADJUSTMENT OF MANHOLES	1.00 EACH		

SECTION 0004 BASES

CONTRACT ID: 13321

PROJECT: OAK ST - MCANDREWS TO TAFT

PROJECT KEY: 13357

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0230	3/4 INCH - 0 AGGREGATE BASE	TON	1,900.00	
0240	4 INCH - 0 AGGREGATE BASE	TON	350.00	

SECTION 0005 WEARING SURFACES

0250	LEVEL 2, 1/2 INCH DENSE HMAC MIXTURE	TON	1,040.00	
0260	CURB AND GUTTER CONCRETE CURBS	FOOT	1,750.00	
0270	CONCRETE DRIVEWAYS, REINFORCED	SQFT	570.00	
0280	VALLEY GUTTER	SQFT	424.00	
0290	CONCRETE WALKS	SQFT	7,830.00	
0300	CONCRETE SIDEWALK RAMPS	EACH	5.00	

SECTION 0006 PERMANENT TRAFFIC SAFETY AND GUIDANCE DEVICES

0310	GUARDRAIL, TYPE 2A	FOOT	54.00	
0320	GUARDRAIL END PIECES, TYPE B	EACH	2.00	
0330	REMOVE AND REINSTALL EXISTING SIGNS	LS	ALL	

SECTION 0007 PERMANENT TRAFFIC CONTROL AND ILLUMINATION SYSTEMS

BID SCHEDULE

CONTRACT ID: 13321

PROJECT: OAK ST - MCANDREWS TO TAFT

PROJECT KEY: 13357

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0340	ILLUMINATION INSTALLATION, COMPLETE	LS ALL		

SECTION 0008 RIGHT-OF-WAY DEVELOPMENT AND CONTROL

0350	PERMANENT SEEDING	LS ALL		
0360	TOPSOIL	CUYD 83.00		
0370	REMOVING AND REBUILDING FENCE	FOOT 168.00		
0380	SINGLE MAILBOX SUPPORTS	EACH 2.00		

SECTION 0009 WATER SUPPLY SYSTEMS

0390	MOVING EXISTING HYDRANTS	EACH 2.00		
0400	3/4 INCH WATER SERVICE CONNECTIONS	EACH 5.00		

SECTION 0010 ADDED BID ITEMS

0410	POLLUTION CONTROL PLAN	LS ALL		
	TOTAL BID			