



Oregon

Theodore R. Kulongoski, Governor

Department of Transportation
Technical Services
Roadway Engineering Section
355 Capitol Street NE, Room 222
Salem, OR 97301-3871
Telephone 503-986-3714
FAX 503-986-3749

DATE: June 18, 2009

Addenda No. 1

TO: PLAN HOLDERS

PREPARED BY:

Michael Gumbel

APPROVED BY:

Mats Halverson P.E.

SUBJECT: OR234: Rogue River Bridge (Rock Point) Rehab Section
Sams Valley Highway
Jackson County
Structure Project
(Bids to be opened and read June 25, 2009)

The following changes are made to the Project Bid Booklet:

1. The following change is made to the Project Bid Items:

a. Quantity and Unit changes:

<u>Number</u>	<u>Item</u>	<u>Unit</u>		<u>Quantity</u>	
		<u>Original</u>	<u>New</u>	<u>Original</u>	<u>New</u>
0410	Seismic Restraints	Each	LS	2	1

b. Added items:

<u>Number</u>	<u>Item</u>	<u>Unit</u>	<u>Quantity</u>
0610	Repair Slider Bearing	Lump Sum	1

Make a copy of and use the new attached Bid Sheets. A Bid **not** including these new Bid Sheets **will be rejected as non-responsive**.

The following changes are made to the Project Special Provisions:

1. Subsection 00582.80 Measurement and 00582.90 Payment - The following is added after subsection 00582.00(d):

Replace the following subsections:

00582.80 Measurement – The quantities of work performed under this Section will be measured according to the following:

(a) Repair Slider Bearing – Repair slider bearings will be measured on the lump sum basis. The estimated number of slider bearing repairs are (15) at bents 6, 7, and 10.

(b) Elastomeric Bearing Pads - Elastomeric bearing pads will not be measured.

00582.90 Payment – The accepted quantities of bridge bearings will be paid for according to the following:

(a) Repair Slider Bearing - Work performed under this item will be paid for at the Contract lump sum amount for the item "Repair Slider Bearing".

Payment will be payment in full for furnishing and placing all materials, and for furnishing all equipment, labor, and incidentals necessary to complete the work as specified.

(b) Elastomeric Bearing Pads - No separate payment will be made for elastomeric bearing pads. This work is included for payment in Section 00588.

2. Subsection 00588.80 General - The first sentence of the paragraph that begins with the words " Measurement will be " is replaced with the following:

No measurement of quantities will be made for seismic restraints work performed under this Section.

3. Subsection 00588.90 General - This subsection is replaced with the following subsection:

00588.90 General - The accepted quantities of seismic restraints will be paid for at the Contract lump sum amount for the item "Seismic Restraints". All work associated with the installation of elastomeric bearings pads is incidental to this bid item.

Payment will be full compensation for furnishing all materials, equipment, tools, labor, and incidentals necessary to complete the work specified.

4. Section 02690 PCC Aggregates - This Section is replaced with the following Section:

SECTION 02690 - PCC AGGREGATES

Comply with Section 02690 of the Standard Specifications modified as follows:

Add the following:

02690.20 (f-3) Coarse Aggregate For SFC or LMC – Provide coarse aggregates meeting the following grading requirements:

Sieve Size (inch)	Percent Passing by weight
3/4	100
3/8	35 - 65
No. 4	0 - 15
No. 200	0 - 1.5

Add the following:

02690.30 (f-1) Sand Equivalent For SFC or LMC – Fine aggregate shall be tested according to AASHTO T 176 and shall have a sand equivalent of not less than 75.

These changes will be included in the Contract for this Project. It is understood that your Bid will be submitted accordingly.

Make copies of the new Bid Sheets to replace the Special Provisions Bid Schedule Sheets.

mg:MH

Attachments: New Bid Sheets

BID SCHEDULE

CONTRACT ID: 14075

PROJECT: OR234: ROGUE RIVER BRIDGE (ROCK POINT) REHAB

PROJECT KEY: 12690

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
SECTION 0001 TEMPORARY FEATURES AND APPURTENANCES				
0010	0210-0100000A MOBILIZATION	LS ALL		
0020	0225-0100000A TEMPORARY PROTECTION AND DIRECTION OF TRAFFIC	LS ALL		
0030	0225-0102000J TEMPORARY SIGNS	SQFT 515.00		
0040	0225-0105000E TEMPORARY BARRICADES, TYPE III	EACH 15.00		
0050	0225-0145000E TEMPORARY PLASTIC DRUMS	EACH 12.00		
0060	0225-0164000E PORTABLE CHANGEABLE MESSAGE SIGNS	EACH 2.00		
0070	0225-0168000T FLAGGERS	HOUR 200.00		
0080	0253-0106000A TEMPORARY WORK PLATFORM	LS ALL		
0090	0280-0100000A EROSION CONTROL	LS ALL		
0100	0280-0106000E CHECK DAM	EACH 4.00		
0110	0280-0115000F SEDIMENT BARRIER	FOOT 250.00		
0120	0290-0100000A POLLUTION CONTROL PLAN	LS ALL		

BID SCHEDULE

CONTRACT ID: 14075

PROJECT: OR234: ROGUE RIVER BRIDGE (ROCK POINT) REHAB

PROJECT KEY: 12690

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0130	0290-0102000A WORK CONTAINMENT PLAN AND SYSTEM	LS ALL		

SECTION 0002 ROADWORK

0140	0305-0100000A CONSTRUCTION SURVEY WORK	LS ALL		
0150	0310-0106000A REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS ALL		
0160	0330-0105000K GENERAL EXCAVATION	CUYD 1,050.00		
0170	0331-0106000J 12 INCH SUBGRADE STABILIZATION	SQYD 203.00		
0180	0350-0105000J SUBGRADE GEOTEXTILE	SQYD 1,900.00		

SECTION 0003 BRIDGES

0190	0501-9Z90000A BRIDGE REMOVAL WORK	LS ALL		
0200	0503-0101000J BRIDGE DECK COLD PLANE PAVEMENT REMOVAL, 0-2 INCHES DEEP	SQYD 545.00		
0210	0503-0102000J BRIDGE DECK COLD PLANE PAVEMENT REMOVAL, 2-4 INCHES DEEP	SQYD 586.00		
0220	0503-0102000J BRIDGE DECK COLD PLANE PAVEMENT REMOVAL, 4-6 INCHES DEEP	SQYD 94.00		

BID SCHEDULE

CONTRACT ID: 14075

PROJECT: OR234: ROGUE RIVER BRIDGE (ROCK POINT) REHAB

PROJECT KEY: 12690

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0230	0530-0100000A REINFORCEMENT	LS ALL		
0240	0530-9Z90000A ALL THREAD RESIN BONDED ANCHOR SYSTEMS	LS ALL		
0250	0540-0203000A DECK CONCRETE, CLASS HPC4000	LS ALL		
0260	0540-0301000A GENERAL STRUCTURAL CONCRETE, CLASS 3300	LS ALL		
0270	0540-9Z90000A POWER WASHING OF EXISTING CONCRETE SURFACES	LS ALL		
0280	0540-9Z90000A PREPARE AND COAT CONCRETE STRUCTURES	LS ALL		
0290	0540-9Z90000J CLASS 2 FINISH WORK	SQYD 840.00		
0300	0550-9Z90000F INJECT AND SEAL CRACKS	FOOT 2,000.00		
0310	0559-0101000J CONSTRUCT SFC RESURFACING	SQYD 618.00		
0320	0559-0102000J CLASS 2 PREPARATION	SQYD 62.00		
0330	0559-0103000K FURNISH SILICA FUME CONCRETE	CUYD 68.00		
0340	0560-9Z90000A FRP STRENGTHENING	LS ALL		
0350	0560-9Z90000A STRUCTURAL STEEL	LS ALL		

BID SCHEDULE

CONTRACT ID: 14075

PROJECT: OR234: ROGUE RIVER BRIDGE (ROCK POINT) REHAB

PROJECT KEY: 12690

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0360	0581-0100000E BRIDGE DRAINS	4.00 EACH		
0370	0585-0100000A ASPHALTIC PLUG JOINT SEALS	ALL LS		
0380	0585-0106000A POURED JOINT SEALS	ALL LS		
0390	0587-0136000A ORNAMENTAL CONCRETE RAIL	ALL LS		
0400	0589-0100000A UTILITY ATTACHMENT ON STRUCTURES	ALL LS		
0410	0595-9Z90000A SEISMIC RESTRAINTS	ALL LS		
0420	0596-9Z90000A RETAINING WALL, CONVENTIONAL SEGMENTAL	ALL LS		
0430	0760-9Z90000J REPAIR DAMAGED CONCRETE	3,608.00 SQFT		

SECTION 0004 BASES

0440	0620-0120000J COLD PLANE PAVEMENT REMOVAL, 2 INCHES DEEP	39.00 SQYD		
0450	0641-0102000M AGGREGATE BASE	1,400.00 TON		

SECTION 0005 WEARING SURFACES

0460	0745-0302000M LEVEL 3, 1/2 INCH DENSE HMAC	760.00 TON		
------	--	---------------	--	--

BID SCHEDULE

CONTRACT ID: 14075

PROJECT: OR234: ROGUE RIVER BRIDGE (ROCK POINT) REHAB

PROJECT KEY: 12690

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0470	0745-0640000M PG 70-22 ASPHALT IN HMAC	44.00 TON		
0480	0749-0100000E EXTRA FOR ASPHALT APPROACHES	4.00 EACH		

SECTION 0006 PERMANENT TRAFFIC SAFETY AND GUIDANCE DEVICES

0490	0810-0104000F GUARDRAIL, TYPE 2A	937.50 FOOT		
0500	0810-0107000F GUARDRAIL, TYPE 3	37.50 FOOT		
0510	0810-0126000E GUARDRAIL TRANSITION	3.00 EACH		
0520	0810-0129000E GUARDRAIL TERMINALS, NON-FLARED	3.00 EACH		
0530	0810-0133000E EXTRA FOR 8 FOOT POSTS	10.00 EACH		
0540	0820-0100000F CONCRETE BARRIER	150.00 FOOT		
0550	0855-0102000E BI-DIRECTIONAL YELLOW TYPE 1 MARKERS	22.00 EACH		
0560	0860-0200000F LONGITUDINAL PAVEMENT MARKINGS - PAINT	2,816.00 FOOT		

SECTION 0007 PERMANENT TRAFFIC CONTROL AND ILLUMINATION SYSTEMS

0570	0910-0100000K WOOD SIGN POSTS	19.00 FBM		
------	----------------------------------	--------------	--	--

BID SCHEDULE

CONTRACT ID: 14075

PROJECT: OR234: ROGUE RIVER BRIDGE (ROCK POINT) REHAB

PROJECT KEY: 12690

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0580	0930-0105000A BRIDGE STRUCTURE MOUNTS	LS ALL		
0590	0940-0113000J TYPE "G" SIGNS IN PLACE	SQFT 11.00		

SECTION 0008 RIGHT-OF-WAY DEVELOPMENT AND CONTROL

0600	1030-0108000R PERMANENT SEEDING	ACRE 0.25		
------	------------------------------------	-----------	--	--

SECTION 0009 ADDED BID ITEMS

0610	0582-9Z90000A REPAIR SLIDER BEARING	LS ALL		
	TOTAL BID			