



# Oregon

Theodore R. Kulongoski, Governor

Department of Transportation  
Technical Services  
Roadway Engineering Section  
355 Capitol Street NE, Room 222  
Salem, OR 97301-3871  
Telephone 503-986-3714  
FAX 503-986-3749

DATE: April 23, 2009

TO: PLAN HOLDERS

Addendum No. 3

PREPARED BY:

APPROVED BY:

  
P.E.

SUBJECT: OR99E: Aurora – Salem Paving Section  
Pacific Highway East  
Marion County  
Paving, Signing and Signals Project  
(Bids to be opened and read May 14, 2009)

**The following changes are made to the Project Bid Booklet:**

1. The following changes are made to the Project Bid Items:

a. Quantity changes:

<u>Number</u>	<u>Item</u>	<u>Quantity</u>	
		<u>Original</u>	<u>New</u>
0230	COLD PLANE PAVEMENT REMOVAL, 3 INCHES DEEP	135,310.00	126,300.00
0240	COLD PLANE PAVEMENT REMOVAL, 6 INCHES DEEP	400.00	4,910.00

Make a copy of and use the new attached Bid Sheets. A Bid **not** including these new Bid Sheets **will be rejected as non-responsive**.

**The following changes are made to the Project Special Provisions:**

1. Subsection **00150.50(f) Utility Information** – The contact name and phone number for **360 Networks USA** are changed to: "Corrie Lucas (541) 554-5809".

2. Subsection **00150.50(f) Utility Information** – The contact name and phone number for **MCI-WorldCom** are changed to: "Allen Schaeffer (503) 849-1390".
3. Subsection **00290.38 Protection of Plants** – This subsection is added after subsection 00290.30(a-7):

**00290.38 Protection of Plants** – Add the following:

Within two weeks following issuance of Notice to Proceed, and prior to performing any ground disturbing activity, complete a Rare Plant Survey of all areas where potential vegetation disturbance may occur within the Project limits. The survey shall be conducted by a qualified plant biologist.

The purpose of the survey is to determine presence and location of the following rare plant species:

- Golden Indian Paintbrush (*Castilleja levisecta*)
- Willamette Daisy (*Erigeron decumbens* var. *decumbens*)
- Howellia (*Howellia aquatilis*)
- Bradshaw's Lomatium (*Lomatium bradshawii*)
- Kincaid's Lupine (*Lupinus sulphureus* var. *kincaidii*)
- Nelson's Checker-mallow (*Sidalcea nelsoniana*)
- Peacock Larkspur (*Delphinium pavonaceum*)

Submit documentation signed by the biologist, certifying that the survey was conducted and detailing the result. Do not begin ground-disturbing activities prior to receipt of the Engineer's approval. In the event that no rare plant species are found by the survey, the Engineer will immediately approve commencement of ground-disturbing work. If the survey determines that any of the above listed species occur within a potential area of vegetation disturbance, do not perform ground-disturbing work within that area until suitable protective or avoidance measures are implemented, as directed by the Engineer, or the Engineer has authorized commencement of work.

4. **Section 00350 - Geosynthetic Installation** - This Section is added after Section 00331:

**SECTION 00350 - GEOSYNTHETIC INSTALLATION**

Comply with Section 00350 of the Standard Specifications modified as follows:

**00350.10 Materials** - Add the following to the end of this subsection:

Provide manufacturer's certifications complying with 02320.10(c) for the following geosynthetics:

Geotextile	Certification	
	Level A	Level B
Subgrade .....		X

5. Subsection **00745.11(a) Asphalt Cement** – Replace this subsection with the following subsection:

**00745.11(a) Asphalt Cement** – Use PG 70-22 asphalt cement.

These changes will be included in the Contract for this Project. It is understood that your Bid will be submitted accordingly.

Make copies of the new Bid Sheets to replace the Special Provisions Bid Schedule Sheets.

JKP:jkp

Attachments: New Bid Sheets

BID SCHEDULE

CONTRACT ID: 14032

PROJECT: OR99E: AURORA - SALEM PAVING  
SECTION

PROJECT KEY: 13624

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
SECTION 0001 TEMPORARY FEATURES AND APPURTENANCES				
0010	0210-0100000A MOBILIZATION	LS ALL		
0020	0225-0100000A TEMPORARY PROTECTION AND DIRECTION OF TRAFFIC	LS ALL		
0030	0225-0102000J TEMPORARY SIGNS	SQFT 2,630.00		
0040	0225-0105000E TEMPORARY BARRICADES, TYPE III	EACH 27.00		
0050	0225-0145000E TEMPORARY PLASTIC DRUMS	EACH 165.00		
0060	0225-0153000F TEMPORARY STRIPING	FOOT 317,000.00		
0070	0225-0154000F STRIPE REMOVAL	FOOT 317,000.00		
0080	0225-0168000T FLAGGERS	HOUR 1,500.00		
0090	0225-0168100E FLAGGER STATION LIGHTING	EACH 6.00		
0100	0225-0169000E TRAFFIC CONTROL SUPERVISOR	EACH 90.00		
0110	0280-0100000A EROSION CONTROL	LS ALL		
0120	0280-0114000E INLET PROTECTION	EACH 200.00		

BID SCHEDULE

CONTRACT ID: 14032

PROJECT: OR99E: AURORA - SALEM PAVING  
SECTION

PROJECT KEY: 13624

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0130	0290-0100000A POLLUTION CONTROL PLAN	LS ALL		

SECTION 0002 ROADWORK

0140	0310-0106000A REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS ALL		
0150	0331-0106000J 12 INCH SUBGRADE STABILIZATION	SQYD 500.00		

SECTION 0003 Category Number 0400

0160	0490-0100000E ADJUSTING BOXES	EACH 30.00		
0170	0490-0120000E MINOR ADJUSTMENT OF MANHOLES	EACH 95.00		

SECTION 0004 BASES

0180	0620-0104000J COLD PLANE PAVEMENT REMOVAL, 0 - 2 INCHES DEEP	SQYD 7,070.00		
0190	0620-0106000J COLD PLANE PAVEMENT REMOVAL, 0 - 3 INCHES DEEP	SQYD 220.00		
0200	0620-0113000J COLD PLANE PAVEMENT REMOVAL, 2 - 6 INCHES DEEP	SQYD 430.00		
0210	0620-0120000J COLD PLANE PAVEMENT REMOVAL, 2 INCHES DEEP	SQYD 197,280.00		

## BID SCHEDULE

CONTRACT ID: 14032

PROJECT: OR99E: AURORA - SALEM PAVING  
SECTION

PROJECT KEY: 13624

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0220	0620-0121000J COLD PLANE PAVEMENT REMOVAL, 2-1/2 INCHES DEEP	SQYD 47,340.00		
0230	0620-0122000J COLD PLANE PAVEMENT REMOVAL, 3 INCHES DEEP	SQYD 126,300.00		
0240	0620-0125000J COLD PLANE PAVEMENT REMOVAL, 6 INCHES DEEP	SQYD 4,910.00		
0250	0641-0102000M AGGREGATE BASE	TON 1,100.00		

## SECTION 0005 WEARING SURFACES

0260	0730-0100000M EMULSIFIED ASPHALT FOR TACK COAT	TON 170.00		
0270	0745-0302000M LEVEL 3, 1/2 INCH DENSE HMAC	TON 67,400.00		
0280	0745-0640000M PG 70-22 ASPHALT IN HMAC	TON 4,100.00		
0290	0748-0114000J 23 INCH ASPHALT CONCRETE PAVEMENT REPAIR	SQYD 500.00		
0300	0749-0100000E EXTRA FOR ASPHALT APPROACHES	EACH 142.00		

## SECTION 0006 PERMANENT TRAFFIC SAFETY AND GUIDANCE DEVICES

0310	0855-0106000E MONO-DIRECTIONAL WHITE TYPE 1AR MARKERS, RECESSED	EACH 1,459.00		
------	--	------------------	--	--

BID SCHEDULE

CONTRACT ID: 14032

PROJECT: OR99E: AURORA - SALEM PAVING  
SECTION

PROJECT KEY: 13624

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0320	0855-0107000E BI-DIRECTIONAL YELLOW TYPE 1AR MARKERS, RECESSED	EACH 1,099.00		
0330	0865-0107000F THERMOPLASTIC, NON-PROFILE, 120 MILS, EXTRUDED	FOOT 317,000.00		
0340	0867-0103000E PAVEMENT LEGEND, TYPE B: ARROWS	EACH 81.00		
0350	0867-0119000E PAVEMENT LEGEND, TYPE B: RAILROAD CROSSING	EACH 4.00		
0360	0867-0131000E PAVEMENT LEGEND, TYPE B: BICYCLE LANE STENCIL	EACH 8.00		
0370	0867-0145000J PAVEMENT BAR, TYPE B	SQFT 4,030.00		

SECTION 0007 PERMANENT TRAFFIC CONTROL AND ILLUMINATION SYSTEMS

0380	0902-0100000E CROSSWALK CLOSURE BARRICADES	EACH 2.00		
0390	0905-0100000A REMOVE EXISTING SIGNS	LS ALL		
0400	0905-0101000A REMOVE AND REINSTALL EXISTING SIGNS	LS ALL		
0410	0910-0100000K WOOD SIGN POSTS	FBM 200.00		
0420	0920-0100000A SIGN SUPPORT FOOTINGS	LS ALL		

BID SCHEDULE

CONTRACT ID: 14032

PROJECT: OR99E: AURORA - SALEM PAVING  
SECTION

PROJECT KEY: 13624

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0430	0930-0117000A SQUARE TUBE SIGN SUPPORTS	LS ALL		
0440	0940-0113000J TYPE "G" SIGNS IN PLACE	SQFT 549.13		
0450	0940-0121000J TYPE "R" SIGNS IN PLACE	SQFT 522.00		
0460	0940-0124000J TYPE "W1" SIGNS IN PLACE	SQFT 15.00		
0470	0940-0134000J TYPE "Y1" SIGNS IN PLACE	SQFT 27.00		
0480	0990-0103000A LOOP DETECTOR INSTALLATION	LS ALL		
0490	0990-0107000A AUTOMATIC TRAFFIC RECORDER INSTALLATION	LS ALL		

SECTION 0008 RIGHT-OF-WAY DEVELOPMENT AND CONTROL

0500	1070-0100000E SINGLE MAILBOX SUPPORTS	EACH 43.00		
0510	1070-0101000E MULTIPLE MAILBOX SUPPORTS	EACH 6.00		
0520	1070-0102000E MAILBOX CONCRETE COLLARS	EACH 49.00		
	TOTAL BID			