



Oregon

Theodore R. Kulongoski, Governor

Department of Transportation
Technical Services
Roadway Engineering Section
355 Capitol Street NE, Room 222
Salem, OR 97301-3871
Telephone 503-986-3714
FAX 503-986-3749

DATE: July 17, 2009

Addendum No. 1

TO: PLAN HOLDERS

PREPARED BY:


J. Brad Larsen, P.E.

APPROVED BY:


Jeffrey Bernardo, P.E.

SUBJECT:

Old Hwy 99: MP 0.00 – 0.67 Overlay (Wolf Creek)
Old Hwy 99
Josephine County
Paving Project
(Bids to be opened and read July 30, 2009)

The following change is made to the Project Special Provisions:

1. Subsection **00744.11(a) Asphalt Cement** – This sentence is replaced with the following two paragraphs:

Use PG 70-22ER asphalt cement.

In addition to the requirements in ODOT's publication "Standard Specifications for Asphalt Materials", PG 70-22ER asphalt cement shall meet the following limit when tested according to AASHTO T 301 "Standard Method of Test for Elastic Recovery Test of Asphalt Materials by Means of a Ductilometer". The samples shall be conditioned per AASHTO T 240 "Standard Method of Test for Effect of Heat and Air on a Moving Film of Asphalt" (RTFOT) prior to testing per AASHTO T 301. The specified temperature for section 3.3 of the AASHTO T 301 procedure shall be 77°F.

% Elastic Recovery – **50** minimum

This change will be included in the Contract for this Project. It is understood that your Bid will be submitted accordingly.

JBL:jbl