



Oregon

Theodore R. Kulongoski, Governor


Department of Transportation
Technical Services
Roadway Engineering Section
355 Capitol Street NE, Room 222
Salem, OR 97301-3871
Telephone 503-986-3714
FAX 503-986-3749

DATE: August 20, 2009


Addenda No. 1

TO: PLAN HOLDERS

PREPARED BY:


David Stitz
Sr. Specification Writer
David Evans and Associates, Inc.

APPROVED BY:


Shon Heern
Design Project Manager
David Evans and Associates, Inc.

SUBJECT: Stayton – Scio Rd. & Oakville Rd. Paving (Linn County)
Various Highways
Linn County
Paving Project
(Bids to be opened and read August 27, 2009)

The following changes are made to the Project Bid Booklet:

1. The following change is made to the Project Bid Items:

a. Name change:

Number Item

0020 TEMPORARY PROTECTION AND DIRECTION OF TRAFFIC

Make a copy of and use the new attached Bid Sheets. A Bid not including these new Bid Sheets will be rejected as non-responsive.

The following changes are made to the Project Special Provisions:

1. Subsection 00220.02 Public Safety and Mobility - The first paragraph (including the bulleted item) that begins with the words "Replace the bulleted item..." is deleted.
2. Subsection 00220.02 Public Safety and Mobility - The bulleted item that begins with the words "Traffic Control – Traffic control and traffic control devices..." is deleted.
3. Subsection 00220.02 Public Safety and Mobility - The bulleted item that begins with the words "The Contractor is responsible for all signing..." is deleted.
4. Subsection 00220.02 Public Safety and Mobility - The bulleted item that begins with the words "When the work in progress requires flaggers..." is replaced with the following:
 - For flagging operations, provide traffic control devices and signing as shown on TM841 (or TM850, or TM870). Temporary signing shall be 48" x 48" unless otherwise indicated.
5. Subsection 00220.02 Public Safety and Mobility - The bulleted item that begins with the words "Public traffic is to be maintained..." is deleted.
6. Subsection 00220.02 Public Safety and Mobility - The bulleted item that begins with the words "Limitation of Operation – The Contractor..." is deleted.
7. Subsection 00220.02 Public Safety and Mobility - The bulleted item that begins with the words "Traveled ways shall be maintained..." is deleted.
8. Subsection 00220.02 Public Safety and Mobility - The bulleted item that begins with the words "The Contractor will provide all barricades..." is replaced with the following:
 - Provide all barricades, signals, warning lights, pilot cars and flaggers as necessary for the safety and protection of the public. Provide additional signing and flagging if in the opinion of the County Engineer it is needed to protect the public or the work being performed.

9. Subsection 00220.40(e) Lane Restrictions - The third paragraph that begins with the words " Replace subsections (1) and (2)..." is replaced with the following:

Replace subsections (1) and (2) with the following:

(1) Weekdays:

- Between 12:00 a.m. and 7:00 a.m. on Mondays
- Between 8:00 p.m. and 7:00 a.m. Monday through Friday

(2) Weekends:

- Between 12:00 a.m. and 7:00 a.m. on Saturdays
- Between 8:00 p.m. on Saturday and midnight on Sunday

These changes will be included in the Contract for this Project. It is understood that your Bid will be submitted accordingly.

Make copies of the new Bid Sheets to replace the Special Provisions Bid Schedule Sheets.

dajs:

Attachments: New Bid Sheets

BID SCHEDULE

CONTRACT ID: 14105

PROJECT: STAYTON - SCIO RD & OAKVILLE RD
PAVING (LINN COUNTY)

PROJECT KEY: 16484

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
---------	------------------	--------------------	----------------------------	----------------------------

SECTION 0001 TEMPORARY FEATURES AND APPURTENANCES

0010	0210-0100000A MOBILIZATION	LS	ALL	
0020	0225-0100000A TEMPORARY PROTECTION AND DIRECTION OF TRAFFIC	LS	ALL	
0030	0225-0102000J TEMPORARY SIGNS	SQFT	1,200.00	
0040	0225-0149000E TEMPORARY FLEXIBLE PAVEMENT MARKERS	EACH	3,500.00	
0050	0225-0168000T FLAGGERS	HOUR	1,750.00	
0060	0225-0172000T PILOT CARS	HOUR	400.00	
0070	0280-0100000A EROSION CONTROL	LS	ALL	
0080	0290-0100000A POLLUTION CONTROL PLAN	LS	ALL	

SECTION 0002 ROADWORK

0090	0350-0106000J PAVEMENT OVERLAY GEOTEXTILE	SQYD	3,000.00	
------	-------------------------------------------------	------	----------	--

SECTION 0003 DRAINAGE AND SEWERS

0100	0490-0100000E ADJUSTING BOXES	EACH	2.00	
------	----------------------------------	------	------	--

BID SCHEDULE

CONTRACT ID: 14105

PROJECT: STAYTON - SCIO RD & OAKVILLE RD
PAVING (LINN COUNTY)

PROJECT KEY: 16484

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0110	0490-0120000E MINOR ADJUSTMENT OF MANHOLES	EACH 1.00		

SECTION 0004 BRIDGES

0120	0503-0101000J BRIDGE DECK COLD PLANE PAVEMENT REMOVAL, 0-2 INCHES DEEP	SQYD 125.00		
------	---------------------------------------------------------------------------------	-------------	--	--

SECTION 0005 BASES

0130	0620-0104000J COLD PLANE PAVEMENT REMOVAL, 0 - 2 INCHES DEEP	SQYD 1,100.00		
0140	0620-0120000J COLD PLANE PAVEMENT REMOVAL, 2 INCHES DEEP	SQYD 6,100.00		
0150	0640-0101000M AGGREGATE SHOULDERS	TON 6,800.00		

SECTION 0006 WEARING SURFACES

0160	0730-0100000M EMULSIFIED ASPHALT FOR TACK COAT	TON 62.00		
0170	0745-0302000M LEVEL 3, 1/2 INCH DENSE HMAC	TON 20,000.00		
0180	0745-0331000M LEVEL 3, 1/2 INCH DENSE HMAC IN LEVELING	TON 300.00		
0190	0745-0620000M PG 64-22 ASPHALT IN HMAC	TON 1,220.00		

BID SCHEDULE

CONTRACT ID: 14105

PROJECT: STAYTON - SCIO RD & OAKVILLE RD
PAVING (LINN COUNTY)

PROJECT KEY: 16484

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0200	0749-0100000E EXTRA FOR ASPHALT APPROACHES	255.00 EACH		

SECTION 0007 PERMANENT TRAFFIC SAFETY AND GUIDANCE DEVICES

0210	0860-0200000F LONGITUDINAL PAVEMENT MARKINGS - PAINT	149,300.00 FOOT		
0220	0867-0119000E PAVEMENT LEGEND, TYPE B: RAILROAD CROSSING	2.00 EACH		
0230	0867-0145000J PAVEMENT BAR, TYPE B	250.00 SQFT		
	TOTAL BID			