



Oregon

Theodore R. Kulongoski, Governor

Department of Transportation
Technical Services
Roadway Engineering Section
355 Capitol Street NE, Room 222
Salem, OR 97301-3871
Telephone 503-986-3714
FAX 503-986-3749

DATE: April 16, 2009

Addenda No. 5

TO: PLAN HOLDERS

PREPARED BY: *Michelle Wright*

APPROVED BY: *Thomas Stull* P.E.

SUBJECT: US 30: Court – Dorion (Pendleton) – OR11 @ Athena
Oregon – Washington Highway & Pendleton Highway
Umatilla County
Grading, Drainage, Structure, Paving, Signing, Illumination, & Roadside
Development Project
(Bids to be opened and read April 23, 2009)

The following changes are made to the Project Special Provisions:

1. Subsection **00291.31 Submittals** - This subsection is replaced with the following subsection:

00294.41 Submittals - The following information, receipts, and reports are required:

- Provide recycling or disposal facility location and licensing information at least 15 calendar days before beginning contaminated soil excavation work.
- Submit contaminated soil recycling or disposal receipts within 72 hours of delivery to the recycling or disposal facility.
- If soil is re-used under a SWLA permit, provide volume estimates for contaminated soil re-used and all documentation required by the permit.

2. Subsection **00598.42 Leveling Pads** - This subsection is replaced with the following subsection:

00598.42 Leveling Pads – Construct an aggregate leveling pad at each wall segment as shown. Compact leveling pads according to 00596.41(b).

3. Subsection **00598.80 General** – This subsection is replaced with the following subsection:

00598.80 Measurement – No measurement of quantities will be made for work performed under this Section.

The estimated quantities, for estimating purposes only, of listed materials are as follows:

Material	Estimated Quantity
Concrete	32 CUYD
Stone Veneer	1,507 SFF (square face feet)
Reinforcement	1,180 LB

No separate measurement will be made for excavation, leveling pads, or specified backfill.

4. Subsection **00598.90 General** – This subsection is replaced with the following subsection:

00598.90 Payment – The accepted quantities of work performed under this Section will be paid for at the Contract unit price, per unit of measurement, for the following items:

Pay Item	Unit of Measurement
(a) Freestanding Stone Veneer Walls	Lump Sum

Payment will be payment in full for constructing, maintaining, and removing the walls and for furnishing all materials, labor, technical representatives, and incidentals necessary to complete the work specified.

5. Subsection **00759.47 Grinding Curbs** - This subsection is replaced with the following subsection:

00759.47 Grinding Curbs – Grind off curbs as shown on plans and to tolerances shown on plans.

6. Subsection **00760.42 Concrete Mortar Base** - This subsection is replaced with the following subsection:

00760.42 Concrete Mortar Base – Pour concrete base to minimum of 4" thick conforming to Section 00756 for concrete paving.

7. Subsection **00760.90 General** - This subsection is replaced with the following subsection:

00760.90 General – The accepted quantities will be paid for at the Contract unit price per square foot for the item "Unit Pavers".

US 30: Court – Dorion (Pendleton) – OR11 @ Athena
Oregon – Washington Highway & Pendleton Highway
Umatilla County
Grading, Drainage, Structure, Paving, Signing, Illumination, & Roadside Development Project
(Bids to be opened and read April 23, 2009)

Addenda No. 5

Payment will be in full for base preparation, installation of dowels, and for furnishing all materials, equipment, labor and incidentals necessary to complete the work as specified.

These changes will be included in the Contract for this Project. It is understood that your Bid will be submitted accordingly.

mfw:DGF