



Oregon

Theodore R. Kulongoski, Governor

Department of Transportation
Technical Services
Roadway Engineering Section
355 Capitol Street NE, Room 222
Salem, OR 97301-3871
Telephone 503-986-3714
FAX 503-986-3749

DATE: June 4, 2009

Addenda No. 1

TO: PLAN HOLDERS

PREPARED BY:



APPROVED BY:

 P.E.

SUBJECT: US30:Old Portland Rd-Crown-Zellerbach Rd Sidewalks
Lower Columbia River Highway
Columbia County
Grading, Drainage, Sidewalks and Roadside Development
(Bids to be opened and read June 18, 2009)

The following changes are made to the Project Bid Booklet:

1. The following changes are made to the Project Bid Items:
 - a. Name changes:

<u>Number</u>	<u>Item</u>
0180	Embankment In Place

Make a copy of and use the new attached Bid Sheets. A Bid **not** including these new Bid Sheets **will be rejected as non-responsive**.

The following changes are made to the Project Special Provisions:

1. Section 00330 – Earthwork - This Section is replaced with the following Section:

SECTION 00330 - EARTHWORK

Comply with Section 00330 of the Standard Specifications modified as follows:

00330.00 Scope – Replace this subsection, except for the heading, with the following:

This work consists of backfilling all areas cleared and grubbed per Section 00320 with suitable embankment material as described in this Section. Embankment limits will be from bottom of cleared and grubbed areas to bottom limits of aggregate base for sidewalks.

00330.03 Basis of Performance - Add the following paragraph to the end of this subsection:

Perform all earthwork under this Section on the embankment basis.

00330.41(a-5) Waste Materials - Replace this subsection, except for the subsection number and title, with the following:

Unless otherwise specifically allowed and subject to the requirements of 00280.03, dispose of materials, classed as waste materials in 00330.41(a-3) and 00330.41(a-4), outside and beyond the limits of the Project and Agency controlled property according to 00290.20. Do not dispose of materials on wetlands, either public or private, or within 300 feet of rivers or streams.

00330.82 Embankment Basis Measurement – Replace this subsection, except for the heading, with the following:

No separate measurement of earthwork will be made under this section. The estimated quantity of embankment material is 200 cubic yards.

00330.92 Kinds of Incidental Earthwork - Delete the bullet that reads "If shown on the plans."

00330.94 Embankment Basis Payment – Replace Pay Item (a) with the following:

Pay Item	Unit of Measurement
(a) Embankment in Place.....	Lump Sum

Replace the sentence that begins with "Item (a) includes..." with the following:

Item (a) includes hauling, placing, and compacting of the materials as specified and all other costs incurred in furnishing required embankment materials.

These changes will be included in the Contract for this Project. It is understood that your Bid will be submitted accordingly.

Make copies of the new Bid Sheets to replace the Special Provisions Bid Schedule Sheets.

IGM:igm
Attachments: New Bid Sheets

BID SCHEDULE

CONTRACT ID: 14070

PROJECT: US30: OLD PORTLAND
RD-CROWN-ZELLERBACH RD SIDEWALKS

PROJECT KEY: 16548

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
SECTION 0001 TEMPORARY FEATURES AND APPURTENANCES				
0010	0210-0100000A MOBILIZATION	LS	ALL	
0020	0225-0100000A TEMPORARY PROTECTION AND DIRECTION OF TRAFFIC	LS	ALL	
0030	0225-0102000J TEMPORARY SIGNS	SQFT	263.00	
0040	0225-0104000E TEMPORARY BARRICADES, TYPE II	EACH	4.00	
0050	0225-0105000E TEMPORARY BARRICADES, TYPE III	EACH	2.00	
0060	0225-0142000E SURFACE MOUNTED TUBULAR MARKERS	EACH	48.00	
0070	0225-0145000E TEMPORARY PLASTIC DRUMS	EACH	22.00	
0080	0225-0162000E SEQUENTIAL ARROW SIGNS	EACH	1.00	
0090	0225-0168000T FLAGGERS	HOUR	20.00	
0100	0280-0100000A EROSION CONTROL	LS	ALL	
0110	0280-0114000E INLET PROTECTION	EACH	29.00	
0120	0280-9Z90000M DISPOSAL OF CONTAMINATED SOIL	TON	20.00	

BID SCHEDULE

CONTRACT ID: 14070

PROJECT: US30: OLD PORTLAND
RD-CROWN-ZELLERBACH RD SIDEWALKS

PROJECT KEY: 16548

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0130	0280-9Z90000M DISPOSAL OF PAINTED CONCRETE	TON 60.00		
0140	0290-0100000A POLLUTION CONTROL PLAN	LS ALL		

SECTION 0002 ROADWORK

0150	0305-0100000A CONSTRUCTION SURVEY WORK	LS ALL		
0160	0310-0106000A REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS ALL		
0170	0320-0100000A CLEARING AND GRUBBING	LS ALL		
0180	0330-9Z90000A EMBANKMENT IN PLACE	LS ALL		

SECTION 0003 DRAINAGE AND SEWERS

0190	0430-0100040F 4 INCH DRAIN PIPE	FOOT 102.00		
0200	0490-0100000E ADJUSTING BOXES	EACH 14.00		
0210	0490-0105000E ADJUSTING INLETS	EACH 1.00		

SECTION 0004 BASES

0220	0640-0100000M AGGREGATE BASE	TON 550.00		
------	---------------------------------	------------	--	--

SECTION 0005 WEARING SURFACES

BID SCHEDULE

CONTRACT ID: 14070

PROJECT: US30: OLD PORTLAND
RD-CROWN-ZELLERBACH RD SIDEWALKS

PROJECT KEY: 16548

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0230	0759-0103000F CONCRETE CURBS, CURB AND GUTTER	100.00 FOOT		
0240	0759-0126000J CONCRETE DRIVEWAYS	188.00 SQFT		
0250	0759-0128000J CONCRETE WALKS	645.00 SQFT		
0260	0759-0152000J CONCRETE DRIVEWAY CONNECTIONS	113.00 SQFT		
0270	0759-9Z90000J CONCRETE SIDEWALK RAMPS	404.00 SQYD		
0280	0759-9Z90000J CONCRETE WALKS, REINFORCED	897.00 SQYD		

SECTION 0006 PERMANENT TRAFFIC SAFETY AND GUIDANCE DEVICES

0290	0815-0100000E BOLLARDS	2.00 EACH		
------	---------------------------	--------------	--	--

SECTION 0007 RIGHT-OF-WAY DEVELOPMENT AND CONTROL

0300	1030-9Z90000A PERMANENT SEEDING	ALL LS		
0310	1040-0101000K TOPSOIL	13.00 CUYD		
0320	1040-0107000K SOIL CONDITIONER	7.00 CUYD		
0330	1040-0130000E DECIDUOUS TREES, 2 INCH CALIPER	17.00 EACH		

BID SCHEDULE

CONTRACT ID: 14070

PROJECT: US30: OLD PORTLAND
 RD-CROWN-ZELLERBACH RD SIDEWALKS

PROJECT KEY: 16548

ADDENDUM NUMBER: 1

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0340	1040-0190000K BARK MULCH	CUYD	5.00	
0350	1040-0206000F ROOT BARRIER, 24 INCH WIDTH	FOOT	204.00	
0360	1070-0100000E SINGLE MAILBOX SUPPORTS	EACH	1.00	
	TOTAL BID			