



Oregon

Theodore R. Kulongoski, Governor

Department of Transportation
Technical Services
Roadway Engineering Section
355 Capitol Street NE, Room 222
Salem, OR 97301-3871
Telephone 503-986-3714
FAX 503-986-3749

DATE: February 11, 2010

Addenda No. 3

TO: PLAN HOLDERS

PREPARED BY:

APPROVED BY:

P.E.

SUBJECT: OR42: Hoover Hill To Lookingglass Creek Section
Coos Bay - Roseburg Highway
Douglas County
Grading, Drainage, Paving & Signing Project
(Bids to be opened and read February 25, 2010)

The following changes are made to the Project Bid Booklet:

1. COVER PAGE - The date on the Bid Booklet cover page is replaced with February 25, 2010.
2. DESCRIPTION OF WORK page - The first paragraph under TIME AND PLACE OF RECEIVING BIDS is replaced with the following:

Bids for the work described above will be opened and read at the Oregon Department of Transportation, 455 Airport Road SE, Building E, Salem, Oregon, at 9:00 a.m. on the 25th day of February, 2010.

3. The following changes are made to the Project Bid Items:

Quantity changes:

<u>Number</u>	<u>Item</u>	<u>Quantity</u>	
		<u>Original</u>	<u>New</u>
0070	Temporary Impact Attenuator	4	2
0080	Moving Temporary Impact Attenuators	4	6
0130	Flaggers	2,320	2,600
0150	Pilot Cars	1,160	600

Make a copy of and use the new attached Bid Sheets. A Bid **not** including these new Bid Sheets **will be rejected as non-responsive**.

The following changes are made to the Project Special Provisions:

1. COVER PAGE - The date on the Special Provisions cover page is replaced with February 25, 2010.

2. DESCRIPTION OF WORK page - The paragraph under TIME AND PLACE OF RECEIVING BIDS is replaced with the following:

Bids for the work described above will be opened and read at the Oregon Department of Transportation, 455 Airport Road SE, Bldg. E, Salem, Oregon 97301-5348, at 9:00 a.m. on the 25th day of February, 2010.

3. Subsection 00220.02 Public Safety and Mobility - Add the following bullet:

- During construction of stage 2,3,5, and 6, provide continuous 24-hour flagger operation, with a minimum of 2 flaggers. Occupy the advance flagger stations, as directed.

4. Subsection 00220.40(e-1) Weekdays and Weekends - The third paragraph that begins with the words "Single lane traffic shall not" is replaced with the following paragraph:

Single lane traffic shall not exceed 1.25 miles in length for HMAC placing operations including cold plane pavement removal or as approved by the Engineer. When the 24 hour flagger operation is not occurring, do not close any lanes between 3:00 p.m. Friday to 12:00 a.m. Sunday

OR42: Hoover Hill To Lookingglass Creek Section
Coos Bay - Roseburg Highway
Douglas County
Grading, Drainage, Paving & Signing Project
(Bids to be opened and read February 25, 2010)

Addenda No. 3

5. Subsection 00225.87(a) Flaggers - This subsection is added after subsection 0225.82(e):

00225.87(a) Flaggers - Add the following subsection:

Once stage construction begins, a maximum of 1,500 hours will be allowed for a pay quantity for all 24-hour flagger control. Advanced flaggers hours will not be included in the 1,500 hour maximum for 24 hour flagger control.

6. Subsection 00225.97 Flaggers and Flagger Station Lighting - The following paragraph is added after the paragraph that begins "During stage construction"

All additional 24 hour flagger control, including advanced flaggers, above the 1,500 hour maximum will be at no additional cost to the Agency.

These changes will be included in the Contract for this Project. It is understood that your Bid will be submitted accordingly.

mg:BB

BID SCHEDULE

CONTRACT ID: 14167

PROJECT: OR42: HOOVER HILL TO LOOKINGGLASS CREEK

PROJECT KEY: 16691

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
SECTION 0001 TEMPORARY FEATURES AND APPURTENANCES				
0010	0210-0100000A MOBILIZATION	LS	ALL	
0020	0225-0100000A TEMPORARY PROTECTION AND DIRECTION OF TRAFFIC	LS	ALL	
0030	0225-0102000J TEMPORARY SIGNS	SQFT	850.00	
0040	0225-0105000E TEMPORARY BARRICADES, TYPE III	EACH	6.00	
0050	0225-0126000F TEMPORARY CONCRETE BARRIER, REFLECTORIZED	FOOT	1,150.00	
0060	0225-0132000F MOVING TEMPORARY CONCRETE BARRIER	FOOT	975.00	
0070	0225-0133000E TEMPORARY IMPACT ATTENUATOR	EACH	2.00	
0080	0225-0136000E MOVING TEMPORARY IMPACT ATTENUATORS	EACH	6.00	
0090	0225-0141200E REPAIR TEMPORARY IMPACT ATTENUATOR	EACH	1.00	
0100	0225-0145000E TEMPORARY PLASTIC DRUMS	EACH	48.00	
0110	0225-0149000E TEMPORARY FLEXIBLE PAVEMENT MARKERS	EACH	7,283.00	
0120	0225-0164000E PORTABLE CHANGEABLE MESSAGE SIGNS	EACH	4.00	

BID SCHEDULE

CONTRACT ID: 14167

PROJECT: OR42: HOOVER HILL TO LOOKINGGLASS CREEK

PROJECT KEY: 16691

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0130	0225-0168000T FLAGGERS	2,600.00 HOUR		
0140	0225-0168100E FLAGGER STATION LIGHTING	4.00 EACH		
0150	0225-0172000T PILOT CARS	600.00 HOUR		
0160	0280-0100000A EROSION CONTROL	ALL LS		
0170	0000-0100000A DELETED BID ITEM	ALL LS	0.00	0.00
0180	0280-0106000E CHECK DAM	89.00 EACH		
0190	0280-0110000E CONSTRUCTION ENTRANCE	8.00 EACH		
0200	0280-0113000F SEDIMENT FENCE, UNSUPPORTED	6,706.00 FOOT		
0210	0290-0100000A POLLUTION CONTROL PLAN	ALL LS		

SECTION 0002 ROADWORK

0220	0305-0100000A CONSTRUCTION SURVEY WORK	ALL LS		
0230	0310-0100000F REMOVAL OF PIPES	315.00 FOOT		
0240	0310-0101000F REMOVAL OF FENCE	9,743.00 FOOT		

BID SCHEDULE

CONTRACT ID: 14167

PROJECT: OR42: HOOVER HILL TO LOOKINGGLASS CREEK

PROJECT KEY: 16691

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0250	0310-0106000A REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS ALL		
0260	0320-0100000R CLEARING AND GRUBBING	ACRE 10.70		
0270	0330-0123000K EMBANKMENT IN PLACE	CUYD 56,972.00		
0280	0330-0126000K STONE EMBANKMENT	CUYD 320.00		
0290	0334-0100000L PREPARATION OF SHOULDERS	MILE 1.10		
0300	0350-0103000J RIPRAP GEOTEXTILE, TYPE 1	SQYD 227.00		
0310	0350-0105000J SUBGRADE GEOTEXTILE	SQYD 26,365.00		
0320	0390-0105000K LOOSE RIPRAP, CLASS 50	CUYD 20.00		
0330	0390-0108000K LOOSE RIPRAP, CLASS 100	CUYD 80.00		
0340	0390-0111000K LOOSE RIPRAP, CLASS 200	CUYD 70.00		

SECTION 0003 DRAINAGE AND SEWERS

0350	0430-0101000E SUBSURFACE DRAIN OUTLETS	EACH 8.00		
0360	0445-010015AF 15 INCH CULVERT PIPE, 5 FT DEPTH	FOOT 146.00		

BID SCHEDULE

CONTRACT ID: 14167

PROJECT: OR42: HOOVER HILL TO LOOKINGGLASS CREEK

PROJECT KEY: 16691

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0370	0445-010018AF 18 INCH CULVERT PIPE, 5 FT DEPTH	60.00 FOOT		
0380	0445-010024AF 24 INCH CULVERT PIPE, 5 FT DEPTH	30.00 FOOT		
0390	0445-0100940F 96 INCH CULVERT PIPE	134.00 FOOT		
0400	0445-0700150E SLOPED END SECTIONS, 15 INCH	6.00 EACH		
0410	0445-0700180E SLOPED END SECTIONS, 18 INCH	4.00 EACH		
0420	0445-0700700E SLOPED END SECTIONS, 96 INCH	2.00 EACH		
0430	0460-0100000J PAVED CULVERT END SLOPES	277.00 SQFT		
0440	0490-0100000E ADJUSTING BOXES	3.00 EACH		
0450	0490-0104000E CONNECTION TO EXISTING STRUCTURES	3.00 EACH		
0460	0490-0105000E ADJUSTING INLETS	8.00 EACH		
0470	0490-0120000E MINOR ADJUSTMENT OF MANHOLES	2.00 EACH		
SECTION 0004 STRUCTURE NO. 21170				
0480	0510-0100000A SHORING, CRIBBING AND COFFERDAMS	ALL LS		

BID SCHEDULE

CONTRACT ID: 14167

PROJECT: OR42: HOOVER HILL TO LOOKINGGLASS CREEK

PROJECT KEY: 16691

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0490	0510-0101000A STRUCTURE EXCAVATION	LS ALL		
0500	0510-0108000A GRANULAR STRUCTURE BACKFILL	LS ALL		

SECTION 0005 STRUCTURE NO. 21171

0510	0510-0100000A SHORING, CRIBBING AND COFFERDAMS	LS ALL		
0520	0510-0101000A STRUCTURE EXCAVATION	LS ALL		
0530	0510-0108000A GRANULAR STRUCTURE BACKFILL	LS ALL		
0540	0595-0100000F REINFORCED CONCRETE BOX CULVERTS	FOOT 69.00		
0550	0595-0102000A WINGWALLS AND APRONS	LS ALL		

SECTION 0006 STRUCTURE NO. 21172

0560	0510-0100000A SHORING, CRIBBING AND COFFERDAMS	LS ALL		
0570	0510-0101000A STRUCTURE EXCAVATION	LS ALL		
0580	0510-0108000A GRANULAR STRUCTURE BACKFILL	LS ALL		
0590	0595-0100000F REINFORCED CONCRETE BOX CULVERTS	FOOT 71.00		

BID SCHEDULE

CONTRACT ID: 14167

PROJECT: OR42: HOOVER HILL TO LOOKINGGLASS CREEK

PROJECT KEY: 16691

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0600	0595-0102000A WINGWALLS AND APRONS	LS ALL		

SECTION 0007 BASES

0610	0620-0104000J COLD PLANE PAVEMENT REMOVAL, 0 - 2 INCHES DEEP	SQYD	1,010.00	
0620	0620-0111000J COLD PLANE PAVEMENT REMOVAL, 1 - 3 INCHES DEEP	SQYD	315.00	
0630	0620-0120000J COLD PLANE PAVEMENT REMOVAL, 2 INCHES DEEP	SQYD	48,791.00	
0640	0620-0122000J COLD PLANE PAVEMENT REMOVAL, 3 INCHES DEEP	SQYD	622.00	
0650	0641-0102000M AGGREGATE BASE	TON	19,120.00	

SECTION 0008 WEARING SURFACES

0660	0730-0100000M EMULSIFIED ASPHALT FOR TACK COAT	TON	40.00	
0670	0745-0302000M LEVEL 3, 1/2 INCH DENSE HMAC	TON	17,500.00	
0680	0745-0640000M PG 70-22 ASPHALT IN HMAC	TON	1,100.00	
0690	0748-0120000J 39 INCH ASPHALT CONCRETE PAVEMENT REPAIR	SQYD	20.00	

BID SCHEDULE

CONTRACT ID: 14167

PROJECT: OR42: HOOVER HILL TO LOOKINGGLASS CREEK

PROJECT KEY: 16691

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0700	0749-0100000E EXTRA FOR ASPHALT APPROACHES	27.00 EACH		

SECTION 0009 PERMANENT TRAFFIC SAFETY AND GUIDANCE DEVICES

0710	0810-0104000F GUARDRAIL, TYPE 2A	2,037.50 FOOT		
0720	0810-0105000F GUARDRAIL, TYPE 2A (MODIFIED)	150.00 FOOT		
0730	0810-0120000E GUARDRAIL ANCHORS, TYPE 1 MODIFIED	3.00 EACH		
0740	0810-0122000E GUARDRAIL END PIECES, TYPE B	3.00 EACH		
0750	0810-0129000E GUARDRAIL TERMINALS, NON-FLARED	7.00 EACH		
0760	0840-0100000E DELINEATORS, TYPE 1	35.00 EACH		
0770	0840-0106000E MILEPOST MARKER POSTS	3.00 EACH		
0780	0840-0106000E NO PASSING ZONE PADDLE MARKERS	10.00 EACH		
0790	0855-0100000E MONO-DIRECTIONAL WHITE TYPE 1 MARKERS	100.00 EACH		
0800	0855-0102000E BI-DIRECTIONAL YELLOW TYPE 1 MARKERS	500.00 EACH		
0810	0865-0114000F THERMOPLASTIC, WET WEATHER PATTERN, EXTRUDED	68,500.00 FOOT		

BID SCHEDULE

CONTRACT ID: 14167

PROJECT: OR42: HOOVER HILL TO LOOKINGGLASS CREEK

PROJECT KEY: 16691

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0820	0867-0103000E PAVEMENT LEGEND, TYPE B: ARROWS	10.00 EACH		
0830	0867-0145000J PAVEMENT BAR, TYPE B	70.00 SQFT		

SECTION 0010 PERMANENT TRAFFIC CONTROL AND ILLUMINATION SYSTEMS

0840	0905-0100000A REMOVE EXISTING SIGNS	ALL LS		
0850	0905-0101000A REMOVE AND REINSTALL EXISTING SIGNS	ALL LS		
0860	0910-0100000K WOOD SIGN POSTS	834.00 FBM		
0870	0920-0100000A SIGN SUPPORT FOOTINGS	ALL LS		
0880	0930-0106000A EXIT NUMBER SIGN MOUNTS	ALL LS		
0890	0930-0112000A TRIANGULAR BASE BREAKAWAY SIGN SUPPORTS	ALL LS		
0900	0930-0117000A PERFORATED STEEL SQUARE TUBE SIGN SUPPORTS	ALL LS		
0910	0940-0113000J TYPE "G" SIGNS IN PLACE	230.10 SQFT		
0920	0940-0121000J TYPE "R" SIGNS IN PLACE	41.00 SQFT		
0930	0940-0124000J TYPE "W1" SIGNS IN PLACE	98.40 SQFT		

BID SCHEDULE

CONTRACT ID: 14167

PROJECT: OR42: HOOVER HILL TO LOOKINGGLASS CREEK

PROJECT KEY: 16691

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
0940	0940-0127000J TYPE "W4" SIGNS IN PLACE	3.00 SQFT		
0950	0940-0134000J TYPE "Y1" SIGNS IN PLACE	138.00 SQFT		
0960	0940-0140000J TYPE "Y8" SIGNS IN PLACE	16.00 SQFT		
0970	0990-0102000A WEIGH STATION SIGNAL MODIFICATION	ALL LS		
0980	0990-0106000A FLASHING BEACON INSTALLATION	ALL LS		
0990	0990-0107000A AUTOMATIC TRAFFIC RECORDER INSTALLATION	ALL LS		

SECTION 0011 RIGHT-OF-WAY DEVELOPMENT AND CONTROL

1000	1030-0108000R PERMANENT SEEDING	10.00 ACRE		
1010	1050-0104000F TYPE 2 FENCE	9,743.00 FOOT		
1020	1050-0108000E 8 FOOT SINGLE GATES	1.00 EACH		
1030	1050-0111000E 16 FOOT SINGLE GATES	1.00 EACH		
1040	1070-0100000E SINGLE MAILBOX SUPPORTS	2.00 EACH		
1050	1070-0102000E MAILBOX CONCRETE COLLARS	2.00 EACH		

BID SCHEDULE

CONTRACT ID: 14167

PROJECT: OR42: HOOVER HILL TO LOOKINGGLASS CREEK

PROJECT KEY: 16691

ADDENDUM NUMBER: 3

ITEM NO	ITEM DESCRIPTION	QUANTITY AND UNITS	UNIT PRICE (IN FIGURES)	BID AMOUNT (IN FIGURES)
1060	1091-0101000E FISH ROCKS	80.00 EACH		
1070	1091-0104000K STREAMBED GRAVEL	140.00 CUYD		
1080	1092-0100000A BIOSLOPES	ALL LS		
1090	1095-9Z90000F BIOFILTRATION SWALE	552.00 FOOT		
1100	1095-9Z90000F BIOFILTRATION SWALE WITH UNDERDRAIN	983.00 FOOT		
	TOTAL BID			