



Highway Project Information

Area 1 Project Office: Astoria (503) 325-7222

State Highway Development and Construction in Clatsop and Tillamook Counties

Region 2 Bridge Painting Project

PROJECT SPECIFICS

- ✓ **Locations :**
Nehalem River (Mohler)
Necanicum Hwy MP 17.76

Trask River (Stillwell)
Netarts Hwy MP 8.33
- ✓ **Key milestones:**
Bid Let Date - April 2008
Construction – Spring 2008 or Fall 2008
- ✓ **Cost Estimate : \$850,000**



KEY CONTACT PERSON

Bill Jablonski, Project Leader (503) 325-7222, william.r.jablonski@odot.state.or.us
Paul Christiansen, Construction Project Manager (503) 325-4732 Ex. 12

PROJECT PURPOSE AND NEED

(MOHLER)

- 4 of the truss diagonals (each diagonal has 2 angle irons with lacing or batten plates between) will be replaced, unless our testing shows that some of the 4 are adequate as is
- The end floor beams have extensive corrosion damage on their lower flanges beneath the bridge joints, the corroded lower flanges will be trimmed flush
- Some of the rivets damaged by corrosion will be removed and replaced with bolts
- Sandblasting and painting will stop the degradation of other areas

(TRASK)

- Sandblasting and painting only

CONSTRUCTION OVERVIEW (PROPOSED)

(MOHLER)

- Full closure for one month for structural repairs and paint
- Detour via County road, to be determined

(STILLWELL)

- Single lane closure for two months