



Oregon Department of Transportation

# Highway Project Information

**Area 1 Project Office: Astoria (503) 325-7222**

*State Highway Development and Construction in Clatsop and Tillamook Counties*

## US 26 Necanicum River (Black Bridge)

Updated: December 20, 2010

### PROJECT SPECIFICS

- ✓ **Location :**  
East of 101 junction at MP 4.5
- ✓ **Key milestones:**  
Bid Let Date – June 2012  
Construction - Fall/Winter 2012-13
- ✓ **Cost Estimate:**  
\$756,000



### KEY CONTACT PERSON

Bill Jablonski, ODOT Project Leader  
503-338-7334

[William.r.jablonski@odot.state.or.us](mailto:William.r.jablonski@odot.state.or.us)

### PROJECT PURPOSE

This project will retrofit the bridge. Retrofit repairs will include: bridge rail with 3-tube rail, widen roadway for new approach rails, repair spalls in underside of deck and columns, seismic phase 1 retrofit, strengthen girders and crossbeams, and fix impact loading.

ODOT will widen the roadway to 2-12' travel lanes and 2-6' shoulders to match the overall bridge approach width. New concrete bridge approach columns will replace the existing sloped concrete rail connections. All bridge approach rails will be brought up to current standards.

During construction, two lanes of traffic will be open during construction. Work that may require one lane to be shut down will be performed at night.