

OR 62: Fort Creek Fish Passage Project Information Paper

Project Location: The project is located approximately 2 miles southeast of Ft. Klamath in Klamath County, Oregon on OR 62 (Crater Lake Highway) at milepost 92.3.

Purpose of the Project: The purpose of the project is two fold. The two existing 48-inch corrugated metal culverts at Ft. Creek are deteriorating and need to be replaced. They also restrict resident fish passage. The culverts restrict the flow causing a damming of the creek. The upstream ends of the culverts are lower than the downstream ends, creating a whirlpool upstream and pressurized flow through the culverts. The fast moving water is a barrier for fish. The culverts will be replaced by a bridge.



Fort Creek looking upstream where it passes under OR 62.

Schedule:

Contract bid let date: April 17, 2008

Construction begins; detour in place: August 1, 2008

Work completed; OR 62 reopened: October 31, 2008

Traffic Changes During Construction:

- OR 62 at Ft. Creek will be closed during construction on or about August 1, 2008. Traffic will be rerouted around the project area using Weed Road and Loosley Road. The detour will be in place until October 31, 2008.
- Local residential and business traffic on OR 62 north and south of Ft. Creek will be permitted. Signs at either end of the detour will alert travelers the highway is still open for local access.
- During construction, traffic impacts will be posted on [TripCheck](#) on a weekly basis or at more frequent intervals as changes occur.

ODOT Contacts:

Name	Title	Office Phone
Mike Redd	Project Leader	541-883-5665
Tom Feeley	Construction Project Manager	541-883-5665
Butch Hansen	Area Manager	541-883-5665

