

TABLE OF CONTENTS

PART 00100 - GENERAL REQUIREMENTS

Section 00110 - Organization, Conventions, Abbreviations and Definitions

00110.00	Organization of Standard Specifications.....	1
00110.05	Conventions Used Throughout the Specifications Include.....	1
00110.10	Abbreviations.....	2
00110.20	Definitions.....	4
00110.30	Metrication.....	2
00110.31	Use of Metric or Customary ("English") System.....	13

Section 00120 - Bidding Requirements and Procedures

00120.00	Prequalification of Bidders.....	14
00120.05	Requests for Solicitation Documents.....	14
00120.10	Bid Booklet.....	14
00120.15	Examination of Work Site and Solicitation Documents; Consideration of Conditions to be Encountered.....	15
00120.16	Material, Equipment and Method Substitutions.....	15
00120.17	Use of Agency-Owned Land for Staging or Storage Areas.....	16
00120.20	Interpretation of Quantities in Bid Schedule.....	16
00120.25	Subsurface Investigations.....	16
00120.30	Changes to Plans, Specifications, or Quantities before Opening of Bids.....	17
00120.40	Preparation of Bid.....	17
00120.45	Submittal of Bids.....	19
00120.50	Submitting Bids for More than One Contract.....	19
00120.60	Revision or Withdrawal of Bids.....	19
00120.65	Opening and Comparing Bids.....	20
00120.70	Rejection of Nonresponsive Bids.....	20
00120.80	Reciprocal Preference for Oregon Resident Bidders.....	21
00120.90	Disqualification of Bidders.....	21
00120.91	Rejection of Bid on Grounds of Nonresponsibility of Bidder.....	22

Section 00130 - Award and Execution of Contract

00130.00	Consideration of Bids.....	23
00130.10	Award of Contract.....	23
00130.15	Right to Protest Award.....	24
00130.20	Cancellation of Award.....	24
00130.30	Contract Booklet.....	24
00130.40	Contract Bonds, Certificates, and Registrations.....	24
00130.50	Execution of Contract and Bonds.....	25
00130.60	Failure to Execute Contract and Bonds.....	26
00130.70	Release of Bid Guaranties.....	26
00130.80	Restrictions on Commencement of Work.....	26
00130.90	Notice to Proceed.....	26

Section 00140 - Scope of Work

00140.00	Purpose of Contract.....	27
00140.10	Typical Sections.....	27
00140.20	Thickness.....	27
00140.30	Agency-Required Changes in the Work.....	27
00140.40	Differing Site Conditions.....	28
00140.50	Environmental Pollution Changes.....	28
00140.60	Extra Work.....	30
00140.65	Disputed Work.....	30

00140.70	Cost Reduction Proposals	30
00140.80	Use of Publicly Owned Equipment	32
00140.90	Final Trimming and Cleanup	32

Section 00150 - Control of Work

00150.00	Authority of the Engineer	33
00150.01	Project Manager's Authority and Duties	33
00150.02	Inspectors' Authority and Duties	33
00150.10	Coordination of Specifications and Plans	34
00150.15	Construction Stakes, Lines and Grades	34
00150.20	Inspection	35
00150.25	Acceptability of Materials and Work	36
00150.30	Delivery of Notices	36
00150.35	Plans and Working Drawings	36
00150.37	Equipment Lists and Other Submittals	37
00150.40	Cooperation and Superintendence by the Contractor	37
00150.50	Cooperation with Utilities	38
00150.55	Cooperation with Other Contractors	45
00150.60	Construction Equipment Restrictions	46
00150.70	Detrimental Operations	47
00150.75	Protection and Maintenance of Work During Construction	47
00150.80	Removal of Unacceptable and Unauthorized Work	47
00150.90	Final Inspection	48
00150.95	Final Acceptance	48
00150.96	Maintenance Warranties and Guarantees	48
00150.97	Responsibility for Materials and Workmanship	48

Section 00160 - Source of Materials

00160.00	Definitions	49
00160.01	Notification of Source of Supply and Materials	49
00160.05	Qualified Products List (QPL)	49
00160.10	Ordering, Producing, and Furnishing Materials	49
00160.20	Preferences for Materials	50
00160.30	Agency-Furnished Materials	51
00160.40	Agency-Furnished Sources	51
00160.50	Agency-Controlled Land; Limitations and Requirements	52
00160.60	Contractor-Furnished Materials and Sources	52
00160.70	Requirements for Plant Operations	53
00160.80	Requirements for Sources of Borrow and Aggregate	53

Section 00165 - Quality of Materials

00165.00	General	54
00165.01	Rejected Materials	54
00165.02	Materials Conformance and Quality Compliance Documents	54
00165.03	Testing by Agency	54
00165.04	Costs of Testing	54
00165.10	Materials Acceptance Guides	54
00165.20	Materials Specifications and Test Method References	54
00165.30	Field-Tested Materials	55
00165.35	Nonfield-Tested Materials	56
00165.40	Statistical Analysis	57
00165.50	Statistical Acceptance Sampling and Testing	63
00165.70	Use of Materials without Acceptable Materials Conformance Documents	64
00165.75	Storage and Handling of Materials	64
00165.80	Measurement	64

00165.90	Incidental Basis.....	64
00165.91	Fabrication Inspection Expense.....	65

Section 00170 - Legal Relations and Responsibilities

00170.00	General	66
00170.01	Other Agencies Affecting Agency Contracts.....	66
00170.02	Permits, Licenses, and Taxes.....	67
00170.03	Furnishing Right-of-Way and Permits.....	68
00170.04	Patents, Copyrights, and Trademarks.....	68
00170.05	Assignment of Antitrust Rights.....	68
00170.10	Required Payments by Contractors	69
00170.32	Protection of Navigable Waters	70
00170.60	Safety, Health, and Sanitation Provisions.....	70
00170.61	Industrial Accident Protection	70
00170.62	Labor Nondiscrimination.....	70
00170.63	Payment for Medical Care.....	70
00170.65	Minimum Wage and Overtime Rates for Public Works Projects.....	71
00170.70	Insurance Coverages	75
00170.71	Independent Contractor Status.....	76
00170.72	Indemnity; Hold Harmless	76
00170.74	Employee Drug Testing Program.....	76
00170.78	Conflict of Interest.....	76
00170.79	Third Party Beneficiary.....	76
00170.80	Responsibility for Damage to Work.....	77
00170.82	Responsibility for Damage to Property and Facilities	78
00170.85	Responsibility for Defective Work	78
00170.89	Protection of Utility, Fire-control, and Railroad Property and Services; Repair; Roadway Restoration.....	79
00170.92	Fencing, Protecting Stock, and Safeguarding Excavations	79
00170.93	Trespass	80
00170.94	Use of Explosives	80

Section 00180 - Prosecution and Progress

00180.00	Scope.....	81
00180.05	Assignment/Delegation of Contract.....	81
00180.06	Assignment of Funds Due under the Contract	81
00180.10	Responsibility for Contract.....	81
00180.15	Agency's Right to Do Work at Contractor's Expense.....	81
00180.20	Subcontracting Limitations	82
00180.21	Subcontracting.....	82
00180.22	Payments to Subcontractors and Agents of the Contractor	84
00180.30	Materials, Equipment, and Work Force	85
00180.31	Required Materials, Equipment and Methods.....	85
00180.32	Alternative Materials, Equipment, and Methods.....	86
00180.33	Metric Submittals	86
00180.40	Limitation of Operations	86
00180.41	Project Work Schedules	87
00180.42	Preconstruction Conference	89
00180.43	Commencement and Performance of Work.....	89
00180.50	Contract Time to Complete Work.....	89
00180.60	Notice of Delay	90
00180.65	Right-of-Way and Access Delays.....	91
00180.70	Suspension of Work.....	91
00180.80	Adjustment of Contract Time	92

00180.85	Failure to Complete on Time; Liquidated Damages	94
00180.90	Termination of Contract and Substituted Performance.....	95

Section 00190 - Measurement of Pay Quantities

00190.00	Scope.....	97
00190.10	Measurement Guidelines.....	97
00190.20	Contractor to Provide Vehicle Weigh Scales	98
00190.30	Plant Scales.....	101

Section 00195 - Payment

00195.00	Scope and Limit.....	102
00195.10	Payment For Changes in Materials Costs	102
00195.20	Changes to Plans or Character of Work.....	102
00195.30	Differing Site Conditions	103
00195.40	Unreasonable Delay by the Agency	103
00195.50	Progress Payments and Retained Amounts	103
00195.60	Advance Allowance for Materials on Hand	107
00195.70	Payment under Terminated Contract	108
00195.80	Allowance for Materials Left on Hand.....	109
00195.90	Final Payment.....	109
00195.95	Error in Final Quantities and Amounts.....	110

Section 00196 - Payment for Extra Work

00196.00	General	111
00196.10	Negotiated Price	111
00196.20	Force Account	111

Section 00197 - Payment for Force Account Work

00197.00	Scope.....	112
00197.01	General	112
00197.10	Materials.....	112
00197.20	Equipment.....	113
00197.30	Labor.....	114
00197.40	Invoices for Special Services.....	115
00197.80	Percentage Allowances.....	115
00197.90	Billings.....	116

Section 00199 - Disagreements, Protests and Claims

00199.00	General	117
00199.10	Procedure for Resolving Disagreements	117
00199.20	Protest Procedure	117
00199.30	Claims Procedure	118
00199.40	Claim Decision; Review; Exhaustion of Administrative Remedies	120
00199.50	Mediation.....	124

PART 00100 REPLACED JANUARY, 2006

PART 00100 - GENERAL REQUIREMENTS

Section 00110 - Organization, Conventions, Abbreviations and Definitions

Organization

00110.00 Organization of Standard Specifications - This publication is comprised of Part 00100 "General Requirements", which deals with the solicitation process and contractual relationships, and Parts 00200 and beyond, which contain the detailed technical specifications involved in prosecution of the Work, organized by subject matter. In addition, throughout these Standard Specifications:

- Each Part is divided into Sections and Subsections.
- Reference to a Section includes all applicable requirements of the Section.
- When referring to a Subsection, only the number of the Subsection is used; the word "Subsection" is implied.
- Where Section and Subsection numbers are not consecutive, the interval has been reserved for use in the Special Provisions, Supplemental Specifications (if any), or future expansion of the Standard Specifications.

Conventions

00110.05 Conventions Used Throughout the Specifications Include:

(a) Grammar - Part 00100 of the Standard Specifications is written in the indicative mood, in which the subject is expressed. Parts 00200 and beyond are generally written in the imperative mood, in which the subject is implied. Therefore, throughout Parts 00200 and beyond, and on the Plans:

- The subject, "the Contractor", is implied.
- "Shall" refers to action required of the Contractor, and is implied.
- "Will" refers to decisions or actions of the Agency and/or the Engineer.
- The following words, or words of equivalent meaning, refer to the actions of the Agency and/or the Engineer, unless otherwise stated: "directed", "established", "permitted", "ordered", "designated", "prescribed", "required", "determined".
- The words "approved", "acceptable", "authorized", "satisfactory", "suitable", "considered", and "rejected", "denied", "disapproved", or words of equivalent meaning, mean by or to the Agency and/or the Engineer, subject in each case to Section 00150 of these Standard Specifications.
- The words "as shown", "shown", "as indicated", or "indicated" mean "as indicated on the Plans".
- Certain Subsections labeled "Payment" contain statements to the effect that "payment will be made at the Contract amounts for the following items" (followed by a list of items). In such cases the Agency shall pay for only those Pay Items listed in the Schedule of Items.

(b) Capitalization of Terms - Capitalized terms, other than titles, abbreviations, and grammatical usage, indicate that they have been given a defined meaning in the Standard Specifications and Supplemental Specifications (if any). Refer to Section 00110.20 "Definitions". Defined terms will

always be capitalized in Part 00100; in Parts 00200 and beyond, defined terms will generally not be capitalized, with the notable exception of "the Contractor", "the Agency" and "the Engineer".

(c) Punctuation - In this publication the "outside method" of punctuation is employed for placement of the comma and the period with respect to quotation marks. Only punctuation that is part of the quoted matter is placed within quotation marks.

(d) References to Laws, Acts, Regulations, Rules, Ordinances, Statutes, Orders, and Permits - References are made in the text of the Specifications to "laws", "acts", "rules", "statutes", "regulations", "ordinances", etc. (collectively referred to for purposes of this Subsection as "Law"), and to "orders" and "permits" (issued by a governmental authority, whether local, State, or federal, and collectively referred to for purposes of this Subsection as "Permits"). Reference is also made to "applicable laws and regulations". The following conventions apply in interpreting these terms, as used in the Specifications.

- **Law** - In each case, unless otherwise expressly stated therein, the Law is to be understood to be the current version in effect. This also applies where a specific Law is referenced or cited, regardless of whether the text of the Law has been included in the Specifications or not, and regardless of whether the text of the Law has been summarized or paraphrased. In each case, the current version of the Law is applicable under any Contract. The reader is therefore cautioned to check the actual text of the Law to confirm that the text included in the Specifications has not been modified or superceded.
- **Permits** - Orders and permits issued by a government agency may be modified during the course of performing the Work under a Contract. Therefore, wherever the term "order" or "permit" is used in the Specifications, it is intended to refer to the then-current version. That version may be embodied in a modified, superceding order or permit, or it may consist of all terms and conditions of prior orders or permits that have not been superceded, as well as the additional terms added by amendment or supplement. In certain cases, the orders and/or permits are identified by name in the Specifications; in other cases the terms are used in the generic sense. The reader is cautioned to check the text(s) of each order and permit identified either by name or by generic reference.
- **Applicable Laws and Regulations** - Where the phrase "applicable laws and regulations" appears, it is to be understood as including all applicable laws, acts, regulations, administrative rules, ordinances, statutes, and orders and permits issued by a governmental or regulatory authority.

Abbreviations

00110.10 Abbreviations - Meanings of abbreviations used in the Standard Specifications, the Supplemental Specifications (if any), in the Special Provisions, on the Plans, and in other Contract Documents are as follows:

AAR	-	Association of American Railroads
AASHTO	-	American Association of State Highway and Transportation Officials
ABC	-	Associated Builders and Contractors, Inc.
AC	-	Asphalt Concrete
ACI	-	American Concrete Institute
ACWS	-	Asphalt Concrete Wearing Surface
AGC	-	Associated General Contractors of America
AIA	-	American Institute of Architects
AISC	-	American Institute of Steel Construction
AISI	-	American Iron and Steel Institute
ANSI	-	American National Standards Institute
APA	-	American Plywood Association

APWA	-	American Public Works Association
ARA	-	American Railway Association
AREA	-	American Railway Engineering Association
ASCE	-	American Society of Civil Engineers
ASME	-	American Society of Mechanical Engineers
ASTM	-	American Society for Testing and Materials
ATPB	-	Asphalt-Treated Permeable Base
AWG	-	American Wire Gauge
AWPA	-	American Wood Preservers Association
AWS	-	American Welding Society
AWWA	-	American Water Works Association
CAGT	-	Certified Aggregate Technician
CAT-I	-	Certified Asphalt Technician I
CAT-II	-	Certified Asphalt Technician II
CBM	-	Certified Ballast Manufacturers
CCO	-	Contract Change Order
CCT	-	Concrete Control Technician
CDT	-	Certified Density Technician
CEBT	-	Certified Embankment and Base Technician
CMDT	-	Certified Mixture Design Technician
CPF	-	Composite Pay Factor
CRSI	-	Concrete Reinforcing Steel Institute
CFR	-	Code of Federal Regulations
CS	-	Commercial Standard, Commodity Standards Division, U.S. Department of Commerce
D1.1	-	Structural Welding Code - Steel, American Welding Society, current edition
D1.5	-	Bridge Welding Code, American Welding Society, current edition
DBE	-	Disadvantaged Business Enterprise
DEQ	-	Department of Environmental Quality, State of Oregon
DOGAMI	-	Department of Geology and Mineral Industries, State of Oregon
DSL	-	Division of State Lands, State of Oregon
EAC	-	Emulsified Asphalt Concrete
EPA	-	U.S. Environmental Protection Agency
ESCP	-	Erosion and Sediment Control Plan
FHWA	-	Federal Highway Administration, U.S. Department of Transportation
FSS	-	Federal Specifications and Standards, General Services Administration
GSA	-	General Services Administration
HMAC	-	Hot Mixed Asphalt Concrete
ICEA	-	Insulated Cable Engineers Association (formerly IPCEA)
IES	-	Illuminating Engineering Society
IMSA	-	International Municipal Signal Association
ISO	-	International Standards Organization
ITE	-	Institute of Transportation Engineers
JMF	-	Job Mix Formula
MFTP	-	(ODOT) Manual of Field Test Procedures
MIL	-	Military Specifications
MSC	-	Minor Structure Concrete
MUTCD	-	Manual on Uniform Traffic Control Devices for Streets and Highways, FHWA, U.S. Department of Transportation
NEC	-	National Electrical Code
NEMA	-	National Electrical Manufacturer's Association
NESC	-	National Electrical Safety Code
NIST	-	National Institute of Standards and Technology
NPDES	-	National Pollutant Discharge Elimination System
NPS	-	Nominal Pipe Size (dimensionless)

OAR	-	Oregon Administrative Rules
ODA	-	Oregon Department of Agriculture
ODOT	-	Oregon Department of Transportation
ORS	-	Oregon Revised Statutes
OR-OSHA	-	Oregon Occupational Safety and Health Division of the Department of Consumer and Business Services
OSHA	-	Occupational Safety and Health Administration, U.S. Department of Labor
PCA	-	Portland Cement Association
PCI	-	Precast/Prestressed Concrete Institute
PCP	-	Pollution Control Plan
PF	-	Pay Factor of a constituent
PLS	-	Professional Land Surveyor
PMBB	-	Plant Mixed Bituminous Base
PTI	-	Post-Tensioning Institute
PUC	-	Public Utility Commission, State of Oregon
QA	-	Quality Assurance
QC	-	Quality Control
QCT	-	Quality Control Technician
QL	-	Quality Level
QPL	-	Qualified Products List
RAP	-	Reclaimed Asphalt Concrete Pavement
REA	-	Rural Electrification Administration, U.S. Department of Agriculture
RMA	-	Radio Manufacturers Association or Rubber Manufacturers Association
SAE	-	Society of Automotive Engineers
SI	-	International System of Units (Système Internationale)
SRCM	-	Soil and Rock Classification Manual (ODOT)
SSPC	-	Steel Structures Painting Council
T	-	Tolerances, AASHTO Test Method
TM	-	Test Method (ODOT)
TV	-	Target Value
UBC	-	Uniform Building Code (as adopted by the State of Oregon)
UL	-	Underwriters Laboratory, Inc.
UPC	-	Uniform Plumbing Code (as adopted by the State of Oregon)
USC	-	United States Code
WAQTC	-	Western Alliance for Quality Transportation Construction
WCLIB	-	West Coast Lumber Inspection Bureau
WWPA	-	Western Wood Products Association

Definitions

00110.20 Definitions - Following are definitions of words and phrases used in the Standard Specifications, the Supplemental Specifications (if any), in the Special Provisions, on the Plans, and in other Contract Documents. Other definitions may be found in the individual Sections of this publication to which they apply, in the Supplemental Specifications (if any), in the Special Provisions, and in OAR Chapter 731, Divisions 5 and 7.

Act of God or Nature - A natural phenomenon of such catastrophic proportions or intensity as would reasonably prevent performance.

Addendum - A written or graphic modification, issued before the opening of Bids, which revises, adds to, or deletes information in the Solicitation Documents or previously issued Addenda.

Additional Work - Increased quantities of any Pay Item, within the scope of the Contract, for which a unit price has been established.

Advertisement - The public announcement (Notice to Contractors) inviting Bids for Work to be performed or Materials to be furnished.

Agency - The city, county, or State agency or special district or political subdivision, as applicable, which has entered into a Contract with the Contractor.

Agency-Controlled Lands - Lands owned by the Agency, or controlled by the Agency under lease or agreement, or under the jurisdiction and control of the Agency for the purposes of the Contract.

Aggregate - Rock of specified quality and gradation.

Attorney in Fact - An Entity appointed by another to act in its place, either for some particular purpose, or for the transaction of business in general.

Award - Written notification to the Bidder that the Bidder has been awarded a Contract.

Base - A Course of specified material of specified thickness placed below the Pavement.

Bid - A competitive offer, binding on the Bidder and submitted in response to an invitation to bid.

Bid Bond - The Surety bond for Bid guarantee.

Bid Booklet - The bound booklet included in the Solicitation Documents that contains the information identified in 00120.10.

Bid Closing - The date and time after which Bids, Bid modifications, and Bid withdrawals will no longer be accepted.

Bid Opening - The date and time Bids are opened.

Bid Schedule - The list of Pay Items, their units of measurement, and estimated quantities. (When a Contract is awarded, the Bid Schedule becomes the Schedule of Items.)

Bid Section - The portion of the Bid Booklet containing all pages after the Bidder's checklist and before the appendix.

Bidder - An Entity that submits a Bid in response to an invitation to bid.

Bike Lane - A lane in the Traveled Way, designated by striping and Pavement markings for the preferential or exclusive use of bicyclists.

Borrow - Material lying outside of planned or required Roadbed excavation used to complete Project earthwork.

Boulders - Particles of rock that will not pass a 300 mm (12 inch) square opening.

Bridge - A single or multiple span Structure, including supports, that carries motorized and non-motorized vehicles, pedestrians, or utilities on a Roadway, walk, or track over a watercourse, highway, railroad, or other feature.

Buttress - A rock fill placed at the toe of a landslide or potential landslide in order to resist slide movement.

Calendar Day - Any day shown on the calendar, beginning and ending at midnight.

Camber - A slight arch in a surface or Structure to compensate for loading.

Change Order - A written order issued by the Engineer to the Contractor modifying Work required by the Contract and, if applicable, establishing the basis of payment for the modified Work.

Changed Work - Work included in a Pay Item and within the scope of the Contract that is different from that reflected in the Plans and Specifications. (See 00140.30.)

Class of Project - A designation based on a Project's funding source, i.e., State or Federal-Aid.

Class of Work - A designation referring to the type of Work in which Bidders must be pre-qualified. Classes of Work are limited to those listed in ODOT's Contractor's Prequalification Application.

Clay - Soil passing a 75 μm (No. 200) sieve that can be made to exhibit plasticity (putty-like properties) within a range of water contents.

Clear Zone - Roadside border area, starting at the edge of the Traveled Way, that is available for safe use by errant vehicles. Establishing a minimum width Clear Zone implies that rigid objects and certain other hazards within the Clear Zone should be relocated outside the Clear Zone, or shielded, or remodeled to make them break away on impact or be safely traversable.

Close Conformance - Where working tolerances are given on the Plans or in the Specifications, Close Conformance means compliance with those tolerances. Where working tolerances are not given, Close Conformance means compliance, in the Engineer's judgment, with reasonable and customary manufacturing and construction tolerances.

Coarse Aggregate - Crushed Rock or crushed Gravel retained on a 6.3 mm (1/4 inch) sieve, with allowable undersize.

Cobbles - Particles of Rock, rounded or not, that will pass a 300 mm (12 inch) square opening and be retained on a 75 mm (3 inch) sieve.

Commercial Grade Concrete - Concrete furnished according to Contractor proportioning, placed in minor Structures and finished as specified.

Contract - The written agreement between the Agency and the Contractor, including without limitation all Contract Documents, describing the Work to be completed and defining the rights and obligations of the Agency and the Contractor.

Contract Administration Engineer - The Agency representative presiding over Agency-level claims review under 00199.40.

Contract Amount - Sum of the Pay Item amounts computed by multiplying the Pay Item quantities by the unit prices in the Schedule of Items.

Contract Documents - Solicitation Documents, Contract booklet, Change Orders, Force Account Work orders, pay documents issued by the Agency, Materials certifications, Project Work schedules, final estimate, written orders and authorizations issued by the Agency, approved Plans, Material source development and reclamation plans, and permits, orders and authorizations obtained by the Contractor or Agency applicable to the Project, as well as all documents incorporated by reference therein.

Contract Time - The amount of time allowed to complete the Work under the Contract, calculated from the date On-Site Work commences.

Contractor - The Entity awarded the Contract pursuant to the solicitation.

Course - A specified Surfacing Material placed in one or more Lifts to a specified thickness.

Coverage - One Pass by a piece of Equipment over an entire designated area.

Cross Section - The exact image formed by a plane cutting through an object, usually at right angles to a central axis, to determine area.

Durable Rock - Rock that has a slake durability index of at least 90% based on a two-cycle slake durability test, according to ASTM D 4644. In the absence of test results, the Engineer may evaluate the durability visually.

Emulsified Asphalt - Emulsified asphalt cement.

Emulsified Asphalt Concrete - A mixture of Emulsified Asphalt and graded Aggregate.

Engineer - The Chief Engineer of the Agency acting either directly or through authorized representatives. If the Agency has not designated a Chief Engineer, this term denotes the person responsible for administering its public works program.

Entity - A natural person capable of being legally bound, sole proprietorship, limited liability company, corporation, partnership, limited liability partnership, limited partnership, profit or nonprofit unincorporated association, business trust, two or more persons having a joint or common economic interest, or any other person with legal capacity to contract, or a government or governmental subdivision.

Equipment - All machinery, tools, manufactured products, and fabricated items needed to complete the Contract or specified for incorporation into the Work.

Establishment Period - The time specified to assure satisfactory establishment and growth of planted Materials.

Existing Surfacing - Pavements, slabs, curbs, gutters, walks, driveways, and similar constructions of bricks, blocks, portland cement concrete, bituminous treated materials, and granular surfacing materials on existing Highways.

Extra Work - Work not included in the Contract, but deemed by the Engineer to be necessary to complete the Project.

Final Acceptance - Written confirmation by the Agency that the Project has been completed in accordance with the Contract, with the exception of latent defects and Warranty obligations, if any, and has been accepted.

Final Inspection - The inspection conducted by the Engineer to determine that the Project has been completed in accordance with the Contract.

Fine Aggregate - Crushed Rock, crushed Gravel, or Sand that passes a 6.3 mm (1/4 inch) sieve, with allowable oversize.

First Notification - Written acknowledgment by the Engineer of the date on which workers employed by the Contractor or a Subcontractor have begun performance of the Contract, including Aggregate source development or erection of a plant, but not including installation of covered temporary signs according to Section 00225.

Force Account Work - Items of Extra Work ordered by the Engineer that are to be paid according to Section 00197.

Granular Material - Graded and selected free-draining material composed of particles of Rock, Sand, and Gravel.

Gravel - Particles of Rock, rounded or not, that will pass a 75 mm (3 inch) sieve and be retained on a 4.75 mm (No. 4) sieve.

Highway - Every road, street, thoroughfare and place, including bridges, viaducts and other structures within the boundaries of the State, open, used or intended for use by vehicular traffic.

Incidental - A term identifying those acts, services, transactions, property, or other items for which the Agency will make no separate or additional payment.

Inspector - The representative of the Engineer authorized to inspect and report on Contract performance.

Leveling - Placing a variable-thickness Course of Materials to restore horizontal and vertical uniformity to existing Pavements, normally continuous throughout the Project.

Lift - The compacted thickness of material placed by Equipment in a single Pass.

Mandatory Source - A material source provided by the Agency from which the Contractor is required to obtain Materials. (See 00160.00(b) and 00160.40.)

Materials - Any natural or manmade substance specified for use in the construction of the Project or for incorporation into the Work.

Median - The portion of a divided Highway separating traffic traveling in opposite directions.

Multiple Course Construction - Two or more Courses, exclusive of Patching or Leveling, placed over the entire Roadway width.

Multi-Use Path - That portion of the Highway Right-of-Way or a separate Right-of-Way, physically separated from motor vehicle traffic and designated for use by pedestrians, bicyclists and other non-motorized users.

Neat Line - Theoretical lines specified or indicated on the Plans for measurement of quantities.

Nondurable Rock - Rock that has a slake durability index of less than 90% based on a two-cycle slake durability test, as tested by ASTM D 4644, or Rock that is observed to readily degrade by air, water, and mechanical influence.

Notice to Contractors - The public announcement inviting Bids for Work to be performed or Materials to be provided.

Notice to Proceed - Written notice authorizing the Contractor to begin performance of the Work.

On-Site Work - Any Work taking place on the Project Site, including designated staging areas adjacent to the Project Site, except for installation of covered temporary signs according to Section 00225.

Organic Soil - A Soil with sufficient organic content to influence the Soil properties.

Panel - The width of specified Material being placed by Equipment in a single Pass.

Pass - One movement of a piece of Equipment over a particular location.

Patching - Placing a variable-thickness Course of Materials to correct sags, dips, and/or bumps to the existing grade and Cross Section, normally intermittent throughout the Project.

Pavement - Asphalt concrete or portland cement concrete placed for the use of motor vehicles, bicycles, or pedestrians on Roadways, Shoulders, Multi-Use Paths and parking areas.

Pay Item (Contract Item) - A specific unit of Work for which a price is provided in the Contract.

Payment Bond - The approved security furnished by the Contractor's Surety as a guaranty of the Contractor's performance of its obligation to pay promptly in full all sums due for Materials, Equipment, and labor furnished to complete the Work.

Peat - A Soil composed primarily of vegetative matter in various stages of decomposition, usually with an organic odor, dark brown to black color, and a spongy consistency.

Performance Bond - The approved security furnished by the Contractor's Surety as a guaranty of the Contractor's performance of the Contract.

Plans - Standard and Supplemental Drawings, and approved unstamped and reviewed stamped Working Drawings. (See 00150.10 and 00150.35.)

Project - The sum of all Work to be performed under the Contract.

Project Manager - The Engineer's representative who directly supervises the engineering and administration of a Contract.

Project Site - The geographical dimensions of the real property on which the Work is to be performed, including designated contiguous staging areas.

Prospective Source - A Material source provided by the Agency, from which the Contractor has the option of obtaining Materials. (See 00160.00(a) and 00160.40).

Publicly-Owned Equipment - Equipment acquired by a state, county, municipality or political subdivision primarily for use in its own operations.

Public Traffic - Vehicular or pedestrian movement, not associated with the Contract Work, on a public way.

Railroad - Publicly or privately owned rail carriers, including passenger, freight, and commuter rail carriers, their tenants, and licensees. Also, Utilities that jointly own or use such facilities.

Right-of-Way - Land, property, or property interest, usually in a strip, acquired for or devoted to transportation or other public works purposes.

Roadbed - Completed excavations and embankments for the Subgrade, including ditches, side slopes, and slope rounding, if any.

Roadside - The area between the outside edges of the Shoulders and the Right-of-Way boundaries. Unpaved median areas between inside Shoulders of divided Highways and infield areas of interchanges are included.

Roadway - That portion of a Highway improved, designed, or ordinarily used for vehicular travel, exclusive of the berm or Shoulder. If a Highway includes two or more separate Roadways, the term "Roadway" refers to any such Roadway separately, but not to all such Roadways collectively. (See Traveled Way.)

Rock - Natural deposit of solid material composed of one or more minerals occurring in large masses or fragments.

Sand - Particles of Rock that will pass a 4.75 mm (No. 4) sieve and be retained on a 75 μ m (No 200) sieve.

Schedule of Items - The list of Pay Items, their units of measurement, estimated quantities, and prices.

Schedule of Values - The breakdown of the values of the component elements comprising a lump sum Pay Item.

Second Notification - Written acknowledgment by the Engineer of the end of Contract Time according to 00180.50(g).

Shoulder - The part of a Roadbed contiguous to the Traveled Way or Roadway, whether paved or unpaved, for accommodating stopped vehicles, for emergency use and for lateral support of Base and surface Courses.

Silt - Soil passing a 75 μ m (No. 200) sieve that is nonplastic or exhibits very low plasticity.

Single Course Construction - A wearing Course only, not including patching or leveling Courses or partial width Base Course.

Slope - Vertical distance to horizontal distance, unless otherwise specified.

Soil - Accumulations of particles produced by the disintegration of Rock, which sometimes contains organic matter. Particles may vary in size from Clay to Boulders.

Solicitation Document - Documents which define the procurement of a public improvement Project, including, but not limited to, the Bid Booklet, Agency-provided Plans, Standard Specifications, Supplemental Specifications (if any), Special Provisions, Addenda, and which includes all documents incorporated by reference.

Special Provisions - The special directions, provisions, and requirements specific to a Project that supplement or modify the Standard Specifications and the Supplemental Specifications (if any). Permits and orders governing the Project that are issued directly to the Agency by a governmental or regulatory authority are considered to be part of the Special Provisions, to the extent and under the conditions stipulated in the Special Provisions. This includes any amended or supplemental permits or orders issued during the course of performing the Work under a Contract.

Special Services - Force Account Work services that the Contractor and Engineer agree cannot be satisfactorily performed by the Contractor's and Subcontractors' forces, e.g., fabrication and machining work that is most effectively performed away from the Project Site, or rental of operated Equipment as defined in 00180.20(c).

Specifications - The Standard Specifications, the Supplemental Specifications (if any), and Special Provisions, together with all provisions of other documents incorporated therein by reference.

Standard Drawings - The Agency-prepared detailed drawings for Work or methods of construction that normally do not change from project to project.

Standard Specifications - "Oregon Standard Specifications for Construction", current edition, published by the Oregon Department of Transportation.

State - The State of Oregon.

Structures - Bridges, retaining walls, endwalls, cribbing, buildings, culverts, manholes, catch basins, drop inlets, sewers, service pipes, underdrains, foundation drains, and other similar features which may be encountered in the Work.

Subbase - A Course of specified material of specified thickness between the Subgrade and a Base.

Subcontractor - An Entity with whom the Contractor contracts to perform a portion of the Work.

Subgrade - The top surface of completed earthwork on which Subbase, Base, Surfacing, Pavement, or a Course of other Material is to be placed.

Substructure - Those parts of a Structure which support the Superstructure, including bents, piers, abutments, and integrally built wingwalls, up to the surfaces on which bearing devices rest. Substructure also includes portions above bearing surfaces when those portions are built integrally with a Substructure unit (e.g., backwalls of abutments). When Substructure and Superstructure elements are built integrally, the division between Substructure and Superstructure is considered to be at the bottom soffit of the longitudinal or transverse beam, whichever is lower. Culverts and rigid frames are considered to be entirely Substructure.

Superstructure - Those parts of a Structure above the Substructure, including bearing devices.

Supplemental Drawings - The Agency-prepared detailed drawings for Work or methods of construction that are Project specific, and are denoted by title in the Project title block.

Supplemental Specifications - "Supplemental Oregon Standard Specifications for Construction". Supplemental Specifications are applicable to the particular Contract, and supplement and modify the Standard Specifications with regard to the Work to be done under that Contract.

Surety - The Entity that issues the bond.

Surfacing - The Course or Courses of material on the Traveled Way, auxiliary lanes, Shoulders, or parking areas for vehicle use.

Third Notification - Written acknowledgment by the Engineer, subject to Final Acceptance, that as of the date of the notification the Contractor has completed the Project in accordance with the Contract, including without limitation completion of all minor corrective work, Equipment and plant removal, site clean-up, and submittal of all certifications, bills, forms and documents required under the Contract.

Topsoil - Soil ready for use in a planting bed.

Traffic Lane - That part of the Traveled Way marked for moving a single line of vehicles.

Traveled Way - That part of the Highway for moving vehicles, exclusive of auxiliary lanes, berms and Shoulders.

Typical Section - That Cross Section established by the Plans which represents in general the lines to which the Contractor shall work in the performance of the Contract.

Unsuitable Material - Frozen material, or material that contains organic matter, muck, humus, peat, sticks, debris, chemicals, toxic matter, or other deleterious materials not normally suitable for use in earthwork.

Utility - A line, facility, or system for producing, transmitting, or distributing communications, power, electricity, heat, gas, oil, water, steam, waste, storm water not connected with highway drainage, or any other similar commodity which directly or indirectly serves the public. The term may also mean the utility company, district, or cooperative owning and operating such facilities, including any wholly-owned or controlled subsidiary.

Warranty Bond - The approved security furnished by the Contractor's Surety as a guaranty of the Contractor's performance of its warranty obligations.

Wetlands - Areas that are inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal circumstances do support, vegetation typically adapted for life in saturated Soil conditions. Wetlands generally include swamps, marshes, bogs, and similar areas.

Work - The furnishing of all Materials, Equipment, tools, labor, and Incidentals, necessary to successfully complete any individual Pay Item or the entire Contract, and the discharge of duties and obligations imposed by the Contract.

Working Drawings - Supplemental Plans, not furnished by the Agency, that the Contractor is required to submit to the Engineer. (See 00150.35.)

Metrication

00110.30 Metrication - These specifications utilize the International System of Units (SI) as defined by IEEE/ASTM SI-10, Standard Practice for Use of the International System of Units (SI). Frequently used units in these specifications and their abbreviations are as follows:

Unit	Abbreviation
meter	m
gram	g
liter	L
degree Celsius	°C
hectare	ha
pascal	Pa
newton	N
joule	J
volt	V
ampere	A
ohm	Ω
watt	W
henry	H
candela	cd
lumen	lm
lux	lx

Prefixes indicating order of magnitude are frequently used in conjunction with these units. The common prefixes used in these specifications and their multiplying factors are shown below:

Prefix	Abbreviation	Multiplying Factor
micro	μ	0.000 001
milli	m	0.001
kilo	k	1000
mega	M	1 000 000

00110.31 Use of Metric or Customary ("English") System - These Specifications include dimensions in customary units of measurement, also known as "English units", in parentheses following metric dimensions. These are provided for the convenience of users who prefer them; however, only metric units may be used in Contract Documents for ODOT projects and local projects involving federal funds.

PART 00100 REPLACED JANUARY, 2006

Section 00120 - Bidding Requirements and Procedures

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

00120.00 Prequalification of Bidders - The Oregon Department of Transportation (ODOT) will prequalify Bidders according to OAR Chapter 734, Division 10, and OAR 731-005-0025. A Bidder must file for prequalification and pay a fee. Prequalification must be renewed by March 1 of each year. Bidders shall make application for prequalification on standard forms furnished by ODOT's Construction Contracts Unit, Room 212 Transportation Building, 355 Capitol St. N.E., Salem, Oregon 97301-3871 (telephone (503) 986-3877). Bidders shall return the completed application and fee to the Construction Contracts Unit.

Contracts will only be awarded to Bidders who, at the time of Bid Opening, are prequalified in the Class or Classes of Work designated in the Special Provisions, except that a Bidder whose prequalification has been revoked or revised as provided in ORS 279.041(3) may also be eligible for Award under that statute if the Project was advertised prior to the revocation or revision. The Agency will consider a Bid from a Bidder whose complete application for prequalification has been received by the Construction Contracts Unit at least 10 Calendar Days before the opening of Bids. Bidders shall submit Bids in the same company name used on the prequalification application; provided however, if Bidder's legal name has changed since the submittal of its application for prequalification, it shall submit its Bid under its current legal name with the former name referenced by "formerly known as".

The Agency will regularly evaluate the performance of Contractors on its projects for purposes of responding to reference checks, future prequalification and determinations of responsibility.

00120.05 Requests for Solicitation Documents - Bidders must obtain Solicitation Documents from the Contractor Plans office, Room 28 Transportation Building, 355 Capitol St. N.E., Salem, Oregon 97301-3871; phone (503) 986-3720. Each request must include both the name of the person ordering or obtaining the Solicitation Documents, and the name of the Entity intending to use them. (The Agency will add the name of the Entity intending to use the Solicitation Documents to the list of Holders of Bidding Plans.) Bidders are cautioned that only Solicitation Documents obtained from the Agency's Contractor Plans office may be used to submit Bids.

Informational Plans and Specifications (not for bidding) and copies of the Oregon Standard Specifications may also be purchased at the Contractor Plans office.

00120.10 Bid Booklet - The Bid Booklet may include, but is not limited to:

- Bidder's checklist
- Bid Section
- Appendix, which includes required time-sensitive forms, DBE information, sample forms, and other informational pages

The Bid Section includes all pages after the Bidder's checklist and before the appendix. The Bid Section may include, but is not limited to:

- Description and location of the proposed Project
- Time, date, and location for opening Bids
- Project completion time
- Class of Project (i.e., Federal-Aid or State)
- Class of Work
- Identification of applicable Supplemental Specifications and Special Provisions
- Bid statement
- Certificate of non-collusion

- Certificate of noninvolvement in any debarment or suspension (for Federal-Aid Projects)
- Certificate regarding lobbying activities (for Federal-Aid Projects)
- Certificate of residency (for State Projects)
- Certificate of compliance with Oregon tax laws
- Bid Schedule
- Identification of Bidder(s) and Sureties
- Limiting statements (See 00120.50)
- Bid signature page
- Bid Bond form
- First-tier Subcontractor disclosure form

Depending on the Class of Project, other certificates or statements may be bound within the Bid Section. Plans, Specifications, and other documents referred to in the Bid Section will be considered part of the Bid.

00120.15 Examination of Work Site and Solicitation Documents; Consideration of Conditions to be Encountered - Before submitting a Bid, Bidders shall carefully examine the site of the proposed Work, the Bid Booklet, Plans, and Specifications. Bidders shall also contact Utility owners to verify all Utilities' anticipated involvement on the Project Site. Bidders are also encouraged to review any subsurface investigation material referenced in 00120.25 that may be available. Submission of a Bid will constitute confirmation that the Bidder has examined the Project Site and Solicitation Documents, finds the Plans and Specifications to be sufficiently detailed and accurate to enable Bidder to properly perform the Work, and understands the conditions to be encountered in performing the Work and all requirements of the Contract.

The Agency and its employees will not be responsible for loss or unanticipated costs suffered by the Bidder because of the Bidder's failure to become fully informed about all conditions of the Work, or failure to request clarification of Plans and Specifications Bidder believes to be erroneous or incomplete.

Any clarification of Plans and Specifications needed by the Bidder shall be requested in writing through the Engineer. Requests shall be made in sufficient time for the Agency's reply to reach all Bidders before Bid Closing. Oral explanations or interpretations given before receiving Bids for a Project will not be binding. To be binding, interpretation of the Plans and Specifications by the Agency must be made by written Addendum furnished to all Holders of Bidding Plans according to 00120.30. Notification of erroneous or incomplete Plans or Specifications shall also be submitted to the Engineer. Such notification shall also be made in sufficient time for the Agency to make any necessary modifications and issue Addenda to Bidders prior to Bid Closing.

00120.16 Material, Equipment and Method Substitutions - When the Contract specifies certain Materials, Equipment, and/or methods, the Bidder shall include those Materials, Equipment, and/or methods in the Bid unless the Engineer has issued an Addendum granting approval to substitute. The procedure for requesting approval is as follows:

(a) Written Request - If a Bidder proposes to use Materials, Equipment and/or methods other than those specified, the Bidder shall send a written request to the Engineer, at least seven Calendar Days prior to Bid Opening, including complete descriptive and technical information on the proposed Materials, Equipment and/or methods.

(b) Functional Similarity - Materials and Equipment proposed for substitution shall be similar in design, and equal or better in quality and function to those specified.

(c) Manufacturer's Information - If manufacturers' brochures or information is needed, the Bidder shall submit three copies of each with all pertinent information clearly marked.

(d) Differences - The Bidder shall specifically note all differences between the specified Materials, Equipment and/or methods and the proposed substitutes.

(e) Cost - Where a substitute will result in alteration of the design or space requirements, or any other modifications to the Plans, the Bidder shall include in the substitution request all items of cost for the revised design and construction.

(f) Notification of Holders of Bidding Plans - If the Engineer approves any proposed substitution, such approval, and any modifications necessitated to the design and construction by the substitution, will also be sent to all Holders of Bidding Plans through an Addendum.

Unless the Engineer has approved substitutions of Materials, Equipment, and/or methods prior to opening of Bids, the Bidder must furnish the items specified in the Contract. Substitution after Award is addressed in 00180.31(b), (c) and (d).

00120.17 Use of Agency-Owned Land for Staging or Storage Areas - The Contractor may use Agency-owned property for staging or storage areas, subject to the following limitations:

(a) Within Normal Right-of-Way Limits - If approved by the Engineer, the Contractor may use available property within the normal Right-of-Way limits for the purpose of constructing improvements under the Contract. Where the Agency owns, or has rights to, other adjacent properties in the Project area, "normal Right-of-Way" is limited to a line drawn across that property connecting the normal Right-of-Way limits on either side of the property.

(b) Outside Normal Right-of-Way Limits - The Contractor may not use Agency-owned property outside of normal Right-of-Way limits for the Project without the approval of the Engineer.

If a Bidder obtains approval before submitting a Bid, use of the property will be at no cost to the Contractor, or at a cost stated by the Engineer upon granting approval, as confirmed by Addendum.

If approval is not obtained before submitting a Bid, and the Contractor proposes to use Agency-owned property outside the normal Right-of-Way limits, then use of the property may be approved by the Engineer, but the Contractor will be assessed fair market value, as determined by the Engineer, for use of the property.

(c) Restrictions on Use - Contractors shall comply with all applicable laws, ordinances, and regulations pertaining to use of Agency-owned property, and shall:

- Not cause unreasonable impacts on traffic and other facility users.
- Clean up all hazardous materials deposited by, or resulting from, Contractor operations.
- Be responsible for all costs associated with use of the property.

00120.20 Interpretation of Quantities in Bid Schedule - Quantities appearing in the Bid Schedule are approximate and are provided only for comparison of Bids. The Agency does not warrant that the actual individual items, amount of Work, or quantities will correspond to those shown in the Bid Schedule. Payment to the Contractor will be made only for actual quantities of Work performed and accepted or Materials furnished and accepted, as required by the Contract. Quantities of Work to be performed and Materials to be furnished may each be increased, decreased, or omitted as provided in 00120.30 and 00140.30.

00120.25 Subsurface Investigations - If the Agency or its consultant has conducted subsurface or geologic investigations of the proposed Project Site, the results of the investigations may be included in written reports. If reports have been prepared, copies will be available at the Engineer's office. If the Agency has retained subsurface samples, they will also be available for inspection. Bidders and the Contractor may make arrangements for viewing the samples through the Engineer's office.

The availability of subsurface information from the Agency is solely for the convenience of the Bidder and shall not relieve the Bidder or the Contractor of any risk, duty to make examinations and investigations as required by 00120.15, or other responsibility under the Contract Documents. It is mutually agreed to by all parties that:

- The written report(s) are reference documents and not part of the Contract Documents.
- The subsurface investigations made by the Agency are for the purpose of obtaining data for planning and design of the Project.
- The data concerning borings is intended to represent with reasonable accuracy conditions and materials found in specific borings at the time the borings were made.

00120.30 Changes to Plans, Specifications, or Quantities before Opening of Bids:

The Agency reserves the right to issue Addenda making changes or corrections to the Plans, Specifications, or quantities. Only holders of Solicitation Documents obtained from the Agency's Contractor Plans office who have been identified by the Agency as Holders of Bidding Plans, as required by 00120.05, will be notified of these Addenda by mail, delivery service, or electronic facsimile (FAX) sent to the Bidder's address or FAX number as it appears in the Agency's files. Holders of informational Plans, obtained from the Agency's Contractor Plans office, will be notified by mail.

The Agency will not be responsible for failure of Bidders to receive Addenda sent as described in the preceding paragraph. Bids may be rejected if opened and found by the Agency not to be based on Addenda issued before Bids were opened.

00120.40 Preparation of Bid:

(a) General - Bidders shall not alter, in any manner, the documents bound within the Bid Section. Bidders shall complete the certifications and statements included in the Bid Section of the Bid Booklet according to the instructions. Signature of the Bidder's authorized representative thereon constitutes the Bidder's confirmation of and agreement to all certifications and statements contained in the booklet. Entries on documents in the Bid Section shall be in ink or typed. Signatures and initials shall be in ink, except for changes submitted by facsimile (FAX) transmission as provided by 00120.60 (in which case FAX signatures shall be considered originals).

The Bidder shall properly complete and bind all documents in the Bid Section, as designated in 00120.10, between the front and back covers of the Bid Booklet, except that the Bid Bond is not required if another permissible type of Bid guaranty is provided (See 00120.40(e)).

(b) Bidding Considerations - Bidders may refer to the following Subsections for requirements that may affect bidding considerations:

- 00120.80, Preference for Oregon Resident Bidders
- 00130.80, Restrictions on Commencement of Work
- 00150.55, Coordination of Work
- 00150.75, Protection and Maintenance of Work
- 00160.20(a), Buy America
- 00160.20(b), Buy Oregon
- 00180.20, Subcontracting Limitations
- 00180.21, Subcontracting
- 00195.50(a-1), Incidentals
- 00195.00(a), Cost of Insurance and Bonds

(c) Bid Schedule Entries - Using figures, Bidders shall fill in all blank spaces in the Bid Schedule. For each item in the Bid Schedule, Bidders shall enter the unit price and the product of the unit price multiplied by the quantity given. Bidders shall also enter the total amount of the Bid obtained by adding amounts for all items in the Bid Schedule. The Bidder shall initial each erasure, change or correction of the Bidder's entries in the Bid.

(d) Bidder's Address and Signature Pages - Bidders shall include in the Bid the address to which all communications concerning the Bid and Contract should be sent. The Bid must be signed by a duly authorized representative of the Bidder.

(e) Bid Guaranty - Bids must be accompanied by a Bid guaranty in the amount of 10% of the total amount of the Bid. The guaranty shall be either a Surety bond, irrevocable letter of credit issued by an insured institution as defined in ORS 706.008 or security in the form of a cashier's check or certified check made payable to the Agency (see ORS 279.027(5)).

If a Surety bond is submitted, Bidders shall use the Agency's standard Bid Bond form included with the Bid Booklet. Bidders shall submit the bond with original signatures and the Surety's seal affixed.

Acceptable Surety companies are limited to those authorized to do business in the State of Oregon.

Forfeiture of Bid guaranties is covered by 00130.60, and return of guaranties is covered by 00130.70.

(f) Disclosure of First-Tier Subcontractors - If a Bidder's Bid on a public improvement Project exceeds \$75,000, the Bidder shall, within four working hours of the time Bids are due to be submitted, submit to the Agency, on a form provided by the Agency, a disclosure identifying any first-tier Subcontractors that will furnish labor or labor and Materials, and whose contract value is equal to or greater than:

- 5% of the total Project Bid, but at least \$15,000, or
- \$350,000, regardless of the percentage of the total Project Bid.

For each Subcontractor listed, Bidders shall state:

- The name of the Subcontractor, and
- The category of Work that the Subcontractor would be performing.

If no subcontracts subject to the above disclosure requirements are anticipated, a Bidder shall so indicate by entering "NONE" or by filling in the appropriate check box. For each Subcontractor listed, Bidders shall provide all requested information. An incomplete form will be cause for rejection of the Bid.

The Subcontractor Disclosure Form may be submitted either:

- By filling out the Subcontractor Disclosure Form included in the Bid Booklet and submitting it together with the Bid at the time and place designated for receipt of Bids,
- By removing it from the Bid Booklet, filling it out and submitting it separately to the Construction Contracts Unit Manager at the address or FAX number given in the Bid Booklet, or
- By e-mail, using the form and address provided on the Agency's web site named in the Bid Booklet.

Subcontractor Disclosure Forms submitted by any method will be considered late if not received by the Construction Contracts Unit within four working hours of the time designated for receiving Bids.

E-mail submissions must be fully compatible with Word for Windows®. The Agency is not responsible for partial, failed, illegible or partially legible facsimile (FAX) transmissions or e-mail submittals, and such forms may be rejected as incomplete.

Bids not in compliance with the requirements of this Subsection will be considered non-responsive.

00120.45 Submittal of Bids - Bids may be submitted by mail or parcel delivery service to the Construction Contracts Unit Manager, at the address given in the Bid Booklet, in a sealed envelope provided by the Agency, or a reasonably similar envelope marked with the word "Bid", the name of the Project, and the words "To Be Opened Only by Authorized Personnel" on the outside. If a delivery or courier service is used, the Bidder shall place the sealed envelope containing the Bid inside the delivery or courier service's envelope.

Bids submitted after the time set for receiving Bids will not be opened or considered. The Agency assumes no responsibility for the receipt and return of late Bids.

Bids may be submitted at the address given in the Bid Booklet prior to 8:30 a.m. local time on the day of Bid Opening. After that time, Bids may be submitted between 8:30 a.m. and 9 a.m. local time to Agency contracts personnel at the Bid deposit box in the main lobby of the Transportation Building or in the room where Bids are to be opened. Closing time for acceptance of Bids is 9 a.m. local time on the day of Bid Opening.

00120.50 Submitting Bids for More than One Contract - A Bidder who desires to submit Bids for more than one Contract at a single opening of multiple Bids may submit one of the "Limiting Statements" in the Bid as follows:

- If the volume of Work to be awarded is to be limited by the number of Contracts, fill in Limiting Statement No. 1 in the Bid Booklet.
- If the volume of Work to be awarded is to be limited by the total of the Contract Amounts, fill in Limiting Statement No. 2 in the Bid Booklet.

If a Bidder makes a limiting statement on any Bid, the statement will apply to all Bids submitted by the Bidder at that opening. Should limiting statements be made on more than one Bid, and the statements differ, the lower limiting number or amount shall govern.

Bidders shall make no qualifications of the Bids that attempt to reserve the right to choose, from among two or more Contracts, the Contract or Contracts that the Bidder will accept. Selection of Contracts will be made by the Agency.

00120.60 Revision or Withdrawal of Bids - Information entered into the Bid Booklet by the Bidder may be changed after the Bid has been delivered to the Agency's Construction Contracts Unit, provided that:

- Changes are prepared in accordance with the instructions found in the Bid Booklet,
- Changes are received by the Agency's Construction Contracts Unit (Room 212) or Second Floor Business Unit (Room 200) before 9 a.m. local time on the day of the Bid Opening,
- The Bid number is included, and

- The changes are submitted in writing or by electronic facsimile (FAX) transmission to the FAX number(s) given in the Bid booklet, signed by an individual authorized to sign the Bid. FAX submittals received by the Agency shall constitute an original document.

A Bidder may withdraw its Bid after it has been delivered to the Agency's Construction Contracts Unit, provided that:

- The written withdrawal request is submitted on the Bidder's letterhead, either in person or by FAX, and includes the Bid number,
- The request is signed by an individual who is authorized to sign the Bid, and proof of authorization to sign the Bid accompanies the withdrawal request, and
- The request is received by the Construction Contracts Unit or Second Floor Business Unit before 9 a.m. local time on the day of the Bid Opening.

00120.65 Opening and Comparing Bids - Bids will be opened and the total price for each Bid will be read publicly at the time and place indicated in the Notice to Contractors and the Bid Booklet. Bidders and other interested parties are invited to be present.

Bids for each Project will be compared on the basis of the total amount of each Bid. The total amount of the Bid will be the total sum computed from quantities listed in the Bid Schedule and unit prices entered by the Bidder.

In case of conflict between the unit price and the corresponding extended amount, the unit price shall govern, and the Agency may make arithmetic corrections on extension amounts.

00120.70 Rejection of Nonresponsive Bids - A Bid will be considered irregular and will be rejected if the irregularity is deemed by the Agency to render the Bid non-responsive. Examples of irregularities include without limitation:

- The Bid Section documents provided are not properly used or contain unauthorized alterations.
- The Bid is incomplete or incorrectly completed.
- The Bid contains improper additions, deletions, alternate Bids, or conditions.
- The Bid is submitted on documents not obtained directly from the Contractor Plans office, or is submitted by a Bidder who has not been identified by the Agency as a Holder of Bidding Plans, as required by 00120.05.
- A member of a joint venture and the joint venture submit Bids for the same Project. Both Bids may be rejected.
- The Bid has entries not typed or in ink, or has signatures or initials not in ink (save for changes received by FAX as provided by 00120.60).
- Each erasure, change, or correction is not individually initialed.
- The price per unit cannot be determined.
- The Bid guaranty is insufficient or improper.
- The original Bid Bond form is not used or is altered.

- The Oregon Construction Contractors Board registration number and expiration date are not shown on the Bid if required in the Solicitation Document. This requirement applies to State-funded Projects, with the exception of Aggregate production and landscape Projects. (Not required on Federal-Aid Projects.)
- A disclosure of first-tier Subcontractors, if required under 00120.40(f), is not received within four working hours of the time Bids are due to be submitted, or the disclosure form is not complete.
- The Bidder has not complied with the DBE requirements of the solicitation.
- The Bid does not evidence recognition of Addenda.

00120.80 Reciprocal Preference for Oregon Resident Bidders - This Subsection applies only to Contracts for Projects financed without federal funds.

Bidders shall complete the certificate of residency provided by the Agency in the Bid Booklet. Failure to properly complete the form will be cause to reject the Bid.

As used in the certificate of residency and this Subsection, "Resident Bidder" means a Bidder who has:

- Paid unemployment taxes or income taxes in the State of Oregon during any of the 12 calendar months immediately preceding submission of the Bid,
- A business address in the State of Oregon, and
- Certified in the Bid that the Bidder qualifies as a Resident Bidder.

"Nonresident Bidder" means a Bidder who is not a Resident Bidder as defined above.

In determining the lowest Bid, the Agency will, for the purpose of awarding the Contract, add a percentage increase to the Bid of a Nonresident Bidder equal to the percentage, if any, of the preference given to that Bidder in the state in which the Bidder resides (ORS 279.029(2)). The percentage preference applied in each state will be published on or before January 1 of each year by the Oregon Department of Administrative Services. The Agency may rely on these percentages without incurring liability to any Bidder (ORS 279.029(3)).

This increase will only be applied to determine the lowest Bid, and will not cause an increase in payment to the Contractor after Award of the Contract.

00120.90 Disqualification of Bidders - The Bid(s) of a disqualified Bidder will be rejected. Any of the following reasons is sufficient to disqualify a Bidder:

- More than one Bid is submitted for the same Work by an Entity under the same or different name(s).
- Evidence of collusion among Bidders. Participants in collusion will be found not responsible, and may be subject to criminal prosecution.
- Any of the grounds for disqualification cited in ORS 279.037

A Bidder will be disqualified if the Bidder has:

- Not been prequalified as required by 00120.00;

00120.90

- Been declared ineligible by the Commissioner of the Bureau of Labor and Industries under ORS 279.361;
- Not been registered (licensed) by the Oregon Construction Contractors Board (CCB) or been licensed by the State Landscape Contractors Board before submitting a Bid (ORS 279.027(1)(k) and 671.530). The Bidder's registration number and expiration date shall be shown in the Bid form, if requested. Failure to furnish the registration number, if requested, will render the Bid non-responsive and subject to rejection. (Not required on Federal-Aid projects.); or
- Been determined by the CCB under ORS 701.227 not to be qualified to hold or participate in a public contract for a public improvement.

00120.91 Rejection of Bid on Grounds of Nonresponsibility of Bidder - The Bid of a Bidder who is found to be nonresponsive according to the criteria listed in 00130.10 will be rejected. Refer also to ORS 279.029(6).

PART 00100 REPLACED JANUARY, 2006

Section 00130 - Award and Execution of Contract

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

00130.00 Consideration of Bids - After opening and reading Bids, the Agency will check them for correct extensions of unit prices and totals (See 00120.65). The total of extensions, corrected where necessary, will be used by the Agency for Award purposes.

The Agency reserves the right to waive minor informalities and irregularities, and to reject any or all Bids for irregularities under 00120.70 or for good cause after finding that it is in the public interest to do so (ORS 279.035). An example of good cause for rejection in the public interest is the Agency's determination that any of the unit Bid prices are significantly unbalanced to the Agency's potential detriment. The Agency may correct obvious errors, when the correct information can be determined from the face of the document, if it finds that the best interest of the Agency and the public will be served thereby.

Bids will be considered and a Contract awarded, if at all, within 30 Calendar Days from the date of Bid Opening, unless an extension beyond that time is agreed to by both parties and acknowledged in writing by the Bidder.

00130.10 Award of Contract - After the Bids are opened and a determination is made that a Contract is to be awarded, the Contract will be awarded to the lowest responsible Bidder. For the purposes of this Section, "lowest responsible Bidder" means the lowest Bidder who is not on the list created by the Construction Contractors Board pursuant to ORS Chapter 701, and who has:

- Substantially complied with all prescribed public bidding procedures and requirements
- Available the appropriate financial, Materials, Equipment, facility and personnel resources and expertise, or ability to obtain the resources and expertise, necessary to indicate the capability of the prospective Bidder to meet all contractual responsibilities
- A satisfactory record of performance
- A satisfactory record of integrity
- Qualified legally to contract with the Agency
- Supplied all necessary information in connection with the inquiry concerning responsibility. If a prospective Bidder fails to promptly supply information requested by the Agency concerning responsibility, the Agency shall base the determination of responsibility upon any available information, or may find the prospective Bidder not to be responsible
- Not been disqualified by the public contracting agency under ORS 279.037

If the Bidder is found not to have a satisfactory record of performance or integrity, the Agency will document the record and the reasons for the unsatisfactory finding.

The Agency will provide Notice of Intent to Award on the Agency's web site, or as otherwise established by the Agency. The Award will not be final until the later of the following:

- Three working days after the Notice of Intent to Award has been posted as specified in the advertised solicitation or Addendum thereto, or

- The Agency has provided a written response to each timely protest, denying the protest and affirming the Award.

If the Agency accepts a Bid and awards a Contract, the Agency will send the successful Bidder written notice of acceptance and Award.

Notice of Award and Contract booklets ready for execution will be sent within 30 Calendar Days of the opening of Bids or within the number of Calendar Days specified in the Special Provisions or a written mutual agreement.

00130.15 Right to Protest Award - Adversely affected or aggrieved Bidders, limited to the three apparent lowest Bidders and any other Bidder directly in line for Contract Award, may submit to the Agency's Construction Contracts Unit a written protest of the Agency's intent to Award within three working days following posting of the Notice of Intent to Award on the Agency's web site. The protest shall specify the grounds upon which it is based.

The Agency is not obligated to consider late protests.

00130.20 Cancellation of Award - Without liability to the Agency, the Agency may for good cause cancel Award at any time before the Contract is executed by all parties to the Contract, as provided by ORS 279.035 for rejection of Bids, upon finding it is in the public interest to do so.

00130.30 Contract Booklet - The Contract booklet may include but is not limited to:

- Supplemental Specifications, if any
- Special Provisions
- Addenda
- Schedule of Items
- Contract
- Performance Bond
- Payment Bond
- Certification of workers' compensation coverage

00130.40 Contract Bonds, Certificates, and Registrations - Before the Agency will execute the Contract, the successful Bidder shall furnish the following bonds, certificates, and registrations:

(a) Performance and Payment Bonds - When Awarded the Contract, the successful Bidder shall furnish a Performance Bond and a Payment Bond of a Surety authorized to do business in the State of Oregon.

The successful Bidder shall submit the standard bond forms, which are bound in the Contract booklet. Faxed or photocopied bond forms will not be accepted. The amount of each bond shall be equal to the Contract Amount. The Performance Bond and the Payment Bond must be signed by the Surety's authorized Attorney-in-Fact, and the Surety's seal must be affixed to each bond. A power of attorney for the Attorney-in-Fact shall be attached to the bonds in the Contract booklet, which must include bond numbers, and the Surety's original seal must be affixed to the power of attorney. Bonds shall not be canceled without the Agency's consent, nor will the Agency normally release them, prior to Contract completion.

(b) Certificates of Insurance - The successful Bidder shall furnish the Agency certificates of insurance applicable to the Project, in accordance with 00170.70. The insurance coverages shall remain in force throughout the performance of the Contract and shall not be allowed to lapse without prior written approval of the Agency. Bidders may refer to 00170.70 for minimum coverage limits and other requirements.

For specified Contracts, certified copies, and in some instances the original, of insurance policies may be required by the Special Provisions.

(c) Workers' Compensation - To certify compliance with the workers' compensation insurance coverage required by 00170.61(a) and 00170.70(c), the successful Bidder shall complete and sign the "Certification of Workers' Compensation Coverage" form bound in the Contract booklet.

(d) Registration Requirements:

(1) ORS 701.055 and ORS 671.530 require that Bidders be registered with the Oregon Construction Contractors Board or licensed by the State Landscape Contractors Board prior to submission of a Bid on a Project not involving federal funds. Registration with the Construction Contractors Board or licensing by the State Landscape Contractors Board is not a prerequisite to bidding on Federal-Aid Projects; however, the Agency will not execute a Contract until the Contractor is so registered or licensed.

(2) Bidders must be registered with the Corporation Division, Oregon Secretary of State, if bidding as a corporation, limited liability company, joint venture, or limited liability partnership, or if operating under an assumed business name and the legal name of each person carrying on the business is not included in the business name.

(3) A Contractor registered under ORS Chapter 701 may bid on a landscaping Project or perform a construction project that includes landscape contracting as a portion of the project if the landscape contracting is subcontracted to a licensed landscaping business as defined in ORS 671.520.

(4) A landscaping business may bid on a Project or perform a Contract that includes the phase of landscape contracting for which it is not licensed if it employs a landscape contractor, or subcontracts with another licensed landscaping business, licensed for that phase.

00130.50 Execution of Contract and Bonds:

(a) By the Bidder - The successful Bidder shall deliver the required number of Contract booklets with the properly executed Contract, Performance Bond, Payment Bond, certification of workers' compensation coverage, and the required certificates of insurance, to the Construction Contracts Unit within 15 Calendar Days after the date on which the Contract booklets are sent or otherwise conveyed to the Bidder under 00130.10. The Bidder shall return the originals of all documents received from the Agency and named in this Subsection, with original signatures. Certificates of insurance shall also be originals. No copies of these documents will be accepted by the Agency.

Proper execution requires that:

- If the Contractor is a partnership, limited liability partnership, joint venture, or limited liability company, an authorized representative of each Entity comprising it shall sign the Contract, Performance Bond, and Payment Bond, and an authorization to sign shall be attached.
- If the Contractor is a corporation, the President and the Secretary of that corporation shall sign the Contract, Performance Bond, and Payment Bond. However, if other corporate officers are authorized to execute contracts and bonds, the successful Bidder shall furnish with those documents a certified, true and correct copy of the corporate bylaws or minutes stating that authority. If only one officer is signing, then the bylaws or minutes must include the authority to sign without the signature of others. The successful Bidder shall also include the title(s) or corporate office(s) held by the signer(s).

00130.50(b)

(b) By the Agency - Within seven Calendar Days after the Agency has received and verified the properly executed documents specified in 00130.50(a) above, and received legal sufficiency approval from the Attorney General (if required), the Agency will execute the Contract. The Agency will then send a fully-executed original Contract booklet to the successful Bidder, who then officially becomes the Contractor.

00130.60 Failure to Execute Contract and Bonds - Failure of the successful Bidder to execute the Contract and provide the required certificates, certifications, and bonds may be cause for cancellation of the Award, and may be cause for forfeiture of the Bid guaranty under ORS 279.031.

Award may then be made to the next lowest responsible Bidder, the Project may be re-advertised, or the Work may be performed otherwise as the Agency decides.

The forfeited Bid guaranty will become the Agency's property, not as a penalty but as liquidation of damages resulting from the Bidder's failure to execute the Contract and provide the certificates, certifications, and bonds as required by these Specifications.

00130.70 Release of Bid Guaranties - Bid guaranties will be released and checks returned seven Calendar Days after Bids are opened, except for those of the three apparent lowest Bidders on each Project. The guaranties of the three apparent lowest Bidders will be released and checks returned to unsuccessful Bidders within seven days of the Agency's execution of the Contract.

00130.80 Restrictions on Commencement of Work - Until the Agency sends the Contractor written Notice to Proceed with the Work, the Contractor shall not go onto the property on which the Work is to be done, nor move Materials, Equipment or workers onto that property.

The Contractor will not automatically be entitled to extra compensation because the commencement of Work is delayed by failure of the Agency to send the Contract for execution. However, if more than 30 Calendar Days elapse between the date the Bid is opened and the date the Agency sends the Contract to be executed, the Agency will consider granting an adjustment of time for completion of the Work to offset any actual delay to Contract completion resulting directly from delay in commencement.

00130.90 Notice to Proceed - Notice to Proceed will be issued within five Calendar Days after the Contract is executed by the Agency.

Should the Agency fail to issue the Notice to Proceed within five Calendar Days of Contract execution, the Contractor may apply for an adjustment of Contract Time according to 00180.80(c).

The Engineer will issue a First Notification recording the date the Work commenced on the Project.

Section 00140 - Scope of Work

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

00140.00 Purpose of Contract - The purpose of the Contract is to set forth the rights and obligations of the parties and the terms and conditions governing completion of the Work. The Contractor's obligations shall include without limitation the following:

- The Contractor shall furnish all Materials, Equipment, labor, transportation, and Incidentals required to complete the Work according to Plans, Specifications, and terms of the Contract.
- The Contractor shall perform the Work according to the lines, grades, Typical Sections, dimensions, and other details shown on the Plans, as modified by written order, or as directed by the Engineer.
- The Contractor shall perform all Work determined by the Engineer to be necessary to complete the Project.
- The Contractor shall contact the Engineer for any necessary clarification or interpretation of the Contract.

00140.10 Typical Sections - The Typical Sections are intended to apply in general. At other locations where the Typical Section is not appropriate, the Contractor shall perform construction to the identified alignment as directed by the Engineer.

00140.20 Thickness - The thickness of Courses of Materials shown on the Plans, given in the Specifications, or established by the Engineer is considered to be the compacted thickness. Minor variations are acceptable when within tolerances defined in the Specifications or Plans, or when approved by the Engineer.

00140.30 Agency-Required Changes in the Work - Changes to the Plans, quantities, or details of construction are inherent in the nature of construction and may be necessary or desirable during the course of Project construction.

Without impairing the Contract, the Agency reserves the right to require changes it deems necessary or desirable within the scope of the Project. These changes may modify, without limitation:

- Specifications and design
- Grade and alignment
- Cross Sections and thicknesses of Courses of Materials
- Method or manner of performance of Work
- Increases and decreases in quantities
- Additional Work
- Elimination of any Contract item of Work
- Project Limits
- Acceleration or delay in performance of Work

Upon receipt of a Change Order, the Contractor shall perform the Work as modified by the Change Order. If the Change Order increases the Contract Amount, the Contractor shall notify its Surety of the increase and shall provide the Agency with a copy of any resulting modification to bond documents. The Contractor's performance of Work pursuant to Change Orders shall neither invalidate the Contract nor release the Surety. Payment for changes in the Work shall be made in accordance with 00195.20. Contract Time adjustments shall be made in accordance with 00180.80.

00140.40 Differing Site Conditions - The following constitute differing Project Site conditions provided such conditions are discovered at the Project Site after commencement of the Work:

- Subsurface or latent physical conditions that differ materially from those indicated in the Contract Documents, or
- Unknown physical conditions of unusual nature that differ materially from those ordinarily encountered and generally recognized as inherent in the Work provided for in the Contract.

The party discovering such a condition shall promptly notify the other party, in writing, of the specific differing conditions before they are disturbed and before the affected Work is performed. The Contractor shall not continue Work in the affected area until the Engineer has inspected such condition according to 00195.30 to determine whether an adjustment to Contract Amount or Contract Time is required.

Payment adjustments due to differing Project Site conditions, if any, will be made according to 00195.30. Contract Time adjustments, if any, will be made according to 00180.80.

00140.50 Environmental Pollution Changes - ORS 279.318 will govern any increases in the scope of the Work required as a result of environmental or natural resources laws enacted after the submission of Bids for the Contract.

**Oregon Revised Statutes 2001
Excerpt from Chapter 279 (Public Contracts and Purchasing)**

279.318 Provisions relating to environmental and natural resources laws and rules; remedies when requirements change.

(1) Bid documents for a public contract for a public improvement shall make specific reference to federal, state and local agencies that have enacted ordinances or regulations dealing with the prevention of environmental pollution and the preservation of natural resources that affect the performance of the contract. If the successful bidder awarded the project is delayed or must undertake additional work by reason of existing regulations or ordinances of agencies not cited in the public contract or due to the enactment of new or the amendment of existing statutes, ordinances or regulations relating to the prevention of environmental pollution and the preservation of natural resources occurring after the submission of the successful bid, the public contracting agency may:

- (a) Terminate the contract;*
- (b) Complete the work itself;*
- (c) Use nonagency forces already under contract with the public contracting agency;*
- (d) Require that the underlying property owner be responsible for cleanup;*
- (e) Go out to bid for a new contractor to provide the necessary services under the competitive bid requirements of ORS 279.015; or*
- (f) Issue the successful bidder a change order setting forth the additional work that must be undertaken.*

(2) In addition to the obligation imposed under subsection (1) of this section to refer to federal, state and local agencies with regulations dealing with the prevention of environmental pollution and the preservation of natural resources, a public bid document must also make specific

reference to known conditions at the construction site that may require the successful bidder to comply with the statutes, ordinances or regulations identified under subsection (1) of this section.

(3) If the successful bidder encounters a condition not referred to in the bid documents and not caused by the successful bidder and not discoverable by a reasonable prebid visual site inspection and the condition requires compliance with the regulations referred to under subsection (1) of this section, the successful bidder shall immediately give notice of the condition to the public contracting agency.

(4) Except in the case of an emergency and except as may otherwise be required by any environmental or natural resource regulation, the successful bidder shall not commence work nor incur any additional job site costs in regard to the condition encountered and described in subsection (3) of this section without written direction from the public contracting agency.

(5) Upon request by the public contracting agency, the successful bidder shall estimate the emergency or regulatory compliance costs as well as the anticipated delay and costs resulting from the encountered condition. This cost estimate shall be promptly delivered to the public contracting agency for resolution.

(6) Within a reasonable period of time, the public contracting agency may:

(a) Terminate the contract;

(b) Complete the work itself;

(c) Use nonagency forces already under contract with the public contracting agency;

(d) Require that the underlying property owner be responsible for cleanup;

(e) Go out to bid for a new contractor to provide the necessary services under the competitive bid requirements of ORS 279.015; or

(f) Issue the successful bidder a change order setting forth the additional work that must be undertaken.

(7) (a) If the public contracting agency chooses to terminate the contract under subsection (6)(a) of this section, the successful bidder shall be entitled to all costs and expenses incurred to the date of termination, including overhead and reasonable profits, on the percentage of the work completed. The awarding agency shall have access to the successful bidder's bid documents when making its determination of the additional compensation due to the successful bidder.

(b) If the public contracting agency causes work to be done by another contractor under subsection (1)(c) or (e) of this section or under subsection (6)(c) or (e) of this section, the successful bidder shall not be held liable for actions or omissions of the other contractor.

(c) The change order under subsection (1)(f) of this section or under subsection (6)(f) of this section shall include the appropriate extension of contract time and compensate the successful bidder for all additional costs, including overhead and profit, reasonably incurred as a result of complying with the applicable regulations. The awarding agency shall have access to the successful bidder's bid documents when making its determination of the additional compensation due to the successful bidder.

(8) Notwithstanding the provisions of this section, an awarding agency:

(a) *May allocate all or a portion of the known environmental and natural resource risks to a contractor by listing such environmental and natural resource risks with specificity in the bid documents; and*

(b) *In a local improvement district, may allocate all or a portion of the known and unknown environmental and natural resource risks to a contractor by so stating in the bid documents.*

Pursuant to ORS 279.318, the Agency has compiled a list at 00170.01 of those federal, State and local agencies, of which the Agency has knowledge, that have enacted ordinances or regulations dealing with the prevention of environmental pollution and the preservation of natural resources that may affect the performance of Agency contracts.

00140.60 Extra Work - If directed by the Engineer's written order, the Contractor shall perform work not included in the Contract. The Contractor shall perform this work according to:

- Standard Specifications
- Supplemental Specifications, if any
- Other Plans and Specifications issued by the Engineer

Payment for Extra Work will be governed by Section 00196. Contract Time adjustments, if any, will be governed by 00180.80.

00140.65 Disputed Work - The Contractor may dispute any part of a Change Order, written order, or an oral order from the Engineer by the procedures set forth in Section 00199.

00140.70 Cost Reduction Proposals - The Contractor may submit written proposals to the Engineer that modify Plans, Specifications, or other Contract Documents for the sole purpose of reducing the total cost of construction.

(a) Proposal Requirements - The Agency will not adopt a cost reduction proposal that impairs essential functions or characteristics of the Project including but not limited to service life, economy of operation, ease of maintenance, designed appearance, or design and safety standards.

To conserve time and funds, the Contractor may first submit a written request for a feasibility review by the Engineer. The request should contain a description of the proposal together with a rough estimate of anticipated dollar and time savings. The Engineer will, within a reasonable time, advise the Contractor in writing whether or not the proposal would be considered by the Agency, should the Contractor elect to submit a detailed cost reduction proposal.

A detailed cost reduction proposal shall include without limitation the following information:

- A description of existing Contract requirements for performing the Work and the proposed change;
- The Contract items of Work affected by the proposed change, including any quantity variation caused by the proposed change;
- Pay Items affected by the proposed change including any quantity variations;
- A detailed cost estimate for performing the Work under the existing Contract and under the proposed change. Cost estimates shall be based on a force account payment basis. Costs of re-design, which are incurred after the Agency has accepted the proposal, will be included in the cost of proposed work; and

- A date by which the Engineer must accept the proposal in order to accept the proposed change without impacting the Contract Time or cost reduction amount.

(b) Continuing to Perform Work - The Contractor shall continue to perform the Work according to Contract requirements until the Engineer issues a Change Order incorporating the cost reduction proposal. If the Engineer fails to issue a Change Order by the date specified in the proposal, the proposal shall be deemed rejected.

(c) Consideration of Proposal - The Engineer is not obligated to consider any cost reduction proposal. The Agency will not be liable to the Contractor for failure to accept or act upon any cost reduction proposal submitted.

The Engineer will determine in its sole discretion whether to accept a cost reduction proposal as well as the estimated net savings in construction costs from the adoption of all or any part of the proposal. In determining the estimated net savings, the Engineer may disregard the Schedule of Items. The Engineer will establish prices that represent a fair measure of the value of Work to be performed or to be deleted as a result of the cost reduction proposal.

(d) Sharing Investigation Costs - As a condition for considering a Contractor's cost reduction proposal, the Agency reserves the right to require the Contractor to share in the Agency's costs of investigating the proposal. If the Agency exercises this right, the Contractor shall provide written acceptance of the condition to the Engineer. Such acceptance will authorize the Agency to deduct its share of investigation costs from payments due or that may become due to the Contractor under the Contract.

(e) Acceptance of Proposal Requirements - If the Contractor's cost reduction proposal is accepted in whole or in part, acceptance will be made by a Change Order that will include without limitation the following:

- Statement that the Change Order is made in accordance with 00140.70;
- Revised Plans and Specifications that reflect all modifications necessary to implement the approved cost reduction measures;
- Any conditions upon which the Agency's approval is subject;
- Estimated net savings in construction costs attributable to the approved cost reduction measures; and
- A payment provision pursuant to which the Contractor will be paid 50% of the estimated net savings amount as full and adequate consideration for performance of the Work of the Change Order.

The Contractor's cost of preparing the cost reduction proposal and the Agency's costs of investigating the proposal, including any portion paid by the Contractor, will be excluded from determination of the estimated net savings in construction costs. Costs of re-design, which are incurred after the Agency has accepted the proposal, will be included in the cost of the Work attributable to cost reduction measures.

If the Agency accepts the cost reduction proposal, the Change Order that authorizes the cost reduction measures will also address any Contract Time adjustment.

(f) Right to General Use - Once submitted, the cost reduction proposal becomes the property of the Agency. The Agency reserves the right to adopt the cost reduction proposal for general use without

00140.70(f)

additional compensation to the Contractor when it determines that a proposal is suitable for application to other contracts.

00140.80 Use of Publicly Owned Equipment - The Contractor is prohibited from using publicly-owned Equipment except in the case of emergency. In an emergency, the Contractor may rent publicly-owned Equipment provided that:

- The Engineer provides written approval that states that such rental is in the public interest; and
- Rental does not increase the Project cost.

00140.90 Final Trimming and Cleanup - Before Final Inspection as described in 00150.90, the Contractor shall neatly trim and finish the Project and remove all remaining unincorporated Materials and debris. Final trimming and cleanup shall include without limitation the following:

- The Contractor shall retrim and reshape earthwork, and shall repair deteriorated portions of the Project Site.
- Where the Work has impacted existing facilities or devices, the Contractor shall restore or replace those facilities to their pre-existing condition.
- The Contractor shall clean all drainage facilities and sanitary sewers of excess Materials or debris resulting from the Work.
- The Contractor shall clean up and leave in a neat, orderly condition, Rights-of-Way, Materials sites, and other property occupied in connection with performance of the Work.
- The Contractor shall remove temporary buildings, construction plants, forms, falsework and scaffolding, surplus and discarded Materials, and rubbish.
- The Contractor shall dispose of Materials and debris including without limitation forms, falsework, scaffolding, and rubbish resulting from clearing, grubbing, trimming, clean-up, removal, and other Work. These Materials and debris become the property of the Contractor. The Contractor shall dispose of these Materials and debris immediately.

Unless the Contract specifically provides for payment for this item, the Agency will make no separate or additional payment for final trimming and cleanup.

Section 00150 - Control of Work

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

00150.00 Authority of the Engineer - The Engineer has full authority over the Work and its suspension. (See Section 00180.) The Contractor shall perform all Work to the complete satisfaction of the Engineer. The Engineer's determination shall be final on all matters, including but not limited to the following:

- Quality and acceptability of Materials and workmanship
- Measurement of unit price Work
- Timely and proper prosecution of the Work
- Interpretation of Plans and Specifications
- Payments due under the Contract

The Engineer's decision is final and, except as provided in 00180.80 for adjustments of Contract Time and Section 00199 for claims for additional compensation, may be challenged only through litigation.

Work performed under the Contract will not be considered complete until it has passed Final Inspection by the Engineer and has been accepted by the Agency.

Interim approvals issued by the Engineer, including but not limited to Third Notification, will not discharge the Contractor from responsibility for errors in prosecution of the Work, for improper fabrication, for failure to comply with Contract requirements, or for other deficiencies, the nature of which are within the Contractor's control.

00150.01 Project Manager's Authority and Duties - The Engineer may designate a Project Manager as its representative on the Project with authority to enforce the provisions of the Contract.

When the Engineer has designated a Project Manager, the Contractor should direct all requests for clarification or interpretation of the Contract, in writing, to the Project Manager. The Project Manager will respond within a reasonable time. Contract clarification or interpretation obtained from persons other than the Project Manager will not be binding on the Agency.

The Project Manager shall have the authority to appoint Inspectors and other personnel as required to assist in the administration of the Contract.

00150.02 Inspectors' Authority and Duties - To the extent delegated under 00150.01, Inspectors are authorized to represent the Engineer and Project Manager to perform the following:

- Inspect Work performed and Materials furnished, including without limitation, the preparation, fabrication, or manufacture of Materials to be used;
- Orally reject defective Materials and to confirm such rejection in writing;
- By oral order, temporarily suspend the Work for improper prosecution pending the Engineer's decision; and
- Exercise additional delegated authority.

Inspectors are not authorized to:

- Accept Work or Materials.

00150.02

- Alter or waive provisions of the Contract.
- Give instructions or advice inconsistent with the Contract Documents.

00150.10 Coordination of Specifications and Plans - The Special Provisions, the Plans, Supplemental Specifications (if any), and the Standard Specifications are intended to collectively describe all of the items of Work necessary to complete the Project.

(a) Order of Precedence - The Engineer will resolve any discrepancies between these documents in the following order of precedence:

- Special Provisions;
- Agency-prepared drawings specifically applicable to the Project and bearing the Project title;
- Reviewed, stamped Working Drawings;
- Standard Drawings;
- Approved Unstamped Working Drawings;
- Supplemental Specifications (if any); and
- Standard Specifications.

Notes on a drawing shall take precedence over drawing details.

Dimensions shown on the drawings, or that can be computed, shall take precedence over scaled dimensions.

(b) Immaterial Discrepancies - The Specifications and Plans set forth details for the construction and completion of the Work. If Specifications or Plans describe portions of the Work in sufficient detail but are silent in some minor respect, the Contractor may proceed utilizing the current best industry practices.

(c) Material Discrepancies - If the Contractor identifies a discrepancy, error, or omission in the Specifications or Plans that cannot be resolved by the approach set forth in (b) above, the Contractor shall immediately request clarification from the Engineer.

00150.15 Construction Stakes, Lines and Grades:

(a) General - The Contractor shall perform no Work until the Engineer establishes field controls. Work performed without field controls will be subject to removal at the Contractor's expense.

(b) Agency Responsibilities - The Engineer will:

- Lay out and set construction stakes and marks to establish the lines, grades, Slopes, Cross Sections, and curve super-elevations for roadwork;
- Provide one set of construction stakes for line and grade for each additional phase of the Work;
- Set bench marks and stakes for centerline of Bridges and bents;

- Calculate and provide finish deck grades; and
- Deduct from payments due the Contractor all costs incurred to replace stakes and marks negligently or intentionally damaged, removed, or destroyed by the Contractor.

(c) Contractor Responsibilities - The Contractor shall:

- Inform the Engineer of staking requirements at least five Calendar Days before the staking needs to begin;
- Coordinate construction to provide sufficient area for the Engineer to perform surveying work efficiently and safely;
- Accurately measure detailed dimensions, elevations, and Slopes from the Engineer's stakes and marks;
- Perform the Work in such a manner as to preserve stakes and marks; and
- Set any reference lines for automatic control from the control stakes provided by the Engineer.

00150.20 Inspection:

(a) Inspection by the Engineer - The Engineer may test Materials furnished and inspect Work performed by the Contractor to ensure Contract compliance.

If the Contractor performs Work without the Engineer's inspection or uses Materials that the Engineer has not approved, the Engineer may order affected portions of the Work removed at the Contractor's expense. The foregoing sentence shall not apply if the Engineer fails to inspect the Work within a specific period of time required in the Contract or in the absence of a specific period of time, within a reasonable period of time after receiving the Contractor's timely written request for inspection or testing.

At the Engineer's direction, any time before the Work is accepted, the Contractor shall uncover portions of the completed Work for inspection. After inspection, the Contractor shall restore these portions of Work to the standard required by the Contract. If the Engineer rejects Work due to Materials or workmanship, or if the Contractor performed such Work without providing sufficient advance request for inspection to the Engineer, the Contractor shall bear all costs of uncovering and restoring the Work. If the Engineer accepts the uncovered Work, and the Contractor performed the Work only after providing the Engineer with sufficient advance notice, the costs of uncovering and restoring the Work will be paid for by the Agency as Extra Work.

(b) Inspection Facilities - The Contractor shall furnish walkways, railings, ladders, tunnels, platforms and other facilities necessary to permit the Engineer to have safe access to the Work to be inspected. The Contractor shall require producers and fabricators to provide safe inspection access as requested by the Engineer.

(c) Sampling - The Contractor shall furnish the Engineer with samples of Materials that the Engineer will test. All of the Contractor's costs related to this required sampling are Incidental.

(d) Inspection by Third Parties - Where third parties have the right to inspect the Work, the Contractor shall coordinate with the Engineer and shall provide safe inspection access.

(e) Contractor's Duty to Make Corrections - The Contractor shall perform all Work according to the Specifications and Plans. The Contractor shall correct Work that does not comply with the Specifications and Plans at its own expense. Inspection of the Work by the Engineer does not relieve the Contractor of responsibility for improper prosecution of the Work.

00150.25 Acceptability of Materials and Work - The Contractor shall furnish Materials and shall perform Work in Close Conformance to the Plans and Specifications. If the Engineer determines that the Materials furnished or the Work performed are not in Close Conformance with the Plans and Specifications, the Engineer may:

- Reject the Materials or Work and order the Contractor, at the Contractor's expense, to remove, replace, or otherwise correct any non-conformity; or
- Accept the Materials or Work as suitable for the intended purpose, adjust the amount paid for applicable Pay Items to account for diminished cost to the Contractor or diminished value to the Agency, document the adjustment, and provide written documentation to the Contractor regarding the basis of the adjustment.

The Engineer's decisions concerning acceptability of Materials or Work will be final.

00150.30 Delivery of Notices - Written notices to the Contractor, the Engineer, or the Agency shall be delivered via first class mail, or in person to the current office address as shown in the records of the Agency. Notices delivered via first class mail shall be deemed delivered five business days following the postmarked date.

00150.35 Plans and Working Drawings:

(a) Plans - The Plans will show details of lines, grades, and Typical Section of the Roadway, and locations and design details of Structures.

(b) Working Drawings - The Contractor shall supplement the Agency-prepared Plans with stamped or unstamped Working Drawings that show all information necessary to complete the Work. The applicable Section or Subsection of the Standard Specifications will indicate the supplemental information required and whether the drawings are to be stamped or unstamped. Stamped and unstamped Working Drawings are defined as follows:

(1) Stamped Working Drawings - Working Drawings, calculations and other data which are prepared by or under the direction of a Professional Engineer licensed in the State of Oregon, and which bear the engineer's signature, seal, and expiration date.

(2) Unstamped Working Drawings - Working Drawings, calculations and other data that do not bear an engineering seal.

(c) Number and Size of Drawings - The Contractor shall submit seven copies of Working Drawings for steel Structures and six copies of Working Drawings for other Structures to the Engineer. The submitted copies shall be clear and readable. Drawing dimensions shall be 215 mm x 279 mm (8 1/2 inches by 11 inches), 279 mm x 431 mm (11 inches by 17 inches) or 558 mm x 914 mm (22 inches by 36 inches) in size. One copy of the submitted Working Drawings will be returned to the Contractor after processing. The Contractor shall submit such additional number of copies to the Engineer for processing that the Contractor would like to have returned.

(d) Processing Working Drawings - The Engineer will process Working Drawings and include all comments on them as follows:

(1) Stamped Working Drawings - Stamped Working Drawings will be designated as "reviewed" or "reviewed with comment" by the Engineer.

(2) Unstamped Working Drawings - Unstamped Working Drawings will be designated on the face of the Drawing, as "approved", "approved as noted", "returned for correction", or "rejected" by the Engineer.

The Contractor shall not fabricate or construct any structural components until the stamped or unstamped Working Drawings are returned by the Engineer with written notation of approval or review, as applicable, of the Working Drawings.

The Engineer's processing of the Working Drawings does not amend any contractual obligations of the parties.

The Engineer will process and return Working Drawings within 21 Calendar Days (65 Calendar Days if Railroad approval is required) after receipt by the Engineer. If the Engineer fails to return such drawings within this period of time, the Engineer will consider granting a Contract Time extension according to 00180.80.

00150.37 Equipment Lists and Other Submittals - The Contractor shall submit Equipment lists, and other required submittals for approval by the Engineer. The Engineer will respond to requests for approval within time frames set forth in each Section of the Specifications that requires such approval.

00150.40 Cooperation and Superintendence by the Contractor:

(a) General - The Contractor shall:

- Keep one complete set of Contract Documents available on the Project Site at all times.
- Cooperate in good faith with the Engineer, Inspectors, and other contractors in performance of the Work.
- Designate, from the Contractor's organization, a competent superintendent experienced in the type of Work being performed, and capable of reading and thoroughly understanding the Plans and Specifications.
- Provide access, facilities and assistance to the Engineer in establishing such lines, grades and points as the Engineer requires.
- Carefully protect and preserve the Engineer's marks and stakes.
- Provide all assistance reasonably required by the Engineer to obtain information regarding the nature, quantity, and quality of any part of the Work.
- Allow the Engineer reasonable access to the Contractor's books and records at all times. To the extent permitted by public records laws, the Engineer will make reasonable efforts to honor the Contractor's request for protection of confidential information.
- Furnish the Engineer all data necessary to determine the actual cost of all, or any part, of the Work.
- Diligently pursue progress of the Work according to the schedule requirements of Section 00180.
- Coordinate and control all Work performed under the Contract, including without limitation the Work performed by Subcontractors.

(b) Superintendence - The Contractor shall appoint the superintendent described under 00150.40(a), in writing. The superintendent shall:

- Have full authority and responsibility to promptly execute orders or directions of the Engineer,

00150.40(b)

- Have full authority and responsibility to promptly supply the Materials, Equipment, labor, and Incidentals required for performance of the Work,
- Be available during the hours of work on the Project Site for communication with the Engineer, and
- Be present for all On-Site Work except as provided in the Contract Documents.

For short periods of time during the performance of minor or Incidental portions of the Work, the Contractor may designate a person to act on behalf of the superintendent. The Contractor shall submit the designation in writing to the Engineer. The form of designation shall state the designee's name, duration of appointment, and scope of authority. The superintendent shall be available to the Engineer at all times for contact by telephone or radio. The Engineer expressly reserves the right to require the superintendent to be on the Project Site by giving 48 hours advance verbal or written notice thereof to the Contractor.

The Contractor's failure to provide the superintendence required by these provisions constitutes a material breach of the Contract, and the Engineer may impose any remedies available under the Contract, including but not limited to Contract termination or suspension of Contract performance.

00150.50 Cooperation with Utilities:

(a) General - Unless otherwise set forth in any Supplemental Specifications, in the Special Provisions, or on the Plans, existing Utilities requiring adjustment may be adjusted by the Utility before, during, or after Project construction. "Adjustment of Utilities" shall mean the alteration, improvement, connection, disconnection, relocation, or removal of existing Utility lines, facilities, or systems in temporary or permanent manner.

(b) Agency Responsibilities - Before Bids are received, the Agency will make preliminary arrangements for planned Adjustment of Utilities. The Agency will list in the Special Provisions the estimated completion dates or times for adjustment work by the Utility owner, and will include a general statement describing any relocation. The Plans will not normally show the anticipated new location of Utilities that have been or will be adjusted.

(c) Contractor's Responsibilities - The Contractor shall:

- Follow applicable rules adopted by the Oregon Utility Notification Center;
- Contact Utility owners during Bid preparation and after the Contract is awarded to verify all Utilities involvement on the Project Site;
- Coordinate Project construction with the Utilities' planned adjustments, take all precautions necessary to prevent disruption of Utility service, and perform its Work in the manner that results in the least inconvenience to the Utility owners;
- Include all Utility adjustment work, whether to be performed by the Contractor or the Utilities, on the Contractor's Project Work schedule submitted under 00180.41;
- Protect from damage or disturbance any Utility that remains within the area in which Work is being performed;
- Not disturb an existing Utility if it requires an unanticipated adjustment, but shall protect it from damage or disturbance and promptly notify the Engineer; and

- Report to the Engineer any Utility owner who fails to cooperate or fails to follow the planned Utility adjustment.

Subject to the Engineer's approval, the Contractor may adjust the Utilities by asking the Utility owners to move, remove, or alter their facilities in ways other than as shown on the Plans, in any Supplemental Specifications, or in the Special Provisions. The Contractor shall conduct all negotiations, make all arrangements, and assume all costs that arise from such changes.

(d) Delays - If the Contractor complies with Subsection (c) above, and if Utility adjustments are completed later than the date specified in the Special Provisions, thus causing Contract completion to be delayed, additional Contract Time will be considered under 00180.80, and additional compensation, if applicable, will be considered under 00195.40.

(e) Notification - If the Project is located within the area served by the Oregon Utility Notification Center, the Contractor shall notify owners of Utilities prior to the performance of Work in the vicinity of their facilities. The Utilities notification system telephone number is 1-800-332-2344.

The Contractor shall comply with OAR 952-001-0010 through 952-001-0090 and ORS 757.993. The Contractor may contact the Oregon Utility Notification Center at (503) 232-1987 about these rules.

**Oregon Administrative Rules 2001
Chapter 952, Division 1
Oregon Utility Notification Center**

**DIVISION 1
952-001-0010
Definitions**

(1) "Abandoned Facility" means an underground facility that is no longer in service and is physically disconnected from the operating facility that is in service.

(2) "Business day" means any 24-hour day other than a Saturday, Sunday or federal or state legal holiday.

(3) "Damage" means harm to, or destruction of underground facilities including, but not limited to, the weakening of structural, lateral or subjacent support; the penetration, impairment or destruction of any coating, housing or other protective device; or the denting of, penetration into or severance of underground facilities.

(4) "Designer" means any person who prepares a drawing for construction or other project which requires excavation or demolition.

(5) "Emergency" means an occurrence involving an immediate danger, demanding prompt action to prevent loss of life, or to mitigate damage to property, or to prevent interruption of essential public services (as determined by an emergency response agency or the facility operator) or to prevent a customer service outage (as determined by the facility operator).

(6) "Excavation" means any operation in which earth, rock or other material on or below the ground is moved or otherwise displaced by any means, except sidewalk, road and ditch maintenance less than 12 inches in depth that does not lower the original grade or original ditch flow line. "Excavation" does not include the tilling of soil for agricultural purposes, as defined in ORS 215.203(2), conducted on private property that is not within the boundaries of a recorded right-of-way or easement for underground facilities.

(7) "Excavator" means any person who engages in excavation.

- (8) *"Locatable underground facilities" means underground facilities which can be marked with reasonable accuracy.*
- (9) *"Mark" or "marking" means an indication, from the use of stakes, paint or other clearly identifiable material, to show the field location or absence of underground facilities at a proposed work site. A "mark" or "marking" also includes permanent marking devices, such as disks, posts or signs, placed to show the location of underground facilities.*
- (10) *"Operator" means any person, municipal corporation, political subdivision of the state with control over underground facilities. Operator includes any person, as defined in ORS 756.010, having the right to bury underground facilities in any public right-of-way, or in any utility easement.*
- (11) *"Oregon Utility Notification Center" (Center) means the state agency that administers a statewide system through which a person can notify operators of underground facilities of proposed excavations and can request that the underground facilities be marked.*
- (12) *"Out-of-service facility" means an underground facility that has not been declared permanently abandoned and may still be connected to a portion of an operating facility that is in service.*
- (13) *"Project plans" mean any drawings, specifications or any other documents prepared in anticipation of work involving excavation.*
- (14) *"Reasonable accuracy" means location, within twenty-four (24) inches, of the outside lateral dimensions of both sides of an underground facility.*
- (15) *"Response" means action taken by operators of underground facilities to:*
- (a) *Mark or identify by other means the location of its locatable underground facilities in the area of the proposed excavation;*
 - (b) *Notify the excavator that there are unlocatable underground facilities in the area of the proposed excavation;*
 - (c) *Notify the excavator that there are no underground facilities in the area of the proposed excavation; or*
 - (d) *Notify the excavator that there are underground facilities in the area of the proposed excavation which are at a depth greater than the proposed excavation.*
- (16) *"Underground facilities" means items partially or entirely below the surface of the ground for use in connection with the storage or conveyance of electrical energy, water, sewage, petroleum products, gas, gaseous vapors or hazardous liquids, or the transmission of electronic, telephonic, telegraphic or cable communications. Such items include, but are not limited to, pipes, sewers, conduits, cables, valves, lines, wires, manholes, attachments and those parts of poles or anchors that are underground.*
- (17) *"Unlocatable underground facilities" mean underground facilities that cannot be marked with reasonable accuracy, including nonconductive sewers and nonmetallic underground facilities that have no trace wires.*

952-001-0020**Project Plans to Notify Excavator of Requirements of Law**

All project plans shall contain the following statement: **ATTENTION:** Oregon law requires you to follow rules adopted by the Oregon Utility Notification Center. Those rules are set forth in OAR 952-001-0010 through OAR 952-001-0090. You may obtain copies of the rules by calling the center. (Note: the telephone number for the Oregon Utility Notification Center is (503) 232-1987).

952-001-0030**Permits to Notify Excavator of Requirements of Law**

Any entity authorized to issue permits for construction which requires excavation shall include on such permits the language set out in OAR 952-001-0020.

952-001-0040**Pre-Marking Required by the Excavator; Exemption**

(1) Except as provided in paragraph (2) of this rule, prior to notifying the Oregon Utility Notification Center, an excavator shall pre-mark with the color white the immediate area of the proposed excavation within both the public rights-of-way and underground easements.

(2) An excavator need not pre-mark as required in paragraph (1) of this rule if:

(a) The operator can determine precisely the direction, length and location of the proposed excavation by referring to a locate ticket; or

(b) The excavator and operator have had a meeting prior to the beginning of the proposed project, at the construction site for the exchange of information required under paragraph (1) of this rule.

952-001-0050**Excavator to Give Notice of Proposed Work; Exemption**

(1) Except as provided in paragraph (2) of this rule, at least two (2) business days, but not more than ten (10) business days before commencing an excavation, the excavator shall notify the Oregon Utility Notification Center of the date and location of the proposed excavation, and the type of work to be performed.

(2) The notice requirement of paragraph (1) of this section shall not apply if the excavation is in response to an emergency, or if all of the following apply:

(a) The excavator is a tenant or an owner of private property;

(b) The excavation is on private property of that owner or tenant;

(c) The excavation is less than twelve (12) inches in depth; and

(d) The excavation is not within an established easement.

(3) An excavator, when giving notice in compliance with paragraph (1) of this rule, shall furnish information as to how the excavator can be contacted.

952-001-0060

When Excavator May Give Less than Forty-Eight (48) Business Day Hour Notice

An excavator may provide less than two (2) business days (48) hours prior notice if:

- (1) The excavator is responding to an emergency, so long as the excavator notifies the Oregon Utility Notification Center immediately and so long as the excavator takes reasonable care to protect underground facilities;*
- (2) The excavator has an agreement with each operator of underground facilities that marks will be provided on a regular basis as the excavator progresses through a project; or*
- (3) The excavator discovers an underground facility in an area where the operator of underground facilities had previously indicated there were no facilities.*

952-001-0070

Operators to Mark Underground Facilities or Notify Excavator that None Exist

(1) Except as provided in paragraph (3) of the rule, within two business days (48 hours) after the excavator notifies the Oregon Utility Notification Center of a proposed excavation, the operator of the underground facilities shall:

(a) Mark with reasonable accuracy all of its locatable underground facilities within the area of proposed excavation. All marks shall indicate the name, initials or logo of the operator of the underground facilities, and the width of the facility if it is greater than two (2) inches;

(b) Provide the excavator the best description available to the operator of the unlocatable underground facilities in the area of the proposed excavation including as-constructed drawings, or other facility maps that are maintained by the facility operator;

(c) Notify the excavator that in the area of the proposed excavation there are underground facilities which are not marked because those facilities are at a depth greater than the excavator plans to excavate; or

(d) Notify the excavator that the operator does not have any underground facilities in the area of the proposed excavation.

(2) Operators of abandoned facilities shall mark said facilities to the standards of locatable facilities or unlocatable facilities.

(3) An operator shall mark any abandoned underground facility that is known to it with a capital letter "A" inside of a circle, using the appropriate operator color and identification.

(4) An operator of any out-of-service underground facility shall mark such facility in the same way it marks an underground facility that is in service.

(5) If an excavator uses offset marking, the excavator shall correctly measure the amount of offset, so that the excavator can reestablish the location of underground facilities where originally marked.

(6) If the excavator notifies the operator of underground facilities discovered during an excavation in response to an emergency, the operator of underground facilities shall comply with subsection (1) of this section as soon as possible.

(7) Underground facilities shall be marked in accordance with the following designated color code:

- (a) *RED - Electric power lines, cables or conduit, and lighting cables.*
 - (b) *YELLOW - Gas, oil, steam, petroleum, or other hazardous liquid or gaseous materials.*
 - (c) *ORANGE - Communications, cable TV, alarm or signal lines, cables or conduits.*
 - (d) *BLUE - Water, irrigation, and slurry lines.*
 - (e) *GREEN - Sewers, drainage facilities or other drain lines.*
 - (f) *WHITE - Pre-marking of the outer limits of the proposed excavation or marking the centerline **and** width of proposed lineal installations of buried facilities.*
 - (g) *PINK - Temporary Survey Markings.*
- (8) *In areas of ongoing excavation or construction operators shall mark newly installed underground facilities immediately upon placement.*
- (9) *Except while making minor repairs to existing non-conductive, unlocatable facilities, an operator burying non-conductive, unlocatable facilities within the public rights-of-way or utility easements shall place a tracer wire or other similar conductive marking tape or device with the facility to allow for later location and marking.*
- (10) *An operator of underground drainage lines is not required to indicate the presence of those facilities if the existence and route of those facilities can be determined from the presence of other visible facilities, such as manholes, catch basins, inlets, outlets, junction boxes, storm drains or permanent marking devices.*

952-001-0080

Operators to Respond to Notifications Requesting Design Information

Within ten (10) business days after a designer notifies the Oregon Utility Notification Center of a proposed project, the operator of the underground facilities shall:

- (1) *Mark with reasonable accuracy all of its locatable underground facilities within the area of proposed excavation. All marks shall indicate the name, initials or logo of the operator of the underground facilities, and the width of the facility if it is greater than two (2) inches;*
- (2) *Provide the excavator the best description available to the operator of the unlocatable underground facilities in the area of the proposed excavation including as-constructed drawings, or other facility maps that are maintained by the facility operator; or*
- (3) *Contact the person requesting design information and agree on a time, prior to the beginning of the proposed project, for exchange of the information required under paragraph (1) or paragraph (2) of this rule.*

952-001-0090

Delay of Excavation Until Response from Facility Operators; Duty of Excavator to Use Reasonable Care; Damage to Facilities

- (1) *An excavator shall not commence an excavation which requires notice under these rules until the excavator has received a response from each operator of underground facilities in the area of the proposed excavation, or until at least two (2) business days (48 hours) have elapsed from the time the excavator notified the Oregon Utility Notification Center.*

(2) *Once underground facilities have been marked, the excavator shall:*

(a) *Maintain marks during the excavation period to ensure that the original marks remain effective for the life of the project and can be re-established;*

(b) *Stop excavating in the vicinity of the underground facility and notify the Oregon Utility Notification Center to have the route re-marked as specified in these rules and, if prior to or during the excavation process, the marking and/or route of any underground facility is removed or no longer visible; and*

(c) *Employ hand tools or other such non-invasive methods to determine the exact location of the underground facility when excavation is to be made within the reasonable accuracy zone.*

(3) *The excavator shall provide such lateral and subjacent support for underground facilities as may be reasonably necessary for the protection of such facilities.*

(4) *If the excavator causes or observes damage to underground facilities, the excavator shall notify the operator of the underground facilities immediately. If the damage causes an emergency, the excavator shall also notify all appropriate local public safety agencies immediately by calling 911 and shall take reasonable steps to insure the public safety. The excavator shall not bury damaged underground facilities without the consent of the operator of the damaged underground facilities.*

(5) *If an excavator discovers underground facilities in an area where the operator of the underground facilities had previously stated there were no underground facilities, the excavator shall, prior to continuing excavation, notify the Oregon Utility Notification Center. After providing notification, the excavator shall use extreme care in the affected area.*

952-001-0100

Record Keeping Requirements

(1) *Abandoned Facilities: Except as provided in Section (3) of this rule, all operators shall maintain records, by mapping or other means, of all underground facilities abandoned on or after April 1, 2002, that show:*

(a) *The location of such facility to the level of detail when abandoned;*

(b) *The date of abandonment of such facility; and*

(c) *Whether each such facility is a locatable underground facility or an unlocatable underground facility.*

(2) *Out-of-Service Facilities: Except as provided in Section (3) of this rule, all operators shall maintain records, by mapping or other means, of all underground facilities placed in out-of-service status on or after April 1, 2002, that show:*

(a) *The location of such facility to the level of detail when placed in out-of-service status;*

(b) *The date of abandonment of such facility; and*

(c) *Whether each such facility is a locatable underground facility or an unlocatable underground facility.*

(3) *These record keeping requirements do not apply to operators who provide telecommunications, CATV or electric service for the underground facilities located between the operator's system and the customer's point of service.*

**Oregon Revised Statues 2001
Excerpt from Chapter 757
Oregon Utility Notification Center**

757.993 Penalty for violation of utility excavation notification provisions.

(1) Except as provided in subsection (2) of this section and in addition to all other penalties provided by law, every person who violates or who procures, aids or abets in the violation of any rule of the Oregon Utility Notification Center shall incur a penalty of not more than \$1,000 for the first violation and not more than \$5,000 for each subsequent violation.

(2) In addition to all other penalties provided by law, every person who intentionally violates or who intentionally procures, aids or abets in the violation of any rule of the Oregon Utility Notification Center shall incur a penalty of not more than \$5,000 for the first violation and not more than \$10,000 for each subsequent violation.

(3) Each violation of any rule of the Oregon Utility Notification Center shall be a separate offense. In the case of a continuing violation, each day that the violation continues shall constitute a separate violation.

(4) Penalties under this section shall not be imposed except by order following complaint as provided in ORS 756.500 to 756.610. A complaint must be filed within two years following the date of the violation.

(5) The Public Utility Commission may reduce any penalty provided in this section on such terms as the commission considers proper if:

(a) The defendant admits to the violation or violations alleged in the complaint and makes a timely request for reduction of the penalty; or

(b) The defendant submits to the commission a written request for reduction of the penalty within 15 days from the date of the penalty order.

(6) If the amount of the penalty is not paid to the commission, the Attorney General, at the request of the commission, shall bring an action in the name of the State of Oregon in the Circuit Court for Marion County to recover the penalty. The action shall not be commenced until after the time has expired for an appeal from the findings, conclusions and order of the commission.

(7) Notwithstanding any other provision of law, the commission shall pay penalties recovered under this section to the Oregon Utility Notification Center.

(8) The commission shall not seek penalties under this section except in response to a complaint alleging a violation of a rule or rules adopted by the Oregon Utility Notification Center. The commission may investigate any such complaint, and the commission shall have sole discretion to seek penalties under this section.

00150.55 Cooperation with Other Contractors - The Agency reserves the right to perform other work on or near the Project Site, including without limitation any Materials site, with forces other than those of the Contractor.

If such work takes place within or next to the Project Site, the Contractor shall have the following obligations:

- The Contractor shall coordinate Work with other contractors or forces.

- The Contractor shall cooperate in good faith with all other contractors or forces.
- The Contractor shall perform the Work set forth in the Contract in a way that will minimize interference and delay for all forces involved.
- The Contractor shall place and dispose of the Materials being used so as not to interfere with the operations of other forces.
- The Contractor shall join the Work with that of other forces in a manner acceptable to the Engineer or the Agency, and shall perform it in the accepted sequence with the work of the other force.

The Engineer will resolve any disagreements under this Subsection that may arise among the Contractor and other work forces, or between the Contractor and the Agency. The Engineer's decision in these matters is final, as provided in 00150.00.

When the schedules for Work of the Contractor and the work of other forces overlap, each contractor involved shall submit a current, realistic progress schedule to the Engineer. Before the Engineer accepts the schedule, each party shall have the opportunity to review all schedules. After this review and any necessary consultations, the Engineer will determine acceptable schedules.

The Contractor waives any right it may have to make claims against the Agency for any damages or claims that may arise because of inconvenience, delay, or loss due solely to the presence of other contractors working on the Project Site.

If the Contract gives notice of work to be performed by other forces that may affect the Contractor's Work under the Contract, the Contractor shall include any costs associated with coordination of the Work in the appropriate Pay Item or as a portion of a Pay Item.

In an emergency, the contractor most immediately able to respond may repair a facility or Utility of another contractor in order to prevent further damage to the facility, Utility, or other Structure as a result of the emergency.

00150.60 Construction Equipment Restrictions:

(a) Load and Speed Restrictions for Construction Vehicles and Equipment - The Contractor shall comply with legal mass (weight) and speed restrictions when moving Materials or Equipment beyond the limits of the Project Site.

The Contractor shall control vehicle and Equipment loads and speeds within the Project Site according to the following restrictions, unless the Special Provisions provide otherwise:

- The Contractor shall restrict loads and speeds as necessary to avoid displacement or loss of Materials on Subgrades and Aggregate Bases.
- The Contractor shall restrict masses (weights) to legal loads, and shall travel at speeds of no more than 70 km/h (45 mph) or the posted construction speed, whichever is less, on treated Bases, Pavement, or wearing Courses.
- The Contractor shall not cross Bridges or other Structures with Equipment or vehicles exceeding the legal load limit without prior written permission of the Engineer. The Contractor shall make any such request in writing, describing the loading details and the arrangement, movement, and position of the Equipment on the Structure. The Contractor shall comply with any restrictions or conditions included in the Engineer's written permission.

(b) Protection of Buried Items - The Contractor shall use temporary fill or other methods to avoid overload of pipes, box culverts, and other items that are covered, or to be covered, by fill or backfill.

(c) Responsibility for Damages - The Contractor shall assume responsibility for damages caused by excessive Equipment speed or loads while performing the Work, both inside and outside the Project Site. The Engineer's permission to cross Bridges and other Structures, according to 00150.60(a) will not relieve the Contractor from responsibility for load-caused damages.

00150.70 Detrimental Operations - The Contractor shall avoid operations whose methods, conditions, or timing may injure people or damage property or the Work. Damage may include without limitation, staining surfaces with mud or asphalt. See also 00150.60, 00150.75, and Section 00170.

When any such damage occurs, the Engineer will determine if it is to be corrected by repair, replacement, or compensatory payment by the Contractor. If compensatory payment is required, the Engineer will determine the amount. Compensatory payment may be deducted from monies due or to become due to the Contractor under the Contract.

00150.75 Protection and Maintenance of Work During Construction - The Contractor shall protect and maintain the Work during construction and until Third Notification has been issued, unless otherwise provided in the Contract. For the purposes of this Subsection, "maintenance" shall include measures to prevent deterioration of Roadway and Structures at the Project Site, and to keep them in good condition at all times during the prosecution of the Work. The Contractor shall continuously allocate sufficient Equipment and workers to achieve such maintenance.

If the Contract requires the placement of a Course upon a previously constructed Course or Subgrade, the Contractor shall maintain the previous Course or Subgrade during all construction operations.

The Contractor shall include costs of protecting and maintaining the Work during construction in the unit prices bid for the various Pay Items. The Contractor will not be paid an additional amount for this Work, unless otherwise specified.

The Engineer will immediately notify the Contractor of Contractor's noncompliance with this Subsection 00150.75. If the Contractor fails to remedy unsatisfactory protection or maintenance within 24 hours after receipt of such notice, the Engineer may proceed immediately to remedy the deficiency, and deduct the entire cost from monies due or to become due the Contractor under the Contract.

00150.80 Removal of Unacceptable and Unauthorized Work - The Contractor shall correct or remove unacceptable Work, as directed by the Engineer in writing. The Contractor shall replace such work with Work and Materials conforming to the requirements of the Contract.

For the purposes of this Subsection, "unauthorized work" shall include without limitation the following:

- Work that extends beyond lines shown on the Plans or otherwise established by the Engineer;
- Work that is contrary to the Engineer's instructions; and
- Work that is conducted without the Engineer's written authorization.

The Agency will not pay the Contractor for unauthorized or unacceptable work. The Engineer may issue a written order for the correction or removal of such work at the Contractor's expense.

If, when ordered by the Engineer, the Contractor fails to correct or remove unacceptable or unauthorized work, the Engineer may have the correction, or removal and replacement, done by others and deduct the entire cost from monies due or to become due the Contractor under the Contract.

00150.90 Final Inspection:

(a) On-site Construction Work - The Engineer will inspect the Project at a time close to the completion of On-Site Work to ensure the Contractor's compliance with the Plans and Specifications.

When all On-Site Work on the Project is completed, including but not limited to Change Order Work and Extra Work, the Engineer will issue Second Notification as specified in 00180.50(g).

Within 15 Calendar Days after the Engineer receives the Contractor's written notification that all punch list items, final trimming and cleanup according to 00140.90 have been completed, the Engineer will review the Project and notify the Contractor that all Work is complete, or will give the Contractor written instruction regarding incomplete or unsatisfactory Work.

(b) All Contract Work - The Engineer will issue the Third Notification when the Contractor has satisfactorily accomplished all of the following:

- The Contractor has completed all On-Site Work required under the Contract;
- The Contractor has removed all Equipment; and
- The Contractor has submitted all required certifications, bills, forms, warranties and other documents.

00150.95 Final Acceptance - After the Engineer completes Final Inspection of all Work and sends Third Notification to the Contractor, the Agency will acknowledge Final Acceptance. The Agency will notify the Contractor in writing of the date of Final Acceptance within seven Calendar Days after Final Acceptance, or as soon thereafter as is practicable.

00150.96 Maintenance Warranties and Guarantees - Prior to Third Notification, the Contractor shall transfer to the Agency all unexpired manufacturers' warranties and guarantees for Materials and Equipment installed on the Project. Such warranties and guarantees shall recite that they are enforceable by the Agency.

00150.97 Responsibility for Materials and Workmanship:

(a) As stated in the Performance Bond, the Contractor shall perform the Work according to the terms, conditions, requirements, Plans, and Specifications set out in the Contract.

(b) Whether before or after the Agency's acceptance of the Work, the Contractor shall be responsible for:

- Correcting or repairing any defects in, or damage to, the Work which results from the use of improper materials or workmanship; or
- Replacing, in its entirety, the Work affected by the use of improper materials or workmanship to the extent provided by law; and

Correcting or repairing any Work, Materials, Structures, Existing Surfacing, Pavement, Utilities, or sites, including without limitation Wetlands, damaged or disturbed in that correction, repair, or replacement. (See 00170.80 to 00170.85.)

Section 00160 - Source of Materials

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

00160.00 Definitions - The following definitions apply to Section 00160:

(a) Prospective Source - Agency-furnished Materials source, use of which by the Contractor is optional. The Agency makes no guarantee or representation, by implication or otherwise, of the land use status, quantity, quality, or acceptability of Materials available from it, except as may be stated in the Special Provisions.

(b) Mandatory Source - Agency-furnished Materials source, use of which by the Contractor is required.

00160.01 Notification of Source of Supply and Materials:

(a) All Materials - The Contractor shall notify the Engineer in writing of all proposed Materials sources of supply, including without limitation any steel or other fabricators within the following time frames:

- At least 15 Calendar Days before using or fabricating Materials, if source is within the State, or
- At least 45 Calendar Days before using or fabricating Materials, if source is outside the State

(b) Prospective Source Materials - When given an option to use Prospective Sources of Materials to be incorporated into the Work, the Contractor shall notify the Engineer in writing of the option selected within 15 Calendar Days from date of Notice to Proceed. Otherwise, such Materials sources may become unavailable.

(c) Approval Required - Before allowing production or delivery of Materials to begin from any source, the Contractor must obtain the Engineer's approval. Approval to use any source does not imply that Materials from that source will be accepted. If approved sources do not provide Materials that meet Specifications, the Materials will be rejected. The Contractor will then be responsible for locating other sources and obtaining the Engineer's approval.

00160.05 Qualified Products List (QPL) - The QPL is a listing of manufactured products available on the market (shelf items) that ODOT has evaluated and found suitable for a specified use in highway construction. The QPL is published twice a year and is available from ODOT's Construction Section; 800 Airport Road SE, Salem, OR 97301-4798; phone (503) 986-3000. It may also be viewed on ODOT's web site.

The current version of the QPL at the time of Award is the version in effect for the Project. The Engineer may approve for use a conditionally qualified product, or a product qualified for inclusion in a later edition of the QPL, if the Engineer finds the product acceptable for use on the Project.

Use of listed products shall be restricted to the category of use for which they are listed. The Contractor shall install all products as recommended by the manufacturer. The Contractor shall replace qualified products not conforming to Specifications or not properly handled or installed at the Contractor's expense.

00160.10 Ordering, Producing, and Furnishing Materials:

(a) Contractor's Duties - In purchasing, producing, or delivering Materials, the Contractor shall take into account the following:

00160.10(a)

- Kind of work involved;
- Amount of work involved;
- Time required to obtain Materials; and
- Other relevant factors.

The Contractor shall not place orders for or produce full quantities of Materials anticipated to be required to complete the Work until the Work has advanced to a stage that allows the quantities to be determined with reasonable accuracy. Upon request, the Engineer will notify the Contractor in writing of the quantities required. Quantity estimates by the Engineer before this notification are only approximate.

(b) Approval of Quantity of Materials Ordered - Materials quantities shown on the Plans, or indicated by quantities and Pay Items, are subject to change or elimination. Therefore, the Contractor is cautioned to order or produce Materials only after having received the approval of the Engineer. The Contractor is responsible for payment for excess Materials delivered to the Project Site or storage sites without advance authorization from the Engineer. Unless otherwise specified in the Contract, the Agency will not be responsible for:

- Materials the Contractor may deliver or produce in excess of Contract requirements;
- Extra expense the Contractor may incur because Materials were not ordered or produced earlier; or
- The Contractor's expenses related to Materials ordered by the Contractor that are not subsequently approved for use.

Any Allowance made to the Contractor for excess Materials will be at the sole discretion of the Engineer.

00160.20 Preferences for Materials:

(a) Buy America - If federal highway funds are involved on the Project, the Contractor shall limit the quantity of foreign Materials incorporated into the Work as follows. Section 635.410 of Title 23, Code of Federal Regulations, and the Intermodal Surface Transportation Efficiency Act require that all iron or steel manufacturing processes, including without limitation the casting of ingots, for iron or steel Materials permanently incorporated into the Project shall occur in the United States, unless the cost of foreign-origin iron or steel Materials does not exceed one-tenth of one percent (0.1%) of the Contract Amount or \$2,500, whichever is greater. The Contractor shall not incorporate foreign-origin iron or steel Materials in excess of this amount into the Project. For purposes of this Specification, the cost of foreign-origin iron or steel Materials shall be the value of the iron or steel products as of the date they are delivered to the Project Site.

Manufacturing processes include without limitation the application of coatings to finished iron or steel products or components. Coatings include epoxy coating, galvanizing, painting, and any other coating that protects or enhances the value of the steel or iron product or component.

The Contractor shall provide the Engineer with a Certificate of Materials Origin, on a form furnished by the Engineer, before incorporating any iron or steel products into the Project. Unless a Certificate of Materials Origin has been provided to the Engineer, the Materials shall be considered of foreign origin.

The Contractor shall retain manufacturers' certificates verifying the origin of all domestic iron or steel Materials for three years after the date of final payment for the Project, and shall furnish copies to the Engineer upon request.

(b) Buy Oregon - Pursuant to ORS 279.021, the Contractor shall give preference to goods or services produced in Oregon if price, fitness, availability, and quality are equal. This provision does not apply to Contracts financed wholly or in part by federal funds.

(c) Recycled Materials - Pursuant to ORS 279.545 to 279.650, and subject to the approval of the Engineer, the Contractor shall use recycled products to the maximum extent economically feasible.

00160.30 Agency-Furnished Materials - Unless otherwise specified in the Special Provisions, Materials listed as Agency-furnished will be available to the Contractor free of charge.

The Contractor shall be responsible for all Materials furnished by the Agency and shall pay all demurrage and storage charges. The Contractor shall replace at its expense Agency-furnished Materials lost or damaged due to any cause.

The locations at which Agency-furnished Materials are available will be designated in the Special Provisions. If the locations are not listed in the Special Provisions, the Agency-furnished Materials will be furnished to the Contractor at the Project Site. In either case, all costs of handling, hauling, unloading, and placing Agency-furnished Material shall be considered included in the price paid for the Pay Item involving such Material.

All Agency-furnished Materials not incorporated into the Work remains the property of the Agency. The Contractor shall deliver such Materials as directed by the Engineer.

00160.40 Agency-Furnished Sources - The Agency may list in the Special Provisions, or show on the Plans, Borrow pits or Aggregate sources from which the Contractor may, or shall, obtain Materials. These sources will be identified and referred to as Prospective or Mandatory Sources. A development plan will be included when such sources are shown on the Plans.

(a) Working in a Different Area of the Materials Source - If the Contractor desires to work in a different area of the Materials source than that shown on the development plan, the Contractor must submit a written request stating the reasons for the requested change. If a new land use permit, development plan, or reclamation plan is needed, the Contractor must submit it and obtain approval from the Engineer before starting work in any area other than that shown on the Plans. Approval for work in a different area will not entitle the Contractor to any added compensation or adjustment of Contract Time.

The Agency will not be responsible for the availability of sources other than as stated in the Special Provisions. If the Contractor has given notice of intent to use, but does not use the source(s) on the Project, the Contractor shall reimburse the Agency for any costs the Agency incurs in making such source(s) available.

(b) Cost of Sources - Unless otherwise specified in the Special Provisions, any Prospective or Mandatory Source will be provided by the Agency for use without payment of royalty or other charge. (See 00160.50)

(c) Exhaustion of Sources - If the Engineer determines that the quantities of specified Materials that can be produced from a Mandatory Source are insufficient for the Work, and it becomes necessary to move to another source, the Agency will pay for the reasonable cost of moving the plant to, and erecting it at, a new approved source from which specified Materials can be produced. Adjustment in hauling costs, other costs, and Contract Time will be determined as provided in 00140.30.

No allowance, reimbursement, compensation, or adjustment will be made for changes in the use of sources, or for moving from one source to another, except as provided above.

00160.50 Agency-Controlled Land; Limitations and Requirements:

(a) General - The Contractor shall have no property rights in, or right of occupancy on, Agency-Controlled Land. Nor shall the Contractor have the right to sell, use, remove, or otherwise dispose of any material from Agency-Controlled Land, areas, or property, except as specified in the Special Provisions or by the written authorization of the Engineer.

Unless authorized in the Contract, the Contractor shall not disturb any material within Rights-of-Way without written authorization from the Engineer.

Unless otherwise specified in the Contract, the ownership of all materials originating on Agency-Controlled Lands will at all times vest in, and remain within the control of, the Agency.

(b) Waste, Excess, and By-Product Materials - All waste, excess, and by-product materials, collectively referred to in this Subsection as "By-Products", from the manufacture or production of Materials shall remain Agency property. Unless otherwise ordered by the Engineer in writing, By-Products shall be placed as required by the development plan:

- In stockpiles at designated locations;
- At locations and in shapes that are readily accessible; and
- In such a manner as to avoid fouling areas containing useable materials, or interfering with future plant setups to use materials from the property.

The Agency will not compensate the Contractor for handling and stockpiling By-Products in accordance with the development plan requirements. If by written order the Engineer directs the Contractor to stockpile or place designated By-Products at alternate sites, the By-Products designated shall be loaded, hauled, and placed as directed, and this work will be paid for as Extra Work.

00160.60 Contractor-Furnished Materials and Sources:

(a) General - The Contractor shall furnish, at its own expense, all products and Materials required for the Project from sources of its own choosing, unless such sources have been designated in the Special Provisions or Plans as Prospective or Mandatory Sources.

(b) Acquisition of Sources - The Contractor shall acquire, at its own expense, the rights of access to, and the use of, all sources the Contractor chooses which are not Agency-controlled and made available by the Agency to the Contractor.

(c) Additional Requirements - Except for continuously-operated commercial sources, Work shall not begin, nor will any Materials be accepted by the Engineer, until the Contractor has:

- (1) Given to the Engineer a copy of permits from, or proof that permits are not required from:
 - The Department of Geology and Mineral Industries, as required under ORS 517.790;
 - The Division of State Lands, as required under ORS 196.815 (when removing material from the bed or banks of any waters or from any Wetland); and
 - Local governmental authorities having jurisdiction over land use at the source location.

(2) Furnished to the Engineer written approval of the property owner, if other than the Contractor, for the Contractor's proposed plans of operation in, and reclamation of, the source. The Contractor shall include in the document containing the property owner's written approval a summary of the requirements of the permits described above, which shall be subject to the Engineer's approval.

00160.70 Requirements for Plant Operations - Before operating mixing plants, Rock crushers, or other Equipment, the Contractor shall provide the Engineer copies of all applicable discharge permits for noise, air contaminants, and water pollutants from DEQ or applicable local jurisdictions, or a letter from DEQ or the local jurisdiction stating that no permits are required for the use of the Equipment and sites.

00160.80 Requirements for Sources of Borrow and Aggregate - The Contractor shall conduct operations according to all applicable federal, State, and local laws (including without limitation ORS Chapter 517 and OAR Chapter 632, Division 30) when developing, using, and reclaiming all sources of Borrow material and Aggregate. The Contractor shall provide erosion control at Borrow sources that are not within the Project Site. The Contractor shall not operate in Wetlands except as allowed by permit. The Contractor shall comply with all requirements for pollution and sediment control, including without limitation the National Pollutant Discharge Elimination System where applicable.

Except for continuously-operated commercial sources, the Contractor shall also conform to the following:

(a) If a natural growth of trees or shrubs is present, preserve a border of such to conceal land scars.

(b) Excavate Borrow sources and Aggregate sources, except for those in streams and rivers, to provide:

- Reasonably uniform depths and widths;
- Natural drainage so no water stands or collects in excavated areas, when practicable;
- Slopes trimmed to blend with the adjacent terrain upon completion of operations;
- Slopes covered with native soil, or acceptable plant rejects to support plant growth, if required by Specifications, Plans, or permits; and
- A vegetative cover that blends with the adjacent natural growth.

(c) Excavate in quarries so that:

- Faces will not be steeper than vertical (no overhang);
- Vertical faces conform to Oregon OSHA standards, Division 3, and as shown on an approved development plan;
- Floors or benches are excavated to a uniform Slope free of depressions and will drain and not interfere with the downland owner's property; and
- Upon completion, the quarry is left appearing neat and compatible with surrounding terrain.

(d) Obliterate haul roads specifically built for access to sources, and restore the areas disturbed by these roads as nearly as practicable to the conditions that existed before the roads were built, unless otherwise directed by the landowner or regulatory body.

Section 00165 - Quality of Materials

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

Description

00165.00 General - The Contractor shall incorporate into the Work only Materials conforming to the Specifications and approved by the Engineer. The Contractor shall incorporate into the Work only manufactured products made of new materials unless otherwise specified in the Contract.

Materials not meeting the Specifications at the time they are to be used are unacceptable and must be removed immediately from the Project Site, unless otherwise directed by the Engineer.

00165.01 Rejected Materials - The Engineer may reject any Materials that appear to be defective (00150.25). The Contractor shall not incorporate any rejected Materials into the Work. Rejected Materials whose defects have been corrected may not be incorporated into the Work until the Engineer has approved their use. The Engineer may order the removal and replacement by the Contractor, at Contractor's expense, of any defective Materials. (Refer also to 00150.20.)

00165.02 Materials Conformance and Quality Compliance Documents - For purposes of this Section, "Materials Conformance Documents" means the Contractor's quality-control test results and identity of the testing facility. "Quality Compliance Documents" means those documents specified in ODOT's Nonfield-Tested Materials Acceptance Guide, unless otherwise specified in the Contract.

00165.03 Testing by Agency - When testing Materials, the Agency will conduct the tests in its central laboratory, field laboratories, or other laboratories designated by the Engineer, even though certain AASHTO, ASTM, and other Materials specifications may require testing at the place of manufacture. Results of the Agency's tests will be made available to the Contractor.

00165.04 Costs of Testing - When the Contract requires that the Agency performs the testing, the testing will be at the Agency's expense. The Agency will pay the cost of Contractor-requested source-review tests on unprocessed Aggregates from no more than two sources for each Project, and on no more than three unprocessed samples from each source. Additional source-review tests performed at the Contractor's request shall be at the Contractor's expense.

Unless otherwise provided in the Contract, all testing required to be performed by the Contractor will be at the Contractor's expense.

Provisions and Requirements

00165.10 Materials Acceptance Guides - Unless otherwise specified elsewhere in the Contract, Materials will be accepted according to the following guides:

(a) Field-Tested Materials - Field-tested Materials will be accepted according to the ODOT Manual of Field Test Procedures ("MFTP"). The MFTP is available at the ODOT Contractor Plans office, Room 28 Transportation Building, 355 Capitol St. NE, Salem, Oregon 97301-3871 (phone (503) 986-3720).

(b) Nonfield-Tested Materials - Nonfield-tested Materials will be accepted according to the ODOT Nonfield Tested Materials Acceptance Guide (NTMAG), unless otherwise specified in the Contract. The NTMAG is available at the ODOT Contractor Plans office.

00165.20 Materials Specifications and Test Method References - References to Materials specifications and test methods of ODOT, WAQTC, AASHTO, ASTM, other governmental agencies, or

other recognized organizations mean those officially adopted and in current use by the agency or organization on the date of Advertisement.

If there are conflicting references, or if no reference is made to Materials specifications or test method, Materials must meet the Materials specifications or test methods required by the first applicable of the following agencies and organizations:

- ODOT;
- WAQTC;
- AASHTO;
- ASTM;
- Other recognized national organizations, such as ANSI, AWWA, IMSA, and UL; and
- Industry standards in the location where the Work is being performed.

If there are conflicting references in the Contract to required sampling and testing frequencies, the Contractor shall sample and test the Materials according to the first applicable of the following:

- Special Provisions;
- MFTP;
- Supplemental Specifications (if any); and
- Standard Specifications.

00165.30 Field-Tested Materials:

(a) Contractor's Duties - The Contractor shall:

- Furnish Materials of the quality specified in the Contract;
- Provide and administer a quality control program as described in the Quality Assurance Manual portion of the MFTP. Upon request, the Contractor shall provide to the Engineer the names, telephone numbers, and copies of certifications for all personnel performing field testing; and
- Perform other testing as required by the Contract.

(b) Types of Tests - The types of tests and testing methods generally required by ODOT are described in the MFTP.

(c) Acceptance of Field-Tested Materials - The Contractor's test results for field-tested Materials will be verified by the Agency according to the Quality Assurance program outlined in the MFTP. If the Agency's QA test results verify the Contractor's results, the Materials will be analyzed for acceptance according to one of the following methods before the Engineer will accept them for incorporation into the Work:

- Statistically, according to 00165.40, to determine "Pay Factors" for produced Aggregate;

00165.30(c)

- Statistically, according to 00165.40, to determine "Composite Pay Factors" for mixtures; or
- Other methods determined by the Engineer.

If acceptance testing reveals that the Contractor's data is incorrect, the Agency will perform additional testing to determine whether the Materials meet Specifications. If the Materials do not meet Specifications, the Contractor shall reimburse the Agency for the cost of the additional testing, which may be deducted from monies due or to become due the Contractor under the Contract.

00165.35 Nonfield-Tested Materials - The Contractor shall furnish Materials meeting Specifications, along with all Materials Conformance and Quality Compliance Documents.

(a) Test Results Certificate - The Certificate shall:

- Be from the manufacturer verifying that the Material furnished has been sampled and tested and the test results meet the Specifications
- Include, or be accompanied by, a copy of the specified test results (ODOT, AASHTO, ASTM, UL or other)
- Identify the testing agency and the representative responsible for the test results
- Permit positive determination that Material delivered to the Project is the same Material covered by the test results
- Be delivered to the Engineer' with the shipment of the material

(b) Quality Compliance Certificate - The Certificate from the manufacturer shall:

- Verify that the Material meets the Specifications, and identify by number the specified test methods used (ODOT, AASHTO, ASTM, UL, or other)
- Permit positive determination that Material delivered to the Project is the same Material covered by the certificate
- Be delivered to the Engineer with the shipment of the Material, or be an identification plate or mark, decal, sticker, label, or tag attached to the container or Material

(c) Equipment List and Drawings - These consist of lists of proposed Equipment and Materials, such as:

- Shop drawings
- Material lists
- Equipment lists
- Catalog description sheets
- Manufacturer's brochures

Submit these lists to the Engineer for review of conformance with the Specifications.

(d) Certificate of Origin of Steel Materials - When specified, complete this document (ODOT Form 734-2126) as required by 00160.20 for Federal-aid projects.

Materials will be subject to acceptance testing if the Engineer so elects. The Engineer may reject damaged or non-Specification Materials regardless of the Materials Conformance Documents furnished.

00165.40 Statistical Analysis - When 00165.30(c) or 00165.50 applies, the Contractor shall divide the Materials into lots and sublots, randomly sample and test them as required, and analyze the results statistically to determine whether the Materials conform to the Specifications.

All acceptance test results of lots and sublots will be analyzed collectively using the Quality Level Analysis procedure set out in this Subsection. This procedure shall not be used for a lot with less than three sublots. Sampling of Material for a lot that contains two or fewer sublots shall be increased to obtain at least three sublots. The Engineer has discretion to either accept or reject lots originating with two or fewer sublots, even after sampling is increased.

(a) Lot - A lot is the quantity of Materials produced by a single process or JMF that is sampled, tested, and statistically evaluated, as specified in this Subsection.

(b) Sublot - A sublot is a portion of a lot, for which a sample test value may be normally obtained.

(c) Quality Level Analysis - Quality Level Analysis is a statistical procedure to determine, for each lot:

- The percentage of each constituent of the Materials meeting Specifications;
- The Pay Factor for each constituent; and
- The Composite Pay Factor, when specified.

(d) Pay Factor and Composite Pay Factor Computation - Procedures for determining the percent meeting Specifications, Pay Factors, and Composite Pay Factor for a lot of Materials are as follows:

(1) Compute lot arithmetic mean (\bar{X}) for each constituent:

$$\bar{X} = \frac{\sum X}{n}$$

Where $\sum X$ = summation of sample test values
 n = total number of samples

(2) Compute standard deviation (sd) for each constituent:

$$sd = \sqrt{\frac{\sum X^2 - n\bar{X}^2}{n-1}}$$

Where $\sum X^2$ = summation of the squares of each sample test value
 \bar{X}^2 = square of the lot arithmetic mean

(3) Compute the upper quality index (Q_U) for each constituent:

$$Q_U = \frac{USL - \bar{X}}{sd}$$

Where USL (upper specification limit) is the target value plus allowable tolerance

- (4) Compute the lower quality index (Q_L) for each constituent:

$$Q_L = \frac{\bar{X} - LSL}{sd}$$

Where LSL (lower specification limit) is the target value minus allowable tolerance

- (5) From Table 00165-1, for each constituent, determine the percent within the upper specification limit (P_U) which corresponds to a given Q_U . If USL is 100% or is not specified, P_U will be 100.

- (6) From Table 00165-1, for each constituent, determine the percent within the lower specification limit (P_L) which corresponds to a given Q_L . If LSL is 0 or not specified, P_L will be 100.

- (7) Compute the quality level, or total percent within specification limits (P_T), for each constituent:

$$P_T = (P_U + P_L) - 100$$

- (8) Using the P_T from Step 7, determine the Pay Factor (PF) from Table 00165-2 for each constituent tested. A minimum PF of 1.00 will be used when all subplot test values are within the upper and lower specification limits, regardless of the calculated PF.

- (9) Compute the Weighted Pay Factor (WPF) for each constituent:

$$WPF = (PF) \times (f_i)$$

Where f_i = weighting factor listed in the specifications for each constituent tested.

- (10) Compute the Composite Pay Factor (CPF) for the lot and report the results to three decimal places.

$$CPF = \frac{\sum WPF}{\sum f_i}$$

Where $\sum WPF$ = sum of the weighted pay factors for each constituent

$\sum f_i$ = sum of the weighting factors listed in the specifications

Table 00165-1

QUALITY LEVEL ANALYSIS BY THE STANDARD DEVIATION METHOD								
P _U or P _L PERCENT WITHIN LIMITS FOR POSITIVE VALUES OF Q _U or Q _L	UPPER QUALITY INDEX Q _U OR LOWER QUALITY INDEX Q _L							
	n = 3	n = 4	n = 5	n = 6	n = 7	n = 8	n = 9	n = 10 to n = 11
100	1.16	1.50	1.79	2.03	2.23	2.39	2.53	2.65
99	-	1.47	1.67	1.80	1.89	1.95	2.00	2.04
98	1.15	1.44	1.60	1.70	1.76	1.81	1.84	1.86
97	-	1.41	1.54	1.62	1.67	1.70	1.72	1.74
96	1.14	1.38	1.49	1.55	1.59	1.61	1.63	1.65
95	-	1.35	1.44	1.49	1.52	1.54	1.55	1.56
94	1.13	1.32	1.39	1.43	1.46	1.47	1.48	1.49
93	-	1.29	1.35	1.38	1.40	1.41	1.42	1.43
92	1.12	1.26	1.31	1.33	1.35	1.36	1.36	1.37
91	1.11	1.23	1.27	1.29	1.30	1.30	1.31	1.31
90	1.10	1.20	1.23	1.24	1.25	1.25	1.26	1.26
89	1.09	1.17	1.19	1.20	1.20	1.21	1.21	1.21
88	1.07	1.14	1.15	1.16	1.16	1.16	1.16	1.17
87	1.06	1.11	1.12	1.12	1.12	1.12	1.12	1.12
86	1.04	1.08	1.08	1.08	1.08	1.08	1.08	1.08
85	1.03	1.05	1.05	1.04	1.04	1.04	1.04	1.04
84	1.01	1.02	1.01	1.01	1.00	1.00	1.00	1.00
83	1.00	0.99	0.98	0.97	0.97	0.96	0.96	0.96
82	0.97	0.96	0.95	0.94	0.93	0.93	0.93	0.92
81	0.96	0.93	0.91	0.90	0.90	0.89	0.89	0.89
80	0.93	0.90	0.88	0.87	0.86	0.86	0.86	0.85
79	0.91	0.87	0.85	0.84	0.83	0.82	0.82	0.82
78	0.89	0.84	0.82	0.80	0.80	0.79	0.79	0.79
77	0.87	0.81	0.78	0.77	0.76	0.76	0.76	0.75
76	0.84	0.78	0.75	0.74	0.73	0.73	0.72	0.72
75	0.82	0.75	0.72	0.71	0.70	0.70	0.69	0.69
74	0.79	0.72	0.69	0.68	0.67	0.66	0.66	0.66
73	0.76	0.69	0.66	0.65	0.64	0.63	0.63	0.62
72	0.74	0.66	0.63	0.62	0.61	0.60	0.60	0.59
71	0.71	0.63	0.60	0.59	0.58	0.57	0.57	0.57
70	0.68	0.60	0.57	0.56	0.55	0.55	0.54	0.54
69	0.65	0.57	0.54	0.53	0.52	0.52	0.51	0.51
68	0.63	0.54	0.51	0.50	0.49	0.49	0.48	0.48
67	0.59	0.51	0.47	0.47	0.46	0.46	0.46	0.45
66	0.56	0.48	0.45	0.44	0.44	0.43	0.43	0.43
65	0.52	0.45	0.43	0.41	0.41	0.40	0.40	0.40
64	0.49	0.42	0.40	0.39	0.38	0.38	0.37	0.37
63	0.46	0.39	0.37	0.36	0.35	0.35	0.35	0.34
62	0.43	0.36	0.34	0.33	0.32	0.32	0.32	0.32
61	0.39	0.33	0.31	0.30	0.30	0.29	0.29	0.29
60	0.36	0.30	0.28	0.27	0.27	0.27	0.26	0.26
59	0.32	0.27	0.25	0.25	0.25	0.24	0.24	0.24
58	0.29	0.24	0.23	0.22	0.21	0.21	0.21	0.21
57	0.25	0.21	0.20	0.19	0.19	0.19	0.18	0.18
56	0.22	0.18	0.17	0.16	0.16	0.16	0.16	0.16
55	0.18	0.15	0.14	0.14	0.13	0.13	0.13	0.13
54	0.14	0.12	0.11	0.11	0.11	0.11	0.10	0.10
53	0.11	0.09	0.08	0.08	0.08	0.08	0.08	0.08
52	0.07	0.06	0.06	0.05	0.05	0.05	0.05	0.05
51	0.04	0.03	0.03	0.03	0.03	0.03	0.03	0.03
50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

NOTE: For negative values of Q_U or Q_L, P_U or P_L is equal to 100 minus the table value for P_U or P_L. If the value of Q_U or Q_L does not correspond exactly to a figure in the table, use the next higher figure.

Table 00165-1

QUALITY LEVEL ANALYSIS BY THE STANDARD DEVIATION METHOD							
P _U or P _L PERCENT WITHIN LIMITS FOR POSITIVE VALUES OF Q _U OR Q _L	UPPER QUALITY INDEX Q _U				OR LOWER QUALITY INDEX Q _L		
	n = 12 to n = 14	n = 15 To n = 18	n = 19 to n = 25	n = 26 to n = 37	n = 38 to n = 69	n = 70 to n = 200	n = 201 to n = ∞
100	2.83	3.03	3.20	3.38	3.54	3.70	3.83
99	2.09	2.14	2.18	2.22	2.26	2.29	2.31
98	1.91	1.93	1.96	1.99	2.01	2.03	2.05
97	1.77	1.79	1.81	1.83	1.85	1.86	1.87
96	1.67	1.68	1.70	1.71	1.73	1.74	1.75
95	1.58	1.59	1.61	1.62	1.63	1.63	1.64
94	1.50	1.51	1.52	1.53	1.54	1.55	1.55
93	1.44	1.44	1.45	1.46	1.46	1.47	1.47
92	1.37	1.38	1.39	1.39	1.40	1.40	1.40
91	1.32	1.32	1.33	1.33	1.33	1.34	1.34
90	1.26	1.27	1.27	1.27	1.28	1.28	1.28
89	1.21	1.22	1.22	1.22	1.22	1.22	1.23
88	1.17	1.17	1.17	1.17	1.17	1.17	1.17
87	1.12	1.12	1.12	1.12	1.12	1.13	1.13
86	1.08	1.08	1.08	1.08	1.08	1.08	1.08
85	1.04	1.04	1.04	1.04	1.04	1.04	1.04
84	1.00	1.00	1.00	1.00	0.99	0.99	0.99
83	0.96	0.96	0.96	0.96	0.95	0.95	0.95
82	0.92	0.92	0.92	0.92	0.92	0.92	0.92
81	0.88	0.88	0.88	0.88	0.88	0.88	0.88
80	0.85	0.85	0.85	0.84	0.84	0.84	0.84
79	0.81	0.81	0.81	0.81	0.81	0.81	0.81
78	0.78	0.78	0.78	0.78	0.77	0.77	0.77
77	0.75	0.75	0.75	0.74	0.74	0.74	0.74
76	0.71	0.71	0.71	0.71	0.71	0.71	0.71
75	0.68	0.68	0.68	0.68	0.68	0.68	0.67
74	0.65	0.65	0.65	0.65	0.65	0.64	0.64
73	0.62	0.62	0.62	0.62	0.62	0.61	0.61
72	0.59	0.59	0.59	0.59	0.59	0.59	0.58
71	0.56	0.56	0.56	0.56	0.56	0.55	0.55
70	0.53	0.53	0.53	0.53	0.53	0.53	0.52
69	0.50	0.50	0.50	0.50	0.50	0.50	0.50
68	0.48	0.48	0.47	0.47	0.47	0.47	0.47
67	0.45	0.45	0.45	0.44	0.44	0.44	0.44
66	0.42	0.42	0.42	0.42	0.41	0.41	0.41
65	0.39	0.39	0.39	0.39	0.39	0.39	0.39
64	0.37	0.37	0.36	0.36	0.36	0.36	0.36
63	0.34	0.34	0.34	0.34	0.33	0.33	0.33
62	0.31	0.31	0.31	0.31	0.31	0.31	0.31
61	0.29	0.29	0.28	0.28	0.28	0.28	0.28
60	0.26	0.26	0.26	0.26	0.26	0.25	0.25
59	0.23	0.23	0.23	0.23	0.23	0.23	0.23
58	0.21	0.21	0.20	0.20	0.20	0.20	0.20
57	0.18	0.18	0.18	0.18	0.18	0.18	0.18
56	0.15	0.15	0.15	0.15	0.15	0.15	0.15
55	0.13	0.13	0.13	0.13	0.13	0.13	0.13
54	0.10	0.10	0.10	0.10	0.10	0.10	0.10
53	0.08	0.08	0.08	0.08	0.08	0.08	0.08
52	0.05	0.05	0.05	0.05	0.05	0.05	0.05
51	0.03	0.03	0.03	0.03	0.03	0.03	0.02
50	0.00	0.00	0.00	0.00	0.00	0.00	0.00

NOTE: For negative values of Q_U or Q_L, P_U or P_L is equal to 100 minus the table value for P_U or P_L. If the value of Q_U or Q_L does not correspond exactly to a figure in the table, use the next higher figure.

Table 00165-2

PAY FACTOR	REQUIRED QUALITY LEVEL FOR A GIVEN SAMPLE SIZE (n) AND A GIVEN PAY FACTOR							
	n = 3	n = 4	n = 5	n = 6	n = 7	n = 8	n = 9	n = 10 to n = 11
1.05	100	100	100	100	100	100	100	100
1.04	90	91	92	93	93	93	94	94
1.03	80	85	87	88	89	90	91	91
1.02	75	80	83	85	86	87	88	88
1.01	71	77	80	82	84	85	85	86
1.00	68	74	78	80	81	82	83	84
0.99	66	72	75	77	79	80	81	82
0.98	64	70	73	75	77	78	79	80
0.97	62	68	71	74	75	77	78	78
0.96	60	66	69	72	73	75	76	77
0.95	59	64	68	70	72	73	74	75
0.94	57	63	66	68	70	72	73	74
0.93	56	61	65	67	69	70	71	72
0.92	55	60	63	65	67	69	70	71
0.91	53	58	62	64	66	67	68	69
0.90	52	57	60	63	64	66	67	68
0.89	51	55	59	61	63	64	66	67
0.88	50	54	57	60	62	63	64	65
0.87	48	53	56	58	60	62	63	64
0.86	47	51	55	57	59	60	62	63
0.85	46	50	53	56	58	59	60	61
0.84	45	49	52	55	56	58	59	60
0.83	44	48	51	53	55	57	58	59
0.82	42	46	50	52	54	55	57	58
0.81	41	45	48	51	53	54	56	57
0.80	40	44	47	50	52	53	54	55
0.79	38	43	46	48	50	52	53	54
0.78	37	41	45	47	49	51	52	53
0.77	36	40	43	46	48	50	51	52
0.76	34	39	42	45	47	48	50	51
0.75	33	38	41	44	46	47	49	50
REJECT	QUALITY LEVELS LESS THAN THOSE SPECIFIED FOR A 0.75							

NOTE: If the computed QUALITY LEVEL does not correspond exactly to a figure in the table, use the next lower value.

Table 00165-2

PAY FACTOR	REQUIRED QUALITY LEVEL FOR A GIVEN SAMPLE SIZE (n) AND A GIVEN PAY FACTOR						
	n = 12 to n = 14	n = 15 to n = 18	n = 19 to n = 25	n = 26 to n = 37	n = 38 to n = 69	n = 70 to n = 200	n = 201 to n = ∞
1.05	100	100	100	100	100	100	100
1.04	95	95	96	96	97	97	98
1.03	92	93	93	94	95	95	97
1.02	89	90	91	92	93	94	95
1.01	87	88	89	90	91	93	94
1.00	85	86	87	89	90	91	93
0.99	83	85	86	87	88	90	92
0.98	81	83	84	85	87	88	90
0.97	80	81	83	84	85	87	89
0.96	78	80	81	83	84	86	88
0.95	77	78	80	81	83	85	87
0.94	75	77	78	80	81	83	86
0.93	74	75	77	78	80	82	84
0.92	72	74	75	77	79	81	83
0.91	71	73	74	76	78	80	82
0.90	70	71	73	75	76	79	81
0.89	68	70	72	73	75	77	80
0.88	67	69	70	72	74	76	79
0.87	66	67	69	71	73	75	78
0.86	64	66	68	70	72	74	77
0.85	63	65	67	69	71	73	76
0.84	62	64	65	67	69	72	75
0.83	61	63	64	66	68	71	74
0.82	60	61	63	65	67	70	72
0.81	58	60	62	64	66	69	71
0.80	57	59	61	63	65	67	70
0.79	56	58	60	62	64	66	69
0.78	55	57	59	61	63	65	68
0.77	52	56	57	60	62	64	67
0.76	51	55	56	58	61	63	66
0.75	51	53	55	57	59	62	65
REJECT	QUALITY LEVELS LESS THAN THOSE SPECIFIED FOR A 0.75						

NOTE: If the computed QUALITY LEVEL does not correspond exactly to a figure in the table, use the next lower value.

00165.50 Statistical Acceptance Sampling and Testing - The Contractor shall sample and test Materials for acceptance, as required by the Contract. The Contractor may statistically evaluate test results for purposes of quality control or to predict a Pay Factor or Composite Pay Factor. The following apply:

(a) Statistical Acceptance - The Engineer will perform statistical analysis according to 00165.40 for acceptance and to determine a Pay Factor (PF) or Composite Pay Factor (CPF). The Engineer's determination of the PF or CPF shall be controlling.

(b) Pay Adjustments - As an incentive to produce quality Materials, the Engineer's acceptance will be based upon the following:

(1) Specification Materials - Any constituent with a PF of 1.00 or greater, or any Materials with a CPF of 1.0000 or greater, will be considered Specification Materials. A constituent with a PF greater than 1.00 or Materials with a CPF greater than 1.0000 will be considered of superior quality and, when specified, may earn a PF adjustment greater than 1.00, up to a maximum of 1.05.

(2) Nonspecification Materials - Any constituent with a PF less than 1.00, or any Materials with a CPF less than 1.0000 will be considered nonspecification Materials. When specified, a lot containing nonspecification Materials may be accepted at a reduced price as described in (c) below.

(c) Nonspecification Materials:

(1) A Lot-in-Progress - The Contractor shall shut down production when any of the following occurs:

- The CPF for a lot-in-progress drops below 1.0000, and the Contractor is taking no corrective action;
- The CPF is less than 0.7500; or
- Any constituent test is continually out of specification limits, regardless of whether or not the CPF is below 0.7500.

The Contractor shall not resume production until the Engineer has determined that Specification Materials can be produced, and has given approval to resume.

(2) An Entire Lot - The Engineer may reject an entire lot of Materials with a CPF between 0.7500 and 1.0000, or may take action in accordance with 00150.25.

For a lot of Material with a CPF below 0.7500, the Engineer will take one or more of the following actions:

a. Remain in Place - Allow Materials to remain in place with an appropriate price reduction that may range from 25% to 100% (no payment);

b. Corrective Work - Require corrective work, at the Contractor's expense, with an appropriate price reduction that may range from zero (full payment) to 100% (no payment); or

c. Remove and Replace - Require complete removal and replacement with Specification Materials. No payment will be made for the rejected Materials, the cost of removal, or for the costs of sampling and testing.

00165.70 Use of Materials without Acceptable Materials Conformance Documents:

(a) General - The Contractor shall not incorporate Materials into the Project prior to submittal of Materials Conformance Documents acceptable to the Engineer. The Engineer may waive this requirement temporarily if Materials are necessary for immediate traffic safety.

(b) Materials Incorporated for Immediate Traffic Safety - If Materials are incorporated into the Project for immediate traffic safety before acceptable Materials Conformance Documents are available, no payment will be made for the value of the Materials, or the costs of incorporating them, until Materials Conformance Documents have been submitted to and approved by the Engineer, or the Materials are otherwise found through testing to comply with Specifications.

(c) Contractor's Request for Testing Assistance - If acceptable Materials Conformance Documents are not available, the Contractor may either have the necessary tests performed at a private laboratory or request in writing that the Engineer:

- Determine if the Agency or its agents can sample and test;
- Estimate the cost to the Contractor for the testing service; and
- Estimate the time required to obtain the test results.

The Engineer will provide this information to the Contractor in writing. If the Contractor requests the Engineer, in writing, to proceed, the Engineer will arrange for the sampling and testing, at the Contractor's expense. If these tests determine the Material complies with the Specifications, the Materials may be incorporated into the Project, or for Materials previously incorporated pursuant to (b) above, payment will be authorized.

00165.75 Storage and Handling of Materials - The Contractor shall store and handle Materials so as to preserve their quality and fitness for incorporation into the Work. The Contractor shall restore all storage sites to their original condition according to 00140.90, or to comply with any applicable permits, orders, or agreements, at the Contractor's expense.

Stored Materials:

- Shall be readily accessible for inspection;
- May be stored on approved parts of the Right-of-Way; and
- May be stored on private property if written permission of the owner or lessor is obtained.

Measurement

00165.80 Measurement - No separate measurement will be made of Work performed under this Section

Payment

00165.90 Incidental Basis - No separate or additional payment will be made for sampling, testing, certification, or other associated Work performed under this Section, whether performed by the Contractor, manufacturer, producer or supplier. No payment will be made for providing quality control personnel.

00165.91 Fabrication Inspection Expense - Fabrication of certain items outside of the State creates additional shop and plant inspection expense to the Agency. It is impractical, and extremely difficult, to determine the actual additional expenses incurred. Therefore, each time that inspection by Agency personnel is necessary, payment to the Contractor will be reduced by an amount computed at the following rates:

Zone	Place of Fabrication	Reduction in Payment
1	All of State of Oregon, and those portions of adjacent states within 80 airline km (50 airline miles) of the Oregon border	\$0
2	Outside of Zone 1, and up to 500 airline km (300 airline miles) from the Oregon border	\$100 per Calendar Day
3	Outside of Zone 2, up to 5000 airline km (3,000 airline miles) from the Oregon border, and within the continental United States.	Round trip coach airfare from Portland, Oregon plus \$100 per Calendar Day
4	Outside of Zone 3, or outside of the continental United States.	Round trip coach airfare from Portland, Oregon plus \$150 per Calendar Day

Calendar Day charges begin on the first day the Agency's inspector begins travel to begin work at the fabrication site, and continue without interruption through the final day of travel back to the State. The Contractor will be notified in writing of the dates of beginning and ending of Calendar Days used in computing payment reduction.

This Subsection applies to all fabricated items or manufactured Materials that are inspected by Agency personnel when fabricated or manufactured in the State. They include, but are not limited to:

- Structural steel fabrication;
- Prestressed concrete members;
- Precast concrete;
- Signs;
- Preservative treatment of wood products;
- Epoxy coating of reinforcing steel; and
- Other items specifically identified in the Specifications as requiring fabrication site or in-plant inspection by the Agency.

Section 00170 - Legal Relations and Responsibilities

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

Description

00170.00 General - The Contractor shall comply with all laws, ordinances, codes, regulations and rules, (collectively referred to as "Laws" in this Section), that relate to the Work or to those engaged in the Work. Where the provisions of the Contract are inconsistent or in conflict, the Contractor shall comply with the more stringent standard.

The Contractor shall indemnify, defend, and hold harmless the Agency and its representatives from liability arising from or related to the violation of Laws by those engaged in any phase of the Work. This provision does not apply to Work performed by Agency employees.

Provisions and Requirements

00170.01 Other Agencies Affecting Agency Contracts - Representatives of regulatory bodies or units of government whose Laws may apply to the Work shall have access to the Work according to 00150.20(d). These may include but are not limited to those in the following (a), (b), (c), and (d).

(a) Federal Agencies:

Agriculture, Department of
Forest Service
Soil Conservation Service

Army, Department of the
Corps of Engineers

Commerce, Department of
National Marine Fisheries Service

Environmental Protection Agency

Interior, Department of
Heritage, Conservation, and Recreation Service
Bureau of Indian Affairs
Bureau of Land Management
Bureau of Reclamation,
Office of Surface Mining, Reclamation, and Enforcement

U.S. Fish and Wildlife Service

Labor, Department of
Occupational Safety and Health Administration
Mine Safety and Health Administration

Transportation, Department of
Coast Guard
Federal Highway Administration

(b) State of Oregon Agencies:

Agriculture, Department of
 Natural Resources Division
 Soil and Water Conservation District

Consumer and Business Services, Department of
 Insurance Division
 Oregon Occupational Safety and Health Division

Energy, Office of

Environmental Quality, Department of

Fish and Wildlife, Department of

Forestry, Department of

Geology and Mineral Industries, Department of

Human Resources, Department of

Labor and Industries, Bureau of

Land Conservation and Development Department

State Lands, Division of

Water Resources Department

(c) Local Agencies:

City Councils

County Courts

County Commissioners, Boards of

Planning Commissions

Port Districts

Special Districts

(d) Oregon Tribal Governments

00170.02 Permits, Licenses, and Taxes - As required to accomplish the Work, the Contractor shall do the following:

- Obtain all necessary permits and licenses, except for those noted in 00170.03;
- Pay all applicable charges, fees and taxes, except for those noted in 00170.03;
- Give all notices required by applicable Laws, or under the terms of the Contract;

- Comply with ORS 274.530 relating to lease of stream beds by Oregon Division of State Lands;
- License, in the State of Oregon, all vehicles subject to licensing;
- Comply with ORS 477.625 and ORS 527.670 relating to clearing and fire hazards on forest lands; and
- Comply with all orders and permits issued by a governmental authority, whether local, State, or federal.

00170.03 Furnishing Right-of-Way and Permits - The Agency will obtain and pay for the following when they are required by the applicable Laws or by Plans or Specifications:

- All necessary Rights-of-Way;
- Permits required for crossing or encroaching upon navigable streams;
- Permits required for removing materials from or depositing materials in waterways;
- Permits required for operating in Agency-controlled source of Materials or disposal area;
- System development fees charged by local units of government;
- Building construction permits, not including specialty work such as heating, ventilation, air conditioning, or electrical; and
- Cost of referencing and replacing endangered survey monuments.

00170.04 Patents, Copyrights, and Trademarks - Prior to use of designs, devices, materials, or processes protected by patent, copyright, or trademark, the Contractor shall obtain from the Entity entitled to enforce the patent, copyright, or trademark all necessary evidence of legal right.

The Contractor shall indemnify, defend and hold harmless the Agency and all third parties and political subdivisions having a possessory or ownership interest or regulatory authority over the Project or Project Site from claims of patent, copyright or trademark infringement, and from costs, expenses and damages the Contractor or Agency may be obligated to pay as a result of such infringement during or after completing the Work.

00170.05 Assignment of Antitrust Rights - The Contractor irrevocably assigns to the Agency any claim for relief or cause of action the Contractor acquires during the term of the Contract, or which may accrue thereafter, by reason of any violation of:

- Title 15 (Commerce and Trade), United States Code;
- ORS 646.725; and
- ORS 646.730.

In connection with this assignment, it is an express obligation of the Contractor to take no action that would in any way impair or diminish the value of the rights assigned to the Agency pursuant to the provisions of this Subsection. Further, it is the express obligation of the Contractor to take all action necessary to preserve the rights assigned. It is an express obligation of the Contractor to advise the Agency's legal counsel:

- In advance, of its intention to commence any action involving such claims for relief or causes of action;
- Immediately upon becoming aware of the fact that an action involving such claims for relief or causes of action has been commenced by some other person or persons; and
- The date on which it notified the obligor(s) of any such claims for relief or causes of action of the fact of the Contractor's assignment to the Agency pursuant to the provisions of this Subsection.

In the event any payment is made to the Contractor under any such claims for relief, the Contractor shall promptly pay the full sum over to the Agency. In the event the Contractor fails to make such payment, the Agency may deduct the amount from monies due or to become due the Contractor under the Contract.

00170.10 Required Payments by Contractors - The Contractor shall comply with ORS 279.312 and ORS 279.314 during the term of the Contract.

(a) Prompt Payment by Contractor for Labor and Materials - As required by ORS 279.312, the Contractor shall:

- Make payment promptly, as due, to all Entities supplying labor or Materials under the Contract;
- Pay all contributions or amounts due the Industrial Accident Fund, whether from the Contractor or a Subcontractor, incurred in the performance of the Contract;
- Not permit any lien or claim to be filed against the State or any political subdivision thereof, on account of any labor or Material furnished in performance of the Contract; and
- Pay to the Department of Revenue all sums withheld from employees pursuant to ORS 316.167.

(b) Prompt Payment by Contractor to First-Tier Subcontractor(s) - In accordance with ORS 279.445(4)(a), after the Contractor has determined and certified to the Agency that one or more of its Subcontractors has satisfactorily performed subcontracted Work, the Contractor may request payment from the Agency for the Work, and shall pay the Subcontractor(s) within ten Calendar Days out of such amounts as the Agency has paid to the Contractor for the subcontracted Work.

(c) Interest on Unpaid Amount - If the Contractor or a first-tier Subcontractor fails, neglects, or refuses to make payment to an Entity furnishing labor or Materials in connection with the Contract within 30 days after the Contractor's receipt of payment, the Contractor or first-tier Subcontractor shall owe the Entity the amount due plus interest charges commencing on the date payment was due under ORS 279.445(4) and ending upon final payment, unless payment is subject to a good-faith dispute as defined in ORS 279.445.

As required by ORS 279.314(2), the rate of interest charged to the Contractor or first-tier Subcontractor on the amount due shall equal three times the discount rate on 90-day commercial paper in effect at the Federal Reserve Bank in the Federal Reserve district that includes Oregon on the date that is 30 days after the date when the payment was received from the Agency or from the Contractor. The amount of interest due may not be waived, but the rate of interest shall not exceed 30 percent.

(d) Agency's Payment of the Contractor's Prompt Payment Obligations - If the Contractor fails, neglects or refuses to make prompt payment of any invoice or other demand for payment for labor or services furnished to the Contractor or a Subcontractor by any Entity in connection with the Contract as such payment becomes due, the Agency may pay the Entity furnishing the labor or services and charge

00170.10(d)

the amount of the payment against monies due or to become due the Contractor under the Contract. (The Agency has no obligation to pay these Entities, and ODOT will not normally do so, but will refer them to the Contractor and the Contractor's Surety.)

The payment of a claim by the Agency in the manner authorized in this Subsection shall not relieve the Contractor or the Contractor's Surety from obligations with respect to any such claims.

(e) Right to Complain to the Construction Contractors Board - If the Contractor or a Subcontractor fails, neglects, or refuses to make payment to an Entity furnishing labor or Materials in connection with the Contract, the Entity may file a complaint with the Construction Contractors Board, unless payment is subject to a good-faith dispute as defined in ORS 279.445.

00170.32 Protection of Navigable Waters - The Contractor shall comply with all applicable Laws, including without limitation the Federal River and Harbor Act of March 3, 1899 and its amendments.

The Contractor shall not interfere with waterway navigation or impair navigable depths or clearances, except as U.S. Coast Guard or Corps of Engineer permits allow.

00170.60 Safety, Health, and Sanitation Provisions - The Contractor shall comply with all Laws concerning safety, health, and sanitation standards. The Contractor shall not require workers to perform Work under conditions that are hazardous, dangerous, or unsanitary.

Workers exposed to traffic shall wear upper body garments or safety vests that are highly visible and meet the requirements of 00225.27.

Workers exposed to falling or flying objects or electrical shock shall wear hard hats.

Upon their presentation of proper credentials, the Contractor shall allow inspectors of the U.S. Occupational Safety and Health Administration (OSHA) and the Oregon Occupational Safety and Health Division (OR-OSHA) to inspect the Work and Project Site without delay and without an inspection warrant.

Pursuant to ORS 468A.720, the Contractor or a Subcontractor who performs Project Work involving asbestos abatement shall possess a valid DEQ asbestos abatement license.

00170.61 Industrial Accident Protection:

(a) Workers' Compensation - The Contractor shall provide workers' compensation coverage for on-the-job injuries as required by 00170.70(c).

(b) Longshoremen's and Harbor Workers' Compensation - If Work to be performed is over or adjacent to navigable waters, the Longshoremen's and Harbor Workers' Compensation Act, (Chapter 18, Title 33 of the USC) may apply, and the Contractor shall be responsible for complying with its provisions (which may include the provision of additional workers' compensation benefits to employees).

00170.62 Labor Nondiscrimination - The Contractor shall comply with all Laws concerning equal employment opportunity, including without limitation those prohibiting discrimination because of race, religion, color, sex, disability, or national origin.

00170.63 Payment for Medical Care - The Contractor shall comply with ORS 279.320:

ORS 279.320 Condition concerning payment for medical care and providing workers' compensation.

(1) *Every public contract shall contain a condition that the contractor shall promptly, as due, make payment to any person, copartnership, association or corporation, furnishing medical, surgical and hospital care or other needed care and attention, incident to sickness or injury, to the employees of such contractor, of all sums which the contractor agrees to pay for such services and all moneys and sums which the contractor collected or deducted from the wages of employees pursuant to any law, contract, or agreement for the purpose of providing or paying for such service.*

(2) *Every public contract also shall contain a clause or condition that all subject employers working under the contract are either employers that will comply with ORS 656.017 or employers that are exempt under ORS 656.126.*

00170.65 Minimum Wage and Overtime Rates for Public Works Projects:

(a) General - The Contractor shall be responsible for investigating local labor conditions. The Agency does not imply that labor can be obtained at the minimum hourly wage rates specified in State or federal wage rate publications, and no increase in the Contract Amount will be made if wage rates paid are more than those listed.

For work performed on Indian Reservations, tribally-owned businesses and businesses owned by tribally-enrolled Native Americans are not subject to the Oregon Bureau of Labor and Industries overtime requirements. These businesses are subject to the Federal Contract Work Hours and Safety Standards Act, which states that employees must be paid time and one-half for all hours worked in excess of forty hours per week.

The Contractor shall comply with the pertinent provisions of ORS 279.316:

ORS 279.316 Condition Concerning Hours of Labor.

(1) (a) *Every public contract shall also contain a condition that no person shall be employed for more than 10 hours in any one day, or 40 hours in any one week, except in cases of necessity, emergency, or where the public policy absolutely requires it, and in such cases, except in cases of contracts for personal services as described in ORS 279.051, the employee shall be paid at least time and a half pay:*

(A) *For all overtime in excess of eight hours a day or 40 hours in any one week when the work week is five consecutive days, Monday through Friday; or*

(B) *For all overtime in excess of 10 hours a day or 40 hours in any one week when the work week is four consecutive days, Monday through Friday; and*

(C) *For all work performed on Saturday and on any legal holiday specified in ORS 279.334.*

(b) *An employer must give notice to employees who work on a public contract in writing, either at the time of hire or before commencement of work on the contract, or by posting a notice in a location frequented by employees, of the number of hours per day and days per week that the employees may be required to work.*

(2) *In the case of contracts for personal services as defined in ORS 279.051, the contract shall contain a provision that the employee shall be paid at least time and a half for all overtime worked in excess of 40 hours in any one week, except for individuals under these contracts who are excluded under ORS 653.010 to 653.261 or under 29 U.S.C. sections 201 to 209 from receiving overtime.*

(3) *In the case of a contract for services at a county fair or for other events authorized by a county fair board, the contract shall contain a provision that the labor performed on the contract shall be paid at least time and a half for work in excess of 10 hours in any one day or 40 hours in any one week. An employer must give notice to employees who work on such a contract in writing, either at the time of hire or before commencement of work on the contract, or by posting a notice in a location frequented by employees, of the number of hours per day and days per week that employees may be required to work.*

(4) (a) *Except as provided in subsection (3) of this section, contracts for services shall contain a provision that requires that persons employed under such contracts shall receive at least time and a half pay for work performed on the legal holidays specified in a collective bargaining agreement or in ORS 279.334 (1)(a)(C)(ii) to (vii) and for all time worked in excess of 10 hours a day or in excess of 40 hours in a week, whichever is greater.*

(b) *An employer must give notice to employees who work on a contract for services in writing, either at the time of hire or before commencement of work on the contract, or by posting a notice in a location frequented by employees, of the number of hours per day and days per week that the employees may be required to work.*

(b) When Federal Funds Are Involved - The Contractor shall pay the wage rate and fringe benefits listed in the publication "General Wage Determinations Issued Under the Davis-Bacon and Related Acts" from the U.S. Secretary of Labor, which is bound with the Special Provisions.

For Federal-Aid projects, the Contractor shall comply with provisions of FHWA Form 1273, "Required Contract Provisions Federal-Aid Construction Contracts" and ORS 279.316 and ORS 279.334.

With regard to overtime pay, the Contractor shall comply with the provision affording the greatest compensation.

ORS 279.334 Maximum hours of labor on public contracts; holidays; exceptions; liability to workers.

(1) (a) *In all cases where labor is employed by the state, county, school district, municipality, municipal corporation, or subdivision, through a contractor, no person shall be required or permitted to labor more than 10 hours in any one day, or 40 hours in any one week, except in cases of necessity, emergency, or where the public policy absolutely requires it, in which event, the person or persons so employed for excessive hours shall receive at least time and a half pay:*

(A) *For all overtime in excess of eight hours a day or 40 hours in any one week when the work week is five consecutive days, Monday through Friday; or*

(B) *For all overtime in excess of 10 hours a day or 40 hours in any one week when the work week is four consecutive days, Monday through Friday; and*

(C) *For all work performed on Saturday and on the following legal holidays:*

- (i) *Each Sunday.*
- (ii) *New Year's Day on January 1.*
- (iii) *Memorial Day on the last Monday in May.*
- (iv) *Independence Day on July 4.*
- (v) *Labor Day on the first Monday in September.*
- (vi) *Thanksgiving Day on the fourth Thursday in November.*
- (vii) *Christmas Day on December 25.*

(b) An employer must give notice to employees who perform work under paragraph (a) of this subsection in writing, either at the time of hire or before commencement of work on the contract, or by posting a notice in a location frequented by employees, of the number of hours per day and days per week that employees may be required to work.

(2) For the purpose of this section, each time a holiday, other than Sunday, listed in subsection (1) of this section falls on Sunday, the succeeding Monday shall be recognized as a legal holiday. Each time a holiday listed in subsection (1) of this section falls on Saturday, the preceding Friday shall be recognized as a legal holiday.

(3) Subsections (1) and (2) of this section do not apply to a contract for a public improvement or for services if the contractor is a party to a collective bargaining agreement in effect with any labor organization.

(4) When specifically agreed to under a written labor-management negotiated labor agreement, an employee may be paid at least time and a half pay for work performed on any legal holiday specified in ORS 187.010 and 187.020 that is not listed in subsection (1) of this section.

(5) This section shall not apply to labor performed in the prevention or suppression of fire under contracts and agreements made pursuant to the authority of the State Forester or the State Board of Forestry, under ORS 477.406.

(6) This section shall not apply to contracts for personal services as defined in ORS 279.051, provided that persons employed under such contracts shall receive at least time and a half pay for work performed on the legal holidays specified in subsection (1)(a)(C)(ii) to (vii) of this section and for all overtime worked in excess of 40 hours in any one week, except for individuals under these contracts who are excluded under ORS 653.010 to 653.261 or under 29 U.S.C. sections 201 to 209 from receiving overtime.

(7) Subsection (1) of this section does not apply to contracts for services at a county fair or for other events authorized by a county fair board if persons employed under the contract receive at least time and a half for work in excess of 10 hours in any one day or 40 hours in any one week.

(8) (a) Subsection (1) of this section does not apply to contracts for services. However, persons employed under such contracts shall receive at least time and a half pay for work performed on the legal holidays specified in a collective bargaining agreement or in subsection (1)(a)(C)(ii) to (vii) of this section and for all time worked in excess of 10 hours a day or in excess of 40 hours in a week, whichever is greater.

(b) An employer must give notice to employees who work on a contract for services in writing, either at the time of hire or before commencement of work on the contract, or by posting a notice in a location frequented by employees, of the number of hours per day and days per week that the employees may be required to work.

(9) Any contractor or subcontractor or contractor's or subcontractor's surety who violates the provisions of this section shall be liable to the employees affected in the amount of their unpaid overtime wages and in an additional amount equal to the unpaid overtime wages as liquidated damages. If the violation resulted from willful falsification of payroll records, the contractor or subcontractor or contractor's or subcontractor's surety shall be liable to the employees affected in the amount of their unpaid overtime wages and in additional amount equal to twice the unpaid overtime wages as liquidated damages.

(10) *An action to enforce liability to employees under subsection (9) of this section may be brought as an action on the contractor's bond as provided for in ORS 279.536.*

(11) *In accordance with any applicable provision of ORS 183.310 to 183.550, the Commissioner of the Bureau of Labor and Industries may adopt rules to carry out the provisions of this section.*

(c) When No Federal Funds Are Involved - The Contractor shall comply with the requirements of the publication, "Oregon Prevailing Wage Rate Schedule for Public Works Contracts in Oregon", which is bound with the Special Provisions.

The Contractor shall comply with the overtime requirements of ORS 279.334 (see (b) of this Subsection) and ORS 279.354:

ORS 279.354 Certification of rate of wage by contractor or subcontractor.

(1) *The contractor or the contractor's surety and every subcontractor or the subcontractor's surety shall file certified statements with the public contracting agency in writing in form prescribed by the Commissioner of the Bureau of Labor and Industries, certifying the hourly rate of wage paid each worker whom the contractor or the subcontractor has employed upon such public work, and further certifying that no worker employed upon such public work has been paid less than the prevailing rate of wage or less than the minimum hourly rate of wage specified in the contract, which certificate and statement shall be verified by the oath of the contractor or the contractor's surety or subcontractor or the subcontractor's surety that the contractor or subcontractor has read such statement and certificate and knows the contents thereof and that the same is true to the contractor or subcontractor's knowledge. The certified statements shall set out accurately and completely the payroll records for the prior week including the name and address of each worker, the worker's correct classification, rate of pay, daily and weekly number of hours worked, deductions made and actual wages paid.*

(2) *Each certified statement required by subsection (1) of this section shall be delivered or mailed by the contractor or subcontractor to the public contracting agency. Certified statements for each week during which the contractor or subcontractor employs a worker upon the public work shall be submitted once a month, by the fifth business day of the following month. Information submitted on certified statements may be used only to ensure compliance with the provisions of ORS 279.348 to 279.380.*

(3) *Each contractor or subcontractor shall preserve the certified statements for a period of three years from the date of completion of the contract.*

(4) *Certified statements received by a public contracting agency are public records subject to the provisions of ORS 192.410 to 192.505.*

(d) Time Limitation on Claim for Overtime - Pursuant to ORS 279.336, the Contractor shall:

(1) Cause a circular, clearly printed in blackface pica type and containing a copy of ORS 279.336, to be posted in a prominent place alongside the door of the timekeeper's office or in a similar place which is readily available and freely visible to any or all workers employed to perform Work, and

(2) Maintain such circular continuously posted from the inception to the completion of the Contract on which workers are or have been employed.

(e) Owner/Operator Data - If requested by the Engineer, the Contractor shall furnish data for each owner/operator providing trucking services covered by Davis-Bacon or Oregon prevailing wage Laws.

The data must be provided at or before the time the services are provided and must include without limitation for each owner/operator:

- Driver's name;
- Social security number;
- Vehicle identification number;
- Motor vehicle license plate number; and
- Motor Carrier Plate Number.

Failure to provide this information upon request may result in withholding payment as provided in 00195.50(e).

00170.70 Insurance Coverages:

(a) Commercial General Liability - The Contractor shall obtain, at its expense, and keep in effect during the term of the Contract, Commercial General Liability Insurance covering bodily injury and property damage. This insurance shall include personal injury coverage, contractual liability coverage for the indemnity provided under the Contract, and products/completed operations liability. The policy limits shall not be less than \$1,000,000 each occurrence/\$2,000,000 general aggregate. The policy shall be endorsed to state that the general aggregate limit of liability shall apply separately to the Contract.

(b) Automobile Liability - The Contractor shall obtain at its expense, and keep in effect during the term of the Contract, Automobile Liability Insurance covering owned, non-owned, and/or hired vehicles, as applicable. This coverage may be written in combination with the Commercial General Liability Insurance. Combined single limit per occurrence shall not be less than \$1,000,000 or the equivalent.

(c) Workers' Compensation - All employers, including the Contractor and its Subcontractors, if any, that employ subject workers who are performing Work or providing labor or Materials under the Contract in the State shall comply with ORS 656.017 and provide the required Workers' Compensation coverage, unless such employers are exempt under ORS 656.126. The Contractor shall ensure that each of its Subcontractors complies with these requirements.

The Contractor shall certify in the Contract that the Contractor is registered by the Oregon Workers' Compensation Division either as a carrier-insured employer, a self-insured employer, an exempt employer, or is an independent contractor who will perform the Work without the assistance of others.

The Contractor shall ensure that its insurance carrier files a guaranty contract with the Oregon Workers' Compensation Division before performing any Work.

(d) Builders' Risk (for Projects with buildings, when the buildings are estimated to cost over \$100,000) - During the term of the Contract, the Contractor shall maintain in force, at its expense, Builders' Risk insurance on an all-risk form, including earthquake and flood damage, for an amount equal to the full Contract Amount. Any deductible shall not exceed \$50,000 each loss, except that the earthquake and flood deductible shall be no more than 5% of each loss or \$50,000, whichever is less. The policy must include as additional insureds: the Agency, (insert the proper jurisdiction: the State, the County, City, or other political jurisdiction, as applicable); the Agency's governing body, board, or commission and its members; and the Agency's officers and employees; each as their interests may appear.

(e) "Tail" Coverage - If any of the aforementioned liability insurance is arranged on a "claims made" basis, "tail" coverage will be required at the completion of the Contract for a duration of 24 months, or the maximum time period the Contractor's insurer will provide such if less than 24 months. The Contractor shall furnish certification of "tail" coverage as described, or continuous "claims made" liability coverage, for 24 months following Contract completion. Continuous "claims made" coverage will be acceptable in lieu of "tail" coverage, provided its retroactive date is on or before the effective date of the Contract. This will be a condition of Final Acceptance.

(f) Additional Insured - The commercial general liability and automobile liability insurance coverages shall include: the Agency (insert the proper jurisdiction: the State, the County, City, or other political jurisdiction, as applicable); the Agency's governing body, board, or commission and its members; and the Agency's officers and employees; all as Additional Insureds, but only with respect to the Contractor's activities to be performed under the Contract.

(g) Notice of Cancellation or Change - The Contractor shall not cancel, change materially, or take any action showing intent not to renew the insurance coverage(s) without 30 days' written notice from the Contractor or its insurer(s) to the Agency. Any failure to comply with the reporting provisions of this insurance shall not affect the coverage(s) provided to: the Agency (the State of Oregon, County, City, or other applicable political jurisdiction); the Agency's governing body, board, or Commission and its members; and the Agency's officers and employees.

(h) Certificate(s) of Insurance - As evidence of the insurance coverages required by this Contract, the Contractor shall furnish Certificate(s) of Insurance to the Agency prior to its issuance of a Notice to Proceed. The Certificate(s) will specify all of the parties who are Additional Insureds. The Contractor shall obtain insurance coverages required under this Contract from insurance companies or entities acceptable to the Agency and authorized to issue insurance in the State. The Contractor shall be responsible for paying all deductibles, self-insured retentions and/or self-insurance included under these provisions.

00170.71 Independent Contractor Status - The service or services to be rendered under this Contract are those of an independent contractor. The Contractor is not an officer, employee, or agent of the State as those terms are used in ORS 30.265.

00170.72 Indemnity; Hold Harmless - The Contractor shall indemnify, defend, and hold harmless: the Agency, and State, County, City, and other political subdivisions having jurisdiction over the Project Site; the Agency's governing body, board, or commission and its members; and the Agency's officers, agents, and employees from all claims, suits, or actions of any nature arising out of, or relating to, the activities of the Contractor, its officers, Subcontractors, agents, or employees under the Contract.

00170.74 Employee Drug Testing Program - As required by ORS 279.312, the Contractor shall have in place, and maintain during the period of the Contract, an employee drug-testing program. The Agency retains the right to audit and/or monitor the program. On request by the Engineer, the Contractor shall furnish a copy of the employee drug-testing program.

00170.75 Conflict of Interest - The Contractor shall not give or offer any gift, loan, or other thing of value to any member of the Agency's governing body or employee of the Agency in connection with the award or performance of any Contract.

The Contractor shall not rent, lease, or purchase Materials, supplies, or Equipment, with or through any Agency employee or member of the Agency's governing body.

No ex-employee of the Agency who has worked for the Agency on any phase of the Project within the prior two years may be employed by the Contractor to perform Work on the Project.

00170.79 Third Party Beneficiary - There are no third-party beneficiaries of the Contract.

00170.80 Responsibility for Damage to Work:

(a) Responsibility for Damage in General - Except as otherwise provided in this Section, the Contractor shall perform Work, and furnish Materials and Equipment for incorporation into the Work, at the Contractor's own risk, until the entire Project has been completed and accepted by the Agency. The Contractor shall repair all damages to Work performed, Materials supplied, and Equipment incorporated into the Work, except as otherwise provided in this Section.

(b) Repair of Damage to Work - The Contractor shall promptly rebuild, repair, restore, and make good damages to any portion of the permanent or temporary Work, regardless of whether the Contractor has been relieved of responsibility pursuant to the provisions of this Subsection, unless the Engineer directs otherwise. Where the Contractor has been relieved of responsibility for the damage, Work required to repair damage to the Work shall be considered Extra or Changed Work. (See 00140.30 and 00140.60.) The Engineer may elect to have such Extra or Changed Work performed by Agency forces or other means.

Where the Contractor has not been relieved of responsibility for the damage pursuant to a provision of this Subsection, the Contractor shall be responsible for promptly rebuilding, repairing, restoring, and making good damages to any portion of the permanent or temporary Work occurring before issuance of Third Notification with no additional compensation, except for repairs necessitated by damage caused by:

- Acts of God or Nature, as defined in Section 00110, or
- Actions of governmental authorities.

(c) Partial Relief of Responsibility for Damage to Work Caused by Public Traffic:

(1) Interim Acceptance - The Contractor may request in writing interim acceptance of certain completed portions of the Work, such as drainage facilities and traffic control devices. If approved, the Engineer will issue written interim acceptance stipulating the scope and duration of the Contractor's relief from responsibility for damage to Work caused by public traffic. The Engineer will also include in the interim acceptance the scope and duration of Contractor's relief, if any, from responsibility for protection and maintenance under 00150.75.

(2) Scope of Relief - For the duration of interim acceptance issued by the Engineer, the Contractor will be relieved of responsibility to repair those portions of the Work upon which relief was granted under this Subsection. The scope of potential relief applies only to damages caused by public traffic and is limited to the following:

- A segment of Roadway, drainage facilities, Slopes, lighting, traffic control devices and access facilities;
- A Bridge or other Structure within a segment of Roadway;
- Traffic signals and appurtenances at an intersection;
- Permanent, passive traffic control devices;
- Complete circuits of a highway lighting system; and
- Portions of a building open to public use.

(d) Vandalism - The Contractor shall provide reasonable protection of the Work from vandalism until Third Notification. If reasonable protection has been provided, the Contractor's responsibility for

damage resulting from vandalism will be limited to \$5,000 per occurrence. Requests for reimbursement of amounts in excess of \$5,000 shall be in writing and directed to the Engineer. Upon receipt, the Engineer will investigate, evaluate the amount of damages and their cause, and determine whether, and how much, the Contractor will be recompensed.

00170.82 Responsibility for Damage to Property and Facilities:

(a) In General - As used in this Subsection, the term "Contractor" shall include the Contractor's agents, Subcontractors, and all workers performing Work under the Contract; and the term "damage" shall include without limitation soiling or staining surfaces by tracking or splashing mud, asphalt, and other materials, as well as damage of a more serious nature.

The Contractor shall be solely responsible for damages arising from:

- The Contractor's operations;
- The Contractor's negligence, gross negligence, or intentional wrongful acts; and
- The Contractor's failure to comply with any Contract provision.

The Agency may withhold funds due the Contractor or the Contractor's Surety until all lawsuits, actions, and claims for injuries or damages are resolved, and satisfactory evidence of resolution is furnished to the Agency.

(b) Protection and Restoration of Agency Property and Facilities - The following requirements apply to highways, highway Structures and other improvements that are existing, under construction, or completed. The Contractor shall:

- Provide adequate protection to avoid damaging Agency property and facilities;
- Be responsible for damage to Agency property and facilities caused by or resulting from the Contractor's operations; and
- Clean up and restore such damage by repair, rebuilding, replacement, or compensation, as determined by the Engineer.

(c) Protection and Restoration of Non-Agency Property and Facilities - The Contractor shall determine the location of properties and facilities that could be damaged by the Contractor's operations, and shall protect them from damage. The Contractor shall protect monuments and property marks until the Engineer has referenced their location and authorized their removal. The Contractor shall restore property or facilities damaged by its operations to the condition that existed before the damage, at no additional compensation.

The Contractor shall provide temporary facilities when needed, e.g., to maintain normal service or as directed by the Engineer, until the required repair, rebuilding, or replacement is accomplished.

The Contractor shall protect specific service signs, e.g., business logos, and tourist-oriented directional signs ("TODS") from damage, whether the signs are to remain in place or be placed on temporary supports. The Contractor shall repair or replace damaged signs at no cost to the Agency. Liquidated damages will be assessed against the Contractor in the amount of \$200 per day for each sign out of service for more than five Calendar Days because of the Contractor's operations.

00170.85 Responsibility for Defective Work - The Contractor shall make good any defective Work, Materials or Equipment incorporated into the Work, in accordance with the provisions of Section 00150.

(a) Latent Defects - The Contractor shall remain liable for all latent defects resulting from causes other than fraud or gross mistakes that amount to fraud until the expiration of the Performance Bond, Warranty Bond, or warranty period, whichever expires last. The Contractor shall remain liable for all latent defects resulting from fraud or gross mistakes that amount to fraud regardless of when those latent defects may be discovered, and regardless of whether such discovery occurs outside any applicable Performance Bond, Warranty Bond, or warranty period.

(b) Warranties - For those Pay Items with Specifications referencing this 00170.85(b) warranty, the Contractor warrants that all Work, including Changed Work, Additional Work, Incidental Work, On-Site Work, and Extra Work, and Materials and Equipment incorporated into the Work, shall meet the technical and performance Specifications required under the Contract, from the date and for the period of time identified in each applicable Specification or elsewhere in the Contract. The Contractor shall be responsible for making good the Work, and for all repairs of damage to other improvements, natural and artificial structures, systems, equipment, and vegetation caused by, or resulting in whole or in part from, defects in warranted Materials, Equipment, and workmanship. The Contractor shall be responsible for all costs associated with site cleanup and remediation caused by, or resulting in whole or in part from, defects in warranted Materials, Equipment, or workmanship. This warranty provision shall survive expiration or termination of the Contract.

00170.89 Protection of Utility, Fire-control, and Railroad Property and Services; Repair; Roadway Restoration:

(a) Protection of Utility, Fire-Control, and Railroad Property and Services; Coordination - The Contractor shall avoid damaging the properties of Utilities, Railroads, railways, and fire-control authorities during performance of the Work. The Contractor shall cooperate with and facilitate the relocation or repair of all Utilities and Utility services, as required under 00150.50, and of Railroad and fire-control property and railways.

The Contractor shall conduct no activities of any kind around fire hydrants until the local fire-control authority has approved provisions for continued service.

The Contractor shall immediately notify any Utility, Railroad, or fire-control authority whose facilities have been damaged.

If an Entity has a valid permit from the proper authority to construct, reconstruct, or repair Utility, Railroad, or fire-control service in the Roadway, the Contractor shall allow the permit holder to perform the work.

(b) Restoration of Roadway after Repair Work - The Contractor shall restore the Roadway to a condition at least equal to that which existed before the repair work addressed under this Subsection was performed, as directed by the Engineer. Restoration will be paid as provided in the Special Provisions or may be paid as Extra Work.

00170.92 Fencing, Protecting Stock, and Safeguarding Excavations - The Contractor shall be responsible for loss, injury, or damage that results from its failure to restrain stock and persons.

(a) At the Contractor's Expense - The Contractor shall restrain stock to lands on which they are confined using temporary fences or other adequate means. The Contractor shall provide adequate temporary fences or other protection around excavations to prevent animals and unauthorized persons from entering.

The Contractor shall repair, at Contractor's expense and to the Engineer's satisfaction, fences damaged by the Contractor's operations and the operations of the Contractor's agents, employees and Subcontractors.

00170.92(b)

(b) At the Agency's Expense - The Contractor shall construct fences, or move and reconstruct fences, as shown on the Contract Documents or as directed by the Engineer. The Contractor shall tear down and remove fencing within the Right-of-Way when no longer needed, as part of the removal Work described in and paid for pursuant to Section 00310.

00170.93 Trespass - The Contractor shall be responsible for its own, its agents' and employees', and its Subcontractors' trespass or encroachment upon, or damage to, property during performance of the Contract.

00170.94 Use of Explosives - The Contractor shall comply with all Laws pertaining to the use of explosives. The Contractor shall notify anyone having facilities near the Contractor's operations of Contractor's intended use or storage of explosives. The Contractor shall be responsible for all damage resulting from its own, its agents' and employees', and its Subcontractors' use of explosives. (See 00330.41(e) and Section 00335.)

PART 00100 REPLACED JANUARY, 2006

Section 00180 - Prosecution and Progress

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

00180.00 Scope - This Section consists of requirements for assignment of the Contract, subcontracting, time for performance, Contract responsibility, suspensions, terminations, and related provisions.

00180.05 Assignment/Delegation of Contract - Unless the Agency gives prior written consent, the Contractor shall not assign, delegate, sell, or transfer to any Entity, or otherwise dispose of any Contract rights or obligations, including without limitation:

- The power to execute or perform the Contract, or
- Any of its right, title or interest in the Contract.

Any attempted assignment, delegation, or disposition without prior Agency consent shall be void.

Such Agency consent will not normally be given except for the assignment of funds due under the Contract, as provided in 00180.06.

If written Agency consent is given to assign, delegate, or otherwise dispose of any Contract rights or obligations, it shall not relieve the Contractor or its Surety of any part of their responsibility under the Contract.

00180.06 Assignment of Funds Due under the Contract - Assignment of funds due or to become due under the Contract to the Contractor will not be permitted unless:

- The assignment request is made on the form provided by the Agency;
- The Contractor secures the written consent of the Contractor's Surety to the assignment; and
- The Engineer approves the assignment.

00180.10 Responsibility for Contract - The Contractor shall direct and coordinate the operations of its employees, Subcontractors and agents performing Work, and see that the Engineer's orders are carried out promptly. The Contractor's failure to direct, supervise and control its employees, Subcontractors and agents performing Work will result in one or more of the following actions, as the Engineer deems appropriate:

- Suspension of the Work;
- Withholding of Contract payments, as necessary to protect the Agency;
- Ordering removal of individuals from the Project Site; or
- Termination of the Contract.

00180.15 Agency's Right to Do Work at Contractor's Expense - Except as otherwise provided in 00150.75 and 00220.60, if the Contractor neglects to prosecute the Work properly or fails to perform any provision of the Contract, the Agency may, after two Calendar Days' written notice, correct the deficiencies at the Contractor's expense. In situations where the Engineer reasonably believes there is danger to life or property, the Agency may immediately and without notice correct the deficiencies at the Contractor's expense.

Action by the Agency under this provision will not prejudice any other remedy it may have.

00180.20 Subcontracting Limitations:

(a) General - The Contractor's own organization shall perform Work amounting to at least 30% of the original Contract Amount. The value of subcontracted Work is the full compensation to be paid to the Subcontractor(s) for all pay items in the Subcontract(s).

(b) Own Organization - The term "own organization", as used in Section 00180, includes only employees of the Contractor, Equipment owned or rented by the Contractor, Incidental rental of operated Equipment, and Materials and Equipment to be incorporated into the Work purchased or produced by the Contractor.

(c) Rental of Operated Equipment - The use of Equipment rented with operators will be permitted only if the following requirements are met:

(1) Written Request - The Contractor has submitted to the Engineer a written request describing the service to be provided, its estimated cost, and the estimated duration. The Engineer must approve the request before the service is provided.

(2) Limitations - The service is limited to:

- Truck hauling of Materials, and
- Performing minor, Incidental, short-duration work under the direct supervision of the Contractor or Subcontractor, with Equipment not customarily owned, leased, or operated by a Contractor, or with Equipment that is temporarily unavailable to the Contractor.

(3) Submittals - The Contractor shall provide the Engineer with a copy of the rental agreement or purchase order covering the service to be provided. The Contractor shall make certain that the provider of approved services submits payrolls required under Section 00170 and complies with applicable Contract provisions. The service provider will not be considered a Subcontractor under the Contract, but will be considered an agent of the Contractor in the performance of Work.

(4) Revocation of Approval - The Engineer may revoke approval for the services provided through rented, operated Equipment at any time the Engineer determines that the work is outside that authorized under Subsection 00180.20(c-2). Unless the Contractor promptly submits to the Engineer a subcontract agreement for consent under 00180.21, the service provider shall be immediately removed from the Project Site.

00180.21 Subcontracting:

(a) General - The Contractor shall not subcontract or perform any portion of the Contract by other than the Contractor's own organization without the Agency's prior written consent. A request for consent to subcontract, at any tier, solely for the furnishing of a labor force will not be considered.

A written request for consent to subcontract any portion of the Contract at any tier shall be submitted to the Engineer, and when required by the Engineer, shall be accompanied by background information showing that the organization proposed to perform the Work is experienced and equipped for such Work. The Agency will review the Contractor's submission to verify compliance with Contract requirements, confirm the percentage of Work subcontracted, and evaluate the proposed Subcontractor's ability to perform the Work.

(b) Submittal of Requests - The Contractor must submit requests for consent to subcontract any portion of the Contract, at any tier, on the Agency's form, available from the Engineer. The Contractor

shall attach a duplicate original subcontract agreement. The Contractor must also submit in writing any amendments or modifications proposed to Agency-approved subcontract agreements, at any tier, before the affected Work begins. The Agency's written consent will be required before such amendments or modifications become effective.

(c) Substitution of Disclosed Subcontractors - The Contractor may only substitute a previously undisclosed first-tier Subcontractor in accordance with the provisions of ORS 279.322. The Contractor shall provide the Engineer with a written notification that identifies the name of the proposed new Subcontractor and the reason for the substitution. Authorized reasons for substitution are limited to the following circumstances (See ORS 279.322(1) through (10)):

- The disclosed Subcontractor fails or refuses to execute a written contract that is reasonably based either upon the Project Plans and Specifications, or the terms of the Subcontractor's written Bid, after having had a reasonable opportunity to do so;
- The disclosed Subcontractor becomes bankrupt or insolvent;
- The disclosed Subcontractor fails or refuses to perform the contract;
- The disclosed Subcontractor fails or refuses to meet the bond requirements of the prime Contractor that had been identified prior to the Bid submittal;
- The Contractor demonstrates to the Agency that the Subcontractor was disclosed as the result of an inadvertent clerical error;
- The disclosed Subcontractor does not hold a license from the Construction Contractors Board and is required to be licensed by the board;
- The Contractor determines that the Work performed by the disclosed Subcontractor is not in substantial compliance with the Plans and Specifications, or that the Subcontractor is substantially delaying or disrupting the progress of the Work;
- The disclosed Subcontractor is ineligible to work on a public improvement pursuant to the applicable statutory provisions;
- The substitution is for "good cause" as defined by State Construction Contractors Board rule; or
- The substitution is reasonably based on the Contract alternates chosen by the Agency.

(d) Terms of Subcontracts - Subcontracts shall provide that work performed under the subcontract shall be conducted and performed according to the terms of the Contract. Additionally, in accordance with the provisions of ORS 279.445, subcontracts shall include:

(1) A payment clause that obligates the Contractor to pay the first-tier Subcontractor for satisfactory performance under its subcontract within ten Calendar Days of the Contractor's receipt of payment from the Agency for the subcontracted Work.

(2) An interest clause that obligates the Contractor, if payment is not made within 30 days after receipt of payment from the Agency, to pay to the first-tier Subcontractor interest on amounts due in the case of each payment not made in accordance with the payment clause included in the subcontract pursuant to paragraph (1) of this Subsection. A Contractor or first-tier Subcontractor shall not be obligated to pay interest if the only reason that the Contractor or first-tier Subcontractor did not make payment when payment was due is that the Contractor or first-tier Subcontractor did not receive payment from the Agency or Contractor when payment was due.

The interest shall be for the period beginning on the day after the required payment date and ending on the date on which payment of the amount due is made; and shall be computed at the rate specified in 00170.10(c).

(3) A provision requiring the first-tier Subcontractor to include a payment clause and an interest clause conforming to the standards of ORS 279.445 (see 00180.21(d-1) and (d-2) above) in each of its subcontracts, and to require each of its subcontractors to include such clauses in their subcontracts with each lower-tier subcontractor or Materials supplier.

This payment clause shall require the Contractor to return all retainage withheld from the Subcontractor, whether held by the Contractor or the Agency, as specified in 00195.50(d).

(e) **Contractor's Responsibilities** - As a condition of the Agency's grant of consent to subcontract, whether or not stated in the subcontract agreement itself, the Contractor shall remain solely responsible for administration of the subcontract, including but not limited to:

- Performance of subcontracted Work;
- Progress of subcontracted Work;
- Payments for accepted subcontracted Work; and
- Disputes and claims for additional compensation regarding subcontracted Work.

The Engineer's consent to subcontract will not create a contract between the Agency and the Subcontractor, will not convey to the Subcontractor any rights against the Agency, and will not relieve the Contractor or the Contractor's Surety of any of their responsibilities under the Contract.

(f) **Failure to Comply** - Failure to comply with 00180.21 will be cause for the Engineer to take action reasonably necessary to obtain compliance. This action may include, but is not limited to:

- Suspension of the Work;
- Withholding of Contract payments as necessary to protect the Agency; and
- Termination of the Contract.

00180.22 Payments to Subcontractors and Agents of the Contractor - To the extent practicable, the Contractor shall pay in the same units and on the same basis of measurement as listed in the Schedule of Items for subcontracted Work or other Work not done by the Contractor's own organization. In making payment to Subcontractors and to its other agents performing Work and furnishing Materials and Equipment to be incorporated into the Work, the Contractor shall assume all losses resulting from overpayment.

If requested, the Engineer will make estimates of the Work quantities performed by Subcontractors or by others on the Project, and of Materials eligible for advances on Materials in the progress payments. These estimates are approximate only, and will be made in units of measure as listed in the Schedule of Items. The Agency does not guarantee the accuracy of these estimates, and an incorrect estimate will not bind the Agency in final settlement.

If requested in writing by a first-tier Subcontractor, the Contractor shall send to the Subcontractor, within ten Calendar Days of receiving the request, a copy of that portion of any invoice or request for payment submitted to the Agency, or pay document provided by the Agency to the Contractor, specifically related to any labor, Equipment, or Materials supplied by the first-tier Subcontractor.

00180.30 Materials, Equipment, and Work Force - The Contractor shall furnish suitable and sufficient Materials, Equipment, and personnel to properly prosecute the Work. The Contractor shall use only Equipment of adequate size and condition to meet the requirements of the Work and Specifications, and to produce a satisfactory quality of Work. Upon receipt of the Engineer's written order, the Contractor shall immediately remove, and not use again on the Project without the Engineer's prior written approval, Equipment that, in the Engineer's opinion, fails to meet Specifications or produce a satisfactory product or result.

The work force shall be trained and experienced (see Section 00150). Upon receipt of the Engineer's written order, the Contractor shall immediately remove from the Project Site, and shall not employ again on the Project without the Engineer's prior written approval, any supervisor or employee of the Contractor or its Subcontractors who, in the Engineer's opinion, does not perform satisfactory Work or whose conduct interferes with the progress of the Work.

If the Contractor fails to remove Equipment or persons as ordered, or fails to furnish suitable and sufficient Materials, Equipment and personnel for the proper prosecution of the Work, the Engineer may suspend the Work by written notice until such orders are complied with and such deficiencies are corrected, or the Engineer may terminate the Contract under the provisions of 00180.90(a).

00180.31 Required Materials, Equipment and Methods:

(a) General - When the Equipment and methods to be used are not specified in the Contract, any Equipment or methods that accomplish the Work as required by the Contract will be permitted.

When the Contract specifies certain Equipment or methods, the Contractor shall use the Equipment or methods specified unless otherwise authorized by the Engineer in writing.

(b) Substitution of Materials and Equipment to be Incorporated into the Work - After execution of the Contract, the Engineer will approve substitution of Materials and Equipment to be incorporated into the Work as follows:

(1) Reasons for Substitution - The Engineer will consider substitution only if:

- The proposed Materials or Equipment are equal to or superior to the specified items in construction, efficiency and utility, or
- Due to reasons beyond the control of the Contractor, the specified Materials or Equipment cannot be delivered to the Project in sufficient time to complete the Work in proper sequence.

(2) Submittal of Request - The Contractor shall submit requests for substitution to the Engineer, including manufacturers' brochures and other information needed to verify equality of the proposed item(s).

(c) Substitution of Equipment Specified to Perform Work - The Agency encourages development of new or improved Equipment and innovative use of Equipment. When the Specifications require Equipment of a particular size or type to be used to perform certain portions of the Work, the Contractor may submit a request to the Engineer to use Equipment of a different size or type. The request will not be considered as a cost reduction proposal under 00140.70. The request shall:

- Be in writing and include a full description of the Equipment proposed and its intended use;
- Include the reasons for requesting the substitution; and

- Include evidence, obtained at the Contractor's expense and satisfactory to the Engineer, that the proposed Equipment is capable of functioning as well as or better than the specified Equipment.

The Engineer will consider the Contractor's request and will provide a written response to the Contractor, either permitting or denying use of the proposed Equipment. The Engineer's decision is final.

Permission may be granted on a trial basis to test the quality of Work actually produced, subject to the following:

- There will be no cost to the Agency, either in Contract Amount or in Contract Time.
- The permission may be withdrawn by the Engineer at any time if, in the Engineer's opinion, the Equipment is not performing in all respects equivalent to the Equipment specified in the Contract;
- If permission is withdrawn, the Contractor shall perform the remaining Work with the originally-specified Equipment; and
- The Contractor shall remove and replace nonspecification Work resulting from the use of the Contractor's proposed Equipment, or otherwise correct it as the Engineer directs, at no additional compensation.

(d) Substitution of Methods - The Agency encourages development of new, improved, and innovative construction methods. When the Plans or Specifications require a certain construction method for a portion of the Work, the Contractor may submit a request for a change by following the provisions of 00140.70, "Cost Reduction Proposals".

00180.32 Alternative Materials, Equipment, and Methods - Whenever the Contract authorizes certain alternative Materials, Equipment, or methods of construction for the Contractor's use to perform portions of the Work, and leaves the selection to the Contractor, the Agency does not guarantee that all listed alternative Materials, Equipment, or methods of construction can be used successfully throughout all or any part of the Work.

The Contractor shall employ only those alternatives that can be used to satisfactorily perform the Work. No additional compensation will be paid for corrective work necessitated by the Contractor's use of an inappropriate alternative.

00180.33 Metric Submittals - The Contractor shall use metric units for all calculations and measurements, Working Drawings, Materials certifications, delivery tickets, and other documents submitted in conjunction with performance of the Contract.

00180.40 Limitation of Operations:

(a) In General - The Contractor shall comply with all Contract provisions and shall:

- Conduct the Work at all times so as to cause the least interference with traffic, and
- Not begin Work that may allow damage to Work already started.

(b) On-Site Work - The Contractor shall not begin On-Site Work until the Contractor has:

- Received Notice to Proceed;

- An approved Project Work schedule;
- An approved Traffic Control Plan;
- An approved Pollution Control Plan;
- An approved Erosion and Sediment Control Plan;
- Met with the Engineer at the required preconstruction conference; and
- Assembled all Materials, Equipment, and labor on the Project Site, or has reasonably assured that they will arrive on the Project Site, so the Work can proceed according to the Project Work schedule.

00180.41 Project Work Schedules - The Contractor shall submit a Project Work schedule meeting the requirements of this Subsection to the Engineer. The Project Work schedule is intended to identify the sequencing of activities and time required for prosecution of the Work. The schedule is used to plan, coordinate, and control the progress of construction. Therefore, the Project Work schedule shall provide for orderly, timely, and efficient prosecution of the Work, and shall contain sufficient detail to enable both the Contractor and the Engineer to plan, coordinate, analyze, document, and control their respective Contract responsibilities.

Contractor's activity related to developing, furnishing, monitoring, and updating these required schedules is Incidental.

(a) Type "A" Schedule - The Contractor shall submit Project Work schedules as outlined below, to plan, coordinate, and control the progress of construction.

Ten Calendar Days prior to the preconstruction conference, the Contractor shall provide to the Engineer four copies of a Project Work schedule, including a time-scaled bar chart and narrative, showing:

- Expected beginning and completion dates of each activity, including all staging; and
- Elements of the Traffic Control Plan as required under 00225.05.

The schedule shall show detailed Work activities as follows:

- Construction activities;
- Submittal and approval of Materials samples and shop drawings;
- Fabrication, installation, and testing of special Materials and Equipment; and
- Duration of Work, including completion times of all stages and their subphases.

For each activity, the Project Work schedule shall list the following information:

- A description in common terminology;
- The quantity of Work, where appropriate, in common units of measure;
- The activity duration in Calendar Days; and
- Scheduled start, completion, and time frame shown graphically using a time-scaled bar chart.

The schedule shall show the Work broken down into logical, separate activities by area, stage, or size. The duration of each activity shall be verifiable by manpower and Equipment allocation, in common units of measure, or by delivery dates.

The bar chart shall be prepared as follows:

- The length of bar shall represent the number of workdays scheduled.
- The time scale shall be appropriate for the duration of the Contract.
- The time scale shall be in Calendar Days.
- The smallest unit shown shall be one Calendar Day.
- The first day and midpoint of each month shall be identified by date.
- Distinct symbols shall be used to denote multiple shift, holiday, and weekend Work.

Each page of the bar chart shall include a title block showing the Contract name, and number, Contractor's name, date of original schedule, and all update dates; and a legend containing the symbols used, their definitions, and the time scale, shown graphically. To ensure readability the bar chart shall be drawn on a reasonable size of paper up to a maximum of 915 mm x 915 mm (36 inch by 36 inch), using multiple sheets when needed.

Within seven Calendar Days after the preconstruction conference, the Engineer and the Contractor shall meet to review the Project Work schedule as submitted. The Engineer will review the schedule for compliance with all Contract Time limitations and other restraints. Review of this and subsequent schedules by the Engineer shall not relieve the Contractor of responsibility for timely and efficient execution of the Contract. Within 10 Calendar Days of this meeting, the Contractor shall resubmit to the Engineer four copies of the Project Work schedule, including required revisions.

(b) Review by the Engineer - The Project Work schedule may need revision as the Work progresses. Therefore, the Contractor shall periodically review the Project Work schedule and progress of the Work with the Engineer. If the Engineer or the Contractor determines that the Project Work schedule no longer represents the Contractor's own plans or expected time for the Work, a meeting shall be held between the Engineer and the Contractor. At this meeting, the Contractor and the Engineer shall review Project events and any changes for their effect on the Project Work schedule.

The Contractor shall compile an updated Project Work schedule incorporating any changes to the Project completion time(s). The bar chart shall reflect the updated information. The Contractor shall submit four copies of the updated Project Work schedule to the Engineer within seven Calendar Days after the meeting. The report shall include without limitation the following:

- Sufficient narrative to describe the past progress, anticipated activities, and stage Work;
- A description of any current and expected changes or delaying factors and their effect on the construction schedule; and
- Proposed corrective actions.

(c) Substitution of Type "B" or "C" Schedule - A Type "B" or Type "C" schedule may be substituted for a Type "A" schedule. Information on Type "B" and Type "C" schedules, if not included in the Special Provisions, may be obtained from the Engineer.

(d) Specified Contract Time Not Superseded by Schedule Revisions - The predicted completion date(s) for the Project Work schedule shall be within the specified Contract Time(s) or adjusted Contract Time or as shown on pending requests for adjustments of Contract Time. If the Contractor believes that additional Contract Time is due, the Contractor shall submit, with the updated Project Work Schedule, a request for adjustment of Contract Time according to 00180.80(c).

(e) Float Time - Float time shown on the Project Work schedule, including any time between a Contractor's scheduled completion date and the specified Contract completion date, does not exist for the exclusive use of either party to the Contract and belongs to the Project.

(f) Schedules Do Not Constitute Notice - Submittal of a Project Work schedule with supporting narrative does not constitute or substitute for any notice the Contractor is required under the terms of the Contract to give the Agency.

(g) Failure to Provide Schedule - The Project Work schedule is essential to the Agency. The Contractor's failure to provide the schedule, schedule information, progress reports or schedule updates when required will be cause to suspend the Work, or to withhold Contract payments as necessary to protect the Agency, until the Contractor provides the required information to the Engineer.

00180.42 Preconstruction Conference - Before any Work is performed, and within 30 Calendar Days of the Notice to Proceed, unless otherwise approved in writing by the Engineer, the Contractor shall meet with the Engineer for a preconstruction conference at a time mutually agreed upon.

00180.43 Commencement and Performance of Work - From the time of commencement of the Work to the time of Contract completion the Contractor shall:

- Provide adequate Materials, Equipment, labor, and supervision to perform the Work;
- Perform the Work as vigorously and as continuously as conditions permit, and according to a Project Work schedule that ensures completion within the Contract Time or the adjusted Contract Time;
- Not voluntarily suspend or slow down operations without prior written approval from the Engineer; and
- Not resume suspended Work without the Engineer's written authorization.

00180.50 Contract Time to Complete Work:

(a) General - The time allowed to complete the Work or Pay Item is stipulated in the Solicitation Documents, and will be known as the "Contract Time" (see 00110.20).

(b) Kinds of Contract Time - The Contract Time will be expressed in one or more of the following ways:

(1) Fixed Date Calculation - The calendar date on which the Work or Pay Item shall be completed, or

(2) Calendar Day Calculation - The number of Calendar Days from a specified beginning point in which the Work or Pay Item shall be completed.

(c) Beginning of Contract Time - When the Contract Time is stated in Calendar Days, counting of Contract Calendar Days will begin with the fifteenth Calendar Day following the date of the Notice to Proceed.

(d) Recording Contract Time - All Contract Time will be recorded and charged to the nearest one-half day.

On Calendar Day Pay Items, the Engineer will furnish the Contractor a weekly statement of Contract Time charges. The statement will show the number of Calendar Days counted for the preceding week and the number of days remaining prior to the established completion date for that Pay Item.

For Contracts with fixed completion dates for Pay Items, the Engineer will furnish the Contractor a weekly statement of Contract Time charges only after expiration of the Contract Time. The statement will show the number of days of liquidated damages that have been assessed, if any.

These statements will include any exclusions from, or adjustments to, Contract Time.

(e) Exclusions from Contract Time - Regardless of the way Contract Time is expressed in the Contract, certain days will not be charged against Contract Time. These exclusions will be allowed when the Contractor is prevented from performing Work due to one of the following reasons, resulting in delay:

- Acts of God or Nature;
- Court orders enjoining prosecution of the Work;
- Strikes, labor disputes or freight embargoes that, despite the Contractor's reasonable efforts to avoid them, cause a shutdown of the entire Project or one or more major operations. "Strike" and "labor dispute" may include union action against the Contractor, a Subcontractor, a Materials supplier, or the Agency; or
- Suspension of the Work by written order of the Engineer for reasons other than the Contractor's failure or neglect.

(f) Time Calculation Protest - In the event the Contractor disputes the accuracy of the statement of Contract Time charges, it shall immediately contact the Engineer and attempt to resolve the dispute. If the dispute cannot be resolved informally, the Contractor shall submit a formal written protest to the Engineer within seven Calendar Days of the date the Engineer mailed or delivered the statement. Failure to submit a formal written protest within the seven Calendar Day period constitutes the Contractor's approval of the time charges, or adjusted time charges, itemized in the statement.

(g) End of Contract Time - When the Engineer determines that the Work has been completed, except for the items listed below, the Engineer will issue a Second Notification.

The Second Notification will list:

- The date the time charges stopped;
- Final trimming and cleanup tasks (See 00140.90);
- Equipment to be removed from the Project Site;
- Minor corrective work not involving additional payment to be completed; and
- Submittals, including without limitation all required certifications, bills, forms, warranties, certificate of insurance coverage (00170.70(e)), and other documents, required to be provided to the Engineer before Third Notification will issue.

The Contractor shall complete all tasks listed in the Second Notification in an expeditious manner within the time frame proposed by the Contractor and accepted by the Engineer.

00180.60 Notice of Delay - The Contractor shall notify the Engineer of any delay that will likely prevent completion of the Work or a Pay Item by the date specified in the Project Work schedule. The

notice shall be in writing and shall be submitted within seven Calendar Days of when the Contractor knew or should have known of the delay. The notice shall include, to the extent available, the following:

- The reasons or causes for the delay;
- The estimated duration of the delay and the estimated resulting cumulative delay in Contract completion;
- Except for 00180.50(e) and 00180.65 delays, whether or not the Contractor expects to request an adjustment of Contract Time due to the delay; and
- Whether or not the Contractor expects to request additional compensation due to the delay. (Except for 00185.50(e) and 00180.65 delays, failure to include this information will constitute waiver of the Contractor's right to later make such a request.)

The Engineer is not required to respond to a notice of delay.

00180.65 Right-of-Way and Access Delays - Right-of-Way and access delays will be taken into consideration in adjusting Contract Time, and in approving additional compensation if the performance of the Work is delayed because of the Agency's failure to make available to the Contractor:

- Necessary Rights-of-Way;
- Agency-owned or Agency-controlled Materials sources that are offered in the Contract for the Contractor's use; or
- Access to, or rights of occupancy of, buildings and other properties the Contractor is required to enter or to disturb pursuant to Contract requirements.

If the ending date of an anticipated delay is stated in the Special Provisions, only the delay occurring after that date will be considered for adjusting Contract Time or providing additional compensation.

00180.70 Suspension of Work:

(a) General - The Engineer has authority to suspend the Work, or part of the Work, for any of the following causes:

- Failure of the Contractor to correct unsafe conditions;
- Failure of the Contractor to carry out any provision of the Contract;
- Failure of the Contractor to carry out orders issued by the Engineer, the Agency, or any regulatory authority;
- Existence of conditions unsuitable to proper or safe performance of the Work; or
- Any reason considered by the Agency to be in the public interest.

When Work has been suspended for any reason, the Contractor shall not resume Work without the Engineer's written authorization.

(b) Contractor's Responsibilities during and after Suspension - During periods of suspension of the Work, the Contractor shall continue to be responsible for protecting and repairing the Work in

00180.70(b)

accordance with the provisions of 00170.80, and for ensuring that a superintendent remains available in accordance with the provisions of 00150.40(b).

When Work is resumed after suspension, unless otherwise specified in the Contract, the Contractor shall perform the following at no additional compensation:

- Replace or repair any Work, Materials, and Equipment to be incorporated into the Work that was lost or damaged because of the temporary use of the Project Site by the public, and
- Remove Materials, Equipment, and temporary construction necessitated by temporary maintenance during the suspension, as directed by the Engineer.

(c) Compensation and Allowances for Suspension - Compensation and allowance of additional Contract Time due to suspension of any portion of the Work will be authorized only for Agency-initiated suspensions for reasons other than the Contractor's failure or neglect. (Refer to 00180.50(e), 00180.65 and 00195.40.)

00180.80 Adjustment of Contract Time:

(a) General - Contract Time established for the Work will be subject to adjustment, either by increase or decrease, for causes beyond the control of the Contractor, according to the terms of this Subsection. After adjustment, the Contract Time will become, and be designated as, the "Adjusted Contract Time". Except as provided in 00180.65 and 00195.40, an adjustment of Contract Time shall be the Contractor's only remedy for any delay arising from causes beyond the control of the Contractor.

(b) Contractor's Request Not Required - The Engineer may increase or decrease the Contract Time or the Adjusted Contract Time if Change Orders or Extra Work orders issued actually increase or decrease the amount of time required to perform the Work. The Engineer may also increase Contract Time in the event of Right-of-Way and Access delays (see 00180.65), and those delays due to causes beyond the Contractor's control specified in 00180.50(e). The Engineer will promptly inform the Contractor of adjustments made to Contract Time pursuant to this Subsection, and will include the reasons for adjustment.

If the Agency anticipates delay during performance of the Contract, and specifies its expected duration in the Special Provisions, the Engineer will only consider additional delay beyond the stipulated duration in determining whether to adjust Contract Time.

(c) Contractor's Request Required - In the event the Contractor believes that additional Contract Time is due, the Contractor shall submit to the Engineer a timely request for adjustment of Contract Time. The Engineer will not consider untimely requests. The Agency regards as timely only those requests for adjustment of Contract Time that:

- Accompany an updated Project Work schedule submitted according to 00180.41; or,
- Are not otherwise deemed waived and are submitted within 21 days after the date of Second Notification, if Second Notification has been issued.

The Engineer will not grant an adjustment of Contract Time for events that occurred prior to the date of the last revision of the Project Work schedule. The Engineer will not authorize, nor the Agency pay, acceleration costs incurred by the Contractor prior to its submittal of a request for adjustment of Contract Time to which the acceleration costs relate.

The Contractor's request for adjustment of Contract Time shall be submitted to the Engineer on a form provided by, or in a format acceptable to, the Engineer, and shall include a copy of the written notice required under 00180.60. The request shall include without limitation:

- Consent of the Contractor's Surety if the request totals more than 30 Calendar Days of additional Contract Time;
- Sufficient detail for the Engineer to evaluate the asserted justification for the amount of additional Contract Time requested;
- The cause of each delay for which additional Contract Time is requested, together with supporting analysis and data;
- Reference to the Contract provision allowing Contract Time adjustment for each cause of delay;
- The actual or expected duration of delay resulting from each cause of delay, expressed in Calendar Days; and
- A schedule analysis based on the current approved Project Work schedule for each cause of delay, indicating which activities are involved and their impact on Contract completion.

(d) Bases for Adjustment of Contract Time - In the adjustment of Contract Time, the Engineer will consider causes that include, but are not limited to:

- Failure of the Agency to submit the Contract and bond forms to the Contractor for execution within the time stated in 00130.50, or to submit the Notice to Proceed within the time stated in 00130.90;
- Errors, changes, or omissions in the Supplemental Drawings, quantities, or Specifications;
- Performance of Extra Work;
- Failure of the Agency or Entities acting for the Agency to act promptly in carrying out Contract duties and obligations;
- Acts or omissions of the Agency or Entities acting for the Agency that result in unreasonable delay referenced in 00195.40;
- Causes cited in 00180.50(e); and
- Right-of-way and access delays referenced in 00180.65.

The Engineer will not consider requests for adjustment of Contract Time based on any of the following:

- Contentions that insufficient Contract Time was originally specified in the Contract;
- Delays that do not affect the Contract completion date;
- Delays that affect the Contractor's planned early completion, but that do not affect the specified or adjusted Contract Time;
- Shortage or inadequacy of Materials, Equipment or labor;

00180.80(d)

- Late delivery of Materials and Equipment to be incorporated into the Work, except under those conditions referenced in 00180.50(e);
- Reasonably predictable weather conditions; or
- Other matters within the Contractor's control or Contract responsibility.

(e) Consideration and Response by Agency - The Engineer will only consider a Contractor's request for Contract Time adjustment submitted in accordance with the requirements of 00180.80(c). The Engineer may elect not to consider claimed delays that do not affect the specified or adjusted Contract Time required to complete the Work.

The Engineer may adjust Contract Time for causes not specifically identified by the Contractor in its request.

The Engineer will review a properly submitted request for Contract Time adjustment, and within a reasonable time will advise the Contractor of the Engineer's findings. Unless the Contractor submits a timely written request to the Engineer for a meeting to review the findings, the findings shall become the Engineer's final decision ten Calendar Days after they are mailed to the Contractor. If a review meeting is requested, the Engineer's final decision on Contract Time adjustment will be issued promptly following the meeting.

The provisions of Section 00199 do not apply to adjustment of Contract Time unless additional compensation, other than return of liquidated damages, is also requested for the same reasons or causes.

00180.85 Failure to Complete on Time; Liquidated Damages:

(a) Time is of the Essence - Time is of the essence in the Contractor's performance of the Contract. Delays in the Contractor's performance of the Work may inconvenience the traveling public, interfere with business and commerce, and increase cost to the Agency. It is essential and in the public interest that the Contractor prosecute the Work vigorously to Contract completion.

The Agency does not waive any rights under the Contract by permitting the Contractor to continue to perform the Contract, or any part of it, after the Contract Time or adjusted Contract Time has expired.

(b) Liquidated Damages - The Agency will sustain damage if the Work is not completed within the specified Contract Time. However, in certain Agency projects it may be unduly burdensome and difficult to demonstrate the exact dollar value of such damages. The Agency will identify such projects in the Special Provisions related to them. In these projects, the Contractor agrees to pay to the Agency, not as a penalty but as liquidated damages, the amount specified in the Special Provisions for each Calendar Day the Contractor expends performing the Contract in excess of the Contract Time or adjusted Contract Time.

Payment by the Contractor of liquidated damages does not release the Contractor from its obligation to fully and timely perform the Contract according to its terms. Nor does acceptance of liquidated damages by the Agency constitute a waiver of the Agency's right to collect any additional damages it may sustain by reason of the Contractor's failure to fully perform the Contract according to its terms. The liquidated damages shall constitute payment in full only of damages incurred by the Agency due to the Contractor's failure to complete the Work on time.

If the Contract is terminated according to 00180.90(a), and if the Work has not been completed by other means on or before the expiration of Contract Time or adjusted Contract Time, liquidated damages will be assessed against the Contractor for the duration of time reasonably required to complete the Work.

00180.90 Termination of Contract and Substituted Performance:

(a) Termination for Default - Termination of the Contract for default may result if the Contractor:

- Violates any material provision of the Contract;
- Disregards applicable laws and regulations or the Engineer's instructions;
- Refuses or fails to supply enough Materials, Equipment or skilled workers for prosecution of the Work in compliance with the Contract;
- Fails to make prompt payment to Subcontractors;
- Makes an unauthorized general assignment for the benefit of the Contractor's creditors;
- Has a receiver appointed because of the Contractor's insolvency;
- Is adjudged bankrupt and the court consents to the Contract termination; or
- Otherwise fails or refuses to faithfully perform the Contract according to its terms and conditions.

If the Contract is terminated by the Agency, upon demand the Contractor and the Contractor's Surety shall provide the Engineer with immediate and peaceful possession of the Project Site, and of all Materials and Equipment to be incorporated into the Work, whether located on and off the Project Site, for which the Contractor received progress payments under 00195.50.

If the Contract is terminated for default, neither the Contractor nor its Surety shall be:

- Relieved of liability for damages or losses suffered by the Agency because of the Contractor's breach of Contract, or
- Entitled to receive any further progress payments until the Work is completed. However, progress payments for completed Work that remain due and owing at the time of Contract termination may be made in accordance with the terms of 00195.50, except that the Engineer will be entitled to withhold sufficient funds to cover costs incurred by the Agency as a result of the termination. Final payment to the Contractor will be made in accordance with the provisions of Section 00195.

If a termination under this provision is determined by a court of competent jurisdiction to be unjustified, the termination shall be deemed a termination for public convenience.

(b) Substituted Performance - In accordance with the Agency's procedures, and upon the Engineer's recommendation that sufficient cause exists, the Agency, without prejudice to any of its other rights or remedies and after giving the Contractor and the Contractor's Surety 10 Calendar Days' written notice, may

- Terminate the Contract;
- Substitute the Contractor with another Entity to complete the Contract;
- Take possession of the Project Site;
- Take possession of Materials on the Project Site;

00180.90(b)

- Take possession of Materials not on the Project Site, for which the Contractor received progress payments under 00195.50;
- Take possession of Equipment on the Project Site that is to be incorporated into the Work;
- Take possession of Equipment not on the Project Site that is to be incorporated into the Work, and for which the Contractor received progress payments under 00195.50; and
- Finish the Work by whatever method the Agency deems expedient.

If, within the 10 Calendar Day notice period provided above, the Contractor and/or its Surety corrects the basis for declaration of default to the satisfaction of the Engineer, or if the Contractor's Surety submits a proposal for correction that is acceptable to the Engineer, the Contract will not be terminated.

(c) Termination for Public Convenience - The Engineer may terminate the Contract in whole or in part whenever the Engineer determines that termination of the Contract is in the best interest of the public.

The Engineer will provide the Contractor and the Contractor's Surety seven Calendar Days' written notice of termination for public convenience. After such notice, the Contractor and the Contractor's Surety shall provide the Engineer with immediate and peaceful possession of the Project Site, and of Materials and Equipment to be incorporated into the Work, whether located on and off the Project Site, for which the Contractor received progress payments under 00195.50.

Compensation for Work terminated by the Engineer under this provision will be determined in accordance with the provisions of Subsection 00195.70(b).

PART 00100 REPLACED JANUARY 2006

Section 00190 - Measurement of Pay Quantities

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

Description

00190.00 Scope - The Engineer will measure pay quantities for accepted Work according to the International System of Units unless otherwise provided in the Contract. Unless otherwise specified in the Contract, the Engineer will round off all quantity computations using the following convention:

- The final significant digit will not be changed when the succeeding digit is less than 5.
- The final significant digit will be increased by one when the succeeding digit is 5 or greater.

The measurement provisions contained in the Specifications for each Pay Item will supplement or modify the above convention by:

- Imposing measurement limitations
- Describing measurement or computation procedures
- Giving conversion factors or adjustment conditions
- Providing for determination of reasonably accurate and representative Pay Item quantities

Measurements required or allowed to be made by the Contractor will be subject to the Engineer's verification. The Engineer's decision about measurement is final.

00190.10 Measurement Guidelines:

(a) Lengths and Dimensions - Lengths and dimensions will be measured horizontally and vertically, at least to the nearest 0.1 m (0.1 foot), unless otherwise specified in the Contract. Measurements will be limited to the dimensions shown or specified, or as directed by the Engineer.

(b) Area - Areas will be measured at least to the nearest 0.1 m² (0.1 square foot) unless otherwise specified in the Contract.

(c) Mass (Weight) - Mass (Weight) will be determined on Contractor-provided scales as required under 00190.20 unless otherwise allowed by the Specifications. Mass (Weight) will be measured at least to the nearest 0.01 Mg (0.01 ton) unless otherwise specified in the Contract.

If bituminous materials, portland cement, lime, and similar bulk Materials are shipped by truck or rail, the supplier's shipping invoice with net scale masses (weights), or volumes converted to masses (weights), may be used for Pay Item quantity determination in place of masses (weights) determined on the Contractor-provided vehicle scales.

Shipping invoice masses (weights) of the supplier's truck or transport shall be subject to periodic check weighing on the Contractor's vehicle scales, or other scales designated, according to 00190.20. If the check mass (weight) is less than the supplier mass (weight) by more than 0.4%, the discrepancy will be resolved by the Engineer.

No payment will be made:

- For quantities in excess of the supplier mass (weight)

00190.10(c)

- When Materials have been lost, wasted, or otherwise not incorporated into the Work
- For additional hauling costs resulting from the check weighing

(d) Volume - Volume will be measured at least to the nearest 0.1 m³ (0.1 cubic yard) unless otherwise specified in the Contract.

When bituminous materials are measured by volume, the volume will be measured at 15 °C (60 °F) or will be corrected to the volume at 15 °C (60 °F) using the correction factors found in the MFTP (ODOT TM321).

(e) Standard Manufactured Items - If standard manufactured items, such as fence, wire, plates, rolled shapes, pipe, conduit and other similar items are specified in the Contract by properties such as gage, unit mass (weight), or section dimensions, the manufacturing tolerances established by the industry involved will be accepted unless more stringent tolerances are cited in the Contract.

(f) Lump Sum - Lump sum, when used, means the Work described shall be completed and accepted without measurement unless changes are ordered in writing by the Engineer. If estimated quantities of the Work to be performed are listed in the Special Provisions, they provide only a basis for adjusting payment amounts. Estimated quantities are approximate only, and are made from a reasonable interpretation of the Plans and Specifications. Computations based on the details and dimensions shown on the Plans or Specifications are not guaranteed to equal estimated quantities.

If the Agency issues no Change Order, the Agency will make no pay adjustment for quantities based on the Contractor's computations that overrun or underrun the estimated quantities.

If the Agency issues Change Orders for changes in the Work, the Engineer will measure such changes according to the standards set by 00195.20 to determine adjustment of payment.

(g) Time - Time will be measured to the nearest 0.5 hour unless otherwise specified.

00190.20 Contractor to Provide Vehicle Weigh Scales:

(a) General - If the Specifications require measurement by weighing on vehicle weigh scales, the Contractor shall provide vehicle weigh scales and shall transport Materials to the scales. Subject to the Engineer's approval, masses (weights) may be determined by plant or hopper scales according to 00190.30.

Contractor-provided scales shall be furnished, installed and maintained by the Contractor or its supplier, or, subject to the Engineer's approval, may be commercial scales located in the vicinity of the Project.

Unless otherwise provided in the Contract, Pay Items to be measured by mass (weight) shall include all Contractor costs for providing, maintaining, inspecting, and testing scales; for furnishing appropriate weigh tickets; for self-printing scales; and for transporting Materials to the scales or to check weighing.

(b) Requirements - The scales shall conform to ORS Chapter 618, or the laws of the state in which they are located, and NIST Handbook 44, and shall be:

- Licensed by the Oregon Department of Agriculture, or by the analogous regulatory body for scales located outside the State;
- Technically suitable for weighing the Materials;
- Properly installed and maintained; and

- Accurate to the required tolerances.

The mass (weight) of any Materials weighed by anyone other than the Engineer will be subject to check weighing as the Engineer directs.

(c) Approaches - Vehicle scale approaches shall be:

- At each end of the scale platform;
- Straight and in line with the platform; and
- Long enough to accommodate combination vehicles longer than the scale platform so that they are level and allow release of brakes before weighing.

(d) Inspections - Contractor shall have all scales certified, that is inspected and their accuracy tested, by the Oregon Department of Agriculture, an analogous regulatory body for scales located outside the State, or a scale service company as follows:

- Before use if installed at a new site;
- 60 Calendar Days after initial inspection;
- Every six months thereafter; and
- When the Engineer directs additional inspections.

No Materials weighed on scales without current certifications in accordance with this Subsection will be accepted. The Contractor shall provide a copy of all required certifications to the Engineer.

Testing by a scale service company within the State of Oregon shall comply with ORS Chapter 618.

If additional inspections directed by the Engineer confirm that the scale accuracy is within the required tolerances, the Agency will pay the cost for inspecting and testing the scales. If the scale accuracy is not within these tolerances, the Contractor shall pay the cost for inspecting and testing the scales.

(e) Inspection Results - If an inspection indicates the scales have been under-weighing (indicating less than the true mass (weight)), the Agency will make no additional payment to the Contractor for Materials previously weighed.

If an inspection indicates the scales have been over-weighing (indicating more than the true mass (weight)), the masses (weights) will be reduced for Materials received after the time the Engineer determines the overweighing began or, if that is not possible, after the last acceptable certification of the scales. The reduction will be the amount of error in excess of the 0.2% maintenance tolerance allowed in the Contract.

(f) Contractor-Provided Weigh Technician - The Contractor shall provide a technician to operate Contractor-provided vehicle weigh scales. The Agency will observe procedures and require check weighing in accordance with the following:

- (1) Scale with Automatic Printer** - If the scales have an automatic weigh memo printer that does not require manual entry of gross mass (weight) information, the Agency will periodically have a representative at the scales to observe the weighing procedures. In addition, the Engineer will periodically check the net mass (weight) for a load of Materials by directing the haul vehicle to reweigh on a different scale that has been inspected and certified in accordance with 00190.20(b) and (d).

If a different scale is not available within a 50 km (30 mile) round trip from the regular haul route the Agency will allow check weighing on an approved alternate basis. Check masses (weights) within 0.4% of the Contractor-provided mass (weight) are acceptable.

The Engineer will resolve discrepancies found by check weighing. Agency employee costs will be paid by the Agency. The Contractor shall pay all other costs resulting from the check weighings, including without limitation the use of other scales.

If more than 50 Mg (50 tons) per day of all types of Materials are received from a scale, the Contractor shall make random check weighings at least every tenth day on which more than 50 Mg (50 tons) is received or at each interval that 10 000 Mg (10,000 tons) has been weighed, whichever occurs first, or as directed by the Engineer.

(2) Scale Without Automatic Printer - If the scales require manual entry of gross mass (weight) information, the Agency will either require check weighing in accordance with 00190.20(f-1) or have an Agency weigh witness observe all weighing procedures for the Project. The Contractor shall pay costs for the weigh witness. The hourly cost of the weigh witness will be as stated in the Special Provisions.

(3) Duties of Weigh Technician - The Contractor's weigh technician shall:

- Determine twice a day, or as otherwise directed by the Engineer, the empty haul masses (weights) (tare masses (weights)) of hauling vehicles, unless vehicles are tared before each load;
- Furnish daily a listing of the tare masses (weights) if 10 or more loads are hauled during that day;
- Furnish a note listing the net mass (weight) for each consecutive ten loads with the following load;
- Furnish a daily listing of the net masses (weights) and total mass (weight) for each type of Material hauled during that day; and
- Furnish a legible, serially numbered weigh memo for each load of Materials to the Agency's Materials receiver at the point of delivery, or as directed by the Engineer. The memo shall identify the Project, the Materials, the date, net mass (weight) (gross and tare as appropriate), and identification of vehicle, driver and weigh technician.

(g) Agency-Provided Weigh Technician - If the Contractor provides vehicle weigh scales without a weigh technician meeting the requirements of this Subsection, the Agency will provide a weigh technician at the Contractor's expense. The hourly cost for the technician will be as stated in the Special Provisions. The Contractor shall provide a weighhouse for the weigh technician in accordance with Section 00205. The Agency's weigh technician will:

- Determine tare masses (weights);
- Prepare weigh memos for each load;
- Compile the weigh records; and
- Not participate in the production of Materials or the loading of haul vehicles.

00190.30 Plant Scales - The Contractor, with the Engineer's written approval, may weigh plant-mixed Materials on scales that have either:

- An automatic mass (weight) batching and mixing control printer system; or
- A weigh hopper printer system.

Any additional costs resulting from the use of these scales shall be borne by the Contractor. Check weighing will be done in accordance with 00190.20(f).

Except for 00190.20(c) regarding approaches, the Contractor's use of plant scales shall comply with all provisions of 00190.20.

The Engineer's approval for the Contractor's use of plant scales to determine pay masses (weights) will be rescinded if check weighing or scale inspections indicate the scales do not consistently determine masses (weights) within the tolerances allowed by state law.

PART 00100 REPLACED JANUARY, 2006

Section 00195 - Payment

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

Description

00195.00 Scope and Limit:

(a) General - The Agency will pay only for measured Pay Item quantities incorporated into the Work or performed in accordance with the terms of the Contract. The Contractor understands and agrees that Pay Item quantities listed in the Schedule of Items do not govern payment.

Payment constitutes full compensation to the Contractor for furnishing all Materials, Equipment, tools, labor, and Incidentals necessary to complete the Work; and for risk, loss, damage, and expense arising from the nature or prosecution of the Work or from the action of the elements, subject to the provisions of 00170.80. The Contractor shall include the costs of bonds and insurance for the Project in the unit price for each Pay Item of Work to be performed.

(b) Essential or Incidental Materials or Work - When the Specifications state that the unit price for a Pay Item is compensation for certain Materials or Work essential or incidental to the Pay Item, the same Materials or Work will not be measured or paid under any other Pay Item.

Provisions and Requirements

00195.10 Payment For Changes in Materials Costs - On certain projects, as identified in the Special Provisions, an asphalt cement price escalation clause will be in effect during the life of the Contract on items containing asphalt cement listed in the Special Provisions.

00195.20 Changes to Plans or Character of Work:

(a) Insignificant Changed Work - If the changes made under 00140.30 do not significantly change the character or unit cost of the Work to be performed under the Contract, the Agency will pay for such work at the Pay Item price.

If the Work involved in the change is measured on a lump sum basis and its character is not significantly changed, payment for the Changed Work will be determined:

- As described in the applicable Section of the Specifications;
- If not described there, on a theoretical unit price determined by dividing the Contractor's lump sum price by the estimated quantity of the Pay Item listed in the Special Provisions; or
- If neither of the above apply, the Engineer will make an equitable adjustment.

(b) Significant Changed Work - If the changes made under 00140.30 significantly alter the character, unit cost, or lump sum cost of the Work, the Agency will adjust the Contract. Adjustments will exclude any loss of anticipated profits. The parties shall agree upon the basis for payment and the amount of adjustment prior to the Contractor commencing the Changed Work. If the basis and amount cannot be agreed upon, the Engineer will make an equitable adjustment, which may increase or decrease the Contract Amount and Contract Time.

Any such adjustments will not be more than the amount justified by the Engineer on the basis of the established procedures set out in Section 00197 for determining rates.

The term "Significant Changed Work" shall apply only to that circumstance in which the character of the Work, as changed, differs materially in kind, nature, or unit cost from that involved or included in the originally proposed construction.

00195.30 Differing Site Conditions - Upon written notification, as required in 00140.40, the Engineer will investigate the identified conditions. If the Engineer determines that the conditions materially differ and cause an increase or decrease in the cost or time required to perform any Work under the Contract, an adjustment in the Contract Amount or Contract Time, excluding loss of anticipated profits, will be made, and the Contract modified accordingly, in writing. The Engineer will notify the Contractor as to whether or not an adjustment of the Contract is warranted.

No Contract adjustment which benefits the Contractor will be allowed unless the Contractor has provided the required written notice.

00195.40 Unreasonable Delay by the Agency - If the Contractor believes that performance of all or any portion of the Work is suspended, delayed, or interrupted for an unreasonable period of time in excess of that originally anticipated or customary in the construction industry, due to acts or omissions of the Agency, or persons acting for the Agency, and that additional compensation, Contract Time, or both, are due the Contractor because of the suspension, delay or interruption, the Contractor shall immediately file a written notice of delay in accordance with 00180.60. The Contractor shall then promptly submit a properly supported request for any additional compensation, Contract Time, or both, in accordance with the applicable provisions in 00180.60 through 00180.80.

The Engineer will promptly evaluate a properly submitted request for additional compensation. If the Engineer determines that the delay was unreasonable, and that the cost required for the Contractor to perform the Contract has increased as a result of the unreasonable suspension, delay or interruption, the Engineer will make an equitable adjustment, excluding profit, and modify the Contract in writing accordingly. The Engineer will notify the Contractor of the determination and whether an adjustment to the Contract is warranted.

Under this provision, no Contract adjustment will be allowed:

- Unless the Contractor has provided the written notice required by 00180.60;
- For costs incurred more than 10 Calendar Days before the Engineer receives the Contractor's properly submitted written request;
- For any portion of a delay that the Engineer deems to be a reasonable delay, or for which an adjustment is provided for or excluded under other terms of the Contract; or
- To the extent that performance would nevertheless have been suspended, delayed or interrupted by causes other than those described in this Subsection.

00195.50 Progress Payments and Retained Amounts:

(a) **Progress Payments** - The Agency's payment of progress payments shall not be construed as acceptance or approval of any part of the Work, and shall not relieve the Contractor of responsibility for defective Materials or workmanship.

The estimates upon which progress payments are based are not represented to be accurate estimates. All estimated quantities are subject to correction in the final estimate. If the Contractor uses these estimates as a basis for making payments to Subcontractors, the Contractor assumes all risk and bears any losses that result.

If the estimated amount due the Contractor for any given month is less than \$1,000, the Agency will make no payment for that month unless requested by the Contractor.

(1) Progress Estimates - At the same time each month, the Engineer will make an estimate of the amount and value of Pay Item Work completed. The amount of Work completed will be the sum of the estimated number of units completed for unit price Pay Items plus the estimated percentage completed of lump sum Pay Items.

The estimated value of the Work completed will then be determined by using the Contract unit price for unit price Pay Items, and by using one of the following methods to determine the value of the lump sum Pay Items:

- The "theoretical unit price", when the Special Provisions contain an estimated number of units;
- A Contractor-submitted, Engineer-approved Schedule of Values, when there is no theoretical unit price available; or
- Engineer's determination, when there is neither an available theoretical unit price, nor an approved, Contractor-submitted Schedule of Values.

The amounts to be allowed for lump sum Pay Items in progress payments will not exceed the reasonable value of the Work performed, as determined by the Engineer.

Incidentals such as formwork, falsework, shoring, and cribbing shall be included in the unit prices for the various Pay Items requiring their use, unless specified as a separate Pay Item. No payment will be made for Pay Items that include Incidentals until units or portions of such Pay Item Work are in place and completed. The costs of Incidentals will be paid in proportion to the percentage of Pay Item Work completed.

(2) Value of Materials on Hand - The Engineer will also make an estimate of the amount and value of acceptable Materials on hand, i.e., already delivered and stored in accordance with 00195.60(a), to be incorporated into the Work.

(3) Value of Work Accomplished - The sum of the values in (1) and (2) above will be collectively referred to in this Subsection as the "value of Work accomplished", subject to (4) below.

(4) Limitations on Value of Work Accomplished - In determining the "value of Work accomplished", the Engineer's estimate will be based on the unit prices for the various Pay Items. Any amounts not included in progress payments due to substantial mathematical unbalancing of Pay Item prices will be included in the final payment issued in accordance with 00195.90(b).

(5) Reductions to Progress Payments - With each progress payment, the Contractor will receive a Contract payment voucher and summary setting forth the value of Work accomplished reduced by the following:

- Amounts previously paid;
- Amounts deductible or owed to the Agency for any cause specified in the Contract;
- Additional amounts retained to protect the Agency's interests pursuant to Subsection (e) below.

(b) Retainage - The amount to be retained from progress payments shall be 5% of the value of Work accomplished, and shall be retained in one of the forms specified in Subsection (c) below. No retainage will be withheld from Work performed as Force Account Work.

(c) Forms of Retainage - Forms of acceptable retainage are set forth below in Subsections (1) through (4). "Cash, Alternate A" is the Agency-preferred form of retainage. If the Agency incurs additional costs as a result of the Contractor's election to use a form of retainage other than Cash, Alternate A, the Agency may recover such costs from the Contractor by a reduction of the final payment.

(1) Cash, Alternate A - Retainage will be deducted from progress payments and held by the Agency until final payment is made in accordance with 00195.90, unless otherwise specified in the Contract.

(2) Cash, Alternate B (Interest Earned) - Upon the Contractor's written request, the Agency will deposit the cash retainage withheld in an interest-bearing account in a bank, trust company, or savings association for the benefit of the Agency, as provided by ORS 279.420(4). Interest earned on the account shall accrue to the Contractor only when the Contractor has requested the deposit. Amounts retained and interest earned will be included in the final payment made in accordance with 00195.90.

Any retainage withheld on Work performed by a Subcontractor shall be released to the Contractor as provided in 00195.50(d).

(3) Cash, Alternate C (Retainage Surety Bond) - Upon receipt of an approved retainage surety bond, the Agency will limit the amount of cash retainage withheld to \$10,000. The surety bond must be in the bond form provided by the Agency. The bond must be provided by the same Surety that provides the Performance and Payment Bonds.

If the Contractor elects this form of retainage, the Agency will withhold from progress payments 5% of the value of Work accomplished as cash retainage until the retained amount equals \$10,000. After that amount is retained, no further cash retainage will be withheld until the additional retainage required exceeds the face amount of the retainage surety bond provided. Thereafter, retainage will be withheld from progress payments as provided by these Specifications.

If an acceptable retainage surety bond is provided, the Contractor shall notify all Subcontractors of the existence of the retainage surety bond and shall advise them of their rights under ORS 279.420(6).

Amounts of retainage withheld under the provision will be included in the final payment in accordance with 00195.90.

Any retainage withheld on Work performed by a Subcontractor shall be released to the Contractor as provided in 00195.50(d).

(4) Bonds and Securities - The Contractor may deposit bonds or securities with the Agency or with any bank or trust company to be held instead of cash retainage for the benefit of the Agency (ORS 279.420). In such event, the Agency will reduce the cash retainage by an amount equal to the value of the bonds and securities. Interest on the bonds and securities shall accrue to the Contractor.

Bonds and securities deposited instead of cash retainage shall be assigned or made payable to the Agency and shall be of a kind approved by the Director of the Oregon Department of Administrative

Services. Examples of approved bonds and securities acceptable in lieu of cash retainage include, but are not limited to:

- Bills, certificates, notes or bonds of the United States;
- Other obligations of the United States or its agencies;
- Obligations of any corporation wholly owned by the Federal Government;
- Indebtedness of the Federal National Mortgage Association;
- General obligation bonds of the State of Oregon or any political subdivision thereof;
- Time certificates of deposit or savings account passbooks issued by a commercial bank, savings and loan association, or mutual savings bank, duly authorized to do business in the State;
- Corporate bonds rated "A" or better by a recognized rating service;
- Irrevocable letters of credit from a bank doing banking business in the State.

When the Engineer determines that requirements for the protection of the Agency's interest have been fulfilled, bonds and securities deposited as specified will be released to the Contractor.

(d) Reduction of Retainage - As the Work progresses, the amounts to be retained under (b) of this Subsection are subject to reduction in the Engineer's sole discretion. Retainage reductions will be considered only as follows:

- When the Work is 50% completed and upon the written application of the Contractor and written approval of the Surety, the Engineer may reduce or eliminate retainage on remaining progress payments if the Work is progressing satisfactorily.
- When the Work is 97.5% or more completed, the Engineer may, without application by the Contractor, reduce the retained amount to 100% of the value of the Work remaining.
- When a Subcontractor has satisfactorily completed all of its Work, it may request release of retainage for that Work from the Contractor. The Contractor shall request reduction of retainage in the amount withheld for the Subcontractor's Work after certifying to the Agency that the Subcontractor's Work is complete, and that all contractual requirements pertaining to the Subcontractor's Work have been satisfied. Within 60 Calendar Days of the end of the month in which the Agency receives the Contractor's certification regarding the Subcontractor's Work, the Agency will either notify the Contractor of any deficiencies which require completion before release of retainage, or verify that the Subcontractor's Work complies with the Contract and release all retainage for that Work with the next scheduled progress payment. Within 10 Calendar Days of receipt of retainage, the Contractor shall pay to the Subcontractor all such retainage released.
- The Agency will only release retainage for satisfactorily completed portions of the Work represented by Pay Items in the Schedule of Items, or by Pay Items added by Change Order. Work not represented by a Pay Item, but which constitutes part of an uncompleted Pay Item, will not be regarded as satisfactorily completed Work for the purposes of this Subsection.

If retainage has been reduced or eliminated, the Agency reserves the right to protect its interests by retaining amounts from further progress payments at the 5% rate provided in 00195.50(b).

(e) Withholding Payments - The Engineer may withhold such amounts from progress payments or final payment as may reasonably protect the Agency's interests until the Contractor has:

- Complied with all orders issued by the Engineer according to the Specifications; and
- Satisfied all legal actions filed against the Agency, the Agency's governing body and its members, and Agency employees that the Contractor is obliged to defend. (See 00170.72.)

(f) Prompt Payment Policy - Payments shall be made promptly in accordance with ORS 279.435.

00195.60 Advance Allowance for Materials on Hand:

(a) General - If the total value of Materials on hand is at least \$1,000 or the total value of a single class of Materials on hand is at least \$500, the Engineer may authorize an advance allowance for the Materials in the progress payments. The Agency will not make advance allowances on the Materials unless the following three conditions are satisfied:

(1) Request for Advance Allowance - If Materials on hand meet the requirement of (2) below, an advance allowance will be made if:

- A written request for advance allowance for Materials on hand has been received by the Engineer at least five Calendar Days before the pay period cutoff date; and
- The request is accompanied by written consent of the Contractor's Surety.

(2) Stored or Stockpiled Conditions - The Materials shall have been delivered and/or acceptably stored or stockpiled in accordance with the Specifications and as follows:

- At the Project Site;
- On Agency-owned property;
- On property in the State of Oregon on which the property owner has authorized storage in writing. The written authorization must allow the Agency to enter upon the property and remove Materials for at least six months after completion of the Project. The Contractor shall furnish a copy of the written permission to the Agency;
- On property outside the State of Oregon on which the property owner has authorized storage in writing, provided that such storage location is allowed by the Special Provisions or authorized in writing by the Engineer. The permit must allow the Agency to enter upon the property and remove Materials for at least six months after completion of the Project. The Contractor shall furnish a copy of the written permission to the Agency.

To be eligible for advance allowance, the Materials shall:

- Meet Specification requirements;
- Have the required Materials conformance and quality compliance documents on file with the Engineer (See Section 00165);
- Be in a form ready for incorporation into the Work; and
- Be clearly marked and identified as being specifically fabricated, or produced, and reserved for use on the Project.

(3) Responsibility for Protection - The Contractor has full control and responsibility for the protection of Materials on hand from the elements and against damage, loss, theft, or other impairment until the entire Project has been completed and accepted by the Agency.

If Materials are damaged, lost, stolen, or otherwise impaired while stored, the monetary value advanced for them, if any, will be deducted from the next progress payment.

If these conditions in 00195.60(a-1) through (a-3) have been satisfied, the amount of advance allowance, less the retainage described in 00195.50, will be determined by one of the following methods as elected by the Engineer:

- Net cost to the Contractor of the Materials, f.o.b. the Project Site or other approved site;
- Price (or portion of it attributable to the Materials), less the cost of incorporating the Materials into the Project, as estimated by the Engineer.

(b) Proof of Payment - The Contractor shall provide the Engineer with proof of payment to the Materials suppliers for purchased Materials within 30 Calendar Days of the date of the progress payment that includes the advance allowance.

If proof of payment is not provided, sums advanced will be deducted from future progress payments, and the Engineer will not approve further prepayment advance allowance requests.

(c) Terminated Contract - If the Contract is terminated, the Contractor shall provide the Agency immediate possession of all Materials for which advance allowances have been received, as provided above. If, for any reason, immediate possession of the Materials cannot be provided, the Contractor shall immediately refund to the Agency the total amount advanced for the Materials. The Agency may deduct any amount not so refunded from final payment.

00195.70 Payment under Terminated Contract - Payment for Work performed under a Contract that is terminated pursuant to the provisions of 00180.90 will be determined under (a) or (b) of this Subsection.

(a) Termination for Default - Upon termination of the Contract for the Contractor's default, the Agency will make no further payment until the Project has been completed. The Agency will make progress payments to the party to whom the Contract is assigned, but may withhold an amount sufficient to cover anticipated Agency costs, as determined by the Engineer, to complete the Project.

Upon completion of the Project, the Engineer will determine the total amount that the defaulting Contractor would have been entitled to receive for the Work, under the terms of the Contract, had the Contractor completed the Work (the "cost of the Work").

If the cost of the Work, less the sum of all amounts previously paid to the Contractor, exceeds the expense incurred by the Agency in completing the Work, including without limitation expense for additional managerial and administrative services, the Agency will pay the excess to the Contractor, subject to the consent of the Contractor's Surety.

If the expense incurred by the Agency in completing the Work exceeds the Contract Amount, the Contractor or the Contractor's Surety shall pay to the Agency the amount of the excess expense.

The Engineer will determine the expense incurred by the Agency and the total amount of Agency damage resulting from the Contractor's default. That determination will be final as provided in 00150.00.

If a termination for default is determined by a court of competent jurisdiction to be unjustified, it shall be deemed a termination for public convenience, and payment to the Contractor will be made as provided in Subsection (b) below.

(b) Termination for Public Convenience:

(1) General - Full or partial termination of the Contract shall not relieve the Contractor of responsibility for completed portions of the Work, or relieve the Contractor's Surety of the obligation for any just claims arising from the completed Work.

(2) Mobilization - If mobilization is not a separate Pay Item, and payment is not otherwise provided for under the Contract, the Agency may pay the Contractor for mobilization expenses, including moving Equipment to and from the Project Site. If allowed, payment of mobilization expenses will be based on cost documentation submitted by the Contractor to the Engineer.

(3) All Other Work - The Agency shall pay the Contractor at the unit price for the number of Pay Item units of completed, accepted Work. For units of Pay Items partially completed, payment will be as mutually agreed, or, if not agreed, as the Engineer determines to be fair and equitable. No claim for loss of anticipated profits will be allowed. The Agency will purchase Materials left on hand in accordance with 00195.80 below.

00195.80 Allowance for Materials Left on Hand:

(a) Purchase of Unused Materials - If Materials are delivered to the Project Site, or otherwise acceptably stored at the order of the Engineer, but not incorporated into the Work due to complete or partial elimination of Pay Items, changes in Plans, or termination of the Contract for public convenience pursuant to 00180.90, and it is not commercially feasible for the Contractor to return them for credit or otherwise dispose of them on the open market; the Agency will purchase them according to the formula and conditions set forth in Subsection (b) below.

(b) Purchase Formula and Conditions:

(1) Formula - The Agency will apply the following formula in determining the Contractor's allowance for Materials left on hand:

Contractor's Actual Cost, plus 5% Overhead Allowance, minus Advance Allowances under 00195.60, but no markup or profit.

(2) Conditions - The Agency will not purchase the Contractor's Materials left on hand unless the Contractor satisfies the following conditions:

- Requests the Agency's purchase of unused Materials;
- Shows acquisition of the Materials in accordance with 00160.10;
- Shows that the Materials meet Specifications; and
- Provides receipts, bills and other records of actual cost of Materials delivered to the designated delivery points.

00195.90 Final Payment:

(a) Final Estimate - As soon as practicable after Final Inspection of the Project, as provided in 00150.90, the Engineer will prepare a final estimate of the quantities of the Pay Items performed. With this estimate of quantities as a base, the total amount due the Contractor will be determined according to the terms of the Contract including without limitation any amounts due for Extra Work performed.

(b) Final Payment - The amount of final payment will be the difference between the total amount due the Contractor and the sum of all payments previously made. All prior partial estimates and payments shall be subject to correction in the final estimate and payment.

After computation of the final amount due, and after Final Acceptance of the Project, final payment will be mailed to the Contractor's last known address as shown in the records of the Agency.

Beginning 30 Calendar Days after the date of Third Notification, interest will begin to accrue at the rate established by ORS 279.435 on any money due and payable to the Contractor as final payment, determined as described above. No interest will be paid on money withheld due to outstanding amounts owed by the Contractor under the provisions of 00170.10.

(c) No Waiver of Right to Make Adjustment - The fact that the Agency has made any measurement, estimate, or certification either before or after completion of the Project, Final Acceptance, Agency assumption of possession of the Project Site, or payment for any part of the Work, shall not prevent either party from:

- Showing the true amount and character of the Work;
- Showing that any measurement, estimate or certification is incorrect;
- Recovering from the other party damages that may have been suffered because the other party failed to comply with the Contract.

00195.95 Error in Final Quantities and Amounts:

(a) Request for Correction of Compensation - If the Contractor believes the quantities and amounts detailed in the final Contract payment voucher, prepared by the Engineer according to 00195.90, to be incorrect, the Contractor shall submit an itemized statement to the Engineer detailing all proposed corrections.

This statement must be submitted to the Engineer within 90 Calendar Days from the date the voucher was mailed to the Contractor, in accordance with 00195.90(b). Any request for compensation not submitted and supported by an itemized statement within the 90 Calendar Day period will not be paid by the Agency. This does not limit the application of Section 00199.

(b) Acceptance or Rejection of Request:

(1) Consideration of Request - The Engineer will consider and investigate the Contractor's request for correction of compensation submitted in accordance with 00195.95(a), and will promptly advise the Contractor of acceptance or rejection of the request in full or in part.

(2) Acceptance of Request - If the Engineer accepts the Contractor's request(s) in full or in part, the Engineer will prepare a post-final Contract payment voucher, including all accepted corrections, and will forward it to the Contractor.

(3) Rejection of Request - If the Engineer rejects the request(s) in full, the Engineer will issue a written notice of rejection and mail it to the Contractor.

(4) Contractor Objection to Revised Voucher or Notice of Rejection - If the Contractor disagrees with the revised voucher or notice of rejection, the Contractor may request review pursuant to the procedure set forth in 00199.40. If the Contractor fails to submit a request for 00199.40 review within 30 Calendar Days after the Engineer mails a post-final Contract payment voucher or notice of rejection, the Contractor waives all rights to a claim based on errors in quantities and amounts.

Section 00196 - Payment for Extra Work

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

Description

00196.00 General - Only work not included in the Contract as awarded but deemed by the Engineer to be necessary to complete the Project (see 00140.60) will be paid as Extra Work. Regardless of alterations and changes, any item of Work provided for in the Contract will not constitute Extra Work. Payment for alterations and changes to Work will be made in accordance with 00195.20.

Compensation for Extra Work will be paid only for Work authorized in writing by the Engineer and performed as specified. Work performed before issuance of the Engineer's written authorization shall be at the Contractor's risk. Extra Work will be paid as determined by the Engineer, in accordance with 00196.10 and 00196.20.

Provisions and Requirements

00196.10 Negotiated Price - If the Engineer can reasonably determine a price estimate for Extra Work, the Engineer may then give written authorization to the Contractor to begin the Extra Work. As soon as practicable, but within 10 Calendar Days after that authorization, the Contractor shall respond in writing to the Engineer's Extra Work price estimate by submitting to the Engineer an Extra Work price quote. The price quote shall detail the following items related to the Extra Work:

- Types and amounts of Materials
- Hours of Equipment use and hours of labor
- Travel
- Overhead and profit
- Other costs associated with the proposed Extra Work

Pending approval of the price quote, the Engineer will maintain force account records of the Extra Work. As soon as practicable, but within 10 Calendar Days of receipt of a properly supported price quote, the Engineer will review the price quote and advise the Contractor if it is accepted or rejected. The Engineer will not accept a price quote that cannot be justified on a Force Account basis. If the Contractor's price is accepted, the Engineer will issue a Change Order, and the Extra Work will be paid at the accepted price.

00196.20 Force Account - If the Engineer and the Contractor cannot agree on a price for the Extra Work, the Engineer may issue a Force Account Work order requiring the Extra Work to be paid as Force Account Work. Force Account Work records and payment will be governed by Section 00197.

Section 00197 - Payment for Force Account Work

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies.)

Force Account Work

00197.00 Scope - The Materials, Equipment and labor rates established in this Section apply only to Extra Work ordered by the Engineer to be performed as Force Account Work. These rates do not apply to any other Work performed under the Contract.

00197.01 General - Before ordering Force Account Work, the Engineer will discuss the proposed work with the Contractor, and will seek the Contractor's comments and advice concerning the formulation of Force Account Work specifications. The Engineer is not bound by the Contractor's comments and advice, and has final authority to:

- Determine and direct the Materials, Equipment and labor to be used on the approved Force Account Work, and
- Determine the time of the Contractor's performance of the ordered Force Account Work.

If the Engineer orders the performance of Extra Work as Force Account Work, the Engineer will record, on a daily basis, the Materials, Equipment, labor, and Special Services used for the Force Account Work during that day. The Engineer and the Contractor shall sign the record daily to indicate agreement on the Materials, Equipment, labor, and Special Services used for the Force Account Work performed on that day.

The following shall be reflected on the daily record:

- Materials used in the Force Account Work as directed by the Engineer, except those furnished and paid under rental rates for use of Equipment;
- Equipment which the Engineer considers necessary to perform the Force Account Work. Equipment hours will be recorded to the nearest quarter hour;
- Labor costs, including that of Equipment operators and supervisors in direct charge of the specific operations while engaged in the Force Account Work;
- Special Services; and
- The Engineer's and Contractor's signatures confirming its accuracy.

00197.10 Materials:

(a) General - The Contractor will be paid for Materials actually used in the Force Account Work as directed by the Engineer, except for those furnished and paid for under rental rates included with the use of Equipment. Payments will be at actual cost, including transportation costs to the specified location, from the supplier to the purchaser, whether the purchaser is the Contractor, a Subcontractor, or other forces. All costs are subject to the provisions of this Subsection.

(b) Trade Discount - If a commercial trade discount is offered or available to the purchaser, it shall be credited to the Agency, even though the discount may not have actually been taken. The Agency will not take any discounts for prompt or early payment, whether or not offered or taken.

(c) Not Directly Purchased From Supplier - If Materials cannot be obtained by direct purchase from and direct billing by the supplier, the cost shall be considered to be the price billed to the purchaser less commercial trade discounts, as determined by the Engineer, but not more than the purchaser paid for the Materials. No markup other than actual handling costs will be permitted.

(d) Purchaser-Owned Source - If Materials are obtained from a supply or source wholly or partly owned by the purchaser, the cost shall not exceed the price paid by the purchaser for similar Materials furnished from that source on Pay Items, or the current wholesale price for the Materials delivered to the Project Site, whichever is lower.

00197.20 Equipment:

(a) General - Equipment approved by the Engineer to perform the Force Account Work will be eligible for payment at the established rates only during the hours it is operated or on standby if so ordered by the Engineer. Equipment hours will be recorded on the daily record to the nearest quarter hour.

Except as modified by these provisions, Equipment use approved by the Engineer will be paid at the rental rates given in the most current edition of the Rental Rate Blue Books for Construction Equipment ("Blue Book"), Volumes 1, 2, and 3, published by Primedia Information, Inc., 1735 Technology Drive, Suite 410, San Jose, CA 95110-1313 (phone 800-NOW-DATA ((800) 669-3282)).

(b) Equipment Description - On the billing form for Equipment costs, the Contractor shall submit to the Engineer sufficient information for each piece of Equipment and its attachments to enable the Engineer to determine the proper rental rate from the Blue Book.

(c) Rental Rates (without Operator):

(1) Rental Rate Formula - Rental rates for Equipment will be paid on an hourly basis for Equipment and for attachments according to the following formula:

$$\text{Hourly Rate} = \frac{\text{Monthly Base Rate} \times \text{Rate Adjustment Factor}}{176 \text{ hours/month}} + \text{Hourly Operating Rate}$$

Some attachments are considered "standard Equipment" and are already included in the monthly base rate for the Equipment. That information can be obtained from Primedia Information, Inc.

(2) Monthly Base Rate - The monthly base rate used above for the machinery and for attachments represents the major costs of Equipment ownership, such as depreciation, interest, taxes, insurance, storage, and major repairs.

(3) Rate Adjustment Factor - The rate adjustment factor used above will be determined as per page iii of each section of the Blue Book.

(4) Hourly Operating Rate - The hourly operating rate used above for the machinery and for attachments represents the major costs of Equipment operations, such as fuel and oil, lubrications, field repairs, tires or ground engaging components, and expendable parts.

(5) Limitations - The Blue Book "Regional Adjustment Factor" shall not apply.

If multiple attachments are included with the rental Equipment, and are not considered "standard Equipment", only the attachment having the higher rental rate will be eligible for payment, provided the attachment has been approved by the Engineer as necessary to the Force Account Work.

Rental will not be allowed for small tools that have a daily rental rate of less than \$5, or for unlisted Equipment that has a fair market value of \$400 or less.

The above rates apply to approved Equipment in good working condition. Equipment not in good working condition, or larger than required to efficiently perform the work, may be rejected by the Engineer or accepted and paid for at reduced rates.

(d) Moving Equipment - If it is necessary to transport Equipment located beyond the Project Site exclusively for Force Account Work, the actual cost to transport the Equipment to, and return it from, its On-Site Work location will be allowed as an additional item of expense. However, the return cost will not exceed the original delivery cost. These costs will not be allowed for Equipment that is brought to the Project Site for Force Account Work if the Equipment is also used on Pay Item or related Work.

If transportation of such Equipment is by common carrier, payment will be made in the amount paid for the freight. No markups will be allowed on common carrier transportation costs. If the Equipment is hauled with the Contractor's own forces, transportation costs will include the rental rate of the hauling unit and the hauling unit operator's wage. If Equipment is transferred under its own power, the rental rate allowed for transportation time will be 75% of the appropriate hourly rate for the Equipment, without attachments, plus the Equipment operator's wage.

(e) Standby Time - If ordered by the Engineer, standby time will be paid at 40% of the hourly rental rate calculated according to this Subsection, excluding the hourly operating rate. Rates for standby time that are calculated at less than \$1 per hour will not be paid. Payment will be limited to not more than eight hours in a 24-hour period or 40 hours in a one-week period.

(f) Blue Book Omissions - If a rental rate has not been established in the Blue Book, the Contractor may:

- If approved by the Engineer, use the rate of the most similar model found in the Blue Book, considering such characteristics as manufacturer, capacity, horsepower, age and fuel type;
- Request Primedia Information, Inc. to furnish a written response for a rental rate on the Equipment, which shall be presented to the Engineer for approval; or
- Request that the Engineer establish a rental rate.

(g) Outside Rental Equipment - If Contractor- or Subcontractor-owned Equipment is not available, and Equipment is rented from outside sources, payment will be based on the actual paid invoice.

If the invoice specifies that rental rate does not include fuel, lubricants, field repairs, and servicing, an amount equal to the Blue Book hourly operating cost may be added for those items that were excluded.

The Agency may reduce the payment when the invoice amount plus allowance is higher than the amount authorized under (c) through (f) of this Subsection.

The provisions of 00180.20(c) apply to owner-operated Equipment.

00197.30 Labor - The Contractor will be paid for all labor engaged directly on Force Account Work, including Equipment operators and supervisors in direct charge of the specific force account operations.

(a) Standard Calculation - The hourly amount paid to the Contractor for each employee engaged on Force Account Work will be two times the actual base hourly wage (excluding fringe benefits, vacation, and all other direct or indirect costs including subsistence) paid to the employee for:

- (1) Work under each Force Account Work order, up to an accumulated total value for labor under that order of \$10,000; and

(2) Workers whose work class has an industrial accident insurance rate of 25% or less as determined by the National Council on Compensation Insurance (NCCI) for the assigned risk pool for the appropriate worker class.

This amount paid to the Contractor will be full compensation for all costs associated with labor on Force Account Work including wages, fringe benefits, vacation, insurance, markup and other direct or indirect costs except for per diem costs. If per diem is paid to workers for similar Pay Item Work, per diem costs will be paid on an actual-cost basis for the Force Account Work. The markup described in 00197.80 will not be added, except that the supplemental markup for Force Account Work performed by Subcontractors will be allowed.

(b) Work Value for Labor over \$10,000 or NCCI Rate over 25% - After the accumulated value of labor performed under a Force Account Work order exceeds either 00197.30(a-1) or (a-2) above, payment for Force Account Work labor will be calculated as follows:

(1) Wages - The actual wages paid to laborers and supervisors, if those wages are paid at rates not more than those for comparable labor currently employed on the Project, or at the recognized, current, prevailing rates in the locality of the Project.

(2) Required Contributions - The actual cost of industrial accident insurance, unemployment compensation contributions, payroll transit district taxes, and social security for old age assistance contributions incurred or required under statutory law and these Specifications. The actual cost of industrial accident insurance is the NCCI rate for the assigned risk pool for the appropriate work class multiplied by the experience modification factor for the Contractor.

(3) Required Benefits - The actual amount paid to, or on behalf of, workers as per diem and travel allowances, health and welfare benefits, pension fund benefits, or other benefits, when such amounts are required by a collective bargaining agreement or other employment contract generally applicable to the classes of labor employed on the Project.

The cost of labor calculated under this Subsection will also be subject to the applicable markups in 00197.80.

00197.40 Invoices for Special Services - Invoices for Special Services that reflect current market pricing may be accepted without complete itemization of Materials, Equipment, and labor costs, if the itemization is impractical or not customary. The invoice for Special Services shall show credit for commercial trade discounts offered or available.

No percentage markup will be allowed other than that specified in 00197.80.

00197.80 Percentage Allowances - To the Contractor's actual costs incurred, as limited in this Section 00197, amounts equal to a percentage markup of such costs will be allowed and paid to the Contractor as follows:

Subsection	Percent
00197.10 Materials	17
00197.20 Equipment	17
00197.30(b) Labor	22
00197.40 Special Services	17

When a Subcontractor performs ordered Force Account Work, the Contractor will be allowed a supplemental markup of 8% on each Force Account Work order.

These allowances made to the Contractor will constitute complete compensation for overhead, general and administrative expense, profit, and all other Force Account Work costs that were incurred by the Contractor, or by other forces that the Contractor furnished. No other reimbursement, compensation, or payment will be made.

00197.90 Billings - Billings for Force Account Work by the Contractor shall be submitted for the Engineer's approval on forms provided by the Agency or approved by the Engineer. Billings for Materials (other than Incidental items out of the inventory of the Contractor or Subcontractors), rental Equipment from sources other than the Contractor or Subcontractors, and Special Services, shall be accompanied by copies of invoices for the goods and services. The invoices shall be fully itemized showing dates, quantities, unit prices, and complete descriptions of goods and services provided. Invoices for amounts of \$10 or less per invoice are not required, unless requested by the Engineer.

Costs included on the billings shall comply with the guidelines of 00197.10 through 00197.40.

When a billing for Force Account Work has been paid at the Project level, no further corrections will be made because of further review if those corrections amount to less than \$10.

PART 00100 REPLACED JANUARY, 2006

Section 00199 - Disagreements, Protests and Claims

ODOT Provisions and Requirements

(These procedures may be applicable, with modifications as necessary, to other Agencies. Local governments should consider particularly 00199.40 "Claim Decision; Review; Exhaustion of Administrative Remedies".)

Description

00199.00 General - This Section details the process through which the parties agree to resolve any disagreement concerning additional compensation or concerning a combination of compensation and Contract Time. These provisions do not apply to disagreements concerning only Contract Time (see 00180.80) or return of liquidated damages. The Agency will not consider direct disagreements, protests, or claims from Subcontractors, Materials suppliers, or any other Entity not a party to the Contract.

Provisions and Requirements

00199.10 Procedure for Resolving Disagreements - When disagreements occur, the Contractor shall first pursue resolution through the Engineer of all issues in the dispute, including without limitation the items to be included in the written notice in 00199.20. If the discussion fails to provide satisfactory resolution of the disagreement, the Contractor shall follow the protest procedures outlined in 00199.20. If the Engineer denies all or part of the Contractor's protest, and the Contractor desires to further pursue the issues, the Contractor must submit a claim for processing according to 00199.30.

00199.20 Protest Procedure - If the Contractor disagrees with anything required in a Change Order or other written or oral order from the Engineer, including any direction, instruction, interpretation, or determination that, in the Contractor's opinion, entitles or would entitle the Contractor to additional compensation, the Contractor shall do all of the following in order to pursue a protest and preserve its claim:

(a) Oral Notice - Give oral notice of protest to the Engineer and outline the areas of disagreement before starting or continuing the protested Work.

(b) Written Notice - File a proper written notice of protest with the Engineer within seven Calendar Days after receiving the protested order. In the notice the Contractor shall:

- Describe the acts or omissions of the Agency or its agents that allegedly caused or may cause damage to the Contractor, citing specific facts, persons, dates and Work involved;
- Describe the nature of the damages;
- Cite the specific Contract provision(s) that support the protest;
- Include the estimated dollar cost, if any, of the protested Work, and furnish a list of estimated Materials, Equipment and labor for which the Contractor might request additional compensation; and
- If additional compensation is estimated to be due, include the estimated amount of additional time required, if any.

The Engineer has no responsibility to evaluate the protest unless the Contractor has timely filed a proper notice submitting all of the above information. Failure to comply with this notice requirement renders the notice improper.

(c) Records - Keep complete records of all costs and time incurred throughout the protested Work, and allow the Engineer access to those and other supporting records. Provide daily records of protested Work, on a weekly basis, on a schedule to be set by agreement with the Engineer.

(d) Comparison of Records - Provide the Engineer adequate facilities for keeping cost and time records of the protested Work. The Contractor and the Engineer will compare records and either bring them into agreement at the end of each day, or record and attempt to explain any differences.

(e) Work to Proceed - In spite of any protest, proceed promptly with the Work ordered by the Engineer.

(f) Evaluation of Protest - The Engineer has no responsibility for evaluating a protest that is not timely filed, or for which adequate supporting documentation has not been kept. Provided the procedures above are followed, the Engineer will promptly evaluate all protests and, if the protest is denied, advise the Contractor in writing of the reasons for full or partial denial. If a protest is found to be valid, the Engineer will, within a reasonable time, make an equitable adjustment of the Contract. Adjustment of time will be evaluated according to 00180.80.

If the Contractor does not accept the Engineer's evaluation of the protest, the Contractor may pursue a claim as described in 00199.30.

00199.30 Claims Procedure:

(a) General - If the Contractor believes that additional compensation is due, and has pursued and exhausted all the procedures provided in 00199.10 and 00199.20 to resolve a disagreement and protest, the Contractor may file a claim. If the requirements of 00199.20 have not been met, or if a claim is not filed as provided in 00199.30, the Contractor waives any claim for additional compensation or for a combination of additional compensation and Contract Time.

The Agency's Contract is with the Contractor. There is no contractual relationship between the Agency and any Subcontractor. It is the Contractor's responsibility to fully analyze any claim before presenting it to the Agency. In addition, when a claim includes Work done or costs incurred by a Subcontractor, Materials supplier, or any Entity other than the Contractor, the Contractor remains solely responsible for presenting the claim to the Agency.

Claims that include Work done or costs incurred by any Entity other than the Contractor will not be considered by the Agency unless the Contractor has:

- Completed and provided its own written analysis and evaluation of the claim, and
- Verified by its own independent review and analysis the amount of compensation sought.

(b) Claims Requirements - At any time during the progress of the Work, but not later than 15 Calendar Days following the date of the Second Notification, the Contractor shall submit to the Engineer claims for compensation additional to that specified in the Contract. A claim not submitted within the 15 day limit is deemed waived by the Contractor, and the Agency may reject it.

Claims shall be made in writing, and shall include all information necessary for the Agency to properly and completely analyze the claim, including without limitation:

- (1) A detailed, factual statement of the claim for additional compensation and Contract Time, if any, with necessary dates and locations of Work involved in the claim;
- (2) The date(s) on which facts arose that gave rise to the claim;

(3) The specific Contract provisions that support the claim and a statement of the reasons why such provisions support the claim;

(4) Detailed facts supporting the Contractor's position relative to the Engineer's decision (see 00199.20(f));

(5) Copies of, or excerpts from, any documents that support the claim, such as manuals standard to the industry and used by the Contractor, other than Agency documents and documents previously furnished to the Engineer by the Contractor;

(6) If an Agency-caused delay is claimed:

- The specific days and dates under claim,
- The specific acts or omissions of the Agency that allegedly caused the delay, and the specific reasons why the resulting delay was unreasonable, and
- A schedule analysis that accurately describes the impacts of the claimed delay;

(7) The exact amount of additional compensation sought and the information and calculations necessary to support that amount. That amount may be calculated on the basis of Section 00197, if applicable, or may be calculated using direct and indirect costs presented in the following categories:

- Direct Materials,
- Direct Equipment. The rate claimed for each piece of Equipment shall not exceed the actual cost. In the absence of actual Equipment costs, the Equipment rates shall not exceed 75% of those calculated under the provisions of 00197.20. For each piece of Equipment, the Contractor shall include a detailed description of the Equipment and attachments, specific days and dates of use or standby, and specific hours of use or standby,
- Direct labor,
- Job overhead,
- General and administrative overhead, and
- Other categories as specified by the Contractor or the Agency; and

(8) If the claim includes Work done or costs incurred by a Subcontractor, Materials supplier, or any Entity other than the Contractor, the following are required:

- Data required by the other Subsections of 00199.30(b);
- Copy of the Contractor's separate analysis and evaluation;
- Copy of the Contractor's independent review and analysis of the amount of damages sought; and

(9) A certified statement by the Contractor, Subcontractor or Materials supplier, as appropriate, as to the validity of facts and costs containing the following language:

Under penalty of law for perjury or falsification, the undersigned, (Name), (Title), (Company) certifies that this claim for additional compensation for Work on the Contract is a true statement of the actual costs incurred (in the amount of \$ _____, exclusive of interest) and is fully documented and supported under the Contract between the parties.

Signature: _____

Date: _____, 20__

Subscribed and sworn before me this _____ day of _____, 20__

Notary Public

My commission expires _____.

A person authorized to execute Change Orders on behalf of the Contractor must countersign this statement.

(c) Records Required - The Contractor shall keep full and complete records of the costs incurred for the submitted claim. These records shall include all worksheets used to prepare the claim establishing the cost components for items of the claim.

(d) Access to Records - The Contractor shall provide the Engineer access to all Contractor records required to determine the facts, contentions, and costs involved in the claim. The Engineer may perform an audit of these records. The Contractor shall retain all Contract records for a period of at least three years after Final Acceptance of the Project by the Agency, or until all disputes, including litigation, if any, are resolved (the "record retention period"). The Agency and/or its agents shall be provided full access to all Contract records during the record retention period.


(e) Compliance Required - Full compliance by the Contractor with the provisions of this Section is a condition precedent to the commencement of any lawsuit by the Contractor to enforce any claim.

00199.40 Claim Decision; Review; Exhaustion of Administrative Remedies - The Agency intends to resolve claims at the lowest possible administrative level. If the Engineer denies the claim, in full or in part, pursuant to 00199.40(a), the Contractor may request review of the denial. The disputed claim may then be resolved, in full or in part, at any of the four progressive steps of claim review procedure as set forth in (b) through (e) of this Subsection. All of the actions and review under each step of the review process shall occur before the review can be advanced to the next higher step.

If, at any step in the claim decision or review process, the Contractor fails to promptly submit requested information or documentation that the Agency deems necessary to analyze the claim, the Contractor is deemed to have waived its right to further review, and the claim will not be considered properly filed and preserved.

(a) Decision by the Engineer - The Engineer will, as soon as practicable, consider, investigate, and evaluate a Contractor's claim for additional compensation, or for additional compensation and Contract Time, if submitted as required by 00199.30.

If the Engineer determines that additional information or documentation is needed to allow proper analysis of the claim, the Contractor shall meet with the Engineer within 14 Calendar Days, or as otherwise agreed by the parties, to present the additional information or documentation, or make other arrangements with the Engineer to supply that material.



The Engineer will advise the Contractor of the decision to accept or deny the claim, and the reasons for any full or partial denial of the claim, within 30 Calendar Days of receipt of the Contractor's claim, or the receipt of requested additional information or documentation regarding the claim, whichever is later, unless the Engineer and Contractor have agreed upon a longer response time. If the Contractor does not accept the Engineer's decision, the Contractor may, within 10 Calendar Days of receipt of the written decision, request in writing that the Engineer arrange a review at Step 1 (See (b) below).

(b) Step 1: Region Level Review - The Contractor shall request that the Engineer arrange a meeting with the Region-level reviewer in order to present the denied or partially denied claim for formal review and discussion. The meeting will take place within 21 Calendar Days of the Agency's receipt of the request, or as otherwise agreed by the parties.

If the Region-level reviewer determines that the Contractor must furnish additional information or documentation to allow proper analysis of the claim, the reviewer will schedule a second meeting, to be held within 14 Calendar Days, or as otherwise agreed by the parties, at which the Contractor shall present the requested information or documentation.

The Region-level reviewer will provide a written decision to the Contractor within 30 Calendar Days of the last Region-level meeting.

If the Contractor does not accept the Step 1 decision, the Contractor may, within 10 Calendar Days of receipt of the written decision, request in writing that the Engineer arrange a review at Step 2 (See (c) below).

(c) Step 2: Agency Level Review - The Contractor shall request a meeting with the Contract Administration Engineer, to present the claim for final Agency review. The presentation will take place within 21 Calendar Days of the Agency's receipt of the Contractor's written request, or as otherwise agreed by the parties.

If the Contract Administration Engineer determines that the Contractor must furnish additional information or documentation to allow proper analysis of the claim, the Contract Administration Engineer will schedule a second meeting, to be held within 14 Calendar Days or as otherwise agreed by the parties, at which the Contractor shall present the requested information or documentation.

The Contract Administration Engineer will provide a written decision to the Contractor within 30 Calendar Days of the final Step 2 meeting.

If the Contractor does not accept the Step 2 decision, the Contractor may, within 10 Calendar Days of receipt of the written decision, request in writing through the Engineer that the claim be advanced to Step 3 or 4 (See (d) and (e) below), as applicable.

(d) Step 3: Arbitration; Claims Review Board:

(1) Claims Less Than \$25,000 (as calculated in accordance with 00199.30(b)(7) above) - At this step, the claim will be resolved by binding arbitration before a single arbitrator according to the Construction Industry Arbitration Rules of the American Arbitration Association or such other arbitration service and rules as agreed by the parties.

Arbitration filing costs and any arbitrator's fees will be divided equally between the Agency and the Contractor.

(2) Claims of \$25,000 to \$250,000 (as calculated in accordance with 00199.30(b)(7) above) - Claims in excess of \$250,000 may be reviewed under this step only upon the agreement of the Contractor and the Engineer pursuant to 00190.40(d)(3) below.

At this step, the Contractor shall present the claim to a Claims Review Board (referred to as "Board") for consideration, review and recommended resolution. The Board will be comprised of three persons. ODOT will establish and maintain, in consultation with representatives of the construction industry, a panel of more than 12 qualified individuals available to serve on Boards.

If a claim within the scope of this step is properly referred for Board consideration and review, copies of biographies of all persons on the panel will be sent to the Contractor. Within 20 Calendar Days after the biographies are mailed, the Contractor and the Engineer shall each nominate, in writing, three individuals from the panel available to serve on the Board. Each party shall affirm the availability of its nominees.

Within 10 Calendar Days after receipt of the nominations, the Contractor and the Engineer shall (a) each appoint to the Board one of the three nominated by the other, (b) inform each other of the appointment, and (c) advise their three nominees, in writing, of the appointments. The two appointees, now Board Members, shall select one of the remaining members of the panel to serve as the Board Chair. If the two appointees cannot agree on the selection of the Board Chair, the Circuit Court in the county in which the Agency's main office is located will resolve the dispute. In this event, the Engineer will act through the Agency's legal counsel to request the Circuit Court to appoint one of the remaining members of the panel to serve as the Board Chair.

The Board may request the Engineer to designate a person not associated with the Contract to act as the recording secretary for the Board. The recording secretary is not a Board member, and will only assist the Board with administrative tasks related to its consideration and review of the referred claim.

The Agency and the Contractor will equally share the costs of the Board members. The Agency will pay the costs of the Board's recording secretary.

Members of the Board are to act impartially and independently in the consideration of facts and conditions surrounding the dispute. Board recommendations concerning the dispute are considered advisory only, shall not be binding on either party, and shall not constitute evidence in any legal proceeding for any reason.

The Board will schedule and conduct an informal hearing at which the Contractor and the Agency will each have an opportunity to present evidence and argument. The Contractor and the Agency shall each submit a brief written summary of the claim to each Board member and the other party at least 10 Calendar Days before the hearing. Unless directed otherwise by the Board Chair, the summary shall include, for each issue under dispute:

- A short statement describing the disputed issue;
- A short position statement by the party on the issue;
- A clear and concise explanation of the contractual basis for that position, including specific reference to Contract Documents;
- A clear and concise description of the costs claimed for each issue, including without limitation specific documents demonstrating productivity, time and costs; and
- Exhibits, including without limitation copies of plan sheets, extracts from the Standard Specifications, Supplemental Specifications (if any), and Special Provisions, correspondence, photographs, or other evidence to support the position.

The proceedings will be conducted in a manner determined by the Chair, in consultation with the other Board members. Unless directed otherwise by the Chair, the hearing will be conducted according to the following guidelines:

- The hearing will be informal;
- The witnesses will not be sworn;
- The Contractor will present its case first;
- The Agency will then present its case;
- Both parties will then have opportunity to present rebuttal;
- The Board may ask questions and, to promote open discussion of the issues, both parties may respond or emphasize issues;
- The parties' attorneys may observe the hearing and may respond to direct questions from the Board, but may not make factual presentations or legal arguments; and
- The Board will conclude the hearing when it appears to the Board Chair that each party has had sufficient opportunity to support its case and the Board has no further questions.

Within 10 Calendar Days after conclusion of the hearing, the Board will forward to the Agency's designated representative and the Contractor the Board's written recommendation for resolution of the claim. Within 10 Calendar Days of its receipt of the Board's recommendation, the Agency will provide to the Contractor the Agency's written decision regarding the claim.

If the Contractor does not accept the Agency's decision regarding the claim, the Contractor may proceed to litigation as described in Step 4 (See (e) below).

(3) Claims Over \$250,000 (as calculated in accordance with 00199.30(b)(7) above) - If the Contractor and the Engineer agree, the parties may employ the Step 3 Board review process in accordance with 00199.40(d)(2) above. If not, the Contractor may proceed to Step 4 (See (e) below).

(e) Step 4: Litigation - This step applies to:

- Claims over \$250,000 (as calculated in accordance with 00199.30(b)(7) above);
- Appeals of arbitration awards issued in Step 3 at 00199.40(d)(1) above, according to ORS 36.300 through 36.365; and
- Appeals of Agency decisions issued under Step 3 at 00199.40(d)(2) above.

The Contractor must follow each step in order, and exhaust all available administrative remedies before resort to litigation. Lawsuits must be properly filed in a court of competent jurisdiction within six months from the date of the final decision that exhausted the Contractor's available administrative remedies under this Section 00199.

In any litigation, the entire text of any order or permit issued by a governmental or regulatory authority, as well as any documents referenced or incorporated therein by reference, shall be admissible for the purpose of Contract interpretation.

The Contract shall not be construed against either party regardless of which party drafted it. Other than as modified by the Contract, the applicable rules of contract construction and evidence shall apply. This Contract shall be governed by and construed in accordance with the laws of the State of Oregon without regard to principles of conflict of laws.

Any dispute between the Agency and the Contractor that arises from or relates to this Contract and that is not resolved under the provisions of Section 00199 shall be brought and conducted solely and exclusively within the Circuit Court for the State of Oregon in the county where the Agency's main office is located; provided, however, if a dispute must be brought in a federal forum, then it shall be brought and conducted solely and exclusively within the United States District Court for the District of Oregon. In no event shall this Subsection be construed as a waiver by the State of Oregon on any form of defense or immunity, whether sovereign immunity, governmental immunity, immunity based on the Eleventh Amendment to the Constitution of the United States or otherwise, from any claim or from the jurisdiction of any court. CONTRACTOR BY EXECUTION OF THE CONTRACT HEREBY CONSENTS TO THE IN PERSONAM JURISDICTION OF THE COURTS REFERENCED IN THIS SECTION.

00199.50 Mediation - Notwithstanding the formal claims procedure set forth above, the parties may enter into nonbinding mediation by mutual agreement at any time, in which case the parties may also agree to suspend the time requirements in Section 00199 pending the outcome of the mediation process. The rules, time and place for mediation, as well as selection of the mediator, shall be established by mutual agreement. Costs shall be divided equally between the Contractor and the Agency. Either party may terminate mediation at any time upon five Calendar Days notice to the other, after which the time requirements of Section 00199 shall be automatically reinstated.

PART 00100 REPLACED JANUARY 2008