

**SECTION 00810 - METAL GUARDRAIL**

*(Follow all instructions. If there are no instructions above a subsection, paragraph, sentence, or bullet, then include them in the project but make necessary modifications to only include project specific specifications. Delete specifications that do not apply to the project.)*

*[ NOTE: Except for extra length guardrail posts, do not separately pay for new guardrail posts under this Section. New posts are already included in the appropriate guardrail pay item. Replacing existing guardrail posts are now covered in Section 00812. ]*

*(Use the following paragraph when subsections .40 and .90 is NOT included in the project.)*

Comply with Section 00810 of the Standard Specifications.

*(Use the following lead-in paragraph and subsections .40 and .90 when hand dug guardrail post holes are required. Obtain information from the Region Utility Specialist and the Designer.)*

Comply with Section 00810 of the Standard Specifications modified as follows:

**00810.40 Timing and Coordination of Work** - Add the following paragraph at the end of this subsection:

Contact the Engineer and the appropriate utilities 72 hours before beginning hand digging guardrail post holes.

**00810.90 Payment** - Add the following pay item:

- (j) Extra for Hand Dug Guardrail Post Holes .....Each

In item (j) the extra costs for hand dug holes are costs that are not covered and included in the unit price for one or more of the other listed pay items.

Payment for item (j) performed beyond the quantity shown in the Contract Schedule of Items will be made at the Contract unit price if the Engineer determines that the Contract unit price does not exceed the value of the work as determined on the basis of rates given in Section 00197. If the Engineer determines that the Contract unit price exceeds the value of the work, payment for the additional work will be made according to Section 00196.