ENERGY FACILITY SITING COUNCIL

OF THE

STATE OF OREGON

Third Amended Site Certificate for the Carty Generating Station

ISSUE DATES

Site Certificate	July 2, 2012
First Amended Site Certificate	December 14, 2018
Second Amended Site Certificate	November 19, 2020
Third Amended Site Certificate	July 22, 2022

THIS PAGE INTENTIONALLY LEFT BLANK

CARTY GENERATING STATION SITE CERTIFICATE TABLE OF CONTENTS

Page

1.0	INTRODUCTION	1
2.0	SITE CERTIFICATION	2
3.0	DESCRIPTION OF FACILITY	4
4.0	GENERAL ADMINISTRATIVE CONDITIONS	12
5.0	PRE-CONSTRUCTION REQUIREMENTS	13
6.0	DESIGN, CONSTRUCTION AND OPERATIONS	16
7.0	PUBLIC HEALTH AND SAFETY	21
8.0	ON-SITE SAFETY AND SECURITY	23
9.0	PROTECTION OF SOIL	24
10.0	PROTECTION OF NATURAL RESOURCES	26
11.0	PROTECTION OF HISTORIC, CULTURAL AND ARCHAEOLOGICAL RESOURCE	CES.37
12.0	Carbon Dioxide Emissions	40
13.0	NOISE CONTROL AND NOISE COMPLAINT RESPONSE	46
14.0	MONITORING AND REPORTING REQUIREMENTS - GENERAL	46
15.0	RETIREMENT AND FINANCIAL ASSURANCE	47
16. SU	JCCESSORS AND ASSIGNS	50
17. SE	VERABILITY AND CONSTRUCTION	50
18. GC	OVERNING LAW AND FORUM	50
19. EX	ECUTION	51

Acronyms and Abbreviations

AC	alternating current
ACEC	Area of Critical Environmental Concern
ADA	Americans with Disabilities Act
AMD1	Final Order on Amendment No. 1
AMD2	Final Order on Amendment No. 2
AMD3	Final Order on Amendment No. 3
Btu	British Thermal Unit
BCP	Boardman Coal Plant
Carty	Carty Generating Station
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
Council	Oregon Energy Facility Siting Council
CTG	combustion turbine generator
CTUIR	Confederated Tribes of the Umatilla Indian Reservation
DC	direct current
Department	Oregon Department of Energy
DEQ	Oregon Department of Environmental Quality
DOGAMI	Oregon Department of Geology and Mineral Industries
DPO	Draft Proposed Order
EPCRA	Emergency Planning and Community Right-to-Know Act
ESCP	Erosion and Sediment Control Plan
FAA	Federal Aviation Administration
FERC	Federal Energy Regulatory Commission
GTN	Gas Transmission Northwest LLC
HMA	Habitat Mitigation Area
HRSG	Heat Recovery Steam Generator
kV	kilovolt

MCZO	Morrow County Zoning Ordinance
MOU	Memorandum of Understanding
MSL	mean sea level
MW	megawatt
NPDES	National Pollutant Discharge Elimination System
O&M	Operations and Maintenance
OAR	Oregon Administrative Rule
ODFW	Oregon Department of Fish and Wildlife
ORS	Oregon Revised Statutes
OSSC	Oregon Structural Specialty Code
PGE	Portland General Electric Company
PV	photovoltaic
SHPO	Oregon State Historic Preservation Office
SPCC	Spill Prevention, Control, and Countermeasure
STG	Steam Turbine Generator
USFWS	United Stated Fish and Wildlife Service
Unit 1	450 megawatt natural gas-fueled, combined-cycle, combustion turbine generator
WGS	Washington Ground Squirrel
WPCF	Water Pollution Control Facilities

1.0 INTRODUCTION

The Oregon Energy Facility Siting Council (Council) issues this site certificate for the Carty Generating Station in the manner authorized under the Oregon Revised Statutes (ORS) Chapter 469. This site certificate is a binding agreement between the State of Oregon (State), acting through the Council, and Portland General Electric Company (certificate holder) authorizing the certificate holder to construct and operate the facility in Morrow and Gilliam counties, Oregon.

The findings of fact, reasoning, and conclusions of law underlying the terms and conditions of this site certificate are set forth in the following documents, which by this reference are incorporated herein: (a) the Council's Final Order in the Matter of the Application for a Site Certificate for the Carty Generating Station (Final Order on the Application) issued on June 29, 2012, (b) the Council's Final Order in the Matter of the Site Certificate for the Carty Generating Station Request for Amendment No. 1 (Final Order on Amendment No. 1 [AMD1]), (c) the Council's Final Order in the Matter of the Site Certificate for the Carty Generating Station Request for Amendment No.2 (Final Order on Amendment No. 2 [AMD2]), and (d) the Council's Final Order in the Matter of the Site Certificate for the Carty Generating Station Request for Amendment No. 3 (Final Order on Amendment No. 3 [AMD3]). In interpreting this site certificate, any ambiguity will be clarified by reference to the following, in order of priority: (1) this Site Certificate (issued July 22, 2022, effective July 22, 2022), (2) the Final Order on Amendment No. 3, (3) the record of the proceedings that led to the Final Order on Amendment No. 3, (4) the Final Order on Amendment No. 2, (5) the record of the proceedings that led to the Final Order on Amendment No. 2, (6) the Final Order on Amendment No. 1, (7) the record of the proceedings that led to the Final Order on Amendment No. 1, (8) the Final Order on the Application, and (9) the record of the proceedings that led to the Final Order on the Application.

This Site Certificate does not address, and is not binding with respect to, matters that were not addressed in the Council's Final Order on the Application, Final Order on Amendment No. 1, Final Order on Amendment No. 2, or Final Order on Amendment No. 3. Such matters include, but are not limited to: building code compliance; wage; hour; and other labor regulations; local government fees and charges; other design or operational issues that do not relate to siting the facility [ORS 469.401(4)]; and permits issued under statutes and rules for which the decision on compliance has been delegated by the federal government to a state agency other than the Council. ORS 469.503(3).

The obligation of the certificate holder to report information to the Department or the Council under the conditions listed in this site certificate is subject to the provisions of ORS 192.502 *et seq.* and ORS 469.560. To the extent permitted by law, the Department and the Council will not publicly disclose information that may be exempt from public disclosure if the certificate holder has clearly labeled such information and stated the basis for the exemption at the time of submitting the information to the Department or the Council. If the Council or the Department receives a request for the disclosure of the information, the Council or the Department, as appropriate, will make a reasonable attempt to notify the certificate holder and will refer the matter to the Attorney General for a determination of whether the exemption is applicable, pursuant to ORS 192.450.

The Council recognizes that many specific tasks related to the design, construction, operation and retirement of the facility will be undertaken by the certificate holder's agents or contractors. Nevertheless, the certificate holder is responsible for ensuring compliance with all provisions of the site certificate. The definitions in ORS 469.300 and Oregon Administrative Rule (OAR) 345-001-0010 apply to terms used in this site certificate, except where otherwise stated, or where the context clearly indicates otherwise.

2.0 SITE CERTIFICATION

- 2.1 To the extent authorized by state law and subject to the conditions set forth herein, the State authorizes the certificate holder to construct, operate, and retire a facility that includes a natural gas-fueled electrical generating unit and a photovoltaic (PV) solar electrical generating unit, together with certain related or supporting facilities, at the site in Morrow County and Gilliam County, Oregon, as described in Section 3.0 of this site certificate. [ORS 469.401(1)][AMD1; AMD2]
- 2.2 This site certificate is effective until 1) it is terminated under OAR 345-027-0110 or the rules in effect on the date that termination is sought; or 2) until the site certificate is revoked under ORS 469.440 and OAR 345-029-0100 or the statutes and rules in effect on the date that revocation is ordered.
 - [ORS 469.401(1)]
- 2.3 Both the State and the certificate holder shall abide by local ordinances, state law, and the rules of the Council in effect on the date this site certificate is executed. ORS 469.401(2). In addition, upon a clear showing of a significant threat to public health, safety, or the environment that requires application of later-adopted laws or rules, the Council may require compliance with such later-adopted laws or rules. [ORS 469.401(2)]

- 2.4 For a permit, license, or other approval addressed in and governed by this site certificate, the certificate holder shall comply with applicable state and federal laws adopted in the future to the extent that such compliance is required under the respective state agency statutes and rules. [ORS 469.401(2)]
- 2.5 Subject to the conditions herein, this site certificate binds the State and all counties, cities, and political subdivisions in Oregon as to the approval of the site and the construction, operation, and retirement of the facility as to matters that are addressed in and governed by this site certificate. [ORS 469.401(3)]
- 2.6 Each affected state agency, county, city, and political subdivision in Oregon with authority to issue a permit, license, or other approval addressed in or governed by this site certificate shall, upon submission of the proper application and payment of the proper fees, but without hearings or other proceedings, issue such permit, license, or other approval subject only to conditions set forth in this site certificate. [ORS 469.401(3)]
- 2.7 After issuance of this site certificate, each state agency or local government agency that issues a permit, license, or other approval for the facility shall continue to exercise enforcement authority over such permit, license, or other approval. [ORS 469.401(3)]
- 2.8 After issuance of this site certificate, the Council shall have continuing authority over the site and may inspect, or direct the Oregon Department of Energy (Department) to inspect, or request another state agency or local government to inspect, the site at any time in order to ensure that the facility is being operated consistently with the terms and conditions of this site certificate. [ORS 469.430]
- 2.9 The certificate holder shall design, construct, operate and retire the facility:
 - a. Substantially as described in the site certificate;
 - b. In compliance with the requirements of ORS Chapter 469, applicable Council rules, and applicable state and local laws, rules and ordinances in effect at the time the site certificate is issued; and
 - c. In compliance with all applicable permit requirements of other state agencies. [Final Order III.D.2] [Mandatory Condition OAR 345-025-0006(3)]
- 2.10 Before any transfer of ownership of any unit of the facility or ownership of the site certificate holder, the certificate holder shall inform the Department of the proposed new owners. The requirements of OAR 345-027-0400 apply to any transfer of ownership that requires a transfer of the site certificate. [Final Order IV.B.2.8] [Mandatory Condition OAR 345-025-0006(15)] [AMD1; AMD2]

- 2.11 Any matter of non-compliance under the site certificate shall be the responsibility of the certificate holder. Any notice of violation issued under the site certificate shall be issued to the certificate holder. Any civil penalties assessed under the site certificate shall be levied on the certificate holder. [Final Order IV.B.2.5]
- 2.12 Within 72 hours after discovery of conditions or circumstances that may violate the terms or conditions of the site certificate, the certificate holder shall report the conditions or circumstances to the Department. [Final Order IV.B.2.7]
- 2.13 The Council shall not change the conditions of this site certificate except as provided for in OAR Chapter 345, Division 27.
 [Final Order VI.1] [Mandatory Condition OAR 345-025-0006(1)] [AMD2]
- 2.14 The certificate holder must: Prior to construction of the Carty Solar Farm, provide evidence to the Department that a limited water use license from Oregon Department of Water Quality has been obtained by its third-party-contractor.
- 2.15 During construction of the Carty Solar Farm, provide to the Department in semi-annual reports, pursuant to OAR 345-026-0080, documentation of the record of all water use, as required by the third-party's limited water use license, demonstrating that the allowable total and per minute water use (total gallons and gallons per minute) have not been exceeded. [AMD1]

3.0 DESCRIPTION OF FACILITY

3.1 LOCATION AND SITE BOUNDARY

The Carty Generating Station is located in Morrow and Gilliam Counties, Oregon, southwest of the City of Boardman and adjacent to the Carty Reservoir.

As defined by OAR 345-001-0010, the "site boundary" is the perimeter of the site of the energy facility, its related or supporting facilities, all temporary staging areas, and all corridors. The site boundary for the Carty Generating Station encompasses approximately 4,997 acres.

3.2 THE ENERGY FACILITY

The Carty Generating Station includes a natural gas-fueled combined-cycle unit and a solar photovoltaic (PV) electric power generating unit. The Carty Generating Station is capable of generating up to 500 megawatts (MW) of electrical power (up to 450 MW from the natural gas-fueled combined-cycle unit [Unit 1], and up to 50 MW from the solar PV generating unit).

Unit 1 of the Carty Generating Station includes one natural-gas-fueled generating unit consisting of one high efficiency combustion turbine generator (CTG), heat recovery steam generator (HRSG), and a steam turbine generator (STG). Within this unit, the natural gas CTG produces electricity, with the exhaust gases from the CTG supplying heat to the HRSG. Steam produced in the HRSG is used to power the STG to produce additional electricity. Duct burners fueled by natural gas in the HRSG allow for production of additional steam and additional electricity from the STG. Steam exhausted from the STG is condensed in a water-cooled condenser, with the resultant condensate returned to the HRSG to produce additional steam. Water used for cooling in the water-cooled condenser is routed to a cooling tower, where the water is cooled and then pumped back through the condenser. If required for starting the CTG or to maintain the plant in a ready-to-start condition, a natural gas-fueled auxiliary boiler will be used to supply steam when none is available from the HRSG. The CTG and STG are located within a generating building to control noise during operation and to allow a controlled atmosphere for maintenance activities. A separate water treatment building houses the equipment necessary to purify raw water, producing de-mineralized water for use in the steam cycle of the unit.

Generator transformers step up the voltage produced by the gas-fueled unit to 500 kilovolts (kV). A 500-kV transmission line connects the generator transformers to a 500-kV switchyard, the Grassland Switchyard. From the switchyard, Portland General Electric Company (PGE) utilizes the existing 500-kV Boardman to Slatt transmission line to connect to the Slatt Substation.

The Carty Generating Station consumes about 75 million cubic feet of natural gas per day during operation of the gas-fired generating unit. Natural gas is supplied to the facility through a lateral pipeline operated by Gas Transmission Northwest LLC (GTN). This lateral pipeline is owned and operated by GTN and is outside the jurisdiction of the Council. This natural gas pipeline was permitted by the Federal Energy Regulatory Commission (FERC).

In addition to Unit 1, the Carty Generating Station also includes a 50 MW solar PV power generating unit, the Carty Solar Farm, occupying a 315-acre site located south of the Carty Reservoir. The Carty Solar Farm was permitted through the First and Third Amended Site Certificates, and consists of multiple solar modules mounted on racking systems, connected in series strings, to produce direct current (DC) electricity from sunlight. The DC electricity is then routed to inverters and step-up transformers to be converted to alternating current (AC) electricity and voltage increased to the appropriate collector circuit potential. Electrical power produced by the Carty Solar Farm would be collected and routed via a new 34.5 kV transmission line to one of three interconnection options located north of the Carty Reservoir. Five potential transmission line routes from the Carty Solar Farm to the three interconnection options are currently permitted under the First and Third Amended Site Certificate for Carty Generating Station. Each route would be of the same approximate design and would be approximately 2 to 3 miles long, depending on the route selected. If an interconnection to the Grassland Switchyard is selected, the switchyard would be enlarged to 15 acres, as approved

in the original Site Certificate and the First Amended Site Certificate for Carty Generating Station.

The Carty Generating Station includes the following related or supporting facilities:

- Carty Reservoir and portions of the raw water intake system (includes 400-gallon sodium hypochlorite tank, 1,100-gallon anti-scalant; and 400-gallon sodium hypochlorite tote) and associated electrical connection
- Grassland Switchyard
- 500-kV transmission line from Unit 1 to the Grassland Switchyard
- 500-kV transmission line from Grassland Switchyard to the Slatt Substation
- 230-kV transmission line from the Carty Substation to the Dalreed substation
- 34.5-kV Grassland Switchyard backup station transmission line
- 34.5-kV construction substation to railroad crossing transmission line
- 34.5-kV Carty Solar Farm transmission line
- 7.2-kV Carty Generating Station backup transmission line
- 4.2-kV Grassland substation service line
- Interconnecting water pipelines
- Well (Boeing Well) / pump house and associated 12.5-kV power line
- Cooling tower
- Liquid storage facilities
- Sanitary sewer (sewer lagoons and septic system)
- Accessory buildings
- Utility and communication lines
- Access Roads
- Additional temporary construction areas
- Water Discharge Channel
- Construction Substation
- 300,000-gallon water storage tank, adjacent pumphouse, and associated water pipeline

- Evaporation Ponds
- Irrigation Pump Station and 34.5 kV transmission line
- Septic system
- Water pipeline connecting BCP's 300,000-gallon water tank
- Security guard station
- Office and warehouse building; and 35x40 work station¹
- Carty Substation and associated distribution lines

Two control and administrative buildings provide space for plant controls and offices for plant personnel for Unit 1 and the Carty Solar Farm. A description of major components, structures, and systems of each related or supporting facility that is part of Carty Generating Station per the Site Certificate for Carty Generating Station is provided in the following subsections.

Carty Reservoir

Carty Reservoir is a wastewater and cooling pond that provides service water to the Carty Generating Station and receives cooling tower blow down and wastewater from the wastewater collection sump. The reservoir also stores water used to irrigate nearby agricultural fields. Because the area is arid, all the water for filling and maintaining the reservoir is pumped through pipes from the Columbia River, approximately 10 miles to the north. When full, at a surface elevation of 677 feet above mean sea level (MSL), the reservoir has a capacity of 38,000-acre feet, a surface area of approximately 1,450 acres (2.3 square miles), and a maximum depth of 77 feet. The average pool elevation for the reservoir surface area is approximately 667 to 668 feet above MSL. At this elevation, the reservoir surface area is approximately 1,100 acres and contains approximately 26,000-acre feet of water. The reservoir is not used for recreation, and there is no public access to it.

Water leaves Carty Reservoir through withdrawals for use at the Carty Generating Station, through evaporation from the surface of the reservoir, withdrawals for irrigation, and through underground seepage from the reservoir. A buried toe drain at the West Dam captures seepage to pump back into the reservoir, and there is a concrete emergency spillway adjacent to the West Dam. There is an irrigation pump station located on the southwest arm shore of Carty Reservoir within an approximately 0.2 acre fenced area; the irrigation pump station is used to pump water out of Carty Reservoir for irrigation of nearby agricultural fields. There is a

¹ Facility modification reported by certificate holder in 2021 Annual Report.

2,600 foot-long underground 34.5 kV transmission line that powers the pump station from a PacifiCorp transmission line.

On-Site Transmission Lines

500 kV Unit 1 to Grassland Switchyard Transmission Line An approximate 1-mile long 500kV transmission line, mounted on four steel lattice towers, connects the step-up transformers located at the gas-fueled generating unit to the Grassland Switchyard. These towers are between 100 and 150 feet tall and are spaced approximately between 800 feet and 1,700 feet apart.

4.2 kV Grassland Station Service Line

A 4.2 kV station service line extends approximately 1 mile from Carty Generating Station to the Grassland Switchyard. For most of its length, this line is mounted on wood poles. However, the line runs underground for approximately 750 feet prior to entering the Grassland Switchyard to avoid clearance conflicts with the 230 kV BCP to Dalreed transmission line. This line provides power to the Grassland Switchyard from Carty Generating Station.

7.2 kV Carty Generating Station Backup Power Line

A 7.2 kV above ground backup power line extends approximately 0.5 mile from BCP or the Carty substation once constructed to Carty Generating Station. This line runs underground approximately 0.10 mile north of BCP; the remainder of the line is mounted on wood poles. Once the Carty substation is constructed the line will be entirely above ground.

34.5 kV Grassland Backup Station Service Line

A 34.5 kV line (referred to as the Grassland backup station service line) provides backup power to Grassland Switchyard via an approximately 800-foot underground line extending west and then north from the transformer within Grassland Switchyard, connecting to the existing 34.5 kV BCP to Railroad Crossing at Tower Road Transmission Line described above.

34.5 Carty Solar Farm Transmission Line

A 34.5-kV transmission line from the Carty Solar Farm will route around the eastern end of Carty Reservoir and then follow one of five potential routes to the point of interconnection at the Grassland Switchyard, Unit 1, or the Boardman Plant.

Off-Site Transmission Lines

500 kV BCP to Slatt Transmission Line

To access the grid, certificate holder utilizes the 500-kV Boardman to Slatt transmission line, a 500-kV single circuit transmission line, to connect the Grassland Switchyard to the Slatt Substation. The transmission line is approximately 17 miles long from Grassland Switchyard to Slatt Substation.

230 kV BCP to Dalreed Transmission Line

The 230kV BCP to Dalreed transmission line connects the Dalreed substation to the power block at BCP or the Carty substation once built. It is used to provide power to Carty Generating Station via the 7.2 kV Carty Generating Station back up transmission line and provide power to the construction substation.

34.5 kV BCP to Railroad Crossing at Tower Road Transmission Line

The 34.5 kV BCP to Railroad Crossing at Tower Road Transmission Line provides power to the railroad crossing signal at Tower Road and power to the seepage pumps for Carty Reservoir. The power for this line is provided via the construction substation.

Grassland Switchyard

A 500-kV, alternating current, open-air switchyard is located west of the Carty Generating Station. The switchyard consists of an 8.5-acre leveled and graveled area surrounded by a security fence. The switchyard was approved up to approximately 15 acres in size in the original Site Certificate, and may be expanded to that size depending on the interconnection needs of the Carty Solar Farm. The switchyard includes 500-kV circuit breakers and disconnect switches to allow for clearing faults on the connected transmission lines and for maintenance of the circuit breakers and transmission lines. Steel take-off towers terminate 500-kV overhead transmission lines that connect the switchyard with the plant generator step-up transformers and outgoing transmission lines. An additional small building provides a controlled environment for the protective relaying and communication equipment.

Carty Substation

Carty Substation is a 7.2 kV open box structure substation, with control house for relay, SCADA, communications, and DC system, dead-end structure for the existing 230 kV Boardman to Dalreed transmission line, and surrounding fence that would be located southeast of the construction substation. It will provide backup power to Carty Generating Station via an above ground distribution line that connects to the 7.2 kV Carty Generating Station backup transmission line, and power to the construction substation via an underground distribution line.

Construction Substation

The Construction Substation is located within a 40-foot by 80-foot fenced area that contains three wooden H-frame structures, transformers and associated electrical equipment, including a 6-foot by 8-foot control house. It was built originally to provide construction power during construction of BCP and continues to be used as part of the onsite electrical distribution system. This facility is located approximately 0.3 miles south of CGS. The construction substation is powered by an underground distribution line from Carty substation.

Water Sources and Discharges

There are four categories of water sources and discharges that serve Carty Generating Station: raw water/fire water, wastewater, potable water, and sanitary sewer.

Raw Water/Fire Water

Raw water from the Carty Reservoir is used for service water and fire water. It is withdrawn via a single intake structure located inside the Raw Water Intake Building, from which it is taken in through a channel outfitted with a traveling screen and enters a wet well. Power is provided to the intake building via an underground distribution line from Carty Generating Station to the intake building.

Wastewater

Carty Generating Station process waste and plant drainage waste flows are discharged into holding ponds, which can provide 7 days of holding capacity (if needed for discharge line maintenance or some other event preventing direct discharge). From the holding ponds, wastewater is discharged via an 8-inch-diameter pipeline into Water Discharge Channel prior to entering Carty Reservoir or to evaporation ponds located northeast of Carty Generating Station (formerly BCP evaporation ponds).

Potable Water

Potable water for drinking fountains, showers (emergency and lavatory), sinks, and flushing of lavatory fixtures comes from the Boeing Well. The Boeing Well is a groundwater extraction well located just south of Carty Generating Station. The well is 600 feet deep with a 30 horsepower pump hung at around 440 feet below ground surface. The well fills a holding tank within Carty Generating Station prior to direct distribution to the plant services building. The Boeing Well pump drive motor is powered from a 150-kilovolt-ampere 12470-480/277 V distribution transformer. This transformer is connected via a 12.5 kV overhead underground distribution line to the construction substation. The construction substation, in turn, derives power from a 12.5kV originating at the 1X33 transformer at BCP.

Carty Generating Station also includes backup potable/firewater storage in a 300,000 gallon, welded-steel water storage tank with adjacent pump house. This facility is connected to Boeing well via a 4-inch-diameter intake pipeline and to Carty Generating Station via a water pipeline.

Sanitary Sewer

Sanitary sewer flows at Carty Generating Station are solely from plant lavatories, sinks, and bathroom showers used by plant personnel. These flows are directly discharged to the sewage lagoons via a sewer lift station, or an onsite septic system. There are three existing sewage lagoons: the South Lagoon and Middle Lagoon (both lined), and the North Lagoon (unlined).

The South and Middle Lagoons can also be made common by a gated pipe through the separating dike. The only connection between the lined lagoons and the unlined lagoon is overflow through a chlorinating weir at the northeast corner of the Middle Lagoon. The clay liners in the South and Middle Lagoons were replaced with new synthetic liners in the fall of 2014. The sewage lagoons are permitted under Water Pollution Control Facilities (WPCF) permit number 100189.

The septic system is sized per state and county standards and the Umatilla County Public Health Department requirements and is in an area deemed acceptable for a standard, non-residential septic system. Because the design flow of the system is less than 2,501 gallons per

day, the facility is not governed by a permit from Oregon Department of Environmental Quality (DEQ).

Cooling Tower

The cooling tower at the Carty Generating Station exhausts excess heat from the power generation process. The cooling tower consists of a structure to contain a water-cooling medium, with exhaust fans located within an open-top, bell-shaped housing which pulls air under and through the water-cooling medium. The cooling tower is approximately 50 feet in height. The mechanical-draft wet cooling tower serves the combined cycle unit of the Carty facility.

Liquid Storage Facilities

Liquid fuel is not stored on the Carty facility site. Anhydrous ammonia, a chemical used for emissions control, is stored in steel horizontal sealed storage tanks with secondary containment. Other liquid chemicals such as sulfuric acid (used for pH control) and sodium hypochlorite and sodium bromide (used as biocides in cooling tower water) are stored in tanks or totes with secondary containment. Small-quantity chemicals such as cleaners and lubricants are stored within on-site accessory buildings.

Accessory Buildings

Accessory buildings at the Carty Generating Station site house boiler feed pumps, chemical feed equipment, water treatment equipment, and other equipment requiring protection from weather or noise containment. Accessory buildings common to the gas-fired generating unit and solar unit include warehouse and office space, administration areas, and security guard station.

Communication Lines

Communication lines supporting the Carty Generating Station originate from a Century Link vault near the northwest corner of the BCP lined evaporation ponds, run down the dirt access road, along Tower Road, and then into the Carty facility.

Access Roads

A paved loop road, approximately 24 feet wide and 2,100 feet long, connects with Tower Road at both ends of the loop to serve normal truck and operator vehicle traffic for Unit 1. This loop road has spur roads leading to individual buildings and areas that require access. An existing paved and graveled road provides access to the permitted location of the Carty Solar Farm. The Carty Solar Farm would contain unpaved on-site access roads.

Additional Temporary Construction Areas

Additional areas in the vicinity of the Carty Generating Station are provided for construction offices, construction parking, construction staging, and temporary storage of soil displaced during the construction process. Similar temporary construction areas are provided in the vicinity of the Grassland Switchyard.

4.0 GENERAL ADMINISTRATIVE CONDITIONS

- 4.1 The certificate holder shall:
 - i. Begin construction of Unit 1 within three years after the effective date of the site certificate. Under OAR 345-015-0085(9), a site certificate is effective upon execution by the Council Chair and the applicant. The Council may grant an extension of the deadline to begin construction in accordance with OAR 345-027-0030 or any successor rule in effect at the time the request for extension is submitted.

[Final Order III.D.3; Mandatory Condition OAR 345-027-0020(4)]

- ii. Begin construction of the Carty Solar Farm by February 4, 2025. [AMD1; AMD3]
- Begin construction of the facility components authorized by the Final Order on Request for Amendment 2 within three years after the effective date of the amended site certificate, or [December 9, 2020]. Under OAR 345-015-0085(8), the site certificate is effective upon execution by the Council Chair and the certificate holder. [AMD2]
- 4.2. The certificate holder must:
 - i. Complete construction of Unit 1 of the facility within three years of beginning construction of Unit 1. Construction is complete when: 1) the facility is substantially complete as defined by the certificate holder's construction contract documents; 2) acceptance testing has been satisfactorily completed; and 3) the energy facility is ready to begin continuous operation consistent with the site certificate. The certificate holder shall promptly notify the Department of the date of completion of construction of Unit 1. The Council may grant an extension of the deadline for completing construction in accordance with OAR 345-027-0030 or any successor rule in effect at the time the request for extension is submitted. [Final Order III.D.4] [Mandatory Condition OAR 345-027-0020(4)] [AMD1]
 - ii. Complete construction of the Carty Solar Farm by February 4, 2028. The certificate holder shall promptly notify the Department of the date of completion of construction of the Carty Solar Farm and its supporting facilities. [AMD1; AMD3]
 - iii. Complete construction of the facility components authorized by the Final Order on Request for Amendment 2 within six years of the effective date of the amended site certificate, or [December 9, 2020]. The certificate holder shall promptly notify the Department of the date of completion of construction of these supporting facilities.
 [AMD2]

4.3. [DELETED] [AMD1]

- 4.4. The certificate holder shall submit a legal description of the site to the Department of Energy within 90 days after beginning operation of the facility. The legal description required by this rule means a description of metes and bounds or a description of the site by reference to a map and geographic data that clearly and specifically identifies the outer boundaries that contain all parts of the facility. [Final Order III.D.1] [Mandatory Condition OAR 345-025-0006(2)] [AMD1]
- 4.5 The certificate holder shall obtain all necessary federal, state, and local permits or approvals required for construction, operation, and retirement of the facility or ensure that its contractors obtain the necessary federal, state, and local permits or approvals. [Final Order IV.B.2.4]
- 4.6 The certificate holder must obtain, as required by ORS 469.401(3), all local permits, to include a Conditional Use Permit for the portion of the Carty Generating Station facility located on land zoned Exclusive Farm Use and a Zoning Permit for the entire facility located within Morrow County. [Final Order IV.E.4.6] [AMD2]

5.0 PRE-CONSTRUCTION REQUIREMENTS

In addition to pre-construction requirements contained elsewhere in this site certificate, the certificate holder must meet the following requirements:

- 5.1 Before beginning construction, the certificate holder must notify the Department of the identity and qualifications of the major design, engineering, and construction contractor(s) for the facility. The certificate holder must select contractors that have substantial experience in the design, engineering, and construction of similar facilities. The certificate holder must report to the Department any change of major contractors. [Final Order IV.B.2.1] [AMD1]
- 5.2 The certificate holder must contractually require all construction contractors and subcontractors involved in the construction of the facility to comply with all applicable laws and regulations and with the terms and conditions of the site certificate. Such contractual provisions do not relieve the certificate holder of responsibility under the site certificate.

[Final Order IV.B.2.3] [AMD1]

5.3 Before beginning construction of Unit 1, the certificate holder shall submit a final parking lot plan to Morrow County for approval as part of the certificate holder's building permit application for the energy facility. This parking lot plan shall comply with Section 4.040 and 4.060 of the Morrow County Zoning Ordinance (MCZO) and with Americans with Disabilities Act (ADA) requirements. This plan shall provide a minimum of 22 parking spaces and one ADA-accessible space, or the minimum number of parking spaces required by MCZO Section 4.040 based on the number of employees on the largest

shift, whichever is greater. The certificate holder shall construct on-site parking in conformance with the approved parking lot plan. [Final Order IV.E.4.2] [MCZO Section 4.040-4.060] [AMD2]

- 5.4 Before beginning construction of Unit 1 and Carty Solar Farm, the certificate holder must:
 - i. Complete an investigation of subsurface soil and geologic conditions to identify geological or geotechnical hazards per Condition 5.4.a and obtain Department approval of the investigation report per Condition 5.4.b.
 - a. The investigation must include at least the following activities:
 - Drilling of six to eight exploratory borings up to a depth of 75 feet under proposed critical structure locations, including the gas turbine units, cooling tower, transmission structures, and switchyard. Standard penetration tests should be conducted at 2.5-foot and 5-foot intervals. Drilling of exploratory borings along transmission line corridor is not necessary if such information is available from the construction of the existing transmission line.
 - Digging of test pits to assess the extent and thickness of any loose, surficial soil layers at the site. Key focus areas should include planned locations of critical structures, roadways, and landscaped areas where irrigation would occur.
 - 3. Performing laboratory testing to evaluate the engineering properties of soils, including natural water contents on all samples collected, mechanical and hydrometer gradations, Atterberg limits, and collapsibility and consolidation tests on selected samples.
 - b. The certificate holder must prepare a geotechnical report with final facility design recommendations based on the investigation conducted per the requirements of Condition 5.4.a. The geotechnical report must be submitted to the Oregon Department of Geology & Mineral Industries (DOGAMI) and the Department. The certificate holder may not commence construction of the facility prior to Department approval of this report. [Final Order IV.C.2.1]
 - ii. Complete an investigation of subsurface soil and geologic conditions, based upon a protocol reviewed and approved by the Department in consultation with DOGAMI, to identify geological or geotechnical hazards and obtain Department approval of the investigation report per Condition 5.4.i.b.
 - a. The investigation must include at least the following activities:
 - Drilling of additional borings at scattered locations across the Carty Solar Farm and associated transmission lines and access roads, up to a depth of 50 feet.
 - [AMD1] [AMD2]
- 5.5 Prior to beginning construction of Unit 1, facility components approved in Final Order on RFA1, or facility components approved in Final Order on RFA2, the certificate holder must consult with the Morrow County Weed Control Supervisor and obtain approval of a Revegetation and Noxious Weed Control Plan. The final Revegetation and Noxious

Weed Control Plan must be submitted to the Department of Energy, based upon the draft amended plan provided as Attachment D of the Final Order on Amendment 2, for approval prior to the start of construction.

During construction and operation of the facility, the certificate holder must implement a revegetation and weed control plan. The certificate holder must comply with the applicable provisions of the Morrow County Weed Control Ordinances, as determined by the Morrow County Weed Control Supervisor and the Gilliam County Weed Control Officer.

[Final Order IV.D.2.6] [AMD1] [AMD2]

- Before beginning construction of Unit 1, the certificate holder must submit a Notice of 5.6 Proposed Construction or Alteration to the Federal Aviation Administration (FAA) and the Oregon Department of Aviation identifying the final location of the facility exhaust stack. The certificate holder must promptly notify the Department of the responses from the FAA and the Oregon Department of Aviation. [Final Order V.D.2.5]
- 5.7 Except as necessary for the initial survey or as otherwise allowed for wind energy facilities, transmission lines or pipelines under OAR 345-027-0020, the certificate holder shall not begin construction, as defined in OAR 345-001-0010, or create a clearing on any part of the site until the certificate holder has construction rights on all parts of the site. For the purpose of this rule, "construction rights" means the legal right to engage in construction activities.

[Final Order III.D.6] [Mandatory Condition OAR 345-027-0020(5)]

- Before beginning construction, the certificate holder must notify the Department in 5.8 advance of any work on the site that does not meet the definition of "construction" in ORS 469.300 (excluding surveying, exploration, or other activities to define or characterize the site) and must provide to the Department a description of the work and evidence that its value is less than \$250,000. [Final Order IV.B.2.6]
- 5.9 The certificate holder shall develop and implement a Spill Prevention, Control and Countermeasure (SPCC) Plan in accordance with 40 Code of Federal Regulations (CFR) 112. A copy of this plan shall be provided to the Department prior to the commencement of operation of Carty Generating Station, and shall be updated according to the timelines provided in 40 CFR 112. [Final Order IV.G.2.1] [AMD1] [AMD2]
- 5.10 Before beginning construction of the Carty Solar Farm, the certificate holder shall record in the deed records of Morrow County a document binding the certificate holder and its successors in interest, prohibiting them from pursuing a claim for relief or cause of action alleging injury from farming or forest practices as defined in ORS 30.930(2) and (4).

6.0 DESIGN, CONSTRUCTION AND OPERATIONS

- 6.1 During construction, the certificate holder must have a full-time, on-site manager who is qualified in environmental compliance to ensure compliance with all site certificate conditions. The certificate holder must notify the Department of the name, telephone number, and e-mail address of this person prior to the start of construction and immediately upon any change in the contact information. [Final Order IV.B.2.2]
- 6.2 The certificate holder shall provide portable toilets for on-site sewage handling during construction and shall ensure that they are pumped and cleaned regularly by a licensed contractor who is qualified to pump and clean portable toilet facilities. [Final Order IV.N.2.3]
- 6.3 The certificate holder shall implement a waste management plan during construction that includes but is not limited to the following measures:
 - a. Recycling steel and other metal scrap.
 - b. Recycling wood waste.
 - c. Recycling packaging wastes such as paper and cardboard.
 - d. Collecting non-recyclable waste for transport to a local landfill by a licensed waste hauler.
 - e. Segregating all hazardous wastes such as used oil, oily rags and oil-absorbent materials, mercury-containing lights and lead-acid and nickel-cadmium batteries for disposal by a licensed firm specializing in the proper recycling or disposal of hazardous wastes.
 - f. Confining concrete delivery truck rinse-out to a designated wash-out area and burying other concrete waste as part of backfilling.
 [Final Order IV.N.2.1]
- 6.4 In advance of, and during, preparation of detailed design drawings and specifications for the 500-kV transmission line, the certificate holder shall consult with the Utility Safety and Reliability Section of the Oregon Public Utility Commission to ensure that the designs and specifications are consistent with applicable codes and standards. [Final Order V.D.2.3]
- 6.5 The certificate holder must design, construct and operate the transmission lines in accordance with the requirements of the National Electrical Safety Code (American National Standards Institute, Section C2, 1997 Edition, or its successor document). [Final Order IV.O.2.1] [Mandatory Condition OAR 345-027-0023(4)]] [AMD2]
- 6.6. The certificate holder must design and construct the facility in accordance with requirements of the current Oregon Structural Specialty Code and the International Building Code in effect at the time of the start of construction for each unit. [Final Order IV.C.2.4] [AMD1]

- 6.7. The certificate holder must design, engineer and construct the facility to avoid dangers to human safety and the environment presented by seismic hazards affecting the site that are expected to result from all maximum probable seismic events. As used in this rule "seismic hazard" includes ground shaking, ground failure, landslide, liquefaction, triggering and consequences (including flow failure, settlement buoyancy, and lateral spreading), cyclic softening of clays and silts, fault rupture, directivity effects and soil-structure interaction. For coastal sites, this also includes tsunami hazards and seismically-induced coastal subsidence. [Final Order IV.C.2.5] [Mandatory Condition OAR 345-025-0006(12)][AMD2]
- 6.8. The certificate holder must design, engineer and construct the facility to avoid dangers to human safety presented by non-seismic hazards. As used in this condition, "non-seismic hazards" include settlement, landslides, flooding and erosion. [Final Order IV.C.2.6]
- 6.9. The certificate holder shall design and construct the facility using the minimum land area necessary for safe construction and operation. The certificate holder shall locate access roads and temporary construction laydown and staging areas to minimize disturbance of farming practices. [Final Order IV.E.4.1] [MCZO Section 3.010.D]
- 6.10. The certificate holder must notify the Department, the State Building Codes Division and the Department of Geology and Mineral Industries promptly if site investigations or trenching reveal that conditions in the foundation rocks differ significantly from those described in the application for a site certificate or requests for amendment. After the Department receives the notice, the Council may require the certificate holder to consult with the DOGAMI and the Building Codes Division to propose and implement corrective or mitigation actions.

[Final Order IV.C.2.2] [Mandatory Condition OAR 345-025-0006(13)] [AMD1] [AMD2]

- 6.11. The certificate holder must notify the Department, the State Building Codes Division and the Department of Geology and Mineral Industries promptly if shear zones, artesian aquifers, deformations or clastic dikes are found at or in the vicinity of the site. After the Department receives notice, the Council may require the certificate holder to consult with the Department of Geology and Mineral Industries and the Building Codes Division to propose and implement corrective or mitigation actions. [Final Order IV.C.2.3] [Mandatory Condition OAR 345-025-0006(14)][AMD2]
- 6.12. During construction of the facility, the certificate holder shall ensure that contractors move equipment out of the construction area when it is no longer expected to be used. To the extent practical, contractors shall lower equipment with long arms, such as cranes, bucket trucks, and backhoes when not in use, in order to minimize visibility. [Final Order IV.J.2.1]

- 6.13. To reduce the visual impact of the facility, the certificate holder shall paint the buildings and structures in low-reflectivity neutral colors to blend with the surrounding landscape. [Final Order IV.J.2.2]
- 6.14. The certificate holder shall not use exterior nighttime lighting except:
 - a. The minimum exhaust stack lighting required or recommended by the Federal Aviation Administration.
 - b. Safety and security lighting at the Carty Generating Station, provided that such lighting is shielded or downward-directed to reduce offsite glare.
 - c. Minimum lighting necessary for repairs or emergencies.
 - d. As required during construction.
 - [Final Order IV.J.2.3] [AMD1]
- 6.17 During construction:
 - i. The certificate holder shall implement measures to reduce traffic impacts, as follows:
 - a. The certificate holder shall reduce peak hour volumes during construction by staggering shift start times or implementing other measures that would significantly reduce the total number of construction worker vehicle trips through the westbound I-84/Tower Road ramp terminal; or
 - b. The certificate holder shall install temporary traffic controls during peak construction to prioritize westbound left-turning vehicles at the westbound Tower Road ramp terminal during the weekday a.m. peak hour. [Final Order IV.M.2.9]
 - ii. For construction of the Carty Solar Farm, the certificate holder shall:
 - a. Implement a final Construction Traffic Management Plan, as approved by the Department per Condition 6.26.
 - b. Include the requirements of the Construction Traffic Management Plan in contract specifications for construction contractors, as applicable.
 - c. Maintain a monthly log, to be submitted monthly to the Department for review and confirmation of compliance with the components of the Construction Traffic Management Plan.
 - d. The Department, in consultation with the Morrow County Public Works Department, may require implementation of additional traffic management measures including a Traffic Impact Assessment per MCZO Section 3.010(N)(1) if any requirement of the Construction Traffic Management Plan is determined not adequately implemented, or if additional measures are deemed necessary based on actual passenger car equivalent trips per day during facility construction. Within 30-days of submittal of the monthly compliance report required under sub(c), the certificate holder shall obtain written confirmation from the Department on any additional construction traffic management measures required to be implemented. [AMD1] [AMD2]

6.18 Unless legally permissible, the certificate holder shall ensure that no equipment or machinery associated with the construction is parked or stored on any public road within Morrow or Gilliam Counties. The certificate holder may temporarily park equipment off the road but within County rights-of-way with the approval of the County Roadmaster.

[Final Order IV.M.2.10] [AMD1] [AMD2]

6.19 The certificate holder shall cooperate with the Morrow County Public Works Department and the Gilliam County Road Department to ensure that any unusual damage or wear to county roads that is caused by construction of the facility is repaired by the certificate holder. Upon completion of construction, the certificate holder shall restore public roads to pre-construction condition or better to the satisfaction of applicable county departments.

[Final Order IV.M.2.11] [AMD1] [AMD2]

- 6.20 [Deleted] [Final Order IV.M.2.12] [AMD1]
- 6.21 Oversize and overweight deliveries shall be made by rail and barge when feasible, to limit impacts to the I-84/Tower Road interchange. [Final Order IV.M.2.13]
- 6.22 The certificate holder shall construct all facility components in compliance with the following setback requirements. The transmission lines connecting the Carty Generating Station and the Grassland Switchyard are exempt from this condition.
 - a. For portions of the facility located in the Morrow County General Industrial Zoning District:
 - i. The minimum setback between a structure and the right-of-way of an arterial street shall be 50 feet. The minimum setback of a structure from the right-of-way of a collector shall be 30 feet, and from all lower class streets the minimum setback shall be 20 feet.
 - ii. Any sewage disposal installations such as outhouses, septic tank and drainfield systems shall be set back from the high-water line or mark along all streams and lakes a minimum of 100 feet, measured at right angles to the high-water line or mark. All structures, buildings, or similar permanent fixtures shall be set back from the high-water line or mark along all streams or lakes a minimum of 100 feet measured at right angles to the high-water line or mark.
 - b. For portions of the facility located in the Morrow County Exclusive Farm Use Zoning District:
 - a. The front yard setback from the property line shall be a minimum of 100 feet if the property line is adjacent to an intensive agricultural use; otherwise, front yards shall be 20 feet for property fronting on a local minor collector or marginal access street right-of-way, 30 feet from a property line fronting on a major collector right-of-way, and 80 feet from an arterial right-of-way.

- ii. Each side yard shall be a minimum of 20 feet except that for parcels or lots with side yards adjacent to an intensive agricultural use the adjacent side yard shall be a minimum of 100 feet.
- iii. Rear yards shall be a minimum of 25 feet, except for parcels or lots with rear yards adjacent to an intensive agricultural use, where rear yards shall be a minimum of 100 feet.
- iv. Any sewage disposal installations such as outhouses, septic tank and drainfield systems shall be set back from the high-water line or mark along all streams and lakes a minimum of 100 feet, measured at right angles to the high-water line or mark. All structures, buildings, or similar permanent fixtures shall be set back from the high-water line or mark along all streams or lakes a minimum of 100 feet measured at right angles to the high-water line or mark. [Final Order IV.E.4.3] [MCZO Section 3.010(H)] [AMD1]
- 6.23 The certificate holder must limit signage to directional signs necessary for deliveries and general site circulation. No sign may be placed so as to interfere with visibility or effectiveness of any permanent traffic control device. No sign may be placed so as to impede the sight distance triangle at any access point or intersection as specified in Section 4.020 of the Morrow County Zoning Code. No sign shall cause glare, distraction or other driving hazards within a street or road right-of-way. [Final Order IV.E.4.5] [MCZO Sections 4.020 and 4.070]
- 6.24 The certificate holder shall comply with Section 5, Public Responsibilities, of the Morrow County Solid Waste Management Ordinance. Any hauling of solid waste from the Carty Generating Station facility during construction, operation, or retirement shall be performed by a franchised solid waste hauler or otherwise comply with the Morrow County Solid Waste Management Ordinance.
 [Final Order IV.E.4.7] [Morrow County Waste Management Ordinance Section 5.000] [AMD2]
- 6.25 Recycling by the certificate holder and certificate holder's contractors during construction, operation, and retirement of the Carty Generating Station facility shall be done in accordance with Oregon Department of Environmental Quality regulations and shall be reported as part of the Morrow County wasteshed. [Final Order IV.E.4.7] [AMD2]
- 6.26. The certificate holder is authorized to construct approximately 3 miles of 34.5 kV transmission line anywhere within the approved corridors, subject to the conditions of the site certificate. The approved corridors are approximately 160-feet in width and extend between 2.25 and 3 miles of three routes as described in RFA1 Exhibit B and as presented on Figure 1 to the site certificate of the Second Amended Site Certificate for Carty Generating Station. [Site Specific Condition OAR 345-025-0010(5); AMD1] [AMD2]

6.27 Prior to beginning construction of the Carty Solar Farm, the certificate holder shall:

- a. Confirm whether, based on anticipated construction activities, peak construction traffic is anticipated to exceed 400 passenger car equivalent trips per day. If more than 400 passenger car equivalent trips per day is anticipated, the certificate holder shall prepare and submit to the Department and Morrow County Planning Department a Traffic Impact Assessment per MCZO Section 3.010(N) Transportation Impacts for review and approval. If a TIA is required, the certificate holder shall submit documentation to the Department in accordance with OAR 345-027-0057.
- b. Prepare and submit to the Department a Construction Traffic Management Plan for review and approval. The certificate holder shall demonstrate that the Construction Traffic Management Plan, at a minimum, includes:
 - 1. Traffic management measures or other recommendations to minimize traffic impacts on Tower Road, as applicable, based upon consultation with Morrow County Public Works Department and Morrow County Sherriff's Office.
 - Staggering shift start times or other measures that would significantly reduce the total number of construction worker vehicle trips through the westbound I-84/Tower Road ramp terminal; or
 - Installation of temporary traffic controls during peak construction to prioritize westbound left-turning vehicles at the westbound Tower Road ramp terminal during the weekday a.m. peak hour. [AMD1]
- 6.28 Prior to construction of the Carty Solar Farm, the certificate holder shall record in the real property records of Morrow County a Covenant Not to Sue with regard to generally accepted farming practices on adjacent farmland consistent with MCZO 3.010.K.3(i). [AMD1] [AMD2]

7.0 PUBLIC HEALTH AND SAFETY

- 7.1 The certificate holder shall take the following steps to reduce or manage human exposure to electromagnetic fields:
 - a. Constructing all aboveground transmission lines at least 200 feet from any residence or other occupied structure, measured from the centerline of the transmission line.
 - b. For any transmission lines constructed after June 29, 2012; providing to landowners a map of underground and overhead transmission lines on their property and advising landowners of possible health risks from electric and magnetic fields.
 - c. Designing and maintaining all transmission lines so that alternating current electric fields do not exceed 9 kV per meter at one meter above the ground surface in areas accessible to the public.
 - Designing and maintaining all transmission lines so that induced voltages during operation are as low as reasonably achievable
 [Final Order V.D.2.1] [AMD2]

- 7.2 To protect the public from electrical hazards, the certificate holder must enclose the facility switchyard or substations with appropriate fencing and locked gates. [Final Order V.D.2.2] [AMD2]
- 7.3 If the Council finds, at any time during facility operation, that cooling tower emissions are likely to contribute significantly to ground-level fogging or icing along public roads and to cause a significant threat to public safety, the certificate holder shall cooperate with appropriate local public safety authorities regarding implementation of reasonable safety measures, such as posting warning signs on affected roads. Cooperation may include, but is not necessarily limited to, the reimbursement of expenses for posting warning signs and implementing other safety measures. [Final Order V.D.2.4]
- 7.4 The certificate holder must comply with all emergency planning and notification requirements of Emergency Planning and Community Right-to-Know Act (EPCRA) Section 302.
 [Final Order V.D.2.6]
- 7.5 The certificate holder must comply with all reporting requirements of the Emergency Planning and Community Right-to-Know Act (EPCRA) Section 304, including reporting of any chemical release in an amount equal to or greater than the EPCRA reportable quantity for that chemical. [Final Order V.D.2.7]
- 7.6 [Deleted] [Final Order V.D.2.8][AMD1]
- 7.7 The certificate holder must comply with all reporting requirements of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), including reporting of any chemical release in an amount equal to or greater than the CERCLA reportable quantity for that chemical. [Final Order V.D.2.9]
- 7.8 The certificate holder shall notify the Department of Energy and Morrow County within 72 hours of any occurrence involving the facility if:
 - a. There is an attempt by anyone to interfere with its safe operation;
 - b. A natural event such as an earthquake, flood, tsunami or tornado, or a humancaused event such as a fire or explosion affects or threatens to affect the public health and safety or the environment; or
 - c. There is any fatal injury at the facility.

[Final Order V.D.2.10] [Mandatory Condition OAR 345-026-0170] [AMD1]

7.9 The certificate holder must develop and implement a program that provides reasonable assurance that all fences, gates, cattle guards, trailers, or other objects or structures of a permanent nature that could become inadvertently charged with electricity are

grounded or bonded throughout the life of the line. A current copy of the electrical protection plan must be available at the O&M building and provided upon request by ODOE staff.

[Final Order IV.O.2.2] [Mandatory Condition OAR 345-027-0023(4)]

8.0 ON-SITE SAFETY AND SECURITY

- 8.1 During construction and operation of the facility, the certificate holder shall provide for on-site security and shall establish good communications between on-site security personnel and the Morrow County Sheriff's Office. During operation, the certificate holder shall ensure that appropriate law enforcement agency personnel have an up-to-date list of the names and telephone numbers of facility personnel available to respond on a 24-hour basis in case of an emergency on the facility site. [Final Order IV.M.2.1]
- 8.2 During construction, the certificate holder shall require that all on-site construction contractors develop and implement a site health and safety plan that informs workers and others on-site about first aid techniques and what to do in case of an emergency. The plan shall also include important telephone numbers and the locations of on-site fire extinguishers and nearby hospitals. The certificate holder shall ensure that construction contractors have personnel on-site who are first aid and CPR certified. [Final Order IV.M.2.2]
- 8.3 During operation, the certificate holder shall develop and implement a site health and safety plan that informs employees and others on-site about first aid techniques and what to do in case of an emergency. The plan shall also include important telephone numbers and the locations of on-site fire extinguishers and nearby hospitals. [Final Order IV.M.2.3]
- 8.4 During construction, the certificate holder shall ensure that construction vehicles and equipment are operated on graveled areas to the extent possible and that open flames, such as cutting torches, are kept away from dry grass areas. [Final Order IV.M.2.4]
- 8.5 During operation, the certificate holder shall ensure that all on-site employees receive annual fire prevention and response training by qualified instructors or members of the local fire districts. The certificate holder shall ensure that all employees are instructed to keep vehicles on roads and off dry grassland, except when off-road operation is required for emergency purposes. [Final Order IV.M.2.5]
- 8.6 During construction and operation, the certificate holder shall ensure that all service vehicles are equipped with shovels and portable fire extinguishers of a 4500BC or equivalent rating. [Final Order IV.M.2.6]

- 8.7 During construction and operation, the certificate holder shall develop and implement fire safety plans in consultation with the Boardman Rural Fire Protection District to minimize the risk of fire and to respond appropriately to any fires that occur on the facility site. In developing the fire safety plans, the certificate holder shall take into account the dry nature of the region and shall address risks on a seasonal basis. The certificate holder shall meet annually with local fire protection agency personnel to discuss emergency planning and shall invite local fire protection agency personnel to observe any emergency drill conducted at the facility. [Final Order IV.M.2.7]
- 8.8 Upon the beginning of operation of Unit 1, facility components approved in Final Order on RFA1 or facility components approved in Final Order on RFA2, the certificate holder shall provide a site plan to the Boardman Rural Fire Protection District. The certificate holder shall indicate the actual location of all facility structures on the site plan. The certificate holder shall provide an updated site plan if additional structures are later added to the facility. During operation, the certificate holder shall ensure that appropriate fire protection agency personnel have an up-to-date list of the names and telephone numbers of facility personnel available to respond on a 24-hour basis in case of an emergency on the facility site. [Final Order IV.M.2.8]

9.0 PROTECTION OF SOIL

- 9.1 The certificate holder must conduct all construction work in compliance with an Erosion and Sediment Control Plan (ESCP) satisfactory to the Oregon Department of Environmental Quality and as required under the NPDES Storm Water Discharge General Permit #1200-C. The certificate holder must include in the ESCP any procedures necessary to meet local erosion and sediment control requirements or storm water management requirements. [Final Order IV.D.2.1] [AMD2]
- 9.2 During construction, the certificate holder, to the extent practicable, must limit truck traffic to improved road surfaces to avoid soil compaction. [Final Order IV.D.2.2]
- 9.3 During construction, the certificate holder must implement best management practices to control any dust generated by construction activities, such as applying water to roads and disturbed soil areas. [Final Order IV.D.2.3]
- 9.4 During construction, the certificate holder must complete monitoring according to the NPDES Storm Water Discharge General Permit #1200-C issued to the certificate holder

for construction of the unit to ensure that there are no significant potential adverse impacts to soils and: [AMD1] [AMD2]

- a. [Deleted] [AMD1]
- b. Deleted] [AMD1]
- c. [Deleted] [AMD1]
- d. [Deleted] [AMD1]
- e. After completing construction in an area, the certificate holder must monitor the area until soils are stabilized and evaluate whether construction-related impacts to soils are being adequately addressed by the mitigation procedures described in the Erosion and Sediment Control Plan and the approved Revegetation and Noxious Weed Control Plan. As necessary, the certificate holder must implement follow-up restoration measures such as scarification and reseeding to address those remaining impacts.

[Final Order IV.D.2.4] [AMD1]

- 9.5 During operation, the certificate holder shall routinely inspect and maintain all transmission line corridors, roads, pads and trenched areas and, as necessary, maintain or repair erosion and sediment control measures and control the introduction and spread of noxious weeds. [Final Order IV.D.2.5]
- 9.6 Upon completion of construction, the certificate holder must restore vegetation to the extent practicable and shall landscape all areas disturbed by construction in a manner compatible with the surroundings and proposed use and in compliance with the Revegetation and Noxious Weed Control Plan. Upon completion of construction, the certificate holder must remove all temporary structures not required for facility operation and dispose of all timber, brush, refuse and flammable or combustible material resulting from clearing of land and construction of the facility. [Final Order IV.D.2.7] [Mandatory Condition OAR 345-027-0020(11)]
- 9.7 During operation, the certificate holder shall restore areas that are temporarily disturbed during facility maintenance or repair activities using the same methods and monitoring procedures described in the Revegetation and Noxious Weed Control Plan. [Final Order IV.D.2.8]
- 9.8 The certificate holder must dispose of all accumulated evaporation pond solids, when removed, in a landfill approved for such waste material. All residual solids deposited in evaporation ponds must be removed to an appropriate disposal facility upon closure of the facility. The certificate holder shall include protocols for solids removal and soil restoration at the location of the evaporation ponds in the retirement plan. [Final Order IV.D.2.9] [AMD1] [AMD2]
- 9.9 During operation, the certificate holder must minimize drift from the cooling towers through the use of high efficiency drift eliminators that allow no more than a 0.001% drift rate.

[Final Order IV.D.2.10]

- 9.10 The certificate holder must handle hazardous materials used on the site in a manner that protects public health, safety and the environment and shall comply with all applicable local, state and federal environmental laws and regulations. During operation, the certificate holder may not store gasoline that is intended for fueling vehicles on the facility site. [Final Order IV.D.2.11]
- 9.11 If a reportable release of hazardous substance occurs during construction or operation of the facility, the certificate holder must notify the Department within 72 hours and must clean up the spill or release and dispose of any contaminated soil or other materials according to applicable regulations. The certificate holder must make sure that spill kits containing items such as absorbent pads are located on equipment, near storage areas, and in the administrative or maintenance areas of the facility. The certificate holder must instruct employees about proper handling, storage and cleanup of hazardous materials. [Final Order IV.D.2.12]

10.0 PROTECTION OF NATURAL RESOURCES

[AMD1] [OAR 345-025-0016] [AMD1] [AMD2]

- 10.1 Prior to construction, the certificate holder shall:
 - i. Consult with the Oregon Department of Fish and Wildlife and prepare a final Wildlife and Habitat Monitoring Mitigation Plan and submit the plan to the Department for review and approval. The certificate holder must conduct all wildlife and habitat monitoring as described in the approved Wildlife and Habitat Monitoring and Mitigation Plan, as amended from time to time.
 - [Final Order IV.H.2.1] [Mandatory Condition OAR 345-027-0020(6)]
 ii. Submit for review and approval by the Department, in consultation with the Oregon Department of Fish and Wildlife, a final Wildlife and Habitat Monitoring Mitigation Plan based upon the mitigation methodology and enhancement actions in the draft amended plan provided in the Final Order on Amendment 2. The certificate holder must conduct all wildlife and habitat monitoring as described in the approved Wildlife and Habitat Monitoring and Mitigation Plan, as amended from time to time.
- 10.2 The certificate holder shall:
 - a. Prior to construction, acquire the legal right to create, enhance, maintain and protect a habitat mitigation area as long as the facility is in operation and the site certificate is in effect by means of an outright purchase, conservation easement or similar conveyance and shall provide a copy of the documentation to the Department.
 - b. Prior to construction of the Carty Solar Farm and its supporting facilities, and facility components approved in the Final Order on RFA2, the certificate holder shall provide a habitat assessment of the habitat mitigation area, based on a protocol approved by the Department in consultation with ODFW, which includes

methodology, habitat map, and available acres by habitat category and subtype in tabular format.

c. During operations, the certificate holder shall improve and monitor the habitat quality within the habitat mitigation area, in accordance with the Wildlife and Habitat Monitoring and Mitigation Plan approved by the Department per Condition 10.1.

[Final Order IV.H.2.2] [AMD1] [AMD2]

10.3. The certificate holder shall consult with the Oregon Department of Fish and Wildlife prior to commencement of construction to determine the final acreage of habitat mitigation required. Mitigation shall be provided in accordance with this final acreage determination.

[Final Order IV.H.2.3] [AMD1]

- 10.4. The certificate holder shall conduct noxious weed inventories within the Habitat Mitigation Area (HMA) to identify patches of weed infestation during year one, year three and year five after construction of Unit 1, and then continue once every 5 years for the life of the project, in years divisible by five. Weeds shall be controlled as needed to maintain and enhance habitat quality within the mitigation area, with the goal of working toward eradication of targeted noxious weeds or, if eradication is not practical, decreasing their abundance to minimize impacts to native plant communities. Weed management practices shall be consistent with the Revegetation and Noxious Weed Control Plan and shall include an integrated weed management approach, using an appropriate combination of prevention and control methods. The certificate holder shall obtain ODFW approval prior to the use of pesticides. If a substantial area of soil is left bare from weed control activities, the area shall be seeded using the appropriate methods as described in the Revegetation and Noxious Weed Control Plan. [Final Order IV.H.2.5] [AMD1] [AMD2]
- 10.5. If vegetation in the HMA is damaged from fire or from fire suppression efforts (e.g., vehicular disturbance), the area shall be seeded as necessary with the appropriate seed mix using the appropriate methods for the site, as described in the Revegetation and Noxious Weed Control Plan. [Final Order IV.H.2.6] [AMD2]
- 10.6. The certificate holder shall monitor and control access to the HMA and shall post signs for the life of the facility designating the area as "protected" and including natural resources information. Access to the proposed area shall be limited to operational needs, conservation area monitoring, and noxious weed control efforts. Any fences within or bordering the HMA shall be modified to wildlife-friendly specifications. Livestock grazing shall not be permitted within the HMA. Periodic monitoring (at least annually) shall be conducted to evaluate effectiveness of access control measures and signage maintenance needs. [Final Order IV.H.2.7] [AMD2]

10.7. The certificate holder must:

- i. Implement measures to avoid or minimize temporary and permanent impacts to high quality native habitat and to retain habitat cover in the general landscape, where practicable.
 - a. The certificate holder shall not construct any facility components within areas of Category 1 habitat and shall avoid temporary disturbance of Category 1 habitat.
 - b. Before beginning construction, the certificate holder shall provide to the Department a map showing the final design locations of all components of the facility and the areas that would be disturbed during construction and identifying the survey areas for all plant and wildlife surveys conducted in 2010 or earlier as described in the Final Order on the Application. The certificate holder shall use a qualified professional biologist to conduct a pre-construction plant and wildlife investigation of all areas that would be disturbed during construction that lie outside of the previously surveyed areas. The certificate holder shall provide a written report of the investigation to the Department and to the Oregon Department of Fish and Wildlife. Based on consultation with the Department and ODFW, the certificate holder shall implement appropriate measures to avoid impacts to any Category 1, 2, or 3 habitat, to any State-listed threatened or endangered plant or wildlife species, and to any State Candidate plant species. If any Category 2 or 3 habitat is identified and will be impacted, the certificate holder shall work with the Department and ODFW to identify appropriate mitigation measures for such impacts.
 - c. Before beginning construction, the certificate holder's qualified professional biologist shall survey the previously-identified Category 1 Washington ground squirrel habitat to ensure that the sensitive use area is correctly marked with exclusion flagging and avoided during construction. The certificate holder shall maintain the exclusion markings until construction has been completed.
 - d. Before beginning construction, certificate holder's qualified professional biologist shall complete aerial raptor nest surveys within the raptor nest survey area as described in the Final Order on the Application. The purposes of the survey are to identify any sensitive raptor nests near construction areas and to provide baseline information on raptor nest use for analysis as described in the Wildlife and Habitat Monitoring and Mitigation Plan referenced in Condition 10.1. The certificate holder shall provide a written report on the raptor nest surveys to the Department and to ODFW.
 - [Final Order IV.H.2.9]
- ii. Implement measures to avoid or minimize temporary and permanent impacts to high quality native habitat and to retain habitat cover in the general landscape, where practicable.
 - a. The certificate holder shall not construct any facility components within areas of Category 1 habitat and shall avoid temporary disturbance of Category 1 habitat.
 - b. Before beginning construction, the certificate holder shall provide to the Department a map showing the final design locations of all components of the facility and the areas that would be disturbed during construction and identifying the survey areas for all plant and wildlife surveys conducted prior to

construction. The certificate holder shall use a qualified professional biologist to conduct a pre-construction habitat assessment of all areas that would be disturbed during construction. The certificate holder shall provide a written report of the habitat assessment to the Department and to the Oregon Department of Fish and Wildlife. Based on consultation with the Department and ODFW, the certificate holder shall implement appropriate measures to avoid impacts to any Category 1 habitat, to any State-listed threatened or endangered plant or wildlife species, and to any State Candidate plant species. [AMD1]

10.8. During construction, the certificate holder shall avoid all construction activities within one mile of golden eagle nests, and 0.6 miles of ferruginous hawk nests, and 1,300 feet of other potentially active sensitive raptor species nest sites for the following species during the sensitive period, as provided in this condition:

Sensitive Period	Early Release Date
April 1 to August 15	May 31
March 15 to August 15	May 31
January 1 to August 15	May 31
January 1 to July 15	May 31
April 1 to August 15	July 15
March 8 to June 15	May 31
	April 1 to August 15 March 15 to August 15 January 1 to August 15 January 1 to July 15 April 1 to August 15

During all years in which construction occurs, the certificate holder shall use a protocol approved by the Oregon Department of Fish and Wildlife (ODFW) to determine whether there are any active nests of these species within 1,300 feet of any areas that would be disturbed during construction. Surveys shall be extended to one mile for golden eagle nests and 0.6 miles for ferruginous hawk nests. This construction buffer distance may be decreased with approval by ODFW and USFWS depending on the intensity of construction activity and whether there is an adequate physical barrier (i.e., vegetation, topography, etc.) between the nest site and the construction impacts or if consultation determines a lesser distance is feasible and appropriate. The certificate holder shall begin monitoring potential nest sites by the beginning of the sensitive period, as listed above, and shall continue monitoring until at least May 31 (July 15 for golden eagle nests) to determine whether any potentially-active nest sites become active during the sensitive period.

If any nest site is determined to be unoccupied by the early release date, then unrestricted construction activities may occur within 0.6 miles (one mile for golden eagle nests) of the nest site after that date. If a nest is occupied by any of these species after the beginning of the sensitive period, the certificate holder will flag the boundaries of a 1,300 foot (or 0.6 miles for ferruginous hawk nests, or one mile for golden eagle nests) buffer area around the nest site and shall instruct construction personnel to avoid disturbance of the buffer area. During the sensitive period, the certificate holder shall not engage in high-impact construction activities (activities that involve blasting, grading or other major ground disturbance) within the buffer area. The certificate holder shall restrict construction traffic within the buffer, except on public roads, to vehicles essential to the limited construction activities allowed within the buffer. If a golden eagle nest is identified, construction and maintenance activities between February 1 and July 15 (courtship and nesting period) will be avoided within one mile of the active nest (or 0.5 miles if the active nest is not in line-of-sight of activities).

The certificate holder must use a qualified independent professional biologist to observe the active nest sites during the sensitive period for signs of disturbance and to notify the Department of any non-compliance with this condition. If the biologist observes nest site abandonment or other adverse impact to nesting activity, the certificate holder shall implement appropriate mitigation, in consultation with ODFW and subject to the approval of the Department, unless the adverse impact is clearly shown to have a cause other than construction activity.

The certificate holder may begin or resume construction activities within the buffer area before the ending day of the sensitive period with the approval of ODFW, after the young are fledged. The certificate holder shall use a protocol approved by ODFW to determine when the young are fledged (the young are independent of the core nest site).

[Final Order IV.H.2.10] [AMD1]

- 10.9 The certificate holder shall implement the following measures to avoid or mitigate impacts to sensitive wildlife habitat during construction:
 - a. Preparing maps to show exclusion areas that are off-limits to construction personnel, such as nesting or denning areas for sensitive wildlife species.
 - b. Avoiding unnecessary road construction, temporary disturbance, and vehicle use.
 - c. Limiting construction work to approved and surveyed areas shown on facility constraints maps.
 - d. Ensuring that all construction personnel are instructed to avoid driving crosscountry or taking short-cuts within the site boundary or otherwise disturbing areas outside of the approved and surveyed construction areas.
 [Final Order IV.H.2.11]

10.10 The certificate holder shall reduce the risk of injuries to avian species by designing and installing all aboveground transmission line support structures following the most current suggested practices for avian protection on power lines published by the Avian Power Line Interaction Committee. [Final Order IV.H.2.12]

10.11 Sensitive raptor nest monitoring shall be conducted by qualified biologists in year one, year three, and year five after operations of Unit 1 have begun and then at least every five years after that for the life of the project in years divisible by five. Results of the

monitoring shall be included in an annual sensitive raptor nest monitoring report provided to the Oregon Department of Fish and Wildlife, the U.S. Fish and Wildlife Service, and the Department. This report shall document the nest productivity of sensitive raptor species, including golden eagle (Aquila chrysaetos), occurring within one mile of the Carty Generating Station facility, the Ferruginous Hawk occurring within 0.6 miles, and other sensitive raptor species nests occurring within 1,300 feet of the facility site.

[Final Order IV.H.2.13] [AMD1] [AMD2]

- 10.12. The certificate holder shall use a qualified environmental professional to provide environmental training during construction and operation. Environmental training includes information on the sensitive species present onsite, precautions to avoid injuring or destroying wildlife or sensitive wildlife habitat, exclusion areas, permit requirements, and other environmental issues. The certificate holder shall instruct construction and operations personnel to report any injured or dead wildlife detected while on the site to the appropriate onsite environmental manager. [Final Order IV.H.2.14]
- 10.13. The certificate holder shall not place any structures in jurisdictional waters of Sixmile Canyon and shall avoid new impacts to Sixmile Canyon during construction by using the existing access road for vehicle crossing only during the dry season. Impacts to jurisdictional waters in Sixmile Canyon drainages shall be avoided. [Final Order IV.H.2.15] [AMD1]
- 10.14. Prior to construction, the certificate holder shall conduct surveys for Washington ground squirrel (WGS) and Lawrence's milkvetch.
 - The certificate holder shall determine the boundaries of Category 1 Washington i. ground squirrel (WGS) habitat based on the locations where the squirrels were found to be active in the most recent WGS surveys prior to the beginning of construction in habitat suitable for WGS foraging or burrow establishment ("suitable habitat"). The certificate holder shall use a qualified professional biologist who has experience in detection of WGS to conduct surveys within the site boundary using appropriate search protocols. Except as provided in (a), the biologist shall conduct surveys in the active squirrel season (February 1 to June 30) at least once every three years until the beginning of construction in suitable habitat. The biologist shall survey all areas of suitable habitat where permanent facility components would be located or where construction disturbance could occur. The certificate holder shall provide written reports of the surveys to the Department and to the Oregon Department of Fish and Wildlife (ODFW) and shall identify the boundaries of Category 1 WGS habitat. During each year in which construction will occur, the boundaries of Category 1 WGS habitat shall be marked by the biologist with highvisibility flagging or markers. The certificate holder shall not begin construction until the identified boundaries of Category 1 WGS habitat have been approved by the Department. Category 1 WGS habitat includes the areas described in (b) and (c) below.

- a. The certificate holder may omit the WGS survey in any year if the certificate holder avoids all permanent and temporary disturbance within suitable habitat until a WGS survey has been completed in the following year and the boundaries of Category 1 habitat have been determined and approved based on that survey.
- b. Category 1 WGS habitat includes the area within the perimeter of multiple active WGS burrows plus a 785-foot buffer, excluding areas of habitat types not suitable for WGS foraging or burrow establishment. If the multiple-burrow area was active in a prior survey year, and active burrows are still present, then Category 1 habitat includes the largest extent of the active burrow area ever recorded (in the current or any prior-year survey), plus a 785-foot buffer. If no active burrows are still present, then it is no longer Category 1 habitat for WGS.
- c. Category 1 WGS habitat includes the area containing single active burrow detections plus a 785-foot buffer, excluding areas of habitat types not suitable for WGS foraging or burrow establishment. Category 1 habitat does not include single-burrow areas that were found active in a prior survey year but that are not active in the current survey year.
- ii. The certificate holder shall use a qualified professional biologist who has experience in detection of Lawrence's milkvetch to conduct plant surveys within the site boundary, using appropriate survey protocols, during the blooming season (May through August).
 - a. If the species is found to occur, the certificate holder must install protection flagging around the plant population and avoid any ground disturbance within this zone; and its location shall be presented on construction constraint maps showing restricted work areas.

[Final Order IV.I.2.1] [AMD1]

- 10.15 The certificate holder shall impose and enforce a construction and operation speed limit of 20 miles per hour throughout the facility site and, during the active squirrel season (February 1 to June 30), a speed limit of 10 miles per hour from one hour before sunset to one hour after sunrise on private roads near known Washington ground squirrel (WGS) colonies. The certificate holder shall ensure that all construction and operations personnel are instructed to watch out for and avoid WGS and other wildlife while driving through the facility site. [Final Order IV.I.2.2]
- 10.16 The certificate holder shall use perch-preventing structures on Carty Generating Station components in areas identified as Category 1 habitat for Washington ground squirrels. [Final Order IV.I.2.3]
- 10.17 The certificate holder shall provide environmental awareness training for all project personnel and construction contractors before such contractors or personnel enter the site to perform construction-related activities. The training program shall discuss Washington ground squirrel issues as well as other environmental issues related to the project, and include handouts with identification information and reporting procedures.

Additional training sessions shall be conducted as needed for personnel that start after the beginning of construction. [Final Order IV.I.2.4]

- 10.18 In order to discourage Washington ground squirrels from moving into planned construction areas the certificate holder may disc or till a minimum of an 800-ft. buffer within the perimeter of the site boundary, or implement other approved measures, in closest proximity to squirrel activity areas. Proposed measures and areas where measures will be implemented shall be reviewed by ODFW and shall be informed by the most recent Washington ground squirrel survey data. [Final Order IV.I.2.5] [AMD1]
- 10.19 If the certificate holder discs or tills areas, the certificate holder shall plant dryland wheat or another cover crop in tilled areas within the site boundary. Crops to be planted shall be selected by the certificate holder in coordination with ODFW. [Final Order IV.I.2.6] [AMD1]
- 10.20 Should new Washington ground squirrel burrows become established within 785 feet of the site boundary, the certificate holder shall immediately report to ODFW. The certificate holder shall coordinate with ODFW to establish additional mitigation measures or to obtain an Incidental Take Permit, as appropriate. [Final Order IV.I.2.8] [AMD1]
- 10.21 The certificate holder shall conduct post-construction surveys on known Washington ground squirrel colonies in the Carty Generating Station facility area, on land owned by the certificate holder, both within the HMA and in areas where known active burrows were recorded during preconstruction field surveys. The Washington ground squirrel surveys shall be conducted by qualified biologists in year one, year three, and year five after operations of Unit 1 have begun, and then at least every five years after that for the life of the project in years divisible by five. Surveyors shall record evidence of Washington ground squirrel activity, current land use, and evidence of conditions caused by the project that might increase erosion or result in a decline in vegetation quality and adversely affect a Washington ground squirrel colony. [Final Order IV.I.2.9] [AMD1] [AMD2]
- 10.22 The certificate holder shall implement a waste management plan during operation that includes but is not limited to the following measures:
 - a. Training employees to minimize and recycle solid waste.
 - b. Recycling paper products, metals, glass and plastics.
 - c. Recycling used oil and hydraulic fluid.
 - d. Collecting non-recyclable waste for transport to a local landfill by a licensed waste hauler.
 - e. Segregating all hazardous wastes such as used oil, oily rags and oil-absorbent materials, mercury-containing lights and lead-acid and nickel-cadmium batteries

for disposal by a licensed firm specializing in the proper recycling or disposal of hazardous wastes.

[Final Order IV.N.2.2]

- 10.23 During construction and operation of the Carty Generating Station, the certificate holder shall obtain potable water from the existing Boeing well or from a bottled water vendor. Water for construction and process water shall be obtained from Carty Reservoir. The certificate holder may use other sources of water for on-site uses subject to prior approval by the Department. [Final Order V.C.2.1] [AMD1] [AMD2]
- 10.24 During operation, the certificate holder shall discharge sanitary wastewater generated at the facility to the Boardman Coal Plant and Carty Generating Station sanitary waste facility (sewage lagoons) or the Carty septic system in compliance with DEQ or county permit requirements. [Final Order IV.N.2.4] [AMD2]
- 10.25 Before beginning construction of Unit 1, the certificate holder shall receive approval of the wetlands delineation report by the Department of State Lands and provide an approval letter to the Department. [Final Order V.B.2.1] [AMD2]
- 10.26 The certificate holder shall avoid impacts to waters of the state in the following manner:
 - a. The certificate holder shall avoid any disturbance to delineated wetlands.
 - b. The certificate holder shall construct stream crossings for transmission lines substantially as described in the Final Order on the Application. In particular, the certificate holder shall not remove material from waters of the State or add new fill material to waters of the State such that the total volume of removal and fill exceeds 50 cubic yards for the project as a whole.
 - c. The certificate holder shall construct support structures for aboveground lines outside of delineated stream channels and shall avoid in-channel impacts.
 [Final Order V.B.2.2]
- 10.27 Before beginning construction, the certificate holder shall provide to the Department a map showing the final design locations of all components of the facility and the areas that would be disturbed during construction and showing the wetlands and stream channels delineated through field surveys conducted prior to construction. For areas to be disturbed during construction that lie outside of the previously-surveyed areas, the certificate holder shall hire qualified personnel to conduct a pre-construction investigation to determine whether any jurisdictional waters of the State exist in those locations. The certificate holder shall provide a written report on the pre-construction investigation to the Department and the Department of State Lands for approval before beginning construction. The certificate holder shall ensure that construction and operation of the facility will not impact any jurisdictional water identified in the pre-construction investigation in a manner that would require a Removal-Fill Permit.

[Final Order V.B.2.3] [AMD1]

- 10.28 The certificate holder shall demonstrate that the Oregon Department of Environmental Quality has issued to the certificate holder:
 - i. Prior to operation of Unit 1, a Water Pollution Control Facilities Permit substantially in the form of Exhibit 4 of the Final Order on the Application, allowing for wastewater discharge from the Carty Generating Station.

[Final Order V.E.2.1]

- ii. Prior to operation of the Carty Solar Farm, Addendum 1 of the modified Water Pollution Control Facilities Permit 100189 with the following additional condition, allowing discharge of solar panel washwater:
 - a. Solar panel wash water is permitted to be discharged through evaporation or infiltration into the ground at the point of application. The use of chemicals, soaps, detergents and heated water is prohibited. Pressure washing is allowed, so long as it does not remove paint or other finishes. Soil erosion and runoff from the Carty Solar Farm is prohibited. Soil erosion must be repaired within 30 days of occurrence. [AMD1]
- Prior to operation of facility components authorized by the Final Order on Request for Amendment 2, Addendum 2 of the modified Water Pollution Control Facilities Permit 100189, substantially in the form of Attachment E of the Final Order on Request for Amendment 2. [AMD2]

10.29

- a. The certificate holder shall comply with state laws and rules applicable to Water Pollution Control Facilities Permits that are adopted in the future to the extent that such compliance is required under the respective statutes and rules.
- b. The certificate holder shall obtain and comply with a Umatilla County Public Health construction permit for the (unlined) septic system.
 [Final Order V.E.2.2] [AMD2]
- 10.30 The certificate holder may not dispose of wastewater into the Boardman settling ponds, vehicle wash water pond or coal yard ponds unless the site certificate and the WPCF are amended to permit such use. [Final Order V.E.2.3]
- 10.31 The site certificate holder must meet the compliance dates set out in the WPCF unless alternative compliance dates have been approved in advance in writing by DEQ. Either prior to or not later than 14 calendar days following any lapsed compliance date, the site certificate holder must submit a notice of noncompliance with the established schedule to the Department of Energy and DEQ. Any report of noncompliance must include the cause of noncompliance. [Final Order V.E.2.4]

- 10.32 Prior to constructing or modifying wastewater management treatment and disposal facilities, detailed plans must be submitted to and approved by the Department of Environmental Quality. [Final Order V.E.2.5]
- 10.34. [Deleted] [Final Order V.E.2. [AMD1]
- 10.35. [Deleted] [Final Order V.E.2.7] [AMD1]
- 10.36. Prior to discharge of Carty Generating Station sewage to the lagoons, the certificate holder must:
 - a. Submit a work plan to remove vegetation from the Clay-lined cells and either leak test the cells or recondition them; and
 - b. Submit a long-term plan to ensure the integrity of the clay lined cells. The plan may include evaluating system capacity requirements and modifying system capacity accordingly prior to discharge of Carty Generating Station sewage to lagoons.

[Final Order V.E.2.8]

10.37 The certificate holder must prepare and implement a Hazardous Materials Management and Monitoring plan approved by the Department. The plan(s) must address the handling of potentially hazardous substances (as defined by ORS 465.200) during construction and operation of the facility, measures to prevent on- and off-site contamination and documentation of plan implementation. Separate plans for the construction and operation phases are acceptable. The certificate holder must use hazardous materials in a manner that protects public health, safety and the environment and must comply with all applicable local, state and federal environmental laws and regulations.

The Hazardous Materials Management and Monitoring Plan shall contain the same information required for a Spill Prevention, Control and Countermeasure Plan (40 CFR 112). Whereas the SPCC Plan addresses spill prevention for oil products, the materials management and monitoring plan shall address hazardous substances. The Plan shall include operating procedures to prevent hazardous substances releases, control measures to contain hazardous substance releases, countermeasures to contain, cleanup, and mitigate hazardous substance releases, and procedures for required inspections and testing. This Plan must be submitted to the Department for review and approval prior to respective construction or operation phase of the Carty Generating Station Facility.

[Final Order IV.G.2.2] [AMD1] [AMD2]

10.38. If any inspection performed in accordance with the Hazardous Materials Management and Monitoring Plan identifies improper handling or storage of hazardous substances (as defined by ORS 465.200) or improper record keeping procedures, the certificate holder must correct such deficiencies promptly and must report the corrective actions to the Department. If the certificate holder has not corrected such deficiencies within six months after the date of the inspection report, the certificate holder shall submit to the Council an independently prepared estimate of cost of correction. Upon approval of the estimate by the Council, the certificate holder shall increase the amount of the bond or letter of credit required under Condition IV.G.2.9 by the approved amount of the estimate. In no event, however, shall the certificate holder be relieved of its obligation to exercise all due diligence in correcting deficiencies identified in the course of a site inspection.

[Final Order IV.G.2.3]

- 10.39. The certificate holder shall report any release (as defined by ORS 465.200) of hazardous substances to the Department within 72 hours after the discovery of such release, in addition to any other reporting requirements under applicable law. If the certificate holder has not remedied a release consistent with applicable Oregon Department of Environmental Quality standards within six months after the date of the release, the certificate holder shall submit to the Council an independently prepared estimate of the cost to complete necessary remediation. Upon approval of the estimate by the Council, the certificate holder shall increase the amount of its bond or letter of credit by the approved amount of the estimate. In no event, however, shall the certificate holder be relieved of its obligation to exercise all due diligence in remedying a release of hazardous substances. [Final Order IV.G.2.4] [AMD1]
- 10.40. The certificate holder shall maintain the reservoir at an elevation no lower than an annual average of 665 feet mean sea level (MSL). The certificate holder may operate the reservoir at a lower elevation without a site certificate amendment if the certificate holder consults with the Department and ODFW to determine that the lower elevation would not result in a net loss of habitat and, therefore, does not warrant further analysis and potential mitigation through a site certificate amendment process. The certificate holder shall submit an Amendment Determination Request supporting a conclusion that a site certificate amendment is not required and receive concurrence with the conclusions of the ADR prior to operating the reservoir at a lower elevation. [AMD2]

11.0 PROTECTION OF HISTORIC, CULTURAL AND ARCHAEOLOGICAL RESOURCES

- 11.1 [Deleted] [Final Order IV.K.2.1] [AMD1]
- 11.2 Before beginning construction, the certificate holder shall provide to the Department a map showing the final design locations of all components of the facility, the areas that would be temporarily disturbed during construction, the areas that were surveyed in

2009 as described in the Final Order on the ASC or that have been subsequently surveyed.

[Final Order IV.K.2.2] [AMD1]

- 11.3 The certificate holder shall:
 - a. Use qualified personnel to conduct field investigation of all areas to be disturbed during construction that lie outside the previously-surveyed areas. The certificate holder shall provide a written report of the field investigation to the Department and to the Oregon State Historic Preservation Office (SHPO). If any potentially significant historic, cultural, or archaeological resource sites are found during the field investigation, the certificate holder shall instruct all construction personnel to avoid the identified sites and shall implement appropriate measures to protect the sites, including the measures described in Condition 11.5.
 - b. Prior to construction of facility components approved in the Final Order on RFA2, use qualified personnel to conduct field investigation of all areas to not previously disturbed or minimally disturbed. The certificate holder shall provide a written report of the field investigation to the Department and to the Oregon State Historic Preservation Office (SHPO), and shall consult with the CTUIR on whether any areas would require a cultural monitor during construction. If any potentially significant historic, cultural, or archaeological resource sites are found during the field investigation, the certificate holder shall instruct all construction personnel to avoid the identified sites and shall implement appropriate measures to protect the sites, including the measures described in Condition 11.5.

[Final Order IV.K.2.3; AMD2]

- 11.4. The certificate holder shall ensure that a qualified archaeologist, as defined in OAR 736-051-0070, develops a training program for cultural resources. The program will instruct construction personnel in the identification of cultural materials and avoidance of accidental damage to identified resource sites. Records of such training shall be maintained at the administration/control building and made available to authorized representatives of the Department upon request. [Final Order IV.K.2.4] [AMD1]
- 11.5. The certificate holder shall ensure that construction personnel cease all grounddisturbing activities in the immediate area if any archaeological or cultural resources are found during construction of the facility until a qualified archeologist can evaluate the significance of the find. The certificate holder shall notify the Department and the SHPO of the find. If the SHPO determines that the resource is significant, the certificate holder shall make recommendations to the Council for mitigation, including avoidance, field documentation and data recovery, in consultation with the Department, SHPO, interested tribes and other appropriate parties. The certificate holder shall not restart work in the affected area until the certificate holder has demonstrated to the Department and the SHPO that it has complied with archaeological resource protection regulations.

[Final Order IV.K.2.5]

- 11.6. The certificate holder shall:
 - i. Prepare and implement an Archaeological Monitoring Plan for construction activities to address and mitigate impacts from exposure of unanticipated or previously unidentified cultural resources that may be exposed during construction of the facility. A current copy of the plan must be maintained at the administration/control building and made available to authorized representatives of the Department upon request. The Archaeological Monitoring Plan, as proposed by the certificate holder, shall include the following requirements:
 - a. [Deleted]

[AMD1].

- b. A qualified archaeological monitor is a person who meets the "qualified archaeologist" standards defined by ORS 390.235(6)(b) or who is supervised by a "qualified archaeologist." If the latter applies, the supervising qualified archaeologist must vouch for the work of the archaeological monitor and author or co-author the archaeological monitoring report provided at the end of construction monitoring.
- c. The archaeological monitor will keep a daily log of construction and monitoring activities. If intact archaeological materials are encountered during the monitoring, the archaeological monitor will initiate procedures for inadvertent discovery of archaeological resources, as specified in ORS 358.920.
- d. Artifacts will be examined and documented in the field and will not be collected unless authorized under the provisions of a SHPO permit, if one is obtained in the inadvertent discovery of archaeological resources process.
- e. If human remains are identified during the course of construction monitoring, the monitor will initiate the procedures for Inadvertent Discovery of Human Remains, as specified in ORS 97.740-97.760.
- f. The certificate holder is responsible for providing an archaeological monitoring report to the Department and SHPO after construction work is completed. The report must detail the activities of the archaeological monitor and any inadvertent discoveries encountered, along with actions taken to address them. [Final Order IV.K.2.6]
- ii. At least 45-days prior to construction of the Carty Solar Farm, provide to the Department for review and approval, in consultation with SHPO and the Confederated Tribes of the Umatilla Indian Reservation (CTUIR), an amended Archaeological Monitoring Plan for construction activities to address and mitigate impacts from exposure of unanticipated or previously unidentified cultural resources that may be exposed during construction of the Carty Solar Farm. The amended Archaeological Monitoring Plan shall include the following requirements:
 - a. The certificate holder shall coordinate with CTUIR prior to and during ground disturbing activities to determine if a tribal monitor should be onsite.
 - A qualified archeologist, as defined in 11.6(i)(b) of this condition, shall be mobilized to the site if unanticipated resources are discovered; in this event, Condition 11.6.ii(c) through (f) would then be applicable.

- c. The archeological monitor will keep a daily log of construction and monitoring activities. If intact archaeological materials are encountered during the monitoring, the monitor will initiate procedures for inadvertent discovery of archaeological resources, as specified in ORS 358.920.
- d. Artifacts will be examined and documented in the field and will not be collected unless authorized under the provisions of a SHPO permit, if one is obtained in the inadvertent discovery of archaeological resources process.
- e. If human remains are identified during the course of construction monitoring, the monitor will initiate the procedures for Inadvertent Discovery of Human Remains, as specified in ORS 97.740-97.760.
- f. The certificate holder is responsible for providing an archaeological monitoring report to the Department and SHPO after construction work is completed. The report must detail the activities of the monitor and any inadvertent discoveries encountered, along with actions taken to address them. [AMD1]

12.0 CARBON DIOXIDE EMISSIONS

- 12.1 The net carbon dioxide emissions rate for the base load gas plant must not exceed 0.675 pounds of carbon dioxide per kilowatt-hour of net electric power output, with carbon dioxide emissions and net electric power output measured on a new and clean basis, as defined in OAR 345-001-0010. [Final Order IV.P.2.1]
- 12.2 The net carbon dioxide emissions rate for incremental emissions for the facility operating with power augmentation must not exceed 0.675 pounds of carbon dioxide per kilowatt-hour of net electric power output, with carbon dioxide emissions and net electric power output measured on a new and clean basis at the site during the times of year when the facility is intended to operate with power augmentation, subject to modification under Condition 12.12. [Final Order IV.P.2.2]
- 12.3 For the purposes of the site certificate, "monetary path payment requirement" means the amount of offset funds determined pursuant to OAR 345-024-0550, -0560, -0590 and -0600 and the amount of the selection and contracting funds that the certificate holder must disperse to The Climate Trust, as the qualified organization, pursuant to OAR 345-024-0710 and the site certificate. The certificate holder shall calculate the monetary path payment requirement using an offset fund rate of \$1.27 per ton of carbon dioxide in 2011 dollars.
 - a. The certificate holder shall calculate 2011 dollars using the Index described in Condition 15.1.b.
 - b. The certificate holder shall increase the amount of the letter of credit described in Condition 12.9 by the percentage increase in the Index. The certificate holder

shall index the funds from the date of the Council's approval of the site certificate to the date of disbursement of funds to The Climate Trust. [Final Order IV.P.2.3]

- 12.4 Before beginning construction of the facility, the certificate holder shall submit to the Department information identifying its final selection of a gas turbine vendor, heat recovery steam generator vendor along with the following information, as appropriate:
 - a. For the base load gas plant, the certificate holder shall submit written design information, based on its contracts with vendors, sufficient to verify the plant's designed new and clean heat rate (higher heating value) and its net power output at the average annual site condition. The certificate holder shall submit an affidavit certifying the heat rate and capacity.
 - b. For the base load gas plant designed with power augmentation, the certificate holder shall submit written design information, based on its contracts with vendors, sufficient to verify the facility's designed new and clean heat rate (higher heating value) and its net power output at the site during the times of year when is facility is intended to operate with power augmentation. The certificate holder shall submit an affidavit certifying the heat rate and capacity. [Final Order IV.P.2.4] [AMD1]
- 12.5 Before beginning construction of Unit 1, the certificate holder shall specify to the Department the annual average hours and the times that it expects to operate with power augmentation. [Final Order IV.P.2.5]
- 12.6 To calculate the initial monetary path payment requirement, the certificate holder shall use the contracted design parameters for capacities and heat rates submitted under Condition 12.4 and the annual average hours and times of operation with power augmentation specified under Condition 12.5. [Final Order IV.P.2.6]
- 12.7 Before beginning construction of Unit 1, the certificate holder shall enter into a Memorandum of Understanding (MOU) with The Climate Trust that establishes the disbursement mechanism to transfer selection and contracting funds and offset funds to The Climate Trust.
 - a. The MOU must be substantially in the form of Exhibit 3 to the Final Order on the Application. At the request of the certificate holder, the Council may approve a different form of a letter of credit and concurrent MOU without an amendment of the site certificate.
 - b. Either the certificate holder or The Climate Trust may submit to the Council for the Council's resolution any dispute between the certificate holder and The Climate Trust concerning the terms of the letter of credit, the MOU or any other issues related to the monetary path payment requirement. The Council's decision shall be binding on all parties. [Final Order IV.P.2.7] [AMD1]

- 12.8 The certificate holder shall submit all monetary path payment requirement calculations to the Department for verification in a timely manner before submitting a letter of credit for Council approval, before entering into an MOU with The Climate Trust as required by Condition 12.7, and before making disbursements to The Climate Trust. [Final Order IV.P.2.8] [AMD1]
- 12.9 Before beginning construction of Unit 1, the certificate holder shall submit to The Climate Trust a letter of credit in the amount of the offset funds of the monetary path payment requirement as determined under Condition 12.3.
 - a. The certificate holder shall use a form of letter of credit that is substantially in the form of Appendix B to the MOU described in Condition 12.7. At the request of the certificate holder, the Council may approve a different form of a letter of credit without an amendment of the site certificate.
 - b. The certificate holder shall use an issuer of the letter of credit approved by the Council.
 - c. The certificate holder shall maintain the letter of credit in effect until the certificate holder has disbursed the full amount of the offset funds to The Climate Trust. The certificate holder may reduce the amount of the letter of credit commensurate with payments it makes to The Climate Trust. The letter of credit must not be subject to revocation before disbursement of the full amount of the offset funds.

[Final Order IV.P.2.9] [AMD1]

- 12.10 For any transfer of the site certificate approved under OAR 345-027-0100:
 - a. If The Climate Trust has not yet fully withdrawn the amount of the letter of credit of the current certificate holder at the time of the transfer, the new certificate holder shall submit to The Climate Trust a pro-rated letter of credit, subject to the requirements of Condition 12.9. The new certificate holder shall submit to Council for the Council's approval the identity of the issuer of the letter of credit. The Council may approve a new letter of credit without a site certificate amendment.
 - b. The new certificate holder shall enter into an MOU with The Climate Trust as described in Condition 12.7 unless the new certificate holder demonstrates to the satisfaction of the Department that there has been a valid assignment of the current certificate holder's MOU to the new certificate holder. The Council may approve a new MOU without a site certificate amendment.
 - c. For resolution of any dispute between the new certificate holder and The Climate Trust concerning the disbursement mechanism for monetary path payments or any other issues related to the monetary path payment requirement, either party may submit the dispute to the Council as provided in Condition 12.7.b. [Final Order IV.P.2.10]

- 12.11 The certificate holder shall disburse to The Climate Trust offset funds and selection and contracting funds when requested by The Climate Trust in accordance with Conditions 12.13 and 12.14 and the following requirements:
 - a. The certificate holder shall disburse selection and contracting funds to The Climate Trust before beginning construction and as appropriate when additional offset funds are required under Conditions 12.13 and 12.14.
 - b. Upon notice pursuant to subsection (c), The Climate Trust may request from the issuer of the letter of credit the full amount of all offset funds available or it may request partial payment of offset funds at its sole discretion. Notwithstanding the specific amount of any contract to implement an offset project, The Climate Trust may request up to the full amount of offset funds the certificate holder is required to provide to meet the monetary path payment requirement.
 - c. The Climate Trust may request disbursement of offset funds pursuant to paragraph (b) by providing notice to the issuer of the letter of credit that The Climate Trust has executed a letter of intent to acquire an offset project. The certificate holder shall require that the issuer of the letter of credit disburse offset funds to The Climate Trust within three business days of a request by The Climate Trust for the offset funds in accordance with the terms of the letter of credit.

[Final Order IV.P.2.11]

- 12.12 Within the first 12 months of commercial operation of the facility, the certificate holder shall conduct a 100-hour test at full power without power augmentation (Year One Test-1) and a test at full power with power augmentation (Year One Test-2). Tests performed for purposes of the certificate holder's commercial acceptance of the facility may suffice to satisfy this condition in lieu of testing after beginning commercial operation.
 - a. The certificate holder shall conduct the Year One Test-1 to determine the actual heat rate (Year One Heat Rate-1) and the net electric power output (Year One Capacity-1) on a new and clean basis, without degradation, with the results adjusted for the average annual site condition for temperature, barometric pressure and relative humidity. The certificate holder shall calculate carbon dioxide emissions using a rate of 117 pounds of carbon dioxide per million Btu of natural gas fuel.
 - b. The certificate holder shall conduct the Year One Test-2 to determine the actual heat rate (Year One Heat Rate-2) and net electric power output (Year One Capacity-2) for the facility operating with power augmentation, without degradation, with the results adjusted for the site condition for temperature, barometric pressure and relative humidity at the site during the times of year when the power augmentation is intended to operate. The certificate holder shall calculate carbon dioxide emissions using a rate of 117 pounds of carbon dioxide per million Btu of natural gas fuel.
 - c. The certificate holder shall notify the Department at least 60 days before conducting the tests required in subsections (a) and (b) unless the certificate holder and the Department have mutually agreed that less notice will suffice.
 - d. Before conducting the tests required in subsections (a) and (b), the certificate holder shall, in a timely manner, provide to the Department for its approval a

copy of the protocol for conducting the tests. The Department may approve modified parameters for testing power augmentation on a new and clean basis and pursuant to OAR 345-024-0590(1) without a site certificate amendment. The certificate holder shall not conduct the tests until the Department has approved the testing protocols.

- e. Within two months after completing the Year One Tests, the certificate holder shall provide to the Council reports of the results of the Year One Tests. [Final Order IV.P.2.12]
- 12.13 Based on the data from the Year One Tests described in Condition 12.12, the certificate holder shall calculate an adjusted monetary path payment. The certificate holder shall submit its calculations to the Department for verification. If the adjusted amount exceeds the amount of the letter of credit provided according to Condition 12.9 before beginning construction, the certificate holder shall fully disburse the excess amount directly to The Climate Trust within 30 days of the Department's verification of the calculations.
 - a. The certificate holder shall include the appropriate calculations of the adjusted monetary path payment with its reports of the results of the Year One Tests required under Condition 12.12.
 - b. For calculating the adjusted monetary path payment, the certificate holder shall use an offset fund rate of \$1.27 per ton of carbon dioxide (in 2011 dollars) and shall calculate contracting and selecting funds based on 10 percent of the first \$500,000 in offset funds and 4.286 percent of any offset funds in excess of \$500,000 (in 2011 dollars).
 - c. In no case shall the certificate holder diminish the value of the letter of credit it provided before beginning construction or receive a refund from The Climate Trust based on the calculations made using the Year One Capacities and the Year One Heat Rates. [Final Order IV.P.2.13]
- 12.14 The certificate holder shall use the Year One Capacity-2 and Year One Heat Rate-2 that it reports for the facility, as described in Condition 12.12.b, to calculate whether it owes supplemental monetary path payments due to increased hours that it uses power augmentation.
 - a. Each five years after beginning commercial operation of the facility (five-year reporting period), the certificate holder shall report to the Department the annual average hours the facility operated with power augmentation during that five-year reporting period, as required under OAR 345-024-0590(6). The certificate holder shall submit five-year reports to the Department within 30 days after the anniversary date of beginning commercial operation of the facility.
 - b. If the Department determines that the facility exceeded the projected net total carbon dioxide emissions calculated under Conditions 12.4, 12.5 and 12.12, prorated for five years, during any five-year reporting period described in subsection (a), the certificate holder shall offset excess emissions for the

specific reporting period according to paragraph (i) and shall offset the estimated future excess emissions according to paragraph (ii), as follows:

- i. In determining whether there have been excess carbon dioxide emissions that the certificate holder must offset for a five-year reporting period, the Department shall apply OAR 345-024-0600(4)(a). The certificate holder shall pay for the excess emissions at \$1.27 per ton of carbon dioxide emissions (in 2011 dollars). The Department shall notify the certificate holder and The Climate Trust of the amount of supplemental payment required to offset excess emissions.
- ii. The Department shall calculate estimated future excess emissions for the remaining period of the deemed 30-year life of the facility using the parameters specified in OAR 345-024-0600(4)(b). The certificate holder shall pay for the estimated excess emissions at \$1.27 per ton of carbon dioxide (in 2011 dollars). The Department shall notify the certificate holder of the amount of supplemental payment required to offset future excess emissions.
- iii. The certificate holder shall offset excess emissions identified in paragraphs (i) and (ii) using the monetary path as described in OAR 345-024-0710. The certificate holder shall pay selection and contracting funds of 10 percent of the first \$500,000 in offset funds and 4.286 percent of any offset funds in excess of \$500,000 (in 2010 dollars).
- c. The certificate holder shall disburse the supplemental selection and contracting funds and supplemental offset funds to The Climate Trust within 30 days after notification by the Department of the amount that the certificate holder owes. [Final Order IV.P.2.14]
- 12.15 The certificate holder shall use only pipeline quality natural gas or shall use synthetic gas with a carbon content per million Btu no greater than pipeline-quality natural gas to fuel the combustion turbines and the power augmentation. [Final Order IV.P.2.15] [AMD1]
- 12.16 After the certificate holder has complied with the conditions relating to the carbon dioxide standard before beginning construction, incremental increases in capacity and heat rate that otherwise fall within the limits specified in OAR 345-027-0050(2) do not require an amendment of the site certificate if the certificate holder complies substantially with Conditions 12.1 through 12.15, except as modified below, and if:
 - The Department or the Council determines, as described in OAR 345-027-0050(5), that the proposed change in the facility does not otherwise require an amendment; and
 - b. The certificate holder complies with the appropriate carbon dioxide emissions standard and monetary offset rate in effect at the time the Department or the Council makes its determination under this condition.

[Final Order IV.P.2.16]

12.17 [Deleted] [Final Order IV.P.2.17] [AMD1]

13.0 NOISE CONTROL AND NOISE COMPLAINT RESPONSE

- 13.1 To reduce construction noise impacts at nearby residences, the certificate holder shall:
 - a. Confine the noisiest operation of heavy construction equipment to the daylight hours.
 - b. Require contractors to install and maintain exhaust mufflers on all combustion engine-powered equipment; and
 - c. Establish a complaint response system at the construction manager's office to address noise complaints. Records of noise complaints during construction must be made available to authorized representatives of the Department of Energy upon request.

[Final Order V.A.2.1]

- 13.2 During operation, the certificate holder shall maintain a complaint response system to address noise complaints. The certificate holder shall notify the Department within 15 days of receiving a complaint about noise from the facility. The notification should include the date the complaint was received, the nature of the complaint, the complainant's contact information, the location of the affected property, and any actions taken, or planned to be taken, by the certificate holder to address the complaint. [Final Order V.A.2.2]
- 13.3 Upon written notification from the Department, the certificate holder will monitor and record the actual statistical noise levels during operations to verify that the certificate holder is operating the facility in compliance with the noise control regulations. The monitoring plan must be reviewed and approved by the Department prior to implementation. The cost of such monitoring, if required, will be borne by the certificate holder.

[Final Order V.A.2.3]

14.0 MONITORING AND REPORTING REQUIREMENTS - GENERAL

- 14.1 The following general monitoring conditions apply:
 - a. The certificate holder shall consult with affected state agencies, local governments and tribes and shall develop specific monitoring programs for impacts to resources protected by the standards of divisions 22 and 24 of OAR Chapter 345 and resources addressed by applicable statutes, administrative rules and local ordinances. The certificate holder must submit the monitoring programs to the Department of Energy and receive Department approval before beginning construction or, as appropriate, operation of the facility.
 - b. The certificate holder shall implement the approved monitoring programs described in OAR 345-027-0028(1) and monitoring programs required by permitting agencies and local governments.
 - c. For each monitoring program described in OAR 345-027-0028(1) and (2), the certificate holder shall have quality assurance measures approved by the Department before beginning construction or, as appropriate, before beginning commercial operation.

d. If the certificate holder becomes aware of a significant environmental change or impact attributable to the facility, the certificate holder shall, as soon as possible, submit a written report to the Department describing the impact on the facility and any affected site certificate conditions.

[Final Order VI.2] [Mandatory Condition OAR 345-027-0028]

- 14.2 The certificate holder shall report according to the following requirements:
 - a. General reporting obligation for energy facilities under construction or operating:
 - Within six months after beginning construction, and every six months i. thereafter during construction of the energy facility and related or supporting facilities, the certificate holder shall submit a semiannual construction progress report to the Department of Energy as described in OAR 345-026-0080(1)(a). [AMD1]
 - ii. By April 30 of each year after beginning operation, the certificate holder shall
 - submit an annual report to the Department addressing the subjects listed in OAR 345-026-0080 (1)(b). The Council Secretary and the certificate holder may, by mutual agreement, change the reporting date. [AMD1]
 - iii. To the extent that information required by OAR 345-026-0080 is contained in reports the certificate holder submits to other state, federal or local agencies, the certificate holder may submit excerpts from such other reports to satisfy this rule. The Council reserves the right to request full copies of such excerpted reports.
 - [Final Order VI.4] [Mandatory Condition OAR 345-026-0080] [AMD1]
- 14.3 The certificate holder and the Department of Energy shall exchange copies of all correspondence or summaries of correspondence related to compliance with statutes, rules and local ordinances on which the Council determined compliance, except for material withheld from public disclosure under state or federal law or under Council rules. The certificate holder may submit abstracts of reports in place of full reports; however, the certificate holder shall provide full copies of abstracted reports and any summarized correspondence at the request of the Department. [Final Order VI.5] [Mandatory Condition OAR 345-026-0105]

15.0 RETIREMENT AND FINANCIAL ASSURANCE

15.1 Before beginning construction, the certificate holder shall submit to the State of Oregon through the Council a bond or letter of credit naming the State of Oregon, acting by and through the Council, as beneficiary or payee. The initial bond or letter of credit amount for Block 1 is \$7.884 million (in 3rd Quarter 2011 dollars), to be adjusted to the date of issuance, and adjusted on an annual basis thereafter, as described in sub-paragraph (b) of this condition. The initial bond or letter of credit amount for the Carty Solar Farm and its supporting facilities is \$2.713 million (in 3rd Quarter 2016 dollars) to be adjusted to the date of issuance, and adjusted on an annual basis thereafter, as described in

sub-paragraph (b) of this condition. The initial bond or letter of credit amount for the related or supporting facilities approved in Final Order on RFA2 is \$13.779 million (in 4th Quarter 2020 dollars) to be adjusted to the date of issuance and submitted within 60 days of execution of the Second Amended Site Certificate, and adjusted on an annual basis thereafter, as described in sub-paragraph (b) of this condition.

- a. The certificate holder may adjust the amount of the bond or letter of credit based on the final design configuration of the facility and turbine types selected by applying the unit costs and general costs presented in Site Restoration Cost Estimate of the Final Order on ASC for Unit 1; Table 4 of the Final Order on RFA1 for Carty Solar Farm; and Table 2 of the Final Order on RFA2 for the approved related or supporting facilities. Any revision to the restoration costs should be adjusted to the date of issuance as described in (b), and is subject to review and approval by the Department.
- b. The certificate holder shall adjust the amount of the bond or letter of credit, using the following calculation and subject to approval by the Department.
 - i. Adjust the amount of the bond or letter of credit amount for Unit 1 (expressed in 3rd Quarter 2011 dollars), Carty Solar Farm (expressed in 3rd Quarter 2016 dollars) and related or supporting facilities approved in Final Order on RFA2 (expressed in 4th Quarter 2020 dollars) to present value, using the U.S. Gross Domestic Product Implicit Price Deflator, Chain-Weight, as published in the Oregon Department of Administrative Services' "Oregon Economic and Revenue Forecast" or by any successor agency (the "Index") and using the index value and the quarterly index value applicable for Unit 1, Carty Solar Farm, and RFA2 facility components for the date of issuance of the new bond or letter of credit. If at any time the Index is no longer published, the Council shall select a comparable calculation to adjust the bond or letter of credit to present value.
 - ii. Round the resulting total to the nearest \$1,000 to determine the financial assurance amount.
- c. The certificate holder shall use a form of bond or letter of credit approved by the Council.
- d. The certificate holder shall use an issuer of the bond or letter of credit approved by the Council.
- e. The certificate holder shall describe the status of the bond or letter of credit in the annual report submitted to the Council under Condition VI.4.
- f. The bond or letter of credit shall not be subject to revocation or reduction before retirement of the facility site.
 [Final Order IV.G.2.9] [Mandatory Condition OAR 345-025-0006(8)] [AMD1]
 [AMD2]
- 15.2 If the certificate holder elects to use a bond to meet the requirements of Condition 15.1, the certificate holder shall ensure that the surety is obligated to comply with the requirements of applicable statutes, Council rules and this site certificate when the surety exercises any legal or contractual right it may have to assume construction,

operation or retirement of the energy facility. The certificate holder shall also ensure that the surety is obligated to notify the Council that it is exercising such rights and to obtain any Council approvals required by applicable statutes, Council rules and this site certificate before the surety commences any activity to complete construction, operate or retire the energy facility. [Final Order IV.G.2.10]

- 15.3 The certificate holder shall prevent the development of any conditions on the site that would preclude restoration of the site to a useful, non-hazardous condition to the extent that prevention of such site conditions is within the control of the certificate holder. [Final Order IV.G.2.5] [Mandatory Condition OAR 345-025-0006(7)]
- 15.4 The certificate holder must retire the facility in accordance with a retirement plan approved by the Council if the certificate holder permanently ceases construction or operation of the facility. The retirement plan must describe the activities necessary to restore the site to a useful, non-hazardous condition, as described in OAR 345-027-0110(5). After Council approval of the plan, the certificate holder must obtain the necessary authorization from the appropriate regulatory agencies to proceed with restoration of the site.

[Final Order IV.G.2.6] [Mandatory Condition OAR 345-025-0006(9)]

15.5 The certificate holder is obligated to retire the facility upon permanent cessation of construction or operation. If the Council finds that the certificate holder has permanently ceased construction or operation of the facility without retiring the facility according to a final retirement plan approved by the Council, as described in OAR 345-027-0110, the Council shall notify the certificate holder and request that the certificate holder submit a proposed final retirement plan to the Department within a reasonable time not to exceed 90 days. If the certificate holder does not submit a proposed final retirement plan by the specified date, the Council may direct the Department to prepare a proposed final retirement plan for the Council's approval.

[Final Order IV.G.2.7] [Mandatory Condition OAR 345-025-0006(16)]

15.6 Upon the Council's approval of a final retirement plan prepared per Condition 15.5, the Council may draw on the bond or letter of credit submitted per the requirements of Condition 15.1 to restore the site to a useful, non-hazardous condition according to the final retirement plan, in addition to any penalties the Council may impose under OAR Chapter 345, Division 29. If the amount of the bond or letter of credit is insufficient to pay the actual cost of retirement, the certificate holder shall pay any additional cost necessary to restore the site to a useful, non-hazardous condition. After completion of site restoration, the Council shall issue an order to terminate the site certificate if the Council finds that the facility has been retired according to the approved final retirement plan.

[Final Order IV.G.2.8] [Mandatory Condition OAR 345-027-0020(16)]

15.7 Following receipt of the site certificate or an amended site certificate, the certificate holder shall implement a plan that verifies compliance with all site certificate terms and conditions and applicable statutes and rules. As a part of the compliance plan, to verify compliance with the requirement to begin construction by the date specified in the site certificate, the certificate holder shall report promptly to the Department of Energy when construction begins. Construction is defined in OAR 345-001-0010. In reporting the beginning of construction, the certificate holder shall describe all work on the site performed before beginning construction, including work performed before the Council issued the site certificate, and shall state the cost of that work. For the purpose of this exhibit, "work on the site" means any work within a site or corridor, other than surveying, exploration or other activities to define or characterize the site or corridor. The certificate holder shall document the compliance plan and maintain it for inspection by the Department or the Council.

[Final Order VI.3] [Mandatory Condition OAR 345-026-0048]

16. SUCCESSORS AND ASSIGNS

To transfer this site certificate or any portion thereof or to assign or dispose of it in any other manner, directly or indirectly, the certificate holder shall comply with OAR 345-027-0100.

17. SEVERABILITY AND CONSTRUCTION

If any provision of this agreement and certificate is declared by a court to be illegal or in conflict with any law, the validity of the remaining terms and conditions shall not be affected, and the rights and obligations of the parties shall be construed and enforced as if the agreement and certificate did not contain the particular provision held to be invalid.

18. GOVERNING LAW AND FORUM

This site certificate shall be governed by the laws of the State of Oregon. Any litigation or arbitration arising out of this agreement shall be conducted in an appropriate forum in Oregon.

19. EXECUTION

This site certificate may be executed in counterparts and will become effective upon signature by the Chair of the Energy Facility Siting Council and the authorized representative of the certificate holder.

IN WITNESS THEREOF, this site certificate has been executed by the State of Oregon, acting by and through its Energy Facility Siting Council, and by Portland General Electric Company.

ENERGY FACILITY SITING COUNCIL

PORTLAND GENERAL ELECTRIC COMPANY

By: Marcial & Grant Mag 12, 2022 06:39 P071

Marcy Grail, Chair

Bradley Jenkins (Aug 7, 2022 10:04 PDT) By:

Bradley Jenkins, VP Utility Operations

Print: _____

Date: 12-Aug-2022

Oregon Energy Facility Siting Council

Aug 7, 2022

Date: _____

<u>BJM</u>