

The Oregon Energy Facility Siting Council

SITE CERTIFICATE

FOR THE MONTAGUE WIND POWER FACILITY

I. INTRODUCTION

- 1 The Oregon Energy Facility Siting Council (Council) issues this site certificate for the Montague
- 2 Wind Power Facility (the facility) in the manner authorized under ORS Chapter 469. This site
- 3 certificate is a binding agreement between the State of Oregon (State), acting through the
- 4 Council, and Montague Wind Power Facility LLC (certificate holder) authorizing the certificate
- 5 holder to construct and operate the facility in Gilliam County, Oregon. [Amendment #2]
- 6 The findings of fact, reasoning and conclusions of law underlying the terms and conditions of
- 7 this site certificate are set forth in the following documents, incorporated herein by this
- 8 reference: (a) the Final Order on the Application for Site Certificate for the Montague Wind
- 9 Power Facility issued on September 10, 2010 (hereafter, Final Order on the Application), (b) the
- 10 Final Order on Amendment #1 issued on June 21, 2013; and, (c) the Final Order on Amendment
- #2 issued on December 4, 2015. In interpreting this site certificate, any ambiguity will be
- clarified by reference to the following, in order of priority: (1) this Second Amended Site
- 13 Certificate, (2) the Final Order on Amendment #2, (3) the Final Order on Amendment #1, (4) the
- 14 Final Order on the Application, and (5) the record of the proceedings that led to the Final Order
- on the Application, the Final Order on Amendment #1, and the Final Order on Amendment #2.
- 16 [Amendment #2]
- 17 The definitions in ORS 469.300 and OAR 345-001-0010 apply to terms used in this site
- 18 certificate, except where otherwise stated or where the context clearly indicates otherwise.

II. SITE CERTIFICATION

- 1. To the extent authorized by state law and subject to the conditions set forth herein, the State authorizes the certificate holder to construct, operate and retire a wind energy
- facility, together with certain related or supporting facilities, at the site in Gilliam County,
- Oregon, as described in Section III of this site certificate. ORS 469.401(1).
- 23 2. This site certificate is effective until it is terminated under OAR 345-027-0110 or the rules in
- 24 effect on the date that termination is sought or until the site certificate is revoked under
- ORS 469.440 and OAR 345-029-0100 or the statutes and rules in effect on the date that
- revocation is ordered. ORS 469.401(1).
- 27 3. This site certificate does not address, and is not binding with respect to, matters that were
- 28 not addressed in the Final Order on the Application, Final Order on Amendment #1 and Final
- 29 Order on Amendment #2. Such matters include, but are not limited to: building code
- 30 compliance, wage, hour and other labor regulations, local government fees and charges and
- other design or operational issues that do not relate to siting the facility (ORS 469.401(4))
- and permits issued under statutes and rules for which the decision on compliance has been

- delegated by the federal government to a state agency other than the Council. 469.503(3).

 [Amendment #2]
- 4. Both the State and the certificate holder shall abide by local ordinances, state law and the rules of the Council in effect on the date this site certificate is executed. ORS 469.401(2). In addition, upon a clear showing of a significant threat to public health, safety or the environment that requires application of later-adopted laws or rules, the Council may require compliance with such later-adopted laws or rules. ORS 469.401(2).
- 5. For a permit, license or other approval addressed in and governed by this site certificate, the certificate holder shall comply with applicable state and federal laws adopted in the future to the extent that such compliance is required under the respective state agency statutes and rules. ORS 469.401(2).
- 6. Subject to the conditions herein, this site certificate binds the State and all counties, cities and political subdivisions in Oregon as to the approval of the site and the construction, operation and retirement of the facility as to matters that are addressed in and governed by this site certificate. ORS 469.401(3).
- 7. Each affected state agency, county, city and political subdivision in Oregon with authority to issue a permit, license or other approval addressed in or governed by this site certificate shall, upon submission of the proper application and payment of the proper fees, but without hearings or other proceedings, issue such permit, license or other approval subject only to conditions set forth in this site certificate. ORS 469.401(3).
- 21 8. After issuance of this site certificate, each state agency or local government agency that 22 issues a permit, license or other approval for the facility shall continue to exercise 23 enforcement authority over such permit, license or other approval. ORS 469.401(3).
- 9. After issuance of this site certificate, the Council shall have continuing authority over the site and may inspect, or direct the Oregon Department of Energy (Department) to inspect, or request another state agency or local government to inspect, the site at any time in order to ensure that the facility is being operated consistently with the terms and conditions of this site certificate. ORS 469.430.
- 10. Following the completion of surveys required by this site certificate, the Department will
 present the results of those surveys and required consultations at the next regularly
 scheduled Council meeting.

III. DESCRIPTION

1. The Facility

(a) The Energy Facility

- 32 The energy facility is an electric power generating plant with an average electric generating
- capacity of up to 134.7 megawatts and a peak generating capacity of not more than 404
- megawatts that produces power from wind energy. The facility consists of not more than 269
- wind turbines. The maximum peak generating capacity of each turbine is not more than 3.0

- 1 megawatts. The energy facility is described further in the Final Order on the Application, Final
- 2 Order on Amendment #1, and Final Order on Amendment #2.

(b) Related or Supporting Facilities

- 3 The facility includes the following related or supporting facilities described below and in greater
- 4 detail in the Final Order on the Application, Final Order on Amendment #1, and Final Order on
- 5 Amendment #2:

6 7

9

11

13

- Power collection system
- Control system
 - Substations and 230-kV transmission lines
- Meteorological towers
 - Operations and maintenance facilities
- Access roads
 - Public roadway modifications
 - Temporary construction areas

1415

16

21

26

32

33

34

Power Collection System

- 17 A power collection system operating at 34.5 kilovolts (kV) transports power from each turbine
- 18 to a collector substation. To the extent practicable, the collection system is installed
- underground at a depth of at least three fed. Not more than 27 miles of the collector system is
- installed aboveground.

Control System

- 22 A fiber optic communications network links the wind turbines to a central computer at the
- 23 O&M buildings. A Supervisory, Control and Data Acquisition (SCA DA) system collects operating
- and performance data from each wind turbine and from the project as a whole and allows
- 25 remote operation of the wind turbines.

Substations and 230-kV Transmission Lines

- 27 The facility includes two collector substations. An aboveground, single-circuit 230-kV
- transmission line connects the western substation to the central substation. An aboveground,
- 29 single-circuit 230-kV transmission line connects the central substation to the 500-kV Slatt-
- 30 Buckley transmission line owned by the Bonneville Power Administration (BPA) at the Slatt
- 31 substation.

Meteorological Towers

The facility includes up to eight permanent meteorological towers.

Operations and Maintenance Facilities

- 35 The facility includes one or two operations and maintenance (O&M) facilities. An on-site well at
- and each O&M facility supplies water for use during facility operation. Sewage is discharged to an
- on-site septic system.

Access Roads

1

3

2 The facility includes access roads to provide access to the turbine strings.

Public Roadway Modifications

- 4 The certificate holder may construct improvements to existing state and county public roads
- 5 that are necessary for construction of the facility. These modifications would be confined to the
- 6 existing road rights-of-way and would be undertaken with the approval of the Gilliam County
- 7 Road Department or the Oregon Department of Transportation, depending on the location of
- 8 the improvement.

9 <u>Temporary Construction Areas</u>

- 10 During construction, the facility includes temporary laydown areas used to stage construction
- and store supplies and equipment. Construction crane paths are used to move construction
- 12 cranes between turbine strings.

2. Location of the Proposed Facility

- 13 The facility is located south of Arlington, in Gilliam County, Oregon. The facility is located on
- private land subject to easements or lease agreements with landowners.

IV. CONDITIONS REQUIRED BY COUNCIL RULES

- 15 This section lists conditions required by OAR 345-027-0020 (Mandatory Conditions in Site
- 16 Certificates), OAR 345-027-0023 (Site Specific Conditions), OAR 345-027-0028 (Monitoring
- 17 Conditions) and OAR Chapter 345, Division 26 (Construction and Operation Rules for Facilities).
- 18 These conditions should be read together with the specific facility conditions listed in Section V
- to ensure compliance with the siting standards of OAR Chapter 345, Divisions 22 and 24, and to
- 20 protect the public health and safety. In these conditions the definitions in OAR 345-001-0010
- 21 apply.
- 22 The obligation of the certificate holder to report information to the Department or the Council
- 23 under the conditions listed in this section and in Section V is subject to the provisions of
- ORS 192.502 et seq. and ORS 469.560. To the extent permitted by law, the Department and the
- 25 Council will not publicly disclose information that may be exempt from public disclosure if the
- 26 certificate holder has clearly labeled such information and stated the basis for the exemption at
- 27 the time of submitting the information to the Department or the Council. If the Council or the
- Department receives a request for the disclosure of the information, the Council or the
- 29 Department, as appropriate, will make a reasonable attempt to notify the certificate holder and
- will refer the matter to the Attorney General for a determination of whether the exemption is
- applicable, pursuant to ORS 192.450.
- 32 In addition to these conditions, the site certificate holder is subject to all conditions and
- requirements contained in the rules of the Council and in local ordinances and state law in
- effect on the date the certificate is executed. Under ORS 469.401(2), upon a clear showing of a
- 35 significant threat to the public health, safety or the environment that requires application of
- 36 later-adopted laws or rules, the Council may require compliance with such later-adopted laws
- 37 or rules.
- 38 The Council recognizes that many specific tasks related to the design, construction, operation
- and retirement of the facility will be undertaken by the certificate holder's agents or
- 40 contractors. Nevertheless, the certificate holder is responsible for ensuring compliance with all
- 41 provisions of the site certificate.

- 1 <u>1</u> OAR 345-027-0020(1): The Council shall not change the conditions of the site certificate except as provided for in OAR Chapter 345, Division 27.
- OAR 345-027-0020(2): The certificate holder shall submit a legal description of the site to the Department of Energy within 90 days after beginning operation of the facility. The legal description required by this rule means a description of metes and bounds or a description of the site by reference to a map and geographic data that clearly and specifically identifies the outer boundaries that contain all parts of the facility.
- 8 <u>3</u> OAR 345-027-0020(3): The certificate holder shall design, construct, operate and retire the facility:
 - (a) Substantially as described in the site certificate;

- (b) In compliance with the requirements of ORS Chapter 469, applicable Council rules, and applicable state and local laws, rules and ordinances in effect at the time the site certificate is issued; and
- (c) In compliance with all applicable permit requirements of other state agencies.
- 15 <u>4</u> OAR 345-027-0020(4): The certificate holder shall begin and complete construction of the facility by the dates specified in the site certificate. (See Conditions 24 and 25.)
 - OAR 345-027-0020(5): Except as necessary for the initial survey or as otherwise allowed for wind energy facilities, transmission lines or pipelines under this section, the certificate holder shall not begin construction, as defined in OAR 345-001-0010, or create a clearing on any part of the site until the certificate holder has construction rights on all parts of the site. For the purpose of this rule, "construction rights" means the legal right to engage in construction activities. For wind energy facilities, transmission lines or pipelines, if the certificate holder does not have construction rights on all parts of the site, the certificate holder may nevertheless begin construction, as defined in OAR 345-001-0010, or create a clearing on a part of the site if the certificate holder has construction rights on that part of the site and:
 - (a) The certificate holder would construct and operate part of the facility on that part of the site even if a change in the planned route of the transmission line or pipeline occurs during the certificate holder's negotiations to acquire construction rights on another part of the site; or
 - (b) The certificate holder would construct and operate part of a wind energy facility on that part of the site even if other parts of the facility were modified by amendment of the site certificate or were not built.
 - OAR 345-027-0020(6): If the Council requires mitigation based on an affirmative finding under any standards of Division 22 or Division 24 of this chapter, the certificate holder shall consult with affected state agencies and local governments designated by the Council and shall develop specific mitigation plans consistent with Council findings under the relevant standards. The certificate holder must submit the mitigation plans to the Department and receive Department approval before beginning construction or, as appropriate, operation of the facility.

- OAR 345-027-0020(7): The certificate holder shall prevent the development of any conditions on the site that would preclude restoration of the site to a useful, non-hazardous condition to the extent that prevention of such site conditions is within the control of the certificate holder.
- OAR 345-027-0020(8): Before beginning construction of the facility, the certificate holder shall submit to the State of Oregon, through the Council, a bond or letter of credit, in a form and amount satisfactory to the Council to restore the site to a useful, non-hazardous condition. The certificate holder shall maintain a bond or letter of credit in effect at all times until the facility has been retired. The Council may specify different amounts for the bond or letter of credit during construction and during operation of the facility. (See Condition 32.)
- OAR 345-027-0020(9): The certificate holder shall retire the facility if the certificate holder permanently ceases construction or operation of the facility. The certificate holder shall retire the facility according to a final retirement plan approved by the Council, as described in OAR 345-027-0110. The certificate holder shall pay the actual cost to restore the site to a useful, non-hazardous condition at the time of retirement, notwithstanding the Council's approval in the site certificate of an estimated amount required to restore the site.
- 19 <u>10</u> OAR 345-027-0020(10): The Council shall include as conditions in the site certificate all representations in the site certificate application and supporting record the Council deems to be binding commitments made by the applicant.
- 22 11 OAR 345-027-0020(11): Upon completion of construction, the certificate holder shall restore vegetation to the extent practicable and shall landscape all areas disturbed by construction in a manner compatible with the surroundings and proposed use. Upon completion of construction, the certificate holder shall remove all temporary structures not required for facility operation and dispose of all timber, brush, refuse and flammable or combustible material resulting from clearing of land and construction of the facility.
- 28 12 OAR 345-027-0020(12): The certificate holder shall design, engineer and construct the facility to avoid dangers to human safety presented by seismic hazards affecting the site that are expected to result from all maximum probable seismic events. As used in this rule "seismic hazard" includes ground shaking, landslide, liquefaction, lateral spreading, tsunami inundation, fault displacement and subsidence.
- 33 <u>OAR 345-027-0020(13)</u>: The certificate holder shall notify the Department, the State
 34 Building Codes Division and the Department of Geology and Mineral Industries promptly if
 35 site investigations or trenching reveal that conditions in the foundation rocks differ
 36 significantly from those described in the application for a site certificate. After the
 37 Department receives the notice, the Council may require the certificate holder to consult
 38 with the Department of Geology and Mineral Industries and the Building Codes Division
 39 and to propose mitigation actions.
- 40 <u>14</u> OAR 345-027-0020(14): The certificate holder shall notify the Department, the State
 41 Building Codes Division and the Department of Geology and Mineral Industries promptly if

- shear zones, artesian aquifers, deformations or clastic dikes are found at or in the vicinity of the site.
- OAR 345-027-0020(15): Before any transfer of ownership of the facility or ownership of the site certificate holder, the certificate holder shall inform the Department of the proposed new owners. The requirements of OAR 345-027-0100 apply to any transfer of ownership that requires a transfer of the site certificate.
- 7 OAR 345-027-0020(16): If the Council finds that the certificate holder has permanently 8 ceased construction or operation of the facility without retiring the facility according to a 9 final retirement plan approved by the Council, as described in OAR 345-027-0110, the 10 Council shall notify the certificate holder and request that the certificate holder submit a 11 proposed final retirement plan to the Department within a reasonable time not to exceed 12 90 days. If the certificate holder does not submit a proposed final retirement plan by the 13 specified date, the Council may direct the Department to prepare a proposed final 14 retirement plan for the Council's approval. Upon the Council's approval of the final 15 retirement plan, the Council may draw on the bond or letter of credit described in OAR 16 345-027-0020(8) to restore the site to a useful, non-hazardous condition according to the 17 final retirement plan, in addition to any penalties the Council may impose under OAR 18 Chapter 345, Division 29. If the amount of the bond or letter of credit is insufficient to pay 19 the actual cost of retirement, the certificate holder shall pay any additional cost necessary 20 to restore the site to a useful, non-hazardous condition. After completion of site 21 restoration, the Council shall issue an order to terminate the site certificate if the Council 22 finds that the facility has been retired according to the approved final retirement plan.
- 23 <u>17</u> OAR 345-027-0023(4): If the facility includes any transmission line under Council jurisdiction:
 - (a) The certificate holder shall design, construct and operate the transmission line in accordance with the requirements of the National Electrical Safety Code (American National Standards Institute, Section C2, 1997 Edition); and
 - (b) The certificate holder shall develop and implement a program that provides reasonable assurance that all fences, gates, cattle guards, trailers, or other objects or structures of a permanent nature that could become inadvertently charged with electricity are grounded or bonded throughout the life of the line.
- 32 <u>OAR 345-027-0023(5)</u>: If the proposed energy facility is a pipeline or a transmission line or has, as a related or supporting facility, a pipeline or transmission line, the Council shall specify an approved corridor in the site certificate and shall allow the certificate holder to construct the pipeline or transmission line anywhere within the corridor, subject to the conditions of the site certificate. If the applicant has analyzed more than one corridor in its application for a site certificate, the Council may, subject to the Council's standards, approve more than one corridor.
 - 19 OAR 345-027-0028: The following general monitoring conditions apply:
 - (a) The certificate holder shall consult with affected state agencies, local governments and tribes and shall develop specific monitoring programs for impacts to resources protected by the standards of divisions 22 and 24 of OAR Chapter 345 and resources

26

27

28

29

30

31

39

40

41

- addressed by applicable statutes, administrative rules and local ordinances. The certificate holder must submit the monitoring programs to the Department of Energy and receive Department approval before beginning construction or, as appropriate, operation of the facility.
- (b) The certificate holder shall implement the approved monitoring programs described in OAR 345-027-0028(1) and monitoring programs required by permitting agencies and local governments.
- (c) For each monitoring program described in OAR 345-027-0028(1) and (2), the certificate holder shall have quality assurance measures approved by the Department before beginning construction or, as appropriate, before beginning commercial operation.
- (d) If the certificate holder becomes aware of a significant environmental change or impact attributable to the facility, the certificate holder shall, as soon as possible, submit a written report to the Department describing the impact on the facility and any affected site certificate conditions
- OAR 345-026-0048: Following receipt of the site certificate or an amended site certificate, the certificate holder shall implement a plan that verifies compliance with all site certificate terms and conditions and applicable statutes and rules. As a part of the compliance plan, to verify compliance with the requirement to begin construction by the date specified in the site certificate, the certificate holder shall report promptly to the Department of Energy when construction begins. Construction is defined in OAR 345-001-0010. In reporting the beginning of construction, the certificate holder shall describe all work on the site performed before beginning construction, including work performed before the Council issued the site certificate, and shall state the cost of that work. For the purpose of this exhibit, "work on the site" means any work within a site or corridor, other than surveying, exploration or other activities to define or characterize the site or corridor. The certificate holder shall document the compliance plan and maintain it for inspection by the Department or the Council.
- <u>OAR 345-026-0080</u>: The certificate holder shall report according to the following requirements:
 - (a) General reporting obligation for energy facilities under construction or operating:
 - (i) Within six months after beginning construction, and every six months thereafter during construction of the energy facility and related or supporting facilities, the certificate holder shall submit a semiannual construction progress report to the Department of Energy. In each construction progress report, the certificate holder shall describe any significant changes to major milestones for construction. The certificate holder shall include such information related to construction as specified in the site certificate. When the reporting date coincides, the certificate holder may include the construction progress report within the annual report described in OAR 345-026-0080.
 - (ii) By April 30 of each year after beginning construction, the certificate holder shall submit an annual report to the Department addressing the subjects listed in OAR 345-026-0080. The Council Secretary and the certificate holder may, by mutual agreement, change the reporting date.

- (iii) To the extent that information required by OAR 345-026-0080 is contained in reports the certificate holder submits to other state, federal or local agencies, the certificate holder may submit excerpts from such other reports to satisfy this rule. The Council reserves the right to request full copies of such excerpted reports
- (b) In the annual report, the certificate holder shall include the following information for the calendar year preceding the date of the report:
- (i) Facility Status: An overview of site conditions, the status of facilities under construction, and a summary of the operating experience of facilities that are in operation. In this section of the annual report, the certificate holder shall describe any unusual events, such as earthquakes, extraordinary windstorms, major accidents or the like that occurred during the year and that had a significant adverse impact on the facility.
- (ii) Reliability and Efficiency of Power Production: For electric power plants, the plant availability and capacity factors for the reporting year. The certificate holder shall describe any equipment failures or plant breakdowns that had a significant impact on those factors and shall describe any actions taken to prevent the recurrence of such problems.
 - (iii) Fuel Use: For thermal power plants:
 - (A) The efficiency with which the power plant converts fuel into electric energy. If the fuel chargeable to power heat rate was evaluated when the facility was sited, the certificate holder shall calculate efficiency using the same formula and assumptions, but using actual data; and
 - (B) The facility's annual hours of operation by fuel type and, every five years after beginning operation, a summary of the annual hours of operation by fuel type as described in OAR 345-024-0590(5).
- (iv) Status of Surety Information: Documentation demonstrating that bonds or letters of credit as described in the site certificate are in full force and effect and will remain in full force and effect for the term of the next reporting period.
- (v) Monitoring Report: A list and description of all significant monitoring and mitigation activities performed during the previous year in accordance with site certificate terms and conditions, a summary of the results of those activities and a discussion of any significant changes to any monitoring or mitigation program, including the reason for any such changes.
- (vi) Compliance Report: A description of all instances of noncompliance with a site certificate condition. For ease of review, the certificate holder shall, in this section of the report, use numbered subparagraphs corresponding to the applicable sections of the site certificate.
- (vii) Facility Modification Report: A summary of changes to the facility that the certificate holder has determined do not require a site certificate amendment in accordance with OAR 345-027-0050.
- (viii) Nongenerating Facility Carbon Dioxide Emissions: For nongenerating facilities that emit carbon dioxide, a report of the annual fuel use by fuel type and annual hours of operation of the carbon dioxide emitting equipment as described in OAR 345-024-0630(4).

- 22 OAR 345-026-0105: The certificate holder and the Department of Energy shall exchange 1 2 copies of all correspondence or summaries of correspondence related to compliance with 3 statutes, rules and local ordinances on which the Council determined compliance, except 4 for material withheld from public disclosure under state or federal law or under Council 5 rules. The certificate holder may submit abstracts of reports in place of full reports; 6 however, the certificate holder shall provide full copies of abstracted reports and any 7 summarized correspondence at the request of the Department.
- 8 OAR 345-026-0170: The certificate holder shall notify the Department of Energy within 72 9 hours of any occurrence involving the facility if:
 - (a) There is an attempt by anyone to interfere with its safe operation;
 - (b) A natural event such as an earthquake, flood, tsunami or tornado, or a humancaused event such as a fire or explosion affects or threatens to affect the public health and safety or the environment; or
 - (c) There is any fatal injury at the facility.

٧. **SPECIFIC FACILITY CONDITIONS**

10

11

12

13 14

- 15 The conditions listed in this section include conditions based on representations in the site
- certificate application and supporting record. The Council deems these representations to be 16
- binding commitments made by the applicant. These conditions are required under OAR 17
- 345-027-0020(10). The certificate holder must comply with these conditions in addition to the 18
- conditions listed in Section IV. This section includes other specific facility conditions the Council 19
- finds necessary to ensure compliance with the siting standards of OAR Chapter 345, Divisions 20
- 21 22 and 24, and to protect public health and safety. For conditions that require subsequent
- 22 review and approval of a future action, ORS 469.402 authorizes the Council to delegate the
- future review and approval to the Department if, in the Council's discretion, the delegation is 23
- 24 warranted under the circumstances of the case.

1. Certificate Administration Conditions

- 25 24 The certificate holder shall begin construction of the facility by September 14, 2017. Under OAR 345-015-0085(9), a site certificate is effective upon execution by the Council Chair 26 and the applicant. The Council may grant an extension of the deadline to begin 27 construction in accordance with OAR 345-027-0030 or any successor rule in effect at the 28 29 time the request for extension is submitted. [Amendment #2]
- 30 The certificate holder shall complete construction of the facility by September 14, 2020. 31 Construction is complete when: (1) the facility is substantially complete as defined by the 32 certificate holder's construction contract documents, (2) acceptance testing has been 33 satisfactorily completed and (3) the energy facility is ready to begin continuous operation 34 consistent with the site certificate. The certificate holder shall promptly notify the 35 Department of the date of completion of construction. The Council may grant an extension of the deadline for completing construction in accordance with OAR 345-027-
- 36
- 0030 or any successor rule in effect at the time the request for extension is submitted. 37
- 38 [Amendment #2]

- 1 Before beginning construction of the facility, the certificate holder shall notify the 26 2 Department whether the turbines identified as H1, H2, H3, H4, L8, L9, L10, L11 and L12 on 3 Figure C-3a of the site certificate application will be built as part of the Montague Wind 4 Power Facility or whether the turbines will be built as part of the Leaning Juniper II Wind 5 Power Facility.
 - The certificate holder shall construct a facility substantially as described in the site <u>27</u> certificate and may select turbines of any type, subject to the following restrictions and compliance with all other site certificate conditions. Before beginning construction, the certificate holder shall provide to the Department a description of the turbine types selected for the facility demonstrating compliance with this condition.
 - (a) The total number of turbines at the facility must not exceed 269 turbines.
 - (b) The combined peak generating capacity of the facility must not exceed 404 megawatts and the peak generating capacity of any individual turbine must not exceed 3.0 megawatts.
 - (c) The turbine hub height must not exceed 100 meters and the maximum blade tip height must not exceed 150 meters.
 - (d) The minimum blade tip clearance must be 20 meters above ground. [Amendment #1]
 - (e) The certificate holder shall request an amendment of the site certificate to increase the combined peak generating capacity of the facility beyond 404 megawatts, to increase the number of wind turbines to more than 269 wind turbines or to install wind turbines with a hub height greater than 100 meters, a blade tip height greater than 150 meters or a blade tip clearance less than 20 meters above ground. [Amendment #1]
- 25 The certificate holder shall obtain all necessary federal, state and local permits or 26 approvals required for construction, operation and retirement of the facility or ensure that 27 its contractors obtain the necessary federal, state and local permits or approvals.
- 28 Before beginning construction, the certificate holder shall provide confirmation to the 29 Department that the construction contractor or other third party has obtained all 30 necessary permits or approvals and shall provide to the Department proof of agreements between the certificate holder and the third party regarding access to the resources or 32 services secured by the permits or approvals.
- 33 Before beginning construction, the certificate holder shall notify the Department in 34 advance of any work on the site that does not meet the definition of "construction" in ORS 35 469.300, excluding surveying, exploration or other activities to define or characterize the 36 site, and shall provide to the Department a description of the work and evidence that its value is less than \$250,000. 37
 - Before beginning construction but no more than two years before beginning construction and after considering all micrositing factors, the certificate holder shall provide to the Department, to the Oregon Department of Fish and Wildlife (ODFW) and to the Planning Director of Gilliam County detailed maps of the facility site, showing the final locations where the certificate holder proposes to build facility components, and a table showing

7

8

9

10

11

12

13 14

15

16 17

18

19

20

21

22

23

24

31

38

39

40

41

- the acres of temporary and permanent habitat impact by habitat category and subtype, similar to Table 6 in the Final Order on the Application. The detailed maps of the facility site shall indicate the habitat categories of all areas that would be affected during construction (similar to Figures P-8a through P-8d in the site certificate application). In classifying the affected habitat into habitat categories, the certificate holder shall consult with the ODFW. The certificate holder shall not begin ground disturbance in an affected area until the habitat assessment has been approved by the Department. The Department may employ a qualified contractor to confirm the habitat assessment by on-site inspection.
 - Before beginning construction, the certificate holder shall submit to the State of Oregon through the Council a bond or letter of credit in the amount described herein naming the State of Oregon, acting by and through the Council, as beneficiary or payee. The initial bond or letter of credit amount is either \$21.511 million (3rd Quarter 2010 dollars), to be adjusted to the date of issuance as described in (b), or the amount determined as described in (a). The certificate holder shall adjust the amount of the bond or letter of credit on an annual basis thereafter as described in (b).
 - (a) The certificate holder may adjust the amount of the bond or letter of credit based on the final design configuration of the facility and turbine types selected by applying the unit costs and general costs illustrated in Table 2 in the *Final Order on the Application* and calculating the financial assurance amount as described in that order, adjusted to the date of issuance as described in (b) and subject to approval by the Department.
 - (b) The certificate holder shall adjust the amount of the bond or letter of credit, using the following calculation and subject to approval by the Department:
 - (i) Adjust the Subtotal component of the bond or letter of credit amount (expressed in mid-2004 dollars) to present value, using the U.S. Gross Domestic Product Implicit Price Deflator, Chain-Weight, as published in the Oregon Department of Administrative Services' "Oregon Economic and Revenue Forecast" or by any successor agency (the "Index") and using the average of the 2nd Quarter and 3rd Quarter 2004 index values (to represent mid-2004 dollars) and the quarterly index value for the date of issuance of the new bond or letter of credit. If at any time the Index is no longer published, the Council shall select a comparable calculation to adjust mid-2004 dollars to present value.
 - (ii) Add 1 percent of the adjusted Subtotal (i) for the adjusted performance bond amount to determine the adjusted Gross Cost.
 - (iii) Add 10 percent of the adjusted Gross Cost (ii) for the adjusted administration and project management costs and 10 percent of the adjusted Gross Cost (ii) for the adjusted future developments contingency.
 - (iv) Add the adjusted Gross Cost (ii) to the sum of the percentages (iii) and round the resulting total to the nearest \$1,000 to determine the adjusted financial assurance amount.

- 1 (c) The certificate holder shall use a form of bond or letter of credit approved by the Council.
 - (d) The certificate holder shall use an issuer of the bond or letter of credit approved by the Council.
 - (e) The certificate holder shall describe the status of the bond or letter of credit in the annual report submitted to the Council under Condition 21.
 - (f) The bond or letter of credit shall not be subject to revocation or reduction before retirement of the facility site.
- 9 If the certificate holder elects to use a bond to meet the requirements of Condition 32, the 10 certificate holder shall ensure that the surety is obligated to comply with the requirements 11 of applicable statutes, Council rules and this site certificate when the surety exercises any 12 legal or contractual right it may have to assume construction, operation or retirement of the energy facility. The certificate holder shall also ensure that the surety is obligated to 13 14 notify the Council that it is exercising such rights and to obtain any Council approvals 15 required by applicable statutes, Council rules and this site certificate before the surety 16 commences any activity to complete construction, operate or retire the energy facility.
- Before beginning construction, the certificate holder shall notify the Department of the identity and qualifications of the major design, engineering and construction contractor(s) for the facility. The certificate holder shall select contractors that have substantial experience in the design, engineering and construction of similar facilities. The certificate holder shall report to the Department any change of major contractors.
- The certificate holder shall contractually require all construction contractors and subcontractors involved in the construction of the facility to comply with all applicable laws and regulations and with the terms and conditions of the site certificate. Such contractual provisions shall not operate to relieve the certificate holder of responsibility under the site certificate.
- To ensure compliance with all site certificate conditions during construction, the certificate holder shall have a full-time, on-site assistant construction manager who is qualified in environmental compliance. The certificate holder shall notify the Department of the name, telephone number and e-mail address of this person.
- Within 72 hours after discovery of conditions or circumstances that may violate the terms or conditions of the site certificate, the certificate holder shall report the conditions or circumstances to the Department.

2. Land Use Conditions

3

4

5 6

7

- The certificate holder shall consult with area landowners and lessees during construction and operation of the facility and shall implement measures to reduce or avoid any adverse impacts to farm practices on surrounding lands and to avoid any increase in farming costs.
- The certificate holder shall design and construct the facility using the minimum land area necessary for safe construction and operation. The certificate holder shall locate access roads and temporary construction laydown and staging areas to minimize disturbance of

1 farming practices and, wherever feasible, shall place turbines and transmission 2 interconnection lines along the margins of cultivated areas to reduce the potential for 3 conflict with farm operations. 4 The certificate holder shall install gates on private access roads in accordance with Gilliam 5 County Zoning Ordinance Section 7.020(T)(4)(d)(6) unless the County has granted a 6 variance to this requirement. 7 Before beginning construction of the facility, the certificate holder shall record in the real 41 8 property records of Gilliam County a Covenant Not to Sue with regard to generally 9 accepted farming practices on adjacent farmland consistent with GCZO Section 10 7.020(T)(4)(a)(5). 11 The certificate holder shall construct all facility components in compliance with the 12 following setback requirements: 13 (a) All facility components must be at least 3,520 feet from the property line of 14 properties zoned residential use or designated in the Gilliam County 15 Comprehensive Plan as residential. 16 (b) Where (a) does not apply, the certificate holder shall maintain a minimum distance 17 of 110-percent of maximum blade tip height, measured from the centerline of the 18 turbine tower to the nearest edge of any public road right-of-way. The certificate 19 holder shall assume a minimum right-of-way width of 60 feet. 20 (c) Where (a) does not apply, the certificate holder shall maintain a minimum distance 21 of 1,320 feet, measured from the centerline of the turbine tower to the center of 22 the nearest residence existing at the time of tower construction. 23 (d) Where (a) does not apply, the certificate holder shall maintain a minimum distance 24 of 110-percent of maximum blade tip height, measured from the centerline of the 25 turbine tower to the nearest boundary of the certificate holder's lease area. 26 (e) The certificate holder shall maintain a minimum distance of 250 feet measured 27 from the center line of each turbine tower to the nearest edge of any railroad right-28 of-way or electrical substation. 29 (f) The certificate holder shall maintain a minimum distance of 250 feet measured from 30 the center line of each meteorological tower to the nearest edge of any public road 31 right-of-way or railroad right-of-way, the nearest boundary of the certificate 32 holder's lease area or the nearest electrical substation. 33 (g) The certificate holder shall maintain a minimum distance of 50 feet measured from 34 any facility O&M building to the nearest edge of any public road right-of-way or 35 railroad right-of-way or the nearest boundary of the certificate holder's lease area. (h) The certificate holder shall maintain a minimum distance of 50 feet measured from 36 37 any substation to the nearest edge of any public road right-of-way or railroad rightof-way or the nearest boundary of the certificate holder's electrical substation 38

easement or, if there is no easement, the nearest boundary of the certificate

holder's lease area.

39

- (i) Where (a) does not apply, the certificate holder shall maintain a minimum of 110percent of maximum blade tip height, measured from the centerline of the turbine tower from any overhead utility line. [Amendment #1]
 - (j) Where (a) does not apply, the certificate holder shall maintain a minimum of 150percent of maximum turbine height from blade tip height, measured from the centerline of the turbine tower from federal transmission lines, unless the affected parties agree otherwise. [Amendment #1]
- During construction and operation of the facility, the certificate holder shall implement a weed control plan approved by the Gilliam County Weed Control Officer or other appropriate County officials to control the introduction and spread of noxious weeds.
- During operation of the facility, the certificate holder shall restore areas that are temporarily disturbed during facility maintenance or repair activities using the same methods and monitoring procedures described in the *Revegetation Plan* referenced in Condition 92.
- Within 90 days after beginning operation, the certificate holder shall provide to the
 Department and to the Gilliam County Planning Department the actual latitude and
 longitude location or Stateplane NAD 83(91) coordinates of each turbine tower,
 connecting lines and transmission lines and a summary of as-built changes in the facility
 compared to the original plan.
- The certificate holder shall deliver a copy of the annual report required under Condition 21 21 to the Gilliam County Planning Commission on an annual basis unless specifically 22 discontinued by the County.

3. Cultural Resource Conditions

4

5

6

7

30

31

32

33

34

3536

37

38

- Before beginning construction, the certificate holder shall label all identified historic, cultural or archaeological resource sites on construction maps and drawings as "no entry" areas. If construction activities will occur within 200 feet of an identified site, the certificate holder shall flag a 30-meter no-entry buffer around the site. The certificate holder may use existing private roads within the buffer areas but may not widen or improve private roads within the buffer areas. The no-entry restriction does not apply to public road rights-of-way within the buffer areas or to operational farmsteads.
 - 48 In reference to the alignment of the Oregon Trail described in the *Final Order on the Application*, the certificate holder shall comply with the following requirements:
 - (a) The certificate holder shall not locate facility components on visible remnants of the Oregon Trail and shall avoid any construction disturbance to those remnants.
 - (b) The certificate holder shall not locate facility components on undeveloped land where the trail alignment is marked by existing Oregon-California Trail Association markers.
 - (c) Before beginning construction, the certificate holder shall provide to the State Historic Preservation Office (SHPO) and the Department documentation of the presumed Oregon Trail alignments within the site boundary.

- (d) The certificate holder shall ensure that construction personnel proceed carefully in the vicinity of the presumed alignments of the Oregon Trail. If any physical evidence of the trail is discovered, the certificate holder shall avoid any disturbance to the intact segments by redesign, re-engineering or restricting the area of construction activity and shall flag a 30-meter no-entry buffer around the intact Trail segments. The certificate holder shall promptly notify the SHPO and the Department of the discovery. The certificate holder shall consult with the SHPO and the Department to determine appropriate mitigation measures.
- Before beginning construction, the certificate holder shall provide to the Department a map showing the final design locations of all components of the facility, the areas that would be temporarily disturbed during construction and the areas that were surveyed in 2009 as described in the *Final Order on the Application*. The certificate holder shall hire qualified personnel to conduct field investigations of all areas to be disturbed during construction that lie outside the previously-surveyed areas. The certificate holder shall provide a written report of the field investigations to the Department and to the Oregon State Historic Preservation Office (SHPO) for review and approval. If any potentially significant historic, cultural or archaeological resources are found during the field investigation, the certificate holder shall instruct all construction personnel to avoid the identified sites and shall implement appropriate measures to protect the sites, including the measures described in Condition 47.
- The certificate holder shall ensure that a qualified archaeologist, as defined in OAR 736-051-0070, instructs construction personnel in the identification of cultural materials and avoidance of accidental damage to identified resource sites.
- 24 The certificate holder shall ensure that construction personnel cease all ground-disturbing 25 activities in the immediate area if any archaeological or cultural resources are found 26 during construction of the facility until a qualified archaeologist can evaluate the 27 significance of the find. The certificate holder shall notify the Department and the Oregon 28 State Historic Preservation Office (SHPO) of the find. If the SHPO determines that the 29 resource is significant, the certificate holder shall make recommendations to the Council 30 for mitigation, including avoidance, field documentation and data recovery, in consultation with the Department, SHPO, interested Tribes and other appropriate parties. 31 32 The certificate holder shall not restart work in the affected area until the certificate holder 33 has demonstrated to the Department and the SHPO that it has complied with 34 archaeological resource protection regulations

4. Geotechnical Conditions

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

1617

18

19

20

Before beginning construction, the certificate holder shall conduct a site-specific geotechnical investigation and shall report its findings to the Oregon Department of Geology & Mineral Industries (DOGAMI) and the Department. The certificate holder shall conduct the geotechnical investigation after consultation with DOGAMI and in general accordance with DOGAMI open file report 00-04 "Guidelines for Engineering Geologic Reports and Site-Specific Seismic Hazard Reports."

- The certificate holder shall design and construct the facility in accordance with requirements of the Oregon Structural Specialty Code (OSSC 2007) and the 2006 International Building Code.
- The certificate holder shall design, engineer and construct the facility to avoid dangers to human safety presented by non-seismic hazards. As used in this condition, "non-seismic hazards" include settlement, landslides, flooding and erosion.

5. Hazardous Materials, Fire Protection & Public Safety Conditions

- The certificate holder shall handle hazardous materials used on the site in a manner that protects public health, safety and the environment and shall comply with all applicable local, state and federal environmental laws and regulations. The certificate holder shall not store diesel fuel or gasoline on the facility site.
- If a spill or release of hazardous material occurs during construction or operation of the facility, the certificate holder shall notify the Department within 72 hours and shall clean up the spill or release and dispose of any contaminated soil or other materials according to applicable regulations. The certificate holder shall make sure that spill kits containing items such as absorbent pads are located on equipment and at the O&M buildings. The certificate holder shall instruct employees about proper handling, storage and cleanup of hazardous materials
- The certificate holder shall construct turbines and pad-mounted transformers on concrete foundations and shall cover the ground within a 10-foot radius with non-flammable material. The certificate holder shall maintain the non-flammable pad area covering during operation of the facility.
- The certificate holder shall install and maintain self-monitoring devices on each turbine, linked to sensors at the operations and maintenance building, to alert operators to potentially dangerous conditions, and the certificate holder shall immediately remedy any dangerous conditions. The certificate holder shall maintain automatic equipment protection features in each turbine that would shut down the turbine and reduce the chance of a mechanical problem causing a fire.
- During construction and operation of the facility, the certificate holder shall ensure that the O&M buildings and all service vehicles are equipped with shovels and portable fire extinguishers of a 4A5OBC or equivalent rating.
- 31 During construction and operation of the facility, the certificate holder shall develop and implement fire safety plans in consultation with the North Gilliam County Rural Fire 32 33 Protection District to minimize the risk of fire and to respond appropriately to any fires 34 that occur on the facility site. In developing the fire safety plans, the certificate holder 35 shall take into account the dry nature of the region and shall address risks on a seasonal 36 basis. The certificate holder shall meet annually with local fire protection agency 37 personnel to discuss emergency planning and shall invite local fire protection agency 38 personnel to observe any emergency drill or tower rescue training conducted at the 39 facility.

- 1 Upon the beginning of operation of the facility, the certificate holder shall provide a site 61 2 plan to the North Gilliam County Rural Fire Protection District. The certificate holder shall 3 indicate on the site plan the identification number assigned to each turbine and the actual 4 location of all facility structures. The certificate holder shall provide an updated site plan if 5 additional turbines or other structures are later added to the facility. During operation, the 6 certificate holder shall ensure that appropriate fire protection agency personnel have an 7 up-to-date list of the names and telephone numbers of facility personnel available to 8 respond on a 24-hour basis in case of an emergency on the facility site.
- During construction, the certificate holder shall ensure that construction personnel are trained in fire prevention and response, that construction vehicles and equipment are operated on graveled areas to the extent possible and that open flames, such as cutting torches, are kept away from dry grass areas.
- During operation of the facility, the certificate holder shall ensure that all on-site employees receive annual fire prevention and response training by qualified instructors or members of the local fire districts. The certificate holder shall ensure that all employees are instructed to keep vehicles on roads and off dry grassland, except when off-road operation is required for emergency purposes.
- Before beginning construction, the certificate holder shall submit a Notice of Proposed
 Construction or Alteration to the Federal Aviation Administration (FAA) and the Oregon
 Department of Aviation identifying the proposed final locations of turbine towers and
 meteorological towers. The certificate holder shall promptly notify the Department of the
 responses from the FAA and the Oregon Department of Aviation.
- The certificate holder shall follow manufacturers' recommended handling instructions and procedures to prevent damage to turbine or turbine tower components that could lead to failure.
- The certificate holder shall construct turbine towers with no exterior ladders or access to the turbine blades and shall install locked tower access doors. The certificate holder shall keep tower access doors locked at all times, except when authorized personnel are present.
- During operation of the facility, the certificate holder shall have a safety-monitoring program and shall inspect all turbine and turbine tower components on a regular basis.

 The certificate holder shall maintain or repair turbine and turbine tower components as necessary to protect public safety.
- For turbine types having pad-mounted step-up transformers, the certificate holder shall install the transformers at the base of each tower in locked cabinets designed to protect the public from electrical hazards and to avoid creation of artificial habitat for raptor prey.
- To protect the public from electrical hazards, the certificate holder shall enclose the facility substations with appropriate fencing and locked gates.
- 39 <u>70</u> Before beginning construction of any new State Highway approaches or utility crossings, 40 the certificate holder shall obtain all required permits from the Oregon Department of

- Transportation (ODOT) subject to the applicable conditions required by OAR Chapter 734,
 Divisions 51 and 55. The certificate holder shall submit the necessary application in a form satisfactory to ODOT and the Department for the location, construction and maintenance of a new approach to State Highway 19 for access to the site south of Tree Lane. The certificate holder shall submit the necessary application in a form satisfactory to ODOT and the Department for the location, construction and maintenance of transmission lines crossing Highway 19.
- 8 The certificate holder shall design and construct new access roads and private road 9 improvements to standards approved by the Gilliam County Road Department or, where 10 applicable, the Morrow County Public Works Department. Where modifications of County 11 roads are necessary, the certificate holder shall construct the modifications entirely within 12 the County road rights-of-way and in conformance with County road design standards subject to the approval of the Gilliam County Road Department or, where applicable, the 13 14 Morrow County Public Works Department. Where modifications of State roads or 15 highways are necessary, the certificate holder shall construct the modifications entirely within the public road rights-of-way and in conformance with Oregon Department of 16 17 Transportation (ODOT) standards subject to the approval of ODOT.
- The certificate holder shall construct access roads with a finished width of up to 20 feet, designed under the direction of a licensed engineer and compacted to meet equipment load requirements.
- During construction of the facility, the certificate holder shall implement measures to reduce traffic impacts, including:
 - (a) Providing notice to adjacent landowners when heavy construction traffic is anticipated.
 - (b) Providing appropriate traffic safety signage and warnings.
 - (c) Requiring flaggers to be at appropriate locations at appropriate times during construction to direct traffic.
 - (d) Using traffic diversion equipment (such as advance signage and pilot cars) when slow or oversize construction loads are anticipated.
 - (e) Maintaining at least one travel lane at all times to the extent reasonably possible so that roads will not be closed to traffic because of construction vehicles.
 - (f) Encouraging carpooling for the construction workforce.
 - (g) Including traffic control procedures in contract specifications for construction of the facility.
 - (h) Keeping Highway 19 free of gravel that tracks out onto the highway at facility access points.
 - The certificate holder shall ensure that no equipment or machinery is parked or stored on any County road whether inside or outside the site boundary. The certificate holder may temporarily park equipment off the road but within County rights-of-way with the approval of the Gilliam County Road Department or, where applicable, the Morrow County Public Works Department.

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

- 1 The certificate holder shall cooperate with the Gilliam County Road Department and with 75 2 the Morrow County Public Works Department to ensure that any unusual damage or wear 3 to county roads that is caused by construction of the facility is repaired by the certificate 4 holder. Upon completion of construction, the certificate holder shall restore public roads 5 to pre-construction condition or better to the satisfaction of the applicable county 6 departments. If required by Morrow County or Gilliam County, the certificate holder shall 7 post bonds to ensure funds are available to repair and maintain roads affected by the 8 proposed facility.
- During construction, the certificate holder shall require that all on-site construction contractors develop and implement a site health and safety plan that informs workers and others on-site about first aid techniques and what to do in case of an emergency and that includes important telephone numbers and the locations of on-site fire extinguishers and nearby hospitals. The certificate holder shall ensure that construction contractors have personnel on-site who are trained and equipped for tower rescue and who are first aid and CPR certified.
- During operation of the facility, the certificate holder shall develop and implement a site health and safety plan that informs employees and others on-site about first aid techniques and what to do in case of an emergency and that includes important telephone numbers and the locations of on-site fire extinguishers and nearby hospitals. The certificate holder shall ensure that operations personnel are trained and equipped for tower rescue.
- During construction and operation of the facility, the certificate holder shall provide for on-site security and shall establish good communications between on-site security personnel and the Gilliam County Sheriff's Office. During operation, the certificate holder shall ensure that appropriate law enforcement agency personnel have an up-to-date list of the names and telephone numbers of facility personnel available to respond on a 24-hour basis in case of an emergency on the facility site.
- The certificate holder shall notify the Department of Energy and the Gilliam County
 Planning Department within 72 hours of any accidents including mechanical failures on the
 site associated with construction or operation of the facility that may result in public
 health and safety concerns

6. Water, Soils, Streams & Wetlands Conditions

- The certificate holder shall conduct all construction work in compliance with an Erosion and Sediment Control Plan (ESCP) satisfactory to the Oregon Department of Environmental Quality and as required under the National Pollutant Discharge Elimination System (NPDES) Storm Water Discharge General Permit #1200-C. The certificate holder shall include in the ESCP any procedures necessary to meet local erosion and sediment control requirements or storm water management requirements.
- During construction, the certificate holder shall limit truck traffic to improved road surfaces to avoid soil compaction, to the extent practicable.

- <u>82</u> During construction, the certificate holder shall implement best management practices to control any dust generated by construction activities, such as applying water to roads and disturbed soil areas.
- 4 Before beginning construction, the certificate holder shall provide to the Department a 5 map showing the final design locations of all components of the facility and the areas that 6 would be disturbed during construction and showing the wetlands and stream channels 7 previously surveyed by CH2M HILL as described in the Final Order on the Application. For 8 areas to be disturbed during construction that lie outside of the previously-surveyed 9 areas, the certificate holder shall hire qualified personnel to conduct a pre-construction 10 investigation to determine whether any jurisdictional waters of the State exist in those 11 locations. The certificate holder shall provide a written report on the pre-construction 12 investigation to the Department and the Department of State Lands for approval before beginning construction. The certificate holder shall ensure that construction and operation 13 14 of the facility will have no impact on any jurisdictional water identified in the pre-15 construction investigation.
- 16 84 The certificate holder shall avoid impacts to waters of the state in the following manner:
 - (a) The certificate holder shall avoid any disturbance to delineated wetlands.
 - (b) The certificate holder shall construct stream crossings for roads and underground collector lines substantially as described in the *Final Order on the Application*. In particular, the certificate holder shall not remove material from waters of the State or add new fill material to waters of the State such that the total volume of removal and fill exceeds 50 cubic yards for the project as a whole.
 - (c) The certificate holder shall construct support poles for aboveground lines outside of delineated stream channels and shall avoid in-channel impacts.
- During facility operation, the certificate holder shall routinely inspect and maintain all roads, pads and trenched areas and, as necessary, maintain or repair erosion and sediment control measures.
- During facility operation, the certificate holder shall obtain water for on-site uses from on-site wells located near the O&M buildings. The certificate holder shall construct on-site wells subject to compliance with the provisions of ORS 537.765 relating to keeping a well log. The certificate holder shall not use more than 5,000 gallons of water per day from the on-site wells. The certificate holder may use other sources of water for on-site uses subject to prior approval by the Department.
- During facility operation, if blade-washing becomes necessary, the certificate holder shall ensure that there is no runoff of wash water from the site or discharges to surface waters, storm sewers or dry wells. The certificate holder shall not use acids, bases or metal brighteners with the wash water. The certificate holder may use biodegradable, phosphate-free cleaners sparingly.

7. Transmission Line & EMF Conditions

1

2

3

17

18

19

20

21

22

23

24

39

40

88 The certificate holder shall install the 34.5-kV collector system underground to the extent practical. The certificate holder shall install underground lines at a minimum depth of

- three feet. Based on geotechnical conditions or other engineering considerations, the certificate holder may install segments of the collector system aboveground, but the total length of aboveground segments must not exceed 27 miles.
 - 89 The certificate holder shall take reasonable steps to reduce or manage human exposure to electromagnetic fields, including but not limited to:
 - (a) Constructing all aboveground transmission lines at least 200 feet from any residence or other occupied structure, measured from the centerline of the transmission line.
 - (b) Providing to landowners a map of underground and overhead transmission lines on their property and advising landowners of possible health risks from electric and magnetic fields
 - (c) Designing and maintaining all transmission lines so that alternating current electric fields do not exceed 9 kV per meter at one meter above the ground surface in areas accessible to the public.
 - (d) Designing and maintaining all transmission lines so that induced voltages during operation are as low as reasonably achievable.
- In advance of, and during, preparation of detailed design drawings and specifications for 230-kV and 34.5-kV transmission lines, the certificate holder shall consult with the Utility Safety and Reliability Section of the Oregon Public Utility Commission to ensure that the designs and specifications are consistent with applicable codes and standards.

8. Plants, Wildlife & Habitat Protection Conditions

- The certificate holder shall conduct wildlife monitoring as described in the Wildlife
 Monitoring and Mitigation Plan that is incorporated in the *Final Order on the Application*as Attachment A and as amended from time to time.
- The certificate holder shall restore areas disturbed by facility construction but not occupied by permanent facility structures according to the methods and monitoring procedures described in the Revegetation Plan that is incorporated in the *Final Order on the Application* as Attachment B and as amended from time to time.
 - The certificate holder shall acquire the legal right to create, enhance, maintain and protect a habitat mitigation area as long as the site certificate is in effect by means of an outright purchase, conservation easement or similar conveyance and shall provide a copy of the documentation to the Department. Within the habitat mitigation area, the certificate holder shall improve the habitat quality as described in the Habitat Mitigation Plan that is incorporated in the *Final Order on Application* as Attachment C and as amended from time to time.
 - 94 The certificate holder shall determine the boundaries of Category 1 Washington ground squirrel (WGS) habitat based on the locations where the squirrels were found to be active in the most recent WGS survey prior to the beginning of construction in habitat suitable for WGS foraging or burrow establishment ("suitable habitat"). The certificate holder shall hire a qualified professional biologist who has experience in detection of WGS to conduct surveys using a survey protocol approved by the Oregon Department of Fish and Wildlife

(ODFW). The biologist shall survey all areas of suitable habitat where permanent facility components would be located or where construction disturbance could occur. Except as provided in (a), the biologist shall conduct the protocol surveys in the active squirrel season (March 1 to May 31) in 2010 and in the active squirrel seasons in subsequent years until the beginning of construction in suitable habitat. The certificate holder shall provide written reports of the surveys to the Department and to ODFW and shall identify the boundaries of Category 1 WGS habitat. The certificate holder shall not begin construction within suitable habitat until the identified boundaries of Category 1 WGS habitat have been approved by the Department. Category 1 WGS habitat includes the areas described in (b) and (c).

- (a) The certificate holder may omit the WGS survey in any year if the certificate holder avoids all permanent and temporary disturbance within suitable habitat until a WGS survey has been completed in the following year and the boundaries of Category 1 habitat have been determined and approved based on that survey.
- (b) Category 1 WGS habitat includes the area within the perimeter of multiple active WGS burrows plus a 785-foot buffer, excluding areas of habitat types not suitable for WGS foraging or burrow establishment. If the multiple-burrow area was active in a prior survey year, then Category 1 habitat includes the largest extent of the active burrow area ever recorded (in the current or any prior-year survey), plus a 785-foot buffer.
- (c) Category 1 WGS habitat includes the area containing single active burrow detections plus a 785-foot buffer, excluding areas of habitat types not suitable for WGS foraging or burrow establishment. Category 1 habitat does not include singleburrow areas that were found active in a prior survey year but that are not active in the current survey year.
- <u>95</u> The certificate holder shall implement measures to mitigate impacts to sensitive wildlife habitat during construction including, but not limited to, the following:
 - (a) The certificate holder shall not construct any facility components within areas of Category 1 habitat and shall avoid temporary disturbance of Category 1 habitat.
 - (b) Before beginning construction, but no more than two years prior to the beginning of construction, the certificate holder shall hire a qualified professional biologist to conduct a survey of all areas to be disturbed by construction for threatened and endangered species. The certificate holder shall provide a written report of the survey and a copy of the survey to the Department, the Oregon Department of Fish and Wildlife (ODFW), and the Oregon Department of Agriculture (ODA). If the surveys identify the presence of threatened or endangered species within the survey area, the certificate holder shall implement appropriate measures to avoid a significant reduction in the likelihood of survival or recovery of the species, as approved by the Department, in consultation with ODA and ODFW.
 - (c) Before beginning construction, the certificate holder's qualified professional biologist shall survey the Category 1 Washington ground squirrel habitat to ensure that the sensitive use area is correctly marked with exclusion flagging and avoided

- during construction. The certificate holder shall maintain the exclusion markings until construction has been completed.
 - (d) Before beginning construction, certificate holder's qualified professional biologist shall complete the avian use studies that began in September 2009 at six plots within or near the facility site as described in the *Final Order on the Application*. The certificate holder shall provide a written report on the avian use studies to the Department and to ODFW.
 - (e) Before beginning construction, certificate holder's qualified professional biologist shall complete raptor nest surveys within the raptor nest survey area as described in the Final Order on the Application. The purposes of the survey are to identify any sensitive raptor nests near construction areas and to provide baseline information on raptor nest use for analysis as described in the Wildlife Monitoring and Mitigation Plan referenced in Condition 91. The certificate holder shall provide a written report on the raptor nest surveys and the surveys to the Department and to ODFW. If the surveys identify the presence of raptor nests within the survey area, the certificate holder shall implement appropriate measures to assure that the design, construction and operation of the facility are consistent with the fish and wildlife habitat mitigation goals and standards of OAR 635-415-0025, as approved by the Department, in consultation with ODFW.
 - (f) In the final design layout of the facility, the certificate holder shall locate facility components, access roads and construction areas to avoid or minimize temporary and permanent impacts to high quality native habitat and to retain habitat cover in the general landscape where practicable.
- 96 During construction, the certificate holder shall avoid all construction activities within a 1,300-foot buffer around potentially-active nest sites of the following species during the sensitive period, as provided in this condition:

27	<u>Species</u>	Sensitive Period	Early Release Date
28	Swainson's hawk	April 1 to August 15	May 31
29	Ferruginous hawk	March 15 to August 15	May 31
30	Burrowing owl	April 1 to August 15	July 15

During the year in which construction occurs, the certificate holder shall use a protocol approved by the Oregon Department of Fish and Wildlife (ODFW) to determine whether there are any active nests of these species within a half-mile of any areas that would be disturbed during construction. The certificate holder shall begin monitoring potential nest sites by March 15 and shall continue monitoring until at least May 31 to determine whether any potentially-active nest sites become active during the sensitive period.

If any nest site is determined to be unoccupied by the early release date (May 31), then unrestricted construction activities may occur within 1,300 feet of the nest site after that date. If a nest is occupied by any of these species after the beginning of the sensitive period, the certificate holder will flag the boundaries of a 1,300-foot buffer area around

the nest site and shall instruct construction personnel to avoid disturbance of the buffer area. During the sensitive period, the certificate holder shall not engage in high-impact construction activities (activities that involve blasting, grading or other major ground disturbance) within the buffer area. The certificate holder shall restrict construction traffic within the buffer, except on public roads, to vehicles essential to the limited construction activities allowed within the buffer.

If burrowing owl nests are occupied during the sensitive period, the certificate holder may adjust the 1,300-foot buffer around these nests after consultation with ODFW and subject to the approval of the Department.

The certificate holder shall hire a qualified independent professional biologist to observe the active nest sites during the sensitive period for signs of disturbance and to notify the Department of any non-compliance with this condition. If the biologist observes nest site abandonment or other adverse impact to nesting activity, the certificate holder shall implement appropriate mitigation, in consultation with ODFW and subject to the approval of the Department, unless the adverse impact is clearly shown to have a cause other than construction activity.

The certificate holder may begin or resume construction activities within the buffer area before the ending day of the sensitive period with the approval of ODFW, after the young are fledged. The certificate holder shall use a protocol approved by ODFW to determine when the young are fledged (the young are independent of the core nest site).

- The certificate holder shall protect the area within 1,300 feet of the BLM Horn Butte Wildlife Area during the long-billed curlew nesting season (March 8 through June 15), as described in this condition. Before beginning construction, the certificate holder shall provide to the Department a map showing the areas of potential construction disturbance in the vicinity of the BLM lands that are part of the Horn Butte Wildlife Area and showing a 1,300-foot buffer from those areas. During the nesting season, the certificate holder shall not engage in high-impact construction activities (activities that involve blasting, grading or other major ground disturbance) or allow high levels of construction traffic within the buffer area. The certificate holder shall flag the boundaries of the 1,300-foot buffer area and shall instruct construction personnel to avoid any unnecessary activity within the buffer area. The certificate holder shall restrict construction traffic within the buffer, except on public roads, to vehicles essential to the limited construction activities allowed within the buffer. The certificate holder may engage in construction activities within the buffer area at times other than the nesting season.
- <u>98</u> The certificate holder shall implement measures to avoid or mitigate impacts to sensitive wildlife habitat during construction including, but not limited to, the following:
 - (a) Preparing maps to show occlusion areas that are off-limits to construction personnel, such as nesting or denning areas for sensitive wildlife species.
 - (b) Avoiding unnecessary road construction, temporary disturbance and vehicle use.
 - (c) Limiting construction work to approved and surveyed areas shown on facility constraints maps.

1 (d) Ensuring that all construction personnel are instructed to avoid driving cross-2 country or taking short-cuts within the site boundary or otherwise disturbing areas 3 outside of the approved and surveyed construction areas. 4 The certificate holder shall reduce the risk of injuries to avian species by: 5 (a) Installing turbine towers that are smooth steel structures that lack features that 6 would allow avian perching. 7 (b) Locating turbine towers to avoid areas of increased risk to avian species, such as 8 cliff edges, narrow ridge saddles and gaps between hilltops. 9 (c) Installing meteorological towers that are non-guyed structures to eliminate the risk 10 of avian collision with guy-wires. 11 (d) Designing and installing all aboveground transmission line support structures 12 following the most current suggested practices for avian protection on power lines published by the Avian Power Line Interaction Committee. 13 14 100 The certificate holder shall hire a qualified environmental professional to provide 15 environmental training during construction and operation. Environmental training includes 16 information on the sensitive species present onsite, precautions to avoid injuring or 17 destroying wildlife or sensitive wildlife habitat, exclusion areas, permit requirements and 18 other environmental issues. The certificate holder shall instruct construction and 19 operations personnel to report any injured or dead wildlife detected while on the site to 20 the appropriate onsite environmental manager. 21 101 The certificate holder shall impose and enforce a construction and operation speed limit of 22 20 miles per hour throughout the facility site and, during the active squirrel season (March 23 1 to May 31), a speed limit of 10 miles per hour from one hour before sunset to one hour 24 after sunrise on private roads near known Washington ground squirrel (WGS) colonies. 25 The certificate holder shall ensure that all construction and operations personnel are 26 instructed to watch out for and avoid WGS and other wildlife while driving through the 27 facility site. 9. Visual Effects Conditions 28 102 To reduce the visual impact of the facility, the certificate holder shall: 29 (a) Mount nacelles on smooth, steel structures, painted uniformly in a low-reflectivity, 30 neutral white color. 31 (b) Paint the substation structures in a low-reflectivity neutral color to blend with the 32 surrounding landscape. 33 (c) Not allow any advertising to be used on any part of the facility. 34 (d) Use only those signs required for facility safety, required by law or otherwise 35 required by this site certificate, except that the certificate holder may erect a sign 36 near the O&M buildings to identify the facility, may paint turbine numbers on each 37 tower and may allow unobtrusive manufacturers' logos on turbine nacelles.

(e) Maintain any signs allowed under this condition in good repair.

103 The certificate holder shall design and construct the O&M buildings to be generally

consistent with the character of similar buildings used by commercial farmers or ranchers

38

39

1 in the area and shall paint the building in a low-reflectivity, neutral color to blend with the 2 surrounding landscape. 3 104 The certificate holder shall not use exterior nighttime lighting except: 4 (a) The minimum turbine tower lighting required or recommended by the Federal 5 Aviation Administration. 6 (b) Security lighting at the O&M buildings and at the substations, provided that such 7 lighting is shielded or downward-directed to reduce glare. 8 (c) Minimum lighting necessary for repairs or emergencies. 9 (d) Minimum lighting necessary for construction directed to illuminate the work area 10 and shielded or downward-directed to reduce glare. 11 105 The certificate holder shall maintain a minimum distance of 1,000 feet measured from the 12 centerline of each turbine tower or meteorological tower to the centerline of the line-of-13 sight from the vantage point of the Fourmile Canyon interpretive site looking toward the 14 visible Oregon Trail ruts (bearing S 89-42-34 W from latitude, longitude: 15 45.622047, -120.044112) as described in the Final Order on the Application. 10. Noise Control Conditions 106 To reduce construction noise impacts at nearby residences, the certificate holder shall: 16 17 (a) Confine the noisiest operation of heavy construction equipment to the daylight 18 hours. 19 (b) Require contractors to install and maintain exhaust mufflers on all combustion 20 engine-powered equipment; and 21 (c) Establish a complaint response system at the construction manager's office to 22 address noise complaints. 23 107 Before beginning construction, the certificate holder shall provide to the Department: 24 (a) Information that identifies the final design locations of all turbines to be built at the 25 facility. 26 (b) The maximum sound power level for the substation transformers and the maximum 27 sound power level and octave band data for the turbines selected for the facility 28 based on manufacturers' warranties or confirmed by other means acceptable to 29 the Department. 30 (c) The results of noise analysis of the facility to be built according to the final design 31 performed in a manner consistent with the requirements of OAR 32 340-035-0035(1)(b)(B)(iii) (IV) and (VI) demonstrating to the satisfaction of the 33 Department that the total noise generated by the facility (including the noise from 34 turbines and substation transformers) would meet the ambient degradation test 35 and maximum allowable test at the appropriate measurement point for all 36 potentially-affected noise sensitive properties. 37 (d) For each noise-sensitive property where the certificate holder relies on a noise 38 waiver to demonstrate compliance in accordance with OAR 340-035-39 0035(1)(b)(iii)(III), a copy of the a legally effective easement or real covenant 40 pursuant to which the owner of the property authorizes the certificate holder's

operation of the facility to increase ambient statistical noise levels L₁₀ and L₅₀ by

- more than 10 dBA at the appropriate measurement point. The legally-effective easement or real covenant must: include a legal description of the burdened property (the noise sensitive property); be recorded in the real property records of the county; expressly benefit the certificate holder; expressly run with the land and bind all future owners, lessees or holders of any interest in the burdened property; and not be subject to revocation without the certificate holder's written approval.
- During operation of the facility, the certificate holder shall maintain a complaint response system to address noise complaints. The certificate holder shall promptly notify the Department of any complaints received regarding facility noise and of any actions taken by the certificate holder to address those complaints. In response to a complaint from the owner of a noise sensitive property regarding noise levels during operation of the facility, the Council may require the certificate holder to monitor and record the statistical noise levels to verify that the certificate holder is operating the facility in compliance with the noise control regulations

11. Waste Management Conditions

- 109 The certificate holder shall provide portable toilets for on-site sewage handling during construction and shall ensure that they are pumped and cleaned regularly by a licensed contractor who is qualified to pump and clean portable toilet facilities.
- During operation of the facility, the certificate holder shall discharge sanitary wastewater generated at the O&M buildings to licensed on-site septic systems in compliance with State permit requirements. The certificate holder shall design the septic systems for a discharge capacity of less than 2,500 gallons per day.
- 22 <u>111</u> The certificate holder shall implement a waste management plan during construction that includes but is not limited to the following measures:
 - (a) Recycling steel and other metal scrap.
 - (b) Recycling wood waste.
 - (c) Recycling packaging wastes such as paper and cardboard.
 - (d) Collecting non-recyclable waste for transport to a local landfill by a licensed waste hauler.
 - (e) Segregating all hazardous wastes such as used oil, oily rags and oil-absorbent materials, mercury-containing lights and lead-acid and nickel-cadmium batteries for disposal by a licensed firm specializing in the proper recycling or disposal of hazardous wastes.
 - (f) Confining concrete delivery truck rinse-out within the foundation excavation, discharging rinse water into foundation holes and burying other concrete waste as part of backfilling the turbine foundation.
- The certificate holder shall implement a waste management plan during facility operation that includes but is not limited to the following measures:
 - (a) Training employees to minimize and recycle solid waste.
 - (b) Recycling paper products, metals, glass and plastics.
 - (c) Recycling used oil and hydraulic fluid

- 1 (d) Collecting non-recyclable waste for transport to a local landfill by a licensed waste 2 hauler.
- (e) Segregating all hazardous, non-recyclable wastes such as used oil, oily rags and oil absorbent materials, mercury-containing lights and lead-acid and nickel-cadmium
 batteries for disposal by a licensed firm specializing in the proper recycling or
 disposal of hazardous wastes.

VI. CONDITIONS ADDED BY AMENDMENT # 1 OF MONTAGUE

- 8 113 The transfer of the First Amended Site Certificate from the certificate holder to Portland
- 9 General Electric (PGE), the transferee, shall not be effective until PGE executes in closing the
- 10 form of site certificate naming PGE the certificate holder, which is attached as Attachment B to
- 11 the Final Order on Amendment #1. Upon closing, the First Amended Site Certificate naming
- 12 PGE as the certificate holder shall be in full force and effect and the First Amended Site
- 13 Certificate naming Montague Wind Power LLC as the certificate holder shall be considered
- 14 rescinded and void in its entirety. Removed by Amendment #2.
- 15 <u>114</u> Should the closing contemplated in Condition 113 not occur within 18 months of the
- 16 effective date of the First Amended Site Certificate to Montague Wind Power LLC, the Council's
- 17 transfer approval within the Final Order on Amendment #1 shall be void. Removed by
- 18 Amendment #2.

7

- 19 115 PGE must provide the Department a copy of the executed First Amended Site Certificate
- 20 and documentation of the asset purchase agreement within 7 days of closing. Removed by
- 21 Amendment #2.

VII. SUCCESSORS AND ASSIGNS

- 22 To transfer this site certificate or any portion thereof or to assign or dispose of it in any other
- 23 manner, directly or indirectly, the certificate holder shall comply with OAR 345-027-0100.

VIII. SEVERABILITY AND CONSTRUCTION

- 24 If any provision of this agreement and certificate is declared by a court to be illegal or in conflict
- 25 with any law, the validity of the remaining terms and conditions shall not be affected, and the
- 26 rights and obligations of the parties shall be construed and enforced as if the agreement and
- 27 certificate did not contain the particular provision held to be invalid.

IX. GOVERNING LAW AND FORUM

- 28 This site certificate shall be governed by the laws of the State of Oregon. Any litigation or
- arbitration arising out of this agreement shall be conducted in an appropriate forum in Oregon.

X. EXECUTION

- 30 This site certificate may be executed in counterparts and will become effective upon signature
- 31 by the Chair of the Energy Facility Siting Council and the authorized representative of the
- 32 certificate holder.

- 1 **IN WITNESS WHEREOF**, this site certificate has been executed by the State of Oregon, acting by
- 2 and through its Energy Facility Siting Council, and by Montague Wind Power Facility, LLC.

ENERGY FACILITY SITING COUNCIL

MONTAGUE WIND POWER FACILITY, LLC

GA GA

Barry Beyeler, Chair

Oregon Energy Facility Siting Council

rint: Kany t

Date: December 4, 2015

and

Ву:

Scott Jacobson
Authorized Representative

Print:

Date: 12-7-2015