









- GENERAL NOTES FOR ALL DETAILS ON THIS SHEET:
1. See appropriate guardrail standard drawing(s) for details not shown.
 2. See Bridge Dwgs. for bridge transition guardrail post and block requirements.
 3. Lowest hole(s) required only when channel rail is to be installed. Drill 12" below top 3/4" or 13/16" hole(s) used.
 4. Dimensions shown are for nominal posts and blocks.
 5. Wood blocks shown. Blocks of an approved alternate material may be used. See ODOT's QPL.
 6. When required by the plans, nested thrie beam wood post shall be 8"x8".
 7. Wood block shall be toe-nail to the post with 2 - 16d galvanized nails in top of block to prevent block rotation.

GUARDRAIL WOOD POST TABLE				
	GUARDRAIL TYPE	POST SIZE	POST LENGTH	POST SPACING
W-BEAM	2A	6"x8" or 8"x8"	6'-0"	6'-3"
	3	8"x8"	6'-0"	3'-1 1/2"
	Metal median barrier	8"x8"	6' 6"	6'-3"
THRIE BEAM	4	6"x8" or 8"x8"	7'-0"	6'-3"
	4 (Transition)	8"x8"	6'-0"	3'-1 1/2"



The selection and use of this Standard Drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user and should not be used without first consulting a Registered Professional Engineer.

All materials shall be in accordance with the current Oregon Standard Specifications.			
OREGON STANDARD DRAWINGS			
MIDWEST GUARDRAIL SYSTEM WOOD POST AND BLOCK			
2024			
DATE	REVISION	DESCRIPTION	
07-2021	REVISED DETAILS AND NOTES		
CALC. BOOK NO.	N/A	SDR DATE	19-JUL-2021
			RD403