

OR 140: Antelope Creek – Odegaard Road

Last updated: June 15, 2016

Project Components

- Realign 2 miles of OR 140 in the Antelope Canyon area from MP 83 to 85
- Widen the roadway to 36 feet with two 12-foot travel lanes and six foot shoulders
- Install guardrails and upgrade signs as needed



Project Location

This project is located in Lake County approximately 12 miles west of Lakeview, OR

Need for the Project

OR 140 is an important part of the State's transportation system and is an east-west freight corridor. The route sees an average of 1000 vehicles per day with a truck percentage of approximately 20-30 percent. Keeping the roads in good condition and providing a safe, efficient transportation system that supports economic opportunity is a critical aspect of the mission for the Oregon Department of Transportation (ODOT).

This section of highway borders a stream and is located in a steep canyon with sharp curves. The roadway has 12-foot travel lanes with very narrow shoulders.

Work to be done

The highway will be widened away from the stream and curves will be straightened. The roadway will have 12 ft. travel lanes with six ft. shoulders. Guardrails will be installed for steep slopes. Current signs will also be upgraded as necessary to meet current standards.

Traffic control during construction

During construction traffic will be restricted to one lane and controlled by flaggers and a pilot car. Motorists should plan for delays up to 20 minutes.

Timeline

Project Development – 2015-2016

Bid Opening – Early 2017

Construction – 2017

Estimated Project Cost

Approximately \$5 Million

This project is being funded with Jobs and Transportation Act (JTA) dollars.

Contacts

Name	Title	Office Phone	Email
Jason Armstrong	Project Leader	541-883-5789	Jason.L.Armstrong@odot.state.or.us
Jarod Johnson	Area Manager	541-883-5778	Jarod.E.Johnson@odot.state.or.us
Abbey Driscoll	Community Liaison	541-388-6064	Abbey.Driscoll@odot.state.or.us

