

Runway Reconstruction and Electrical Improvements Project





- Constructed in 1963
- Used for recreation, commerce, and wildfire operations
- Connects local community to the National Air Transportation System
- Prospect State Airport does <u>not</u> receive any Federal funds
- Runway pavement at end of life after being maintained for nearly 60 years

Prospect State Airport

- Wildfire Stage and Operations
 - Heavily used for wildfire staging and response
- Airport serves as a vital alternate landing site for inflight emergencies where landing options are limited due to the area's mountainous terrain



Prospect State Airport







Runway Closure

 Runway 2-20 closed for 49 days due to significant pavement hazards:

- Cracks that could cause loss of directional control for aircraft
- Numerous sinkholes from failed subbase and previous patches











- Runway partially reopened
 - Closed to aircraft over 4,000 pounds
 - Runway 2 threshold displaced 225 feet, landing and takeoff distances now 3,775 feet





Current Conditions

Non-functioning airfield lighting system






Project Scope

- Reconstruct runway to full length (4,000 feet)
- Reconstruct connecting taxiways
- Runway Safety Area grading

- Replace storm drain culvert
- Useful life will exceed 20 years (40 years expected)




Project Scope

- Replacement of rotating beacon
- Install new electrical conduit and cable for wind sock
- Install runway reflectors

 Construct new electrical building with restroom and pilot lounge

DRAIN CULVERT UNDER RUNWAY

Useful life will exceed 20 years



Cost Estimate

- Grant Request: \$1,693,200.00
- Applicant Match: \$796,800.00
 - 32%
- Total Estimate: \$2,490,000.00
 - With \$193,300.00 Contingency

Bid Item	Unit	Quantity Unit Price		it Price	Total Price	
Mobilization	LS	1	\$	199,000.00	\$	199,000.00
Construction Survey and Staking	LS	1	\$	42,000.00	\$	42,000.00
Temporary Erosion and Sediment Control	LS	1	\$	25,000.00	\$	25,000.00
Demolition	LS	1	\$	20,000.00	\$	20,000.00
General Excavation Incl. Haul	CY	6600	\$	14.00	\$	92,400.00
Unsuitable Excavation Incl. Haul	CY	3500	\$	20.00	\$	70,000.00
Backfill for Unsuitable Excavation	CY	3500	\$	35.00	\$	122,500.00
12" Asphalt Milling, In Place	SY	26300	\$	3.00	\$	78,900.00
Subgrade Geotextile	SY	26300	\$	2.00	\$	52,600.00
Shoulder Aggregate	CY	2400	\$	40.00	\$	96,000.00
Aggregate Base	CY	6100	\$	50.00	\$	305,000.00
HMA 1/2" class 2	TON	4700	\$	95.00	\$	446,500.00
Pavement Marking	SF	5400	\$	2.00	\$	10,800.00
Miscellaneous Stormwater Improvements	LS	1	\$	24,000.00	\$	24,000.00
Airport Beacon Tower and Foundation	LS	1	\$	40,000.00	\$	40,000.00
Airport Rotating Beacon, In Place	LS	1	\$	12,000.00	\$	12,000.00
Lighted Windcone and Foundation, In Place	LS	1	\$	15,000.00	\$	15,000.00
20ft x 20ft, 3-room, Pre-Cast Structure and Site Improvements	LS	1	\$	125,000.00	\$	125,000.00
Electrical Building Improvements	LS	1	\$	20,000.00	\$	20,000.00
Retroreflective Markers	EA	60	\$	250.00	\$	15,000.00
2-inch PVC Conduit & Wire	LF	3200	\$	25.00	\$	80,000.00
Junction Can	EA	5	\$	1,000.00	\$	5,000.00
TOTAL CONSTRUCTION ESTIMATE					\$	1,896,700.00
	Aprx.	10%	10% Contingency:		\$	193,300.00
			Subtotal:		\$	2,090,000.00
			Env/Permits:		\$	15,000.00
			Engineering:		\$	195,000.00
			SDC:		\$	190,000.00
			Total Estimate:		\$	2,490,000.00

Project Timeline

- 16 month total project time
- Once awarded the grant:
 - Planning and scoping begin Sept. 2022
 - Environmental Coordination and Permitting – begin Sept. 2022
 - Project Design begin May 2022
 - Advertise for Bids by February 2023
 - Construction Award by April 2023
 - Project Construction April through June 2023
 - Project Closeout July through December 2023.





- Representative Vikki Breese Iverson
- John Rachor, former Jackson County Commissioner and Search and Rescue Pilot
- Brim Aviation, helicopter operator specializing in firefighting, emergency relief, power line construction and maintenance, and more.

