

2022 ODA Pavement Evaluation Program La Grande Airport

La Grande, Oregon

May 8, 2023

Prepared for

State of Oregon Department of Aviation
3040 25th Street SE
Salem, OR 97303-1125

Prepared by



16520 SW Upper Boones Ferry Road, Suite 100
Tigard, OR 97224-7661
(503) 641-3478 | www.gri.com

TABLE OF CONTENTS

| | | |
|----------|---|----------|
| 1 | OVERVIEW..... | 1 |
| 2 | PAVEMENT INVENTORY | 1 |
| 3 | PAVEMENT CONDITION INSPECTION RESULTS..... | 4 |
| | 3.1 Introduction..... | 4 |
| | 3.2 Pavement Condition Index Survey Results | 4 |
| 4 | FUTURE PAVEMENT CONDITION ANALYSIS..... | 5 |
| | 4.1 Introduction..... | 5 |
| | 4.2 Future Condition Analysis | 5 |
| | 4.3 Functional Remaining Life..... | 6 |
| 5 | MAINTENANCE AND REHABILITATION PROJECT RECOMMENDATIONS | 7 |
| | 5.1 Introduction..... | 7 |
| | 5.2 Recommended Localized Maintenance..... | 7 |
| | 5.3 Global Maintenance and Rehabilitation Plan | 8 |
| 6 | LIMITATIONS..... | 9 |

TABLES

| | |
|------------|--|
| Table 3-1: | ASTM PCI Rating Scale |
| Table 5-1: | Localized Maintenance Quantities |
| Table 5-2: | Global Maintenance and Rehabilitation Quantities |

FIGURES

| | |
|-------------|---|
| Figure 2.1: | La Grande Airport Location Map |
| Figure 2.2: | La Grande Airport Pavement Area by Surface Type |
| Figure 2.3: | La Grande Airport Pavement Area by Branch Use |
| Figure 2.4: | La Grande Airport Pavement Inventory |
| Figure 3.1: | 2022 PCI Survey Results La Grande Airport |
| Figure 3.2: | La Grande Airport Pavement Condition Rating by Percent of Area |
| Figure 4.1: | Future Pavement Condition La Grande Airport |
| Figure 5.1: | La Grande Airport Pavement Network General Treatment Type Distribution Based on PCI |
| Figure 5.2: | 5-Year Pavement Management Plan La Grande Airport |

APPENDICES

| | |
|-------------|--|
| Appendix A: | Pavement Inventory Report and Maps |
| Appendix B: | Pavement Condition Index Survey Results |
| Appendix C: | Future Pavement Condition Analysis |
| Appendix D: | Unit Cost Data and Maintenance and Rehabilitation Plan |
| Appendix E: | Reinspection Report |

APPENDICES (continued)

Appendix F: Work History Report

1 OVERVIEW

GRI assisted with updating the Oregon Department of Aviation (ODA) airport pavement management system and developing a five-year plan for global maintenance and rehabilitation (M&R) and preservation work for the La Grande Airport in La Grande, Oregon. This project was implemented as a part of the ODA and Federal Aviation Administration (FAA) *Oregon Continuous Aviation System Plan*. The information provided in this report ensures compliance with FAA Grant Assurance Number 11, which outlines that an airport shall have an effective airport pavement maintenance-management program in place to receive federal financial assistance for the construction, reconstruction, or repair of airport pavements.

GRI conducted surveys of the airside pavement at La Grande Airport in 2022 in accordance with the procedures of Advisory Circular 150/5380-7B and ASTM International (ASTM) D5340. We uploaded the survey data into the PAVER database and used the software to provide a rapid calculation of the pavement condition index (PCI) rating. The PCI is a numerical indicator that defines the functional condition of the pavement based on visual inspection. The scale ranges from zero to 100, where zero represents a pavement in the worst possible condition with no remaining functional life and 100 represents a pavement in the best possible condition with no defects.

2 PAVEMENT INVENTORY

La Grande Airport is located in La Grande, Oregon, and is owned and operated by Union County. The airport consists of two runways that serve a variety of general aviation aircraft as well as military aircraft. The general location of the airport is shown below on La Grande Airport Location Map, Figure 2.1.



Figure 2.1 - LA GRANDE AIRPORT LOCATION MAP

La Grande Airport contains two runways, four primary taxiways, and multiple connector taxiways, taxilanes, aprons, and helipads. The types of airside pavements include asphalt concrete (AC), AC overlaid with AC (AAC), and portland cement concrete (PCC). The airport pavements, delineated by surface type and branch use, are shown on the La Grande Airport Percent of Pavement Area by Surface Type, Figure 2.2 and on the La Grande Airport Pavement Area by Branch Use, Figure 2.3. The pavement inventory, including work history for each pavement section, is displayed spatially on the La Grande Airport Pavement Inventory, Figure 2.4. The pavement facilities summarized by branch and section are listed in Tables 1A and 2A, respectively, in Appendix A. The sample unit layout for each section is shown on Figure 1A in Appendix A. We used the sampling rates outlined in Table 3A of Appendix A in our survey. The pavement inventory, including work history for individual airport pavement sections, is provided in the work history report, Table 1F.




Figure 2.2 - LA GRANDE AIRPORT PERCENT OF PAVEMENT AREA BY SURFACE TYPE






Figure 2.3 - LA GRANDE AIRPORT PAVEMENT AREA BY BRANCH USE



ABBREVIATIONS: AC = ASPHALT CONCRETE; Cr. = CRUSHED; Agg. = AGGREGATE



3 PAVEMENT CONDITION INSPECTION RESULTS

3.1 Introduction

GRI conducted a visual PCI survey of the airside pavements at La Grande Airport in July 2022. The 2022 survey work was performed on sections last inspected in 2017 in order to update the La Grande Airport inspection data. GRI performed the 2022 PCI survey in accordance with the methods described in FAA Advisory Circular 150/5380-6C and ASTM D5340 and further discussed in Appendix B of this report.


The PCI is based on the type, severity, and quantity of each distress found in an inspected sample unit. Further discussion of distress types for flexible and rigid pavement is provided in Appendix B and summarized in Table 1B in Appendix B. The results of the PCI survey are displayed using a seven-category rating scale in accordance with ASTM D5340. Details of the ASTM PCI rating scale are provided in Table 3-1 below.

Table 3-1: ASTM PCI RATING SCALE


| PCI Color Legend | PCI Range | PCI Rating and Definition |
|------------------|-----------|---|
| | 86 – 100 | GOOD: Pavement has minor or no distresses and should require only routine maintenance. |
| | 71 – 85 | SATISFACTORY: Pavement has scattered low-severity distresses that should require only routine maintenance. |
| | 56 – 70 | FAIR: Pavement has a combination of generally low- and medium-severity distresses. Maintenance and repair needs may range from routine to major. |
| | 41 – 55 | POOR: Pavement has low-, medium-, and high-severity distresses that probably cause some operational problems. M&R needs will be major. |
| | 26 – 40 | VERY POOR: Pavement has predominantly medium- and high-severity distresses that cause considerable maintenance and operational problems. M&R needs will be major. |
| | 11 – 25 | SERIOUS: Pavement has mainly high-severity distresses that may affect operational safety; immediate repairs are needed. |
| | 0 – 10 | FAILED: Pavement deterioration has progressed to the point that safe aircraft operations are no longer possible; complete reconstruction is required. |

3.2 Pavement Condition Index Survey Results

The area-weighted average PCI for all airport pavements at La Grande Airport is approximately 81. The section PCIs ranged from a low of 1 to a high of 100. The primary distresses observed during the inspection were weathering, longitudinal and transverse cracking, fatigue (alligator) cracking, bleeding, depression, and patching on AC-surfaced pavements, and patching on PCC pavements. Section PCIs following our pavement survey are displayed below spatially on the 2022 PCI Survey Results La Grande Airport, Figure 3.1.



- 2022 SECTION PCI**
- (86 - 100) GOOD
 - (71 - 85) SATISFACTORY
 - (56 - 70) FAIR
 - (41 - 55) POOR
 - (26 - 40) VERY POOR
 - (11 - 25) SERIOUS
 - (0 - 10) FAILED



The condition distribution of the network by percent of total pavement area is provided on the La Grande Airport Pavement Condition Rating by Percent of Area, Figure 3.2. A summary of the pavement condition results by branch and section are included in Tables 2B and 3B of Appendix B, respectively. A comparison between the previous inspection and the 2022 inspection is provided in Table 4B in Appendix B. The re-inspection report that includes inspection details for individual sample units is provided in Table 1E in Appendix E.




Figure 3.2 - LA GRANDE AIRPORT PAVEMENT CONDITION RATING BY PERCENT OF AREA

4 FUTURE PAVEMENT CONDITION ANALYSIS

4.1 Introduction

In addition to assessing the current condition of a pavement, it is very important from a planning standpoint to be able to predict with reasonable accuracy the future condition. Additional details regarding our future pavement condition analysis, including pavement condition prediction models, are provided in Appendix C. PCI performance curves developed for La Grande Airport are displayed on Figures 1C through 4C in Appendix C.

4.2 Future Condition Analysis

Using the condition prediction models discussed above, the projected condition of each pavement section was determined for 5- and 10-year periods. Based on this analysis, we project the PCI to decrease from a current value of 81 to a value of 74 in 2027 and 67 in

2032 if no maintenance or rehabilitation work is performed. The projected pavement condition in 5 years and 10 years for each pavement section at La Grande Airport is displayed spatially on the Future Pavement Condition La Grande Airport, Figure 4.1, and listed in Table 1C in Appendix C, along with the past and present PCI values for the pavement network.


4.3 Functional Remaining Life

The functional remaining life is the practical amount of time a pavement is in service before requiring rehabilitation, as estimated solely based on visual condition. This is not to be confused with structural remaining life, which requires analysis of the structural capacity of a pavement and typically a field exploration and testing program that includes core explorations and falling weight deflectometer (FWD) deflection tests.


We calculated two forms of functional remaining life based on the current visual condition surveys of the pavement at La Grande Airport. The first type of functional remaining life is the time until rehabilitation, such as an overlay, is needed. The critical PCI, further discussed in Section C.3 of Appendix C, is the threshold used for this type of functional remaining life analysis. The second type of functional remaining life is the time until the pavement is no longer operational due to high foreign object debris (FOD) potential and increased safety concerns for trafficking aircraft. A PCI of 40 was set as the trigger point for the end of the pavement's functional service life with regard to FOD potential.

The two types of functional remaining life for each section at La Grande Airport are summarized in Table 2C in Appendix C.

PREDICTED CONDITION IN 2027




PREDICTED CONDITION IN 2032



SECTION PCI

- (86 - 100) GOOD
- (71 - 85) SATISFACTORY
- (56 - 70) FAIR
- (41 - 55) POOR
- (26 - 40) VERY POOR
- (11 - 25) SERIOUS
- (0 - 10) FAILED



GRI OREGON DEPARTMENT OF AVIATION
STATEWIDE PAVEMENT EVALUATION PROGRAM

FUTURE PAVEMENT CONDITION
LA GRANDE AIRPORT

5 MAINTENANCE AND REHABILITATION PROJECT RECOMMENDATIONS

5.1 Introduction

We evaluated M&R needs, as determined from the PAVER analysis results, in order to develop localized maintenance, global maintenance, and rehabilitation needs. Details of our M&R work priority and unit costs for work activities are provided in Tables 1D and 2D, respectively, in Appendix D.

Based on the 2022 PCI-survey results shown on the La Grande Airport Pavement Network General Treatment Type Distribution Based on PCI, Figure 5.1 displays a breakdown of the La Grande Airport network pavement condition by percent of area and general M&R treatment categories. Approximately 85%, 12%, and 3% of the area require preservation treatments, rehabilitation, and reconstruction, respectively.




Figure 5.1 - LA GRANDE AIRPORT PAVEMENT NETWORK GENERAL TREATMENT TYPE DISTRIBUTION BASED ON PCI

5.2 Recommended Localized Maintenance

Localized maintenance refers to activities such as crack sealing and patching, which should be performed annually in order to properly maintain aging pavements. Using the PAVER Localized Distress Maintenance Analysis tool, we developed a list of recommended localized maintenance. This list is shown in Table 3D in Appendix D and is independent of the global maintenance and rehabilitation projects associated with the five-year global

maintenance and rehabilitation work plan. A summary of total localized maintenance quantities is provided in Table 5-1 below.

Table 5-1: LOCALIZED MAINTENANCE QUANTITIES


| Localized Maintenance Operation | Quantity |
|--------------------------------------|--------------------|
| Asphalt Concrete Crack Sealing | 63,576 linear feet |
| Asphalt Concrete Full-Depth Patching | 27,363 linear feet |

5.3 Global Maintenance and Rehabilitation Plan


To develop the five-year work plan, we first ran the eliminate backlog scenario with the PAVER M&R Work Planning Module in order to generate a list, organized by year, of global and M&R projects. We then reviewed the project list and refined it into practical construction projects for each year. A summary of global and M&R quantities is provided in Table 5-2 below, and maps of the project locations by year are shown on the 5-Year Pavement Management Plan La Grande Airport, Figure 5.2. The complete list of recommended global and M&R projects is presented in Table 4D in Appendix D.

Table 5-2: GLOBAL MAINTENANCE AND REHABILITATION QUANTITIES



| Global Maintenance or Rehabilitation Operation | Quantity, square feet |
|--|-----------------------|
| Reconstruction | 61,970 |
| Overlay | 96,612 |
| Fog Seal | 158,278 |
| Slurry Seal | 1,123,095 |



ACTION TIMING



ACTION



6 LIMITATIONS

This report has been prepared to assist the Oregon Department of Aviation (ODA) with pavement-related project planning for the La Grande Airport. The scope is limited to the specific pavement areas described within this report. The conclusions and recommendations provided in this report are based on information provided by ODA, estimated costs, and an understanding of the pavement conditions based solely on visual assessment. The global maintenance and rehabilitation recommendations and project selections provided in this report, as well as their corresponding cost estimates, are based on a practical grouping of projects and an estimate of the structural requirements. It is possible that recommendations based on a structural evaluation would differ materially from the recommendations given within this report. Therefore, the information included in this report should be used solely for project planning purposes, and it should be understood that rehabilitation costs may vary from the cost estimates given within this report.

Because the condition of the airport pavement network is dynamic, an effective maintenance and rehabilitation program should be reviewed and updated on a regular basis. In addition to regularly surveying and updating the pavement condition, completed construction activities should be tracked in the PAVER database. If La Grande Airport would like to know more about the results presented in this report, please contact the undersigned.

Submitted for GRI,



RENEWS: 06/2023

Lindsy A. Hammond, PE
Principal

Matthew A. Haynes, PE
Project Engineer

Ana-Maria Coca, PhD
Engineering Staff

This document has been submitted electronically.

APPENDIX A

Pavement Inventory Reports and Maps

APPENDIX A

PAVEMENT INVENTORY REPORTS AND MAPS

A.1 PAVEMENT NETWORK

La Grande Airport is located in La Grande, Oregon, and is owned and operated by Union County. The pavement network/facilities at La Grande Airport serve a variety of general aviation aircraft and military aircraft. La Grande Airport consists of two runways, three primary taxiways, multiple connector taxiways, taxilanes, and several aprons and helipads. The types of airside pavements include asphalt concrete (AC), AC overlaid with AC (AAC), and portland cement concrete (PCC).

The current airport pavement management system (APMS) network at La Grande Airport has an approximate area of 1.97 million square feet of paved airside facilities. The pavement network has previously been divided (by others) into a hierarchical order of branches, sections, and sample units that facilitate inspection and maintenance planning. The pavement facilities summarized by branch and section are listed in Tables 1A and 2A, respectively. Pavement sections and the sample unit layout for each section are shown on Figure 1A in this appendix.

A.2 BRANCHES

A branch, as defined in the PAVER system, is a facility that is a readily identifiable part of the pavement system and has a distinct function. For airports, branches typically consist of individual runways, taxiways, and aprons. The current pavement network for La Grande Airport contains 14 branches, tabulated in Table 1A and shown on Figure 1A.

A.3 SECTIONS AND SAMPLE UNITS

A pavement section is the smallest management unit used when considering the application and selection of maintenance and rehabilitation (M&R) repairs and treatments and is defined by Section 2.1.8 of ASTM International (ASTM) D5340 as “*a contiguous pavement area having uniform construction, maintenance, usage history, and condition.*” All sections should also have the same traffic volume and load intensity. The current pavement network included in the PAVER database for La Grande Airport contains 49 sections that are managed by Union County, which are tabulated in Table 2A and shown spatially on Figure 1A.

PAVER assigns a rank, which designates that pavement’s prioritization in receiving maintenance and repair. The highest use or priority pavements, such as runways, taxiways, and terminal aprons, are ranked *Primary*, while the surrounding aprons and shoulders are

ranked *Secondary* and low-use areas are ranked *Tertiary*. The ranks for all sections are shown on Table 2A.

To facilitate the visual survey of the airport pavement, each section is further subdivided into smaller areas called sample units. Similar sizing of these units is critical, and studies have found that maintaining the size of the sample units to within 40% of the established normal distribution reduces the standard error of the average pavement condition index (PCI) values. To meet this criterion, the ASTM method recommends sample units for flexible pavements be $5,000 \pm 2,000$ square feet and $20 \text{ slabs} \pm 8 \text{ slabs}$ for rigid pavements. The delineation of sample units for each section is displayed on Figure 1A.

A.4 SAMPLE UNIT DELINEATION

For an APMS survey, a PCI confidence level of 92% and an allowable error (e) of eight PCI points are used for all airport pavements. To determine the number of sample units that need to be inspected to achieve the required confidence level and allowable error, the following equation is used:

$$n = \frac{N \times s^2}{\left(\frac{e^2}{4}\right)(N-1) + s^2} \quad (\text{Equation 1})$$

where:

- n = number of sample units to be inspected
- N = total number of samples in the pavement sections
- e = allowable error
- s = section standard deviation

For the 2022 La Grande Airport PCI survey, Table 3A was used as a guideline in developing sampling rates for flexible and rigid pavement that reflect similar rates used for other large airport pavement networks. In general, this sampling rate distribution provides a 92% confidence level with a standard error of eight PCI points.

Sample unit locations at La Grande Airport were selected using a systematic random sampling model method. This technique is implemented by first determining the number of sample units needed based on the confidence interval calculated using Equation 1. The first sample unit is randomly placed in the section and then the remaining sample units are systematically spaced throughout the section at an equal distance apart.

Table 1A – LA GRANDE AIRPORT PAVEMENT BRANCHES

| Facility Designation (Branch ID) | Branch Name | Number of Sections | Approximate Area, square feet |
|-------------------------------------|-------------|--------------------|----------------------------------|
| A01LG | LaGrande | 15 | 354,632 |
| AHELILG | LaGrande | 4 | 2,496 |
| AHTALG | LaGrande | 1 | 17,175 |
| AHTCLG | LaGrande | 1 | 29,900 |
| R12LG | LaGrande | 3 | 625,921 |
| R16LG | LaGrande | 7 | 226,415 |
| TA1LG | LaGrande | 1 | 23,227 |
| TA2LG | LaGrande | 1 | 11,300 |
| TALG | LaGrande | 4 | 200,559 |
| TBLG | LaGrande | 3 | 93,318 |
| TC1LG | LaGrande | 2 | 14,223 |
| TC2LG | LaGrande | 2 | 38,359 |
| TCLG | LaGrande | 5 | 241,832 |
| TDLG | LaGrande | 5 | 121,895 |

Table 2A - LA GRANDE AIRPORT CURRENT PAVEMENT INVENTORY

| BranchID | Branch Name | Branch Use | SectionID | From | To | Rank | Length, feet | Width, feet | Approximate Area, square feet | LCD | Surface Type |
|----------|-------------------------------|------------|-----------|----------------------|--------------|------|--------------|-------------|-------------------------------|-----------|--------------|
| A01LG | Apron 01 LaGrande | APRON | 01 | TA-02 | A01-02 | S | 1,088 | 12 | 11,524 | 9/1/2009 | AAC |
| A01LG | Apron 01 LaGrande | APRON | 02 | A01-01 | A01-03 | S | 280 | 45 | 12,600 | 9/1/2009 | AAC |
| A01LG | Apron 01 LaGrande | APRON | 03 | A01-02 | HANGARS | S | 280 | 236 | 48,880 | 9/2/1949 | AC |
| A01LG | Apron 01 LaGrande | APRON | 04 | A01-03 | A01-05 | S | 93 | 80 | 7,440 | 9/2/1949 | AC |
| A01LG | Apron 01 LaGrande | APRON | 05 | A01-04 | A01-08 | S | 245 | 80 | 19,600 | 9/1/1980 | AAC |
| A01LG | Apron 01 LaGrande | APRON | 06 | A01-08 | A01-01 | S | 113 | 40 | 4,529 | 9/2/2009 | AAC |
| A01LG | Apron 01 LaGrande | APRON | 07 | A01-08 | A01-01 | P | 513 | 24 | 12,089 | 9/1/2009 | AAC |
| A01LG | Apron 01 LaGrande | APRON | 08 | A01-05 | A01-10 | P | 400 | 193 | 77,012 | 9/1/1980 | AAC |
| A01LG | Apron 01 LaGrande | APRON | 09 | A01-10 | TA-02 | P | 538 | 34 | 17,817 | 9/1/2009 | AAC |
| A01LG | Apron 01 LaGrande | APRON | 10 | A01-08 | A01-11 | P | 255 | 215 | 54,850 | 9/2/1980 | AC |
| A01LG | Apron 01 LaGrande | APRON | 11 | A01-10 | - | P | 145 | 215 | 30,587 | 9/2/1980 | AC |
| A01LG | Apron 01 LaGrande | APRON | 12 | A01LG-11 | A01LG-15 | P | 370 | 95 | 36,243 | 9/3/2019 | AC |
| A01LG | Apron 01 LaGrande | APRON | 13 | A01LG-11 | A01LG-12 | P | 185 | 30 | 7,040 | 9/4/2019 | AC |
| A01LG | Apron 01 LaGrande | APRON | 14 | A01LG-12 | TALG-03 | P | 115 | 20 | 4,336 | 9/4/2019 | AC |
| A01LG | Apron 01 LaGrande | APRON | 15 | A01LG-12 | TALG-03 | P | 155 | 40 | 10,085 | 9/4/2019 | AC |
| AHELILG | Apron Helipad | HELIPAD | 01 | A01LG-13 | A01LG-13 | P | 20 | 20 | 400 | 9/4/2019 | PCC |
| AHELILG | Apron Helipad | HELIPAD | 02 | A01LG-13 | A01LG-13 | P | 20 | 20 | 400 | 9/4/2019 | PCC |
| AHELILG | Apron Helipad | HELIPAD | 03 | A01LG-14 | A01LG-14 | P | 20 | 20 | 400 | 9/4/2019 | PCC |
| AHELILG | Apron Helipad | HELIPAD | 04 | A01LG-15 | A01LG-15 | P | 36 | 36 | 1,296 | 9/4/2019 | PCC |
| AHTALG | Taxiway A Hold Apron LaGrande | APRON | 01 | Taxiway A | End | P | 170 | 100 | 17,175 | 1/1/2021 | AC |
| AHTCLG | Taxiway C Hold Apron LaGrande | APRON | 01 | Taxiway C at R30 End | End | P | 130 | 230 | 29,900 | 10/4/2012 | AC |
| R12LG | Runway 12/30 LaGrande | RUNWAY | 01 | R12 End | R12LG-2 | P | 4,576 | 100 | 457,600 | 6/1/2014 | AAC |
| R12LG | Runway 12/30 LaGrande | RUNWAY | 02 | R12LG-1 | R30 End | P | 1,024 | 100 | 102,400 | 6/1/2014 | AAC |
| R12LG | Runway 12/30 LaGrande | RUNWAY | 03 | Section 03 | 30 End | P | 659 | 100 | 65,921 | 6/1/2014 | AAC |
| R16LG | Runway 16/34 LaGrande | RUNWAY | 01 | R16-04 | R16-06 | P | 454 | 60 | 27,198 | 1/1/2021 | AAC |
| R16LG | Runway 16/34 LaGrande | RUNWAY | 02 | R16-05 | R16-07 | P | 150 | 60 | 9,000 | 1/1/2021 | AC |
| R16LG | Runway 16/34 LaGrande | RUNWAY | 03 | R16-06 | R34 END | P | 2,800 | 60 | 168,713 | 1/1/2021 | AAC |
| TA1LG | Taxiway A1 | TAXIWAY | 01 | Taxiway A | Runway 17/35 | P | 300 | 75 | 23,227 | 1/1/2021 | AC |
| TA2LG | Taxiway A2 | TAXIWAY | 01 | Taxiway A | Runway 17/35 | P | 175 | 50 | 11,300 | 1/1/2021 | AC |
| TALG | Taxiway A LaGrande | TAXIWAY | 01 | R12 End | TALG-02 | P | 75 | 70 | 5,786 | 6/1/2014 | AAC |
| TALG | Taxiway A LaGrande | TAXIWAY | 02 | TALG-01 | TALG-03 | P | 310 | 50 | 15,500 | 8/3/2008 | AC |
| TALG | Taxiway A LaGrande | TAXIWAY | 03 | TALG-02 | TDLG-04 | P | 2,711 | 50 | 118,555 | 9/1/1974 | AAC |
| TALG | Taxiway A LaGrande | TAXIWAY | 04 | TDLG - 05 | TA2LG - 01 | P | 1,260 | 45 | 60,718 | 1/1/2021 | AC |
| TBLG | Taxiway B LaGrande | TAXIWAY | 01 | R16LG-05 | TBLG-02 | P | 215 | 50 | 19,835 | 6/1/2014 | AAC |
| TBLG | Taxiway B LaGrande | TAXIWAY | 02 | R16LG-05 | R12LG-1 | P | 944 | 50 | 48,734 | 9/3/1993 | AC |
| TBLG | Taxiway B LaGrande | TAXIWAY | 03 | R16LG-05 | T01LG-2 | P | 305 | 54 | 24,749 | 1/2/2021 | AC |
| TC1LG | Taxiway C1 LaGrande | TAXIWAY | 01 | T05LG-1 | R12LG-1 | P | 150 | 50 | 8,573 | 6/1/2014 | AAC |
| TC1LG | Taxiway C1 LaGrande | TAXIWAY | 02 | TC1LG-01 | TCLG-03 | P | 113 | 50 | 5,650 | 9/2/1984 | AC |
| TC2LG | Taxiway C2 LaGrande | TAXIWAY | 01 | RW 30 End | TCLG-02 | P | 125 | 70 | 13,561 | 6/1/2014 | AAC |
| TC2LG | Taxiway C2 LaGrande | TAXIWAY | 02 | TCLG-01 | Taxiway C | P | 200 | 70 | 24,798 | 10/4/2012 | AC |
| TCLG | Taxiway C LaGrande | TAXIWAY | 01 | TBBL-01 | TDLG-01 | P | 2,204 | 50 | 122,032 | 9/3/1991 | AC |
| TCLG | Taxiway C LaGrande | TAXIWAY | 02 | TDLG-01 | TC1LG-01 | P | 566 | 50 | 30,453 | 9/3/1991 | AC |
| TCLG | Taxiway C LaGrande | TAXIWAY | 03 | TC1LG | Intersection | P | 113 | 50 | 10,662 | 9/1/2012 | AAC |
| TCLG | Taxiway C LaGrande | TAXIWAY | 04 | TC1LG-01 | Section 05 | P | 927 | 50 | 44,975 | 9/3/1991 | AC |
| TCLG | Taxiway C LaGrande | TAXIWAY | 05 | Section 04 | Taxiway C2 | P | 680 | 50 | 33,710 | 10/4/2012 | AC |

Table 2A - LA GRANDE AIRPORT CURRENT PAVEMENT INVENTORY

| BranchID | Branch Name | Branch Use | SectionID | From | To | Rank | Length, feet | Width, feet | Approximate Area, square feet | LCD | Surface Type |
|----------|--------------------|------------|-----------|---------|---------|------|--------------|-------------|-------------------------------------|----------|--------------|
| TDLG | Taxiway D LaGrande | TAXIWAY | 01 | TDLG-01 | TDLG-03 | P | 2,165 | 40 | 93,045 | 1/1/2021 | AAC |
| TDLG | Taxiway D LaGrande | TAXIWAY | 02 | TDLG-02 | R16LG | P | 94 | 40 | 4,844 | 1/1/2021 | AAC |
| TDLG | Taxiway D LaGrande | TAXIWAY | 03 | R16LG | TDLG-05 | P | 30 | 40 | 2,746 | 1/1/2021 | AAC |
| TDLG | Taxiway D LaGrande | TAXIWAY | 04 | TDLG-04 | TALG-04 | P | 263 | 40 | 15,923 | 1/1/2021 | AAC |

Abbreviations:

P = Primary pavement, S = Secondary pavement

LCD = Last Construction Date. The date of the last major rehabilitation (e.g. overlay)



AC = Asphalt Concrete, AAC = AC overlaid AC, PCC = Portland Cement Concrete

Table 3A: EXAMPLE SAMPLE RATES FOR AC AND PCC PAVEMENTS

| AC Sampling Rate | | PCC Sampling Rate | |
|---------------------------------|---------------------------|---------------------------------|---------------------------|
| Total Number of Sample Units, N | Sample Units to Survey, n | Total Number of Sample Units, N | Sample Units to Survey, n |
| 1 | 1 | 1 | 1 |
| 2-3 | 2 | 2 | 2 |
| 4-6 | 3 | 3-4 | 3 |
| 7-13 | 4 | 5-6 | 4 |
| 14-38 | 5 | 7-8 | 5 |
| 39+ | 6 | 9-11 | 6 |
| | | 12-14 | 7 |
| | | 15-19 | 8 |
| | | 20-27 | 9 |
| | | 28-38 | 10 |
| | | 39-58 | 11 |
| | | 59-104 | 12 |
| | | 105-313 | 13 |
| | | 314+ | 14 |

Note: AC = Asphalt Concrete

PCC = Portland Cement Concrete



SAMPLE UNIT LAYOUT
LA GRANDE AIRPORT

APPENDIX B

Pavement Condition Index Survey Results

APPENDIX B

PAVEMENT CONDITION INDEX SURVEY RESULTS

B.1 METHODOLOGY

As previously discussed, the PCI is a measure of the pavement's functional surface condition and provides a methodology for assessing the causes of distress and whether the distress is related to a load or climatic conditions. Although the PCI is not a direct measure of structural capacity, it provides a suggestion of the structural needs of the pavement.

The PCI is based on the type, severity, and quantity of each distress found in an inspected sample unit. The results are displayed using a seven-category rating scale in accordance with ASTM D5340. Flexible pavement (e.g., AC and AAC) and rigid pavement (e.g., PCC) distress types are presented in Table 1B. A summary of the pavement condition results by branch and section are included in Tables 2B and 3B of Appendix B, respectively.

Table 1B: PAVER DISTRESS CODES FOR FLEXIBLE AND RIGID PAVEMENT

| Flexible Pavement | | | Rigid Pavement | | |
|-------------------|---------------------------------------|------------------------|----------------|--|------------------------|
| PAVER Code | Pavement Distress | Related Cause | PAVER Code | Pavement Distress | Related Cause |
| 41 | Alligator Cracking | Load | 61 | Blow-Up | Load |
| 42 | Bleeding | Other | 62 | Corner Break | Load |
| 43 | Block Cracking | Climate/ Durability | 63 | Longitudinal, Transverse, & Diagonal Cracks | Climate/ Durability |
| 44 | Corrugation | Other | 64 | Durability Cracking | Climate/ Durability |
| 45 | Depression | Other | 65 | Joint Seal Damage | Other |
| 46 | Jet Blast | Other | 66 | Small Patch | Other |
| 47 | Joint Reflection Cracking | Climate/ Durability | 67 | Large Patch | Other |
| 48 | Longitudinal & Transverse Cracking | Climate/ Durability | 68 | Pop Outs | Other |
| 49 | Oil Spillage | Other | 69 | Pumping | Other |
| 50 | Patching | Climate/ Durability | 70 | Scaling | Other |
| 51 | Polished Aggregate | Other | 71 | Faulting | Other |
| 52 | Raveling | Climate/ Durability | 72 | Shattered Slab | Load |

| Flexible Pavement | | |
|-------------------|-------------------|------------------------|
| PAVER Code | Pavement Distress | Related Cause |
| 53 | Rutting | Load |
| 54 | Shoving | Other |
| 55 | Slippage Cracking | Other |
| 56 | Swelling | Other |
| 57 | Weathering | Climate/ Durability |

| Rigid Pavement | | |
|----------------|--------------------------------|---------------|
| PAVER Code | Pavement Distress | Related Cause |
| 73 | Shrinkage Cracking | Other |
| 74 | Joint Spalls | Other |
| 75 | Corner Spalls | Other |
| 76 | Alkali-Silica Reactivity (ASR) | Other |

To obtain the section PCI, we extrapolated the PCI of each selected sample unit over the entire section area. Distresses found in sample units classified as “additional”– defined as nonrepresentative instead of random- are not extrapolated over the entire section but merely added to the extrapolated quantity. The PCI rating scale presented previously in Table 3-1 of Section 3.1 and is based on ASTM D5340.

Section 4.1 of ASTM D5340 governing PCI surveys offers this caution:

“The PCI is a numerical indicator that rates the surface condition of the pavement. The PCI provides a measure of the **present condition** of the pavement based on the distress observed on the surface of the pavement, which also indicates the structural integrity and surface operational condition (localized roughness and safety). The PCI **cannot** measure structural capacity; nor does it provide a direct measurement of skid resistance or roughness. It provides an objective and rational basis for determining maintenance and repair needs and priorities. Continuous monitoring of the PCI is used to establish the rate of pavement deterioration, which permits early identification of major rehabilitation needs. The PCI provides feedback on pavement performance for validation or improvement of current pavement design and maintenance procedures.”

Based on the limitations of the PCI method, it is imperative that engineers and planners treat the PCI as a tool that will assist them during the M&R planning process. Any major project should always be preceded by an up-to-date, detailed, 100% project-level inspection of the pavement in order to reevaluate maintenance needs prior to the project design process.

B.2 DISTRESS TYPES

Distress tends to fall into one of the following four cause categories:

- **Load-related:** Flexible pavement distresses include alligator/fatigue cracking, corrugation, depression, polished aggregate, rutting, and slippage cracking. Rigid

pavement distresses include corner breaks, longitudinal cracking, divided slabs, polished aggregate, pumping, and joint spalling.

- **Climate- and durability-related:** Flexible pavement distresses include bleeding, block cracking, joint reflection cracking, longitudinal and transverse (L&T) cracking, swelling, and raveling/weathering. Rigid pavement distresses include blow-ups, durability cracking, longitudinal cracking, pop-outs, pumping, scaling, shrinkage cracks, and joint and corner spalling.
- **Moisture- and drainage-related:** Flexible pavement distresses include alligator/fatigue cracking, depressions, potholes, and swelling. Rigid pavement distresses include corner breaks, divided slabs, and pumping.
- **Other factors:** Oil spillage, jet blast erosion, bleeding, patching, and concrete slab joint faulting.

As described above, a distress may be the result of more than one cause. For example, depressions may be caused by incorrect compaction during construction or by subgrade softening due to environmental factors. In addition, distress may be initiated by one cause but may progress to a distress of higher severity by another cause. Therefore, engineering judgment is critical in analyzing the actual cause or causes of the distress.

B.3 PAVEMENT CONDITION INDEX SURVEY RESULTS

The evaluated La Grande Airport pavement network consists of 14 branches and 49 sections. A total of 145 sample units were visually inspected in the field. Data from the inspected sample units were input into the PAVER database, and a resultant PCI for each section was computed. Additional details regarding the PCI and distress types observed for each surveyed sample unit are provided in the re-inspection report, Table 1E, in Appendix E. Based on the 2022 PCI survey, the area-weighted average PCI for the entire pavement network at La Grande Airport is approximately 81, which corresponds to a PCI rating of Satisfactory.

To investigate the rate of deterioration of each pavement section, we compared the PCI results from the 2022 survey to the PCI results from the previous inspection. The variation in PCI between inspections for La Grande Airport pavement sections is outlined in Table 4B in this appendix.

Table 2B - LA GRANDE CITY AIRPORT CURRENT BRANCH CONDITION REPORT

| Branch ID | Number of Sections | Approximate Area, square feet | Use | Area Weighted Average Branch PCI | PCI Category |
|-----------|--------------------|-------------------------------|---------|----------------------------------|--------------|
| A01LG | 15 | 354,632 | APRON | 58 | Fair |
| AHELILG | 4 | 2,496 | HELIPAD | 100 | Good |
| AHTALG | 1 | 17,175 | APRON | 100 | Good |
| AHTCLG | 1 | 29,900 | APRON | 81 | Satisfactory |
| R12LG | 3 | 625,921 | RUNWAY | 81 | Satisfactory |
| R16LG | 3 | 204,911 | RUNWAY | 100 | Good |
| TA1LG | 1 | 23,227 | TAXIWAY | 100 | Good |
| TA2LG | 1 | 11,300 | TAXIWAY | 100 | Good |
| TALG | 4 | 200,559 | TAXIWAY | 80 | Satisfactory |
| TBLG | 3 | 93,318 | TAXIWAY | 81 | Satisfactory |
| TC1LG | 2 | 14,223 | TAXIWAY | 69 | Fair |
| TC2LG | 2 | 38,359 | TAXIWAY | 75 | Satisfactory |
| TCLG | 5 | 241,832 | TAXIWAY | 87 | Good |
| TDLG | 4 | 116,558 | TAXIWAY | 100 | Good |

| Use Category | Number of Sections | Total Area, square feet | Area Weighted Average PCI |
|--------------|--------------------|-------------------------|---------------------------|
| APRON | 21 | 404,203 | 62 |
| RUNWAY | 6 | 830,832 | 85 |
| TAXIWAY | 22 | 739,376 | 86 |
| ALL | 49 | 1,974,411 | 81 |

Abbreviation: PCI = Pavement Condition Index

Table 3B - LA GRANDE AIRPORT 2022 PAVEMENT CONDITION INDEX SURVEY RESULTS

| BranchID | SectionID | Last Construction Date | Surface Type | Use | Last Inspection Date | Age at Inspection | PCI | PCI Category | PCI % Climate | PCI % Load | PCI % Other |
|----------|-----------|------------------------|--------------|---------|----------------------|-------------------|-----|--------------|---------------|------------|-------------|
| A01LG | 01 | 9/1/2009 | AAC | APRON | 7/1/2022 | 13 | 100 | Good | 100 | 0 | 0 |
| A01LG | 02 | 9/1/2009 | AAC | APRON | 7/1/2022 | 13 | 72 | Satisfactory | 100 | 0 | 0 |
| A01LG | 03 | 9/2/1949 | AC | APRON | 7/1/2022 | 73 | 1 | Failed | 43 | 57 | 0 |
| A01LG | 04 | 9/2/1949 | AC | APRON | 7/1/2022 | 73 | 13 | Serious | 35 | 65 | 0 |
| A01LG | 05 | 9/1/1980 | AAC | APRON | 7/1/2022 | 42 | 47 | Poor | 89 | 10 | 1 |
| A01LG | 06 | 9/2/2009 | AAC | APRON | 7/1/2022 | 13 | 83 | Satisfactory | 100 | 0 | 0 |
| A01LG | 07 | 9/1/2009 | AAC | APRON | 7/1/2022 | 13 | 78 | Satisfactory | 100 | 0 | 0 |
| A01LG | 08 | 9/1/1980 | AAC | APRON | 7/1/2022 | 42 | 45 | Poor | 100 | 0 | 0 |
| A01LG | 09 | 9/1/2009 | AAC | APRON | 7/1/2022 | 13 | 74 | Satisfactory | 100 | 0 | 0 |
| A01LG | 10 | 9/2/1980 | AC | APRON | 7/1/2022 | 42 | 66 | Fair | 100 | 0 | 0 |
| A01LG | 11 | 9/2/1980 | AC | APRON | 7/1/2022 | 42 | 67 | Fair | 100 | 0 | 0 |
| A01LG | 12 | 9/3/2019 | AC | APRON | 7/1/2022 | 3 | 100 | Good | 0 | 0 | 0 |
| A01LG | 13 | 9/4/2019 | AC | APRON | 7/1/2022 | 3 | 100 | Good | 0 | 0 | 0 |
| A01LG | 14 | 9/4/2019 | AC | APRON | 7/1/2022 | 3 | 100 | Good | 0 | 0 | 0 |
| A01LG | 15 | 9/4/2019 | AC | APRON | 7/1/2022 | 3 | 100 | Good | 0 | 0 | 0 |
| AHELILG | 01 | 9/4/2019 | PCC | HELIPAD | 7/1/2022 | 3 | 100 | Good | 0 | 0 | 0 |
| AHELILG | 02 | 9/4/2019 | PCC | HELIPAD | 7/1/2022 | 3 | 100 | Good | 0 | 0 | 0 |
| AHELILG | 03 | 9/4/2019 | PCC | HELIPAD | 7/1/2022 | 3 | 100 | Good | 0 | 0 | 0 |
| AHELILG | 04 | 9/4/2019 | PCC | HELIPAD | 7/1/2022 | 3 | 100 | Good | 0 | 0 | 0 |
| AHTALG | 01 | 1/1/2021 | AC | APRON | 7/1/2022 | 2 | 100 | Good | 59 | 34 | 7 |
| AHTCLG | 01 | 10/4/2012 | AC | APRON | 7/1/2022 | 10 | 81 | Satisfactory | 100 | 0 | 0 |
| R12LG | 01 | 6/1/2014 | AAC | RUNWAY | 7/1/2022 | 8 | 79 | Satisfactory | 100 | 0 | 0 |
| R12LG | 02 | 6/1/2014 | AAC | RUNWAY | 7/1/2022 | 8 | 86 | Good | 100 | 0 | 0 |
| R12LG | 03 | 6/1/2014 | AAC | RUNWAY | 7/1/2022 | 8 | 83 | Satisfactory | 100 | 0 | 0 |
| R16LG | 01 | 1/1/2021 | AAC | RUNWAY | 7/1/2022 | 2 | 100 | Good | 0 | 0 | 0 |
| R16LG | 02 | 1/1/2021 | AC | RUNWAY | 7/1/2022 | 2 | 100 | Good | 100 | 0 | 0 |
| R16LG | 03 | 1/1/2021 | AAC | RUNWAY | 7/1/2022 | 2 | 100 | Good | 0 | 0 | 0 |
| TA1LG | 01 | 1/1/2021 | AC | TAXIWAY | 1/1/2022 | 1 | 100 | Good | 100 | 0 | 0 |
| TA2LG | 01 | 1/1/2021 | AC | TAXIWAY | 7/1/2022 | 2 | 100 | Good | 73 | 27 | 0 |
| TALG | 01 | 6/1/2014 | AAC | TAXIWAY | 7/1/2022 | 8 | 80 | Satisfactory | 100 | 0 | 0 |
| TALG | 02 | 8/3/2008 | AC | TAXIWAY | 7/1/2022 | 14 | 65 | Fair | 100 | 0 | 0 |
| TALG | 03 | 9/1/1974 | AAC | TAXIWAY | 7/1/2022 | 48 | 72 | Satisfactory | 100 | 0 | 0 |
| TALG | 04 | 1/1/2021 | AC | TAXIWAY | 7/1/2022 | 2 | 100 | Good | 100 | 0 | 0 |
| TBLG | 01 | 6/1/2014 | AAC | TAXIWAY | 7/1/2022 | 8 | 76 | Satisfactory | 100 | 0 | 0 |
| TBLG | 02 | 9/3/1993 | AC | TAXIWAY | 7/1/2022 | 29 | 73 | Satisfactory | 100 | 0 | 0 |
| TBLG | 03 | 1/2/2021 | AC | TAXIWAY | 7/1/2022 | 1 | 100 | Good | 0 | 0 | 0 |
| TC1LG | 01 | 6/1/2014 | AAC | TAXIWAY | 7/1/2022 | 8 | 92 | Good | 100 | 0 | 0 |
| TC1LG | 02 | 9/2/1984 | AC | TAXIWAY | 7/1/2022 | 38 | 33 | Very Poor | 100 | 0 | 0 |
| TC2LG | 01 | 6/1/2014 | AAC | TAXIWAY | 7/1/2022 | 8 | 76 | Satisfactory | 100 | 0 | 0 |
| TC2LG | 02 | 10/4/2012 | AC | TAXIWAY | 7/1/2022 | 10 | 74 | Satisfactory | 100 | 0 | 0 |
| TCLG | 01 | 9/3/1991 | AC | TAXIWAY | 7/1/2022 | 31 | 90 | Good | 100 | 0 | 0 |
| TCLG | 02 | 9/3/1991 | AC | TAXIWAY | 7/1/2022 | 31 | 89 | Good | 100 | 0 | 0 |
| TCLG | 03 | 9/1/2012 | AAC | TAXIWAY | 7/1/2022 | 10 | 74 | Satisfactory | 100 | 0 | 0 |

Table 3B - LA GRANDE AIRPORT 2022 PAVEMENT CONDITION INDEX SURVEY RESULTS

| BranchID | SectionID | Last Construction Date | Surface Type | Use | Last Inspection Date | Age at Inspection | PCI | PCI Category | PCI % Climate | PCI % Load | PCI % Other |
|----------|-----------|------------------------|--------------|---------|----------------------|-------------------|-----|--------------|---------------|------------|-------------|
| TCLG | 04 | 9/3/1991 | AC | TAXIWAY | 7/1/2022 | 31 | 94 | Good | 100 | 0 | 0 |
| TCLG | 05 | 10/4/2012 | AC | TAXIWAY | 7/1/2022 | 10 | 68 | Fair | 100 | 0 | 0 |
| TDLG | 01 | 1/1/2021 | AAC | TAXIWAY | 7/1/2022 | 2 | 100 | Good | 100 | 0 | 0 |
| TDLG | 02 | 1/1/2021 | AAC | TAXIWAY | 7/1/2022 | 2 | 100 | Good | 100 | 0 | 0 |
| TDLG | 03 | 1/1/2021 | AAC | TAXIWAY | 7/1/2022 | 2 | 100 | Good | 100 | 0 | 0 |
| TDLG | 04 | 1/1/2021 | AAC | TAXIWAY | 7/1/2022 | 2 | 100 | Good | 100 | 0 | 0 |

Abbreviations:

PCI = Pavement Condition Index, AC = Asphalt Concrete, AAC = AC overlaid AC, PCC = Portland Cement Concrete

Table 4B - LA GRANDE AIRPORT COMPARISON OF PREVIOUS INSPECTION AND 2022 RESULTS

| 2017 Survey | | | | | | | | | | | | | 2022 Survey | |
|-------------|------------|---------------------------|-------------------------------|------------------|-----|--------------|------------|-------------|--------------|------------------|-----------------------|--------|-----------------------|--|
| Branch ID | Section ID | Surface Type ¹ | Approximate Area, square feet | LCD ² | PCI | PCI Category | Insp. Date | 2022 Survey | | | | | Rate of Deterioration | |
| | | | | | | | | PCI | PCI Category | Age ³ | Δ PCI/yr ⁴ | | | |
| A01LG | 01 | AAC | 11,524 | 9/1/09 | 100 | Good | 6/13/2017 | 100 | Good | 8 | 0.00 | NONE | | |
| A01LG | 02 | AAC | 12,600 | 9/1/09 | 85 | Satisfactory | 6/13/2017 | 72 | Satisfactory | 8 | -3 | NORMAL | | |
| A01LG | 03 | AC | 48,880 | 9/2/49 | 13 | Serious | 6/13/2017 | 1 | Failed | 68 | 13.00 | NONE | | |
| A01LG | 04 | AC | 7,440 | 9/2/49 | 14 | Serious | 6/13/2017 | 13 | Serious | 68 | -0.20 | NORMAL | | |
| A01LG | 05 | AAC | 19,600 | 9/1/80 | 69 | Fair | 6/13/2017 | 47 | Poor | 37 | -4.35 | HIGH | | |
| A01LG | 06 | AAC | 4,529 | 9/2/09 | 91 | Good | 6/13/2017 | 83 | Satisfactory | 8 | -1.58 | NORMAL | | |
| A01LG | 07 | AAC | 12,089 | 9/1/09 | 94 | Good | 6/13/2017 | 78 | Satisfactory | 8 | -3.17 | NORMAL | | |
| A01LG | 08 | AAC | 77,012 | 9/1/80 | 61 | Satisfactory | 6/13/2017 | 45 | Poor | 37 | -3.17 | NORMAL | | |
| A01LG | 09 | AAC | 17,817 | 9/1/09 | 78 | Satisfactory | 6/13/2017 | 74 | Satisfactory | 8 | -0.79 | NORMAL | | |
| A01LG | 10 | AC | 54,850 | 9/2/80 | 72 | Satisfactory | 6/13/2017 | 66 | Fair | 37 | -1.19 | NORMAL | | |
| A01LG | 11 | AC | 30,587 | 9/2/80 | 73 | Satisfactory | 6/13/2017 | 67 | Fair | 37 | -1.19 | NORMAL | | |
| A01LG | 12 | AC | 36,243 | 9/3/19 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| A01LG | 13 | AC | 7,040 | 9/4/19 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| A01LG | 14 | AC | 4,336 | 9/4/19 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| A01LG | 15 | AC | 10,085 | 9/4/19 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| AHELILG | 01 | PCC | 400 | 9/4/19 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| AHELILG | 02 | PCC | 400 | 9/4/19 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| AHELILG | 03 | PCC | 400 | 9/4/19 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| AHELILG | 04 | PCC | 1,296 | 9/4/19 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| AHTALG | 01 | AC | 17,175 | 1/1/21 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| AHTCLG | 01 | AC | 29,900 | 10/4/12 | 100 | Good | 6/13/2017 | 81 | Satisfactory | 5 | -3.76 | NORMAL | | |
| R12LG | 01 | AAC | 457,600 | 6/1/14 | 98 | Good | 6/13/2017 | 79 | Satisfactory | 3 | -3.76 | NORMAL | | |
| R12LG | 02 | AAC | 102,400 | 6/1/14 | 100 | Good | 6/13/2017 | 86 | Good | 3 | -2.77 | NORMAL | | |
| R12LG | 03 | AAC | 65,921 | 6/1/14 | 100 | Good | 6/13/2017 | 83 | Satisfactory | 3 | -3.36 | NORMAL | | |
| R16LG | 01 | AAC | 27,198 | 1/1/21 | 37 | Very Poor | 6/13/2017 | 100 | Good | -4 | 12.47 | NONE | | |
| R16LG | 02 | AC | 9,000 | 1/1/21 | 66 | Very Poor | 6/13/2017 | 100 | Good | -4 | 6.73 | NONE | | |
| R16LG | 03 | AAC | 168,713 | 1/1/21 | 88 | Good | 6/13/2017 | 100 | Good | -4 | 2.38 | NONE | | |
| TA1LG | 01 | AC | 23,227 | 1/1/21 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| TA2LG | 01 | AC | 11,300 | 1/1/21 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| TALG | 01 | AAC | 5,786 | 6/1/14 | 100 | Good | 6/13/2017 | 80 | Satisfactory | 3 | -3.96 | NORMAL | | |
| TALG | 02 | AC | 15,500 | 8/3/08 | 75 | Satisfactory | 6/13/2017 | 65 | Fair | 9 | -1.98 | NORMAL | | |
| TALG | 03 | AAC | 118,555 | 9/1/74 | 82 | Satisfactory | 6/13/2017 | 72 | Satisfactory | 43 | -1.98 | NORMAL | | |
| TALG | 04 | AC | 60,718 | 1/1/21 | - | Good | 6/13/2017 | 100 | Good | N/A | N/A | N/A | | |
| TBLG | 01 | AAC | 19,835 | 6/1/14 | 97 | Good | 6/13/2017 | 76 | Satisfactory | 3 | -4.16 | HIGH | | |
| TBLG | 02 | AC | 48,734 | 9/3/93 | 78 | Satisfactory | 6/13/2017 | 73 | Satisfactory | 24 | -0.99 | NORMAL | | |
| TBLG | 03 | AC | 24,749 | 1/2/21 | 81 | Satisfactory | 6/13/2017 | 100 | Good | -4 | 3.76 | NONE | | |
| TC1LG | 01 | AAC | 8,573 | 6/1/14 | 100 | Good | 6/13/2017 | 92 | Good | 3 | -1.58 | NORMAL | | |
| TC1LG | 02 | AC | 5,650 | 9/2/84 | 59 | Satisfactory | 6/13/2017 | 33 | Very Poor | 33 | -5.15 | HIGH | | |
| TC2LG | 01 | AAC | 13,561 | 6/1/14 | 97 | Good | 6/13/2017 | 76 | Satisfactory | 3 | -4.16 | HIGH | | |
| TC2LG | 02 | AC | 24,798 | 10/4/12 | 100 | Good | 6/13/2017 | 74 | Satisfactory | 5 | -5.15 | HIGH | | |
| TCLG | 01 | AC | 122,032 | 9/3/91 | 80 | Satisfactory | 6/13/2017 | 90 | Good | 26 | 1.98 | NONE | | |
| TCLG | 02 | AC | 30,453 | 9/3/91 | 86 | Good | 6/13/2017 | 89 | Good | 26 | 0.59 | NONE | | |
| TCLG | 03 | AAC | 10,662 | 9/1/12 | 86 | Good | 6/13/2017 | 74 | Satisfactory | 5 | -2.38 | NORMAL | | |
| TCLG | 04 | AC | 44,975 | 9/3/91 | 76 | Satisfactory | 6/13/2017 | 94 | Good | 26 | 3.56 | NONE | | |
| TCLG | 05 | AC | 33,710 | 10/4/12 | 100 | Good | 6/13/2017 | 68 | Fair | 5 | -6.33 | HIGH | | |
| TDLG | 01 | AAC | 93,045 | 1/1/21 | 100 | Good | 6/13/2017 | 100 | Good | -4 | 0.00 | NONE | | |
| TDLG | 02 | AAC | 4,844 | 1/1/21 | 59 | Fair | 6/13/2017 | 100 | Good | -4 | 8.12 | NONE | | |
| TDLG | 03 | AAC | 2,746 | 1/1/21 | 82 | Fair | 6/13/2017 | 100 | Good | -4 | 3.56 | NONE | | |
| TDLG | 04 | AAC | 15,923 | 1/1/21 | 83 | Satisfactory | 6/13/2017 | 100 | Good | -4 | 3.36 | NONE | | |

Abbreviations:

¹ AC = Asphalt Concrete, AAC = Asphalt Overlay AC, PCC = Portland Cement Concrete, PCI = Pavement Condition Index² LCD = Last construction date. The date of the last major pavement rehabilitation (e.g. AC overlay)³ Age = Pavement age in years at the time of the PCI survey in 2017⁴ Δ PCI/yr = Change in PCI points per year between 2017 survey and 2022 survey⁵ N/A = Not applicable due to changes in sectioning

APPENDIX C

Future Pavement Condition Analysis

APPENDIX C

PAVEMENT CONDITION ANALYSIS

C.1 METHODOLOGY

In addition to assessing the current condition of a pavement, it is very important from a planning standpoint to be able to predict with reasonable accuracy its future condition. In a pavement management plan (PMP), this is done with the aid of a prediction model. When an APMS is initially implemented, the default models are typically used to predict the future condition of a pavement. However, after PCI surveys are completed, the historical data are then used to refine the models, so they better represent the deterioration of a particular class of pavement based on local climatic conditions, loading, material sources, construction procedures, etc. The importance of accurate prediction models is part of the reason it is essential to conduct periodic, routine surveys in order to track the rate of deterioration.

In PAVER, the pavement deterioration curves are developed based on the “family” model procedure. A pavement “family” is defined as a group of pavements with similar deterioration characteristics. The procedure for developing the prediction models is:

- 1) Define the pavement families.
- 2) Review the data.
- 3) Conduct a data outlier analysis.
- 4) Model the data.

C.2 PREDICTION MODELS

We developed separate condition prediction models for each pavement “family” at La Grande Airport. The delineation is based on branch use, surface type, section rank, and structural design life. We use five distinct models for the following “families” of pavements at La Grande Airport. For each model, we reviewed the data in order to filter out any inconsistent or inaccurate data or any data that fall outside boundary values set by PAVER. After outliers are removed and the data are checked for accuracy and reasonableness, the PAVER program calculates a best-fit curve using a polynomial-constrained, least-squares analysis procedure. This best-fit curve for each family is used in the analysis to predict the average behavior of all sections within each “family.” Our condition prediction models for each “family” are provided on Figures 1C through 4C below.




Figure 1C - CONDITION PREDICTION MODEL FOR EASTERN CATEGORY 3 PCC RUNWAYS, TAXIWAYS, AND APRONS




Figure 2C - CONDITION PREDICTION MODEL FOR EASTERN CATEGORY 3 AC AND AAC APRONS




Figure 3C - CONDITION PREDICTION MODEL FOR EASTERN CATEGORY 3 AC AND AAC RUNWAYS




Figure 4C - CONDITION PREDICTION MODEL FOR EASTERN CATEGORY 3 AC AND AAC TAXIWAYS

C.3 CRITICAL PCI

Each of the condition-prediction models have an assigned critical PCI. The critical PCI is the point at which the pavement condition begins to deteriorate more quickly over time. As the condition deteriorates to a worse state, major M&R is triggered because the cost to apply localized M&R increases significantly. Pavement sections with PCI above the critical value are given a higher priority for funding during budget analysis in order to

prevent them from deteriorating to the point where more costly rehabilitation is necessary. We used the following critical PCI values at La Grande Airport:

- Runways – 60
- Taxiways/Taxilanes – 55
- Aprons – 50

C.4 FUTURE CONDITION ANALYSIS

As previously discussed, the projected condition of each pavement section was determined for 5- and 10-year periods. The projected pavement conditions in 5 years and 10 years for each pavement section at La Grande Airport, along with the conditions at the previous inspection, are listed in Table 1C.

C.5 FUNCTIONAL REMAINING LIFE

As mentioned above, functional remaining life is the practical amount of time a pavement is in service before requiring rehabilitation, as estimated solely based on visual condition. This is not to be confused with structural remaining life, which requires analysis of the structural capacity of a pavement.

We calculated two forms of functional remaining life based on the current visual condition surveys of the pavement at La Grande Airport, the time until rehabilitation, and the time until the pavement is no longer operational due to high foreign object debris potential and increased safety concerns for trafficking aircraft (PCI less than 40). The results of the functional life analysis are provided in Table 2C.

Table 1C - PAST, PRESENT AND FUTURE PCI

| BranchID | SectionID | Past Inspection PCI | Current PCI | Predicted Future PCI | |
|----------|-----------|---------------------|-------------|----------------------|------|
| | | 2017 | 2022 | 2027 | 2032 |
| A01LG | 01 | 100 | 100 | 93 | 85 |
| A01LG | 02 | 85 | 72 | 65 | 57 |
| A01LG | 03 | 13 | 1 | 0 | 0 |
| A01LG | 04 | 14 | 13 | 6 | 0 |
| A01LG | 05 | 69 | 47 | 40 | 32 |
| A01LG | 06 | 91 | 83 | 76 | 68 |
| A01LG | 07 | 94 | 78 | 71 | 63 |
| A01LG | 08 | 61 | 45 | 38 | 30 |
| A01LG | 09 | 78 | 74 | 67 | 59 |
| A01LG | 10 | 72 | 66 | 59 | 51 |
| A01LG | 11 | 73 | 67 | 60 | 52 |
| A01LG | 12 | - | 100 | 93 | 85 |
| A01LG | 13 | - | 100 | 93 | 85 |
| A01LG | 14 | - | 100 | 93 | 85 |
| A01LG | 15 | - | 100 | 93 | 85 |
| AHELILG | 01 | - | 100 | 95 | 91 |
| AHELILG | 02 | - | 100 | 95 | 91 |
| AHELILG | 03 | - | 100 | 95 | 91 |
| AHELILG | 04 | - | 100 | 95 | 91 |
| AHTALG | 01 | - | 100 | 93 | 85 |
| AHTCLG | 01 | 100 | 81 | 74 | 66 |
| R12LG | 01 | 98 | 79 | 72 | 65 |
| R12LG | 02 | 100 | 86 | 79 | 72 |
| R12LG | 03 | 100 | 83 | 76 | 69 |
| R16LG | 01 | 37 | 100 | 93 | 86 |
| R16LG | 02 | 66 | 100 | 93 | 86 |
| R16LG | 03 | 88 | 100 | 93 | 86 |
| TA1LG | 01 | - | 99 | 92 | 85 |
| TA2LG | 01 | - | 100 | 93 | 86 |
| TALG | 01 | 100 | 80 | 73 | 66 |
| TALG | 02 | 75 | 65 | 58 | 51 |
| TALG | 03 | 82 | 72 | 65 | 58 |
| TALG | 04 | - | 100 | 93 | 86 |
| TBLG | 01 | 97 | 76 | 69 | 62 |
| TBLG | 02 | 78 | 73 | 66 | 59 |
| TBLG | 03 | 81 | 100 | 93 | 86 |
| TC1LG | 01 | 100 | 92 | 85 | 78 |
| TC1LG | 02 | 59 | 33 | 26 | 19 |
| TC2LG | 01 | 97 | 76 | 69 | 62 |
| TC2LG | 02 | 100 | 74 | 67 | 60 |
| TCLG | 01 | 80 | 90 | 83 | 76 |
| TCLG | 02 | 86 | 89 | 82 | 75 |
| TCLG | 03 | 86 | 74 | 67 | 60 |
| TCLG | 04 | 76 | 94 | 87 | 80 |
| TCLG | 05 | 100 | 68 | 61 | 54 |
| TDLG | 01 | 100 | 100 | 93 | 86 |
| TDLG | 02 | 59 | 100 | 93 | 86 |
| TDLG | 03 | 82 | 100 | 93 | 86 |
| TDLG | 04 | 83 | 100 | 93 | 86 |

Abbreviation: PCI = Pavement Condition Index

Table 2C - LA GRANDE AIRPORT FUNCTIONAL REMAINING LIFE ANALYSIS

| Branch ID | Section ID | Surface Type | Current PCI | Years to Major M&R | Major M&R Trigger PCI ¹ | Years to End of Functional Service |
|-----------|------------|--------------|-------------|--------------------|------------------------------------|------------------------------------|
| A01LG | 01 | AAC | 100 | > 20 | 50 | > 20 |
| A01LG | 02 | AAC | 72 | 11 - 15 | 50 | > 20 |
| A01LG | 03 | AC | 1 | 0 - 5 | 50 | 0 - 5 |
| A01LG | 04 | AC | 13 | 0 - 5 | 50 | 0 - 5 |
| A01LG | 05 | AAC | 47 | 0 - 5 | 50 | 0 - 5 |
| A01LG | 06 | AAC | 83 | > 20 | 50 | > 20 |
| A01LG | 07 | AAC | 78 | > 20 | 50 | > 20 |
| A01LG | 08 | AAC | 45 | 0 - 5 | 50 | 0 - 5 |
| A01LG | 09 | AAC | 74 | 16 - 20 | 50 | > 20 |
| A01LG | 10 | AC | 66 | 6 - 10 | 50 | 16 - 20 |
| A01LG | 11 | AC | 67 | 11 - 15 | 50 | 16 - 20 |
| A01LG | 12 | AC | 100 | > 20 | 50 | > 20 |
| A01LG | 13 | AC | 100 | > 20 | 50 | > 20 |
| A01LG | 14 | AC | 100 | > 20 | 50 | > 20 |
| A01LG | 15 | AC | 100 | > 20 | 50 | > 20 |
| AHELILG | 01 | PCC | 100 | > 20 | 50 | > 20 |
| AHELILG | 02 | PCC | 100 | > 20 | 50 | > 20 |
| AHELILG | 03 | PCC | 100 | > 20 | 50 | > 20 |
| AHELILG | 04 | PCC | 100 | > 20 | 50 | > 20 |
| AHTALG | 01 | AC | 100 | > 20 | 50 | > 20 |
| AHTCLG | 01 | AC | 81 | > 20 | 50 | > 20 |
| R12LG | 01 | AAC | 79 | 11 - 15 | 60 | > 20 |
| R12LG | 02 | AAC | 86 | 16 - 20 | 60 | > 20 |
| R12LG | 03 | AAC | 83 | 16 - 20 | 60 | > 20 |
| R16LG | 01 | AAC | 100 | > 20 | 60 | > 20 |
| R16LG | 02 | AC | 100 | > 20 | 60 | > 20 |
| R16LG | 03 | AAC | 100 | > 20 | 60 | > 20 |
| TA1LG | 01 | AC | 100 | > 20 | 55 | > 20 |
| TA2LG | 01 | AC | 100 | > 20 | 55 | > 20 |
| TALG | 01 | AAC | 80 | 16 - 20 | 55 | > 20 |
| TALG | 02 | AC | 65 | 6 - 10 | 55 | 16 - 20 |
| TALG | 03 | AAC | 72 | 11 - 15 | 55 | > 20 |
| TALG | 04 | AC | 100 | > 20 | 55 | > 20 |
| TBLG | 01 | AAC | 76 | 11 - 15 | 55 | > 20 |
| TBLG | 02 | AC | 73 | 11 - 15 | 55 | > 20 |
| TBLG | 03 | AC | 100 | > 20 | 55 | > 20 |
| TC1LG | 01 | AAC | 92 | > 20 | 55 | > 20 |
| TC1LG | 02 | AC | 33 | 0 - 5 | 55 | 0 - 5 |
| TC2LG | 01 | AAC | 76 | 11 - 15 | 55 | > 20 |
| TC2LG | 02 | AC | 74 | 11 - 15 | 55 | > 20 |
| TCLG | 01 | AC | 90 | > 20 | 55 | > 20 |
| TCLG | 02 | AC | 89 | > 20 | 55 | > 20 |
| TCLG | 03 | AAC | 74 | 11 - 15 | 55 | > 20 |
| TCLG | 04 | AC | 94 | > 20 | 55 | > 20 |
| TCLG | 05 | AC | 68 | 6 - 10 | 55 | > 20 |
| TDLG | 01 | AAC | 100 | > 20 | 55 | > 20 |
| TDLG | 02 | AAC | 100 | > 20 | 55 | > 20 |
| TDLG | 03 | AAC | 100 | > 20 | 55 | > 20 |
| TDLG | 04 | AAC | 100 | > 20 | 55 | > 20 |

Abbreviations:

PCI = Pavement Condition Index, AC = Asphalt Concrete, AAC = AC overlaid AC,
PCC = Portland Cement Concrete

¹ Major M&R (Maintenance and Rehabilitation) Trigger PCI = Critical PCI

APPENDIX D

Unit Cost Data and Maintenance and Rehabilitation Plan

APPENDIX D

UNIT COST DATA AND MAINTENANCE AND REHABILITATION PLAN

D.1 ANALYSIS METHODOLOGY

We evaluated the M&R needs, as determined from the PAVER analysis results, in order to develop project recommendations for the next five years. The purpose of this analysis is to determine the M&R needs of the La Grande Airport pavement network condition over time. We used PAVER v7.0.8 software to develop network-level project recommendations for the next five years.

The PAVER M&R Work Planning Module identifies when and where M&R is required and how much it will cost. M&R plans can be developed either by assuming an annual budget or by identifying specific constraints, such as a condition goal, to determine the budget required to meet the goal. The M&R work planning analysis was based on a five-year period beginning on August 1, 2024. A backlog elimination analysis scenario was selected to generate a list of global maintenance and rehabilitation projects in order to optimize the allocation of capital and establish preservation-based project recommendations. The repair strategies considered for pavement sections in our analysis are as follows:

- Reconstruction – Considered for pavements with a PCI less than 40.
- Flexible Overlay – Considered for pavements between 40 PCI and the critical PCI, and for pavements exhibiting significant load-related distresses.
- Global Maintenance – Treatments (fog seal, slurry seal, thin AC overlay) applied to an entire pavement section with the intent of slowing the rate of deterioration.
- Localized Maintenance – Maintenance performed on a routine basis such as crack sealing, wide crack repair, and patching.

It should be noted that the five-year list of recommended projects only includes the highest-cost maintenance items and does not include routine localized maintenance (e.g., crack sealing) work that should also be conducted in addition to and concurrently with the five-year work plan.

D.1.1 Pavement Rank and Use Prioritization

Pavement sections are assigned a rank to establish their relative importance in the overall pavement network, which is most commonly defined by their use (e.g., Taxiway, Apron, Runway). The PAVER analysis uses the combination of the section rank and the branch use

to define the priority of each section during the M&R analysis. Table 1D displays the branch use and section rank prioritization schema we used for analysis.

Table 1D: M&R WORK PRIORITY BY BRANCH USE AND SECTION RANK

| Branch Use | Section Rank | | |
|------------|--------------|-----------|----------|
| | Primary | Secondary | Tertiary |
| RUNWAY | 1 | 3 | 6 |
| TAXIWAY | 2 | 5 | 8 |
| APRON | 4 | 7 | 9 |

D.2 MAINTENANCE POLICIES AND UNIT COSTS

The distress-maintenance policies are policies that determine what type of work should be applied to a specific distress type and severity. For example, on an AC pavement, a medium-severity longitudinal/transverse crack would be repaired by crack sealing. Policies for all the distress types and severities are established by ASTM D5340.

Although our work scope does not include budget analysis, we did assign construction costs to the maintenance work so that PAVER would allocate M&R projects that were approximately equal in cost for each year of the five-year period. The anticipated cost of performing M&R is based on cost tables that relate M&R work type costs to PCI. We reviewed the unit costs from the 2017 report and updated them by reviewing the bid tabulations for recent projects within the vicinity of La Grande Airport and information provided by the project team. The costs for reconstruction are based on the existing pavement sections present within each branch use at La Grande Airport. The costs represent the fully loaded costs and include aspects of the project such as administration, contingencies, mobilization, and striping. The cost tables used in the analysis are presented in Table 2D below.

Table 2D: LA GRANDE AIRPORT UNIT COST DATA

| Type of M&R | Work Type | Unit Cost | Work Unit |
|--------------------------|--|-----------|-----------|
| Major M&R | Complete Reconstruction with AC | \$13.32 | Sq Ft |
| | Cold Mill and Overlay – 2 Inches Thick | \$5.88 | Sq Ft |
| Global M&R | Surface Treatment - Slurry Seal | \$0.40 | Sq Ft |
| | Surface Treatment - Fog Seal | \$0.24 | Sq Ft |
| Localized Preventive M&R | Crack Sealing - AC | \$2.40 | Ft |
| | Crack Sealing - PCC | \$18.00 | Ft |
| | Crack Sealing – Wide Cracks | \$39.60 | Ft |
| | AC Patching – Full Depth | \$60.00 | Sq Ft |
| | PCC Patching – Full Depth | \$120.00 | Sq Ft |

D.3 RECOMMENDED LOCALIZED MAINTENANCE

In order to properly maintain aging pavements, localized M&R activities such as crack sealing and patching should be performed on a routine basis. A list of recommended localized maintenance activities is provided in Table 3D of this appendix.

D.4 RECOMMENDED GLOBAL MAINTENANCE AND REHABILITATION PROJECTS

Global maintenance and rehabilitation projects refer to activities such as slurry seal and thin AC overlays, as well as thick AC overlays and reconstruction. A list of recommended global and M&R activities is provided in Table 4D of this appendix.

Table 3D - LA GRANDE AIRPORT NETWORK MAINTENANCE REPORT

| Network | Branch ID | Section ID | Distress | Severity | Action | Work Quantity | Unit | Unit Cost | Work Cost | Section Total |
|-----------|-----------|------------|-------------------------|----------|--------------------|---------------|------|-----------|-------------|---------------|
| La Grande | A01LG | 02 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 90 | Ft | \$2.40 | \$215 | \$1,223 |
| La Grande | A01LG | 02 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 420 | Ft | \$2.40 | \$1,008 | |
| La Grande | A01LG | 03 | Patching | High | Patching - AC Deep | 4,137 | SqFt | \$60.00 | \$248,185 | \$1,549,397 |
| La Grande | A01LG | 03 | Alligator Cracking | Medium | Patching - AC Deep | 985 | SqFt | \$60.00 | \$59,088 | |
| La Grande | A01LG | 03 | Alligator Cracking | High | Patching - AC Deep | 20,702 | SqFt | \$60.00 | \$1,242,124 | |
| La Grande | A01LG | 04 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 396 | Ft | \$2.40 | \$950 | \$91,074 |
| La Grande | A01LG | 04 | Alligator Cracking | Medium | Patching - AC Deep | 318 | SqFt | \$60.00 | \$19,058 | |
| La Grande | A01LG | 04 | Alligator Cracking | High | Patching - AC Deep | 1,184 | SqFt | \$60.00 | \$71,065 | |
| La Grande | A01LG | 05 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 161 | Ft | \$2.40 | \$387 | \$6,197 |
| La Grande | A01LG | 05 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 1,470 | Ft | \$2.40 | \$3,528 | |
| La Grande | A01LG | 05 | Alligator Cracking | Medium | Patching - AC Deep | 38 | SqFt | \$60.00 | \$2,282 | |
| La Grande | A01LG | 06 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 56 | Ft | \$2.40 | \$134 | \$134 |
| La Grande | A01LG | 07 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 152 | Ft | \$2.40 | \$365 | \$1,337 |
| La Grande | A01LG | 07 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 405 | Ft | \$2.40 | \$972 | |
| La Grande | A01LG | 08 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 3,080 | Ft | \$2.40 | \$7,393 | \$17,758 |
| La Grande | A01LG | 08 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 4,319 | Ft | \$2.40 | \$10,365 | |
| La Grande | A01LG | 09 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 630 | Ft | \$2.40 | \$1,512 | \$2,095 |
| La Grande | A01LG | 09 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 243 | Ft | \$2.40 | \$583 | |
| La Grande | A01LG | 10 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 2,956 | Ft | \$2.40 | \$7,094 | \$9,895 |
| La Grande | A01LG | 10 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 1,167 | Ft | \$2.40 | \$2,801 | |
| La Grande | A01LG | 11 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 1,507 | Ft | \$2.40 | \$3,616 | \$5,915 |
| La Grande | A01LG | 11 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 958 | Ft | \$2.40 | \$2,299 | |
| La Grande | AHTCLG | 01 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 1,188 | Ft | \$2.40 | \$2,851 | \$2,851 |
| La Grande | AHTCLG | 01 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 71 | Ft | \$2.40 | \$171 | \$171 |
| La Grande | R12LG | 01 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 21,599 | Ft | \$2.40 | \$51,837 | \$53,667 |
| La Grande | R12LG | 01 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 763 | Ft | \$2.40 | \$1,830 | |
| La Grande | R12LG | 02 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 205 | Ft | \$2.40 | \$492 | \$5,633 |
| La Grande | R12LG | 02 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 2,142 | Ft | \$2.40 | \$5,141 | |
| La Grande | R12LG | 03 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 2,498 | Ft | \$2.40 | \$5,996 | \$5,996 |
| La Grande | TALG | 01 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 290 | Ft | \$2.40 | \$696 | \$696 |
| La Grande | TALG | 02 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 367 | Ft | \$2.40 | \$881 | \$2,311 |
| La Grande | TALG | 02 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 595 | Ft | \$2.40 | \$1,429 | |
| La Grande | TALG | 03 | Block Cracking | Low | Crack Sealing - AC | 651 | Ft | \$2.40 | \$1,561 | \$16,015 |
| La Grande | TALG | 03 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 2,893 | Ft | \$2.40 | \$6,943 | |
| La Grande | TALG | 03 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 3,130 | Ft | \$2.40 | \$7,512 | |
| La Grande | TBLG | 01 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 205 | Ft | \$2.40 | \$492 | \$1,811 |
| La Grande | TBLG | 01 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 550 | Ft | \$2.40 | \$1,319 | |
| La Grande | TBLG | 02 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 1,291 | Ft | \$2.40 | \$3,099 | \$5,129 |
| La Grande | TBLG | 02 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 845 | Ft | \$2.40 | \$2,029 | |
| La Grande | TC1LG | 01 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 29 | Ft | \$2.40 | \$70 | \$70 |
| La Grande | TC1LG | 02 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 12 | Ft | \$2.40 | \$29 | \$29 |

Table 3D - LA GRANDE AIRPORT NETWORK MAINTENANCE REPORT

| Network | Branch ID | Section ID | Distress | Severity | Action | Work Quantity | Unit | Unit Cost | Work Cost | Section Total |
|-----------|-----------|------------|-------------------------|----------|--------------------|---------------|------|-----------|-----------|---------------|
| La Grande | TC2LG | 01 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 516 | Ft | \$2.40 | \$1,238 | \$1,687 |
| La Grande | TC2LG | 01 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 187 | Ft | \$2.40 | \$449 | |
| La Grande | TC2LG | 02 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 381 | Ft | \$2.40 | \$913 | \$4,152 |
| La Grande | TC2LG | 02 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 1,349 | Ft | \$2.40 | \$3,239 | |
| La Grande | TCLG | 01 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 406 | Ft | \$2.40 | \$974 | \$1,668 |
| La Grande | TCLG | 01 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 289 | Ft | \$2.40 | \$694 | |
| La Grande | TCLG | 02 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 104 | Ft | \$2.40 | \$250 | \$989 |
| La Grande | TCLG | 02 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 308 | Ft | \$2.40 | \$739 | |
| La Grande | TCLG | 03 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 401 | Ft | \$2.40 | \$962 | \$1,320 |
| La Grande | TCLG | 03 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 149 | Ft | \$2.40 | \$358 | |
| La Grande | TCLG | 05 | Long. & Trans. Cracking | Medium | Crack Sealing - AC | 939 | Ft | \$2.40 | \$2,253 | \$5,166 |
| La Grande | TCLG | 05 | Long. & Trans. Cracking | Low | Crack Sealing - AC | 1,214 | Ft | \$2.40 | \$2,913 | |

Abbreviations:

Long. = Longitudinal; Trans. = Transverse; AC = Asphalt Concrete; Ft = Feet; SqFt = Square Feet

Table 4D - FIVE-YEAR GLOBAL MAINTENANCE AND REHABILITATION PLAN

| Action Year | Branch ID | Section ID | Branch Use | Surface Type | Current PCI | Action | Area, square feet | Unit Cost per square foot | Total Cost |
|-------------|-----------|------------|------------|--------------|-------------|----------------|-------------------|---------------------------|------------|
| 2024 | A01LG | 03 | APRON | AC | 1 | Reconstruction | 48,880 | \$13.32 | \$651,103 |
| | A01LG | 04 | APRON | AC | 13 | Reconstruction | 7,440 | \$13.32 | \$99,104 |
| | TC1LG | 02 | TAXIWAY | AC | 33 | Reconstruction | 5,650 | \$13.32 | \$75,260 |
| 2025 | A01LG | 05 | APRON | AAC | 47 | Overlay | 19,600 | \$10.38 | \$203,475 |
| | A01LG | 08 | APRON | AAC | 45 | Overlay | 77,012 | \$12.96 | \$998,329 |
| 2026 | A01LG | 02 | APRON | AAC | 72 | Fog Seal | 12,600 | \$0.24 | \$3,024 |
| | A01LG | 06 | APRON | AAC | 83 | Fog Seal | 4,529 | \$0.24 | \$1,087 |
| | A01LG | 07 | APRON | AAC | 78 | Fog Seal | 12,089 | \$0.24 | \$2,901 |
| | A01LG | 09 | APRON | AAC | 74 | Fog Seal | 13,070 | \$0.24 | \$3,137 |
| | A01LG | 10 | APRON | AC | 66 | Fog Seal | 54,850 | \$0.24 | \$13,164 |
| | A01LG | 11 | APRON | AC | 67 | Fog Seal | 31,240 | \$0.24 | \$7,497 |
| 2028 | AHTCLG | 01 | APRON | AC | 81 | Fog Seal | 29,900 | \$0.24 | \$7,176 |
| | R12LG | 01 | RUNWAY | AAC | 79 | Slurry Seal | 457,600 | \$0.40 | \$183,042 |
| | R12LG | 02 | RUNWAY | AAC | 86 | Slurry Seal | 102,400 | \$0.40 | \$40,960 |
| | R12LG | 03 | RUNWAY | AAC | 83 | Slurry Seal | 65,921 | \$0.40 | \$26,369 |
| | TALG | 01 | TAXIWAY | AAC | 80 | Slurry Seal | 5,786 | \$0.40 | \$2,314 |
| | TALG | 02 | TAXIWAY | AC | 65 | Slurry Seal | 15,500 | \$0.40 | \$6,200 |
| | TALG | 03 | TAXIWAY | AAC | 72 | Slurry Seal | 118,555 | \$0.40 | \$47,422 |
| | TBLG | 01 | TAXIWAY | AAC | 76 | Slurry Seal | 19,835 | \$0.40 | \$7,934 |
| | TBLG | 02 | TAXIWAY | AC | 73 | Slurry Seal | 48,734 | \$0.40 | \$19,494 |
| | TC1LG | 01 | TAXIWAY | AAC | 92 | Slurry Seal | 8,573 | \$0.40 | \$3,429 |
| | TC2LG | 01 | TAXIWAY | AAC | 76 | Slurry Seal | 13,561 | \$0.40 | \$5,424 |
| | TC2LG | 02 | TAXIWAY | AC | 74 | Slurry Seal | 24,798 | \$0.40 | \$9,919 |
| | TCLG | 01 | TAXIWAY | AC | 90 | Slurry Seal | 122,032 | \$0.40 | \$48,813 |
| | TCLG | 02 | TAXIWAY | AC | 89 | Slurry Seal | 30,453 | \$0.40 | \$12,181 |
| | TCLG | 03 | TAXIWAY | AAC | 74 | Slurry Seal | 10,662 | \$0.40 | \$4,265 |
| | TCLG | 04 | TAXIWAY | AC | 94 | Slurry Seal | 44,975 | \$0.40 | \$17,990 |
| | TCLG | 05 | TAXIWAY | AC | 68 | Slurry Seal | 33,710 | \$0.40 | \$13,484 |

Abbreviations:

PCI = Pavement Condition Index, AC = Asphalt Concrete, AAC = AC overlaid AC

| Cost Summary | |
|----------------------------------|--------------------|
| 2024 Total Project Cost | \$825,468 |
| 2025 Total Project Cost | \$1,201,804 |
| 2026 Total Project Cost | \$37,986 |
| 2027 Total Project Cost | \$0 |
| 2028 Total Project Cost | \$449,242 |
| Total 5-Year Project Cost | \$2,514,500 |

APPENDIX E

Reinspection Report

Re-Inspection Report

ODA_WOC3_4-10-2023_PostWHEdits_4PM

Generated Date 4/13/2023

Page 1 of 53

| | | | | | | | | | | | |
|--------------------------|------------|----------------|--------------------------------|-------------------|-------------------------|--------------------|------------|------------------|----------------------|---------------------|----------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | | Area: | 354,632 SqFt | |
| Section: | 04 | of | 15 | From: | A01-03 | | To: | A01-05 | | Last Const.: | 9/2/1949 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | KLGD | | Category: | O | Rank: | S |
| Area: | 7,440 SqFt | | Length: | 93 Ft | | Width: | 80 Ft | | | | |
| Slabs: | | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | |
| Shoulder: | | | Street Type: | | | Grade: | 0 | | Lanes: | 0 | |
| Section Comments: | | | | | | | | | | | |

| | | | | | | | | | |
|-------------------|----------|-------------------|----------------------------------|--|--|--------------|-------|--------------------------|------|
| Work Date: | 9/1/1949 | Work Type: | Base Course - Unknown (Major MR) | | | Code: | BA-UN | Is Major M&R: | True |
|-------------------|----------|-------------------|----------------------------------|--|--|--------------|-------|--------------------------|------|

| | | | | | | | | | |
|-------------------|----------|-------------------|-----------------------|--|--|--------------|-------|--------------------------|------|
| Work Date: | 9/2/1949 | Work Type: | New Construction - AC | | | Code: | NC-AC | Is Major M&R: | True |
|-------------------|----------|-------------------|-----------------------|--|--|--------------|-------|--------------------------|------|

| | | | | | | | | | | |
|-------------------------|----------|----------------------|---|--|--|------------------|---|--|--|--|
| Last Insp. Date: | 7/1/2022 | TotalSamples: | 2 | | | Surveyed: | 2 | | | |
|-------------------------|----------|----------------------|---|--|--|------------------|---|--|--|--|

Conditions: PCI: 13

Inspection Comments:

| | | | | | | | | | | |
|-----------------------|----|--------------|---|--------------|--------------|--|-------------|---|--|--|
| Sample Number: | 01 | Type: | R | Area: | 4000.00 SqFt | | PCI: | 4 | | |
|-----------------------|----|--------------|---|--------------|--------------|--|-------------|---|--|--|

Sample Comments: Created by Inspection Schedule

| | | | | |
|----|--------------|---|---------|------|
| 41 | ALLIGATOR CR | M | 250.00 | SqFt |
| 41 | ALLIGATOR CR | H | 100.00 | SqFt |
| 41 | ALLIGATOR CR | H | 750.00 | SqFt |
| 48 | L & T CR | M | 200.00 | Ft |
| 57 | WEATHERING | M | 4000.00 | SqFt |

| | | | | | | | | | | |
|-----------------------|----|--------------|---|--------------|--------------|--|-------------|----|--|--|
| Sample Number: | 02 | Type: | R | Area: | 3440.00 SqFt | | PCI: | 24 | | |
|-----------------------|----|--------------|---|--------------|--------------|--|-------------|----|--|--|

Sample Comments: Created by Inspection Schedule

| | | | | |
|----|--------------|---|---------|------|
| 41 | ALLIGATOR CR | H | 200.00 | SqFt |
| 48 | L & T CR | M | 116.00 | Ft |
| 48 | L & T CR | M | 80.00 | Ft |
| 57 | WEATHERING | M | 3000.00 | SqFt |
| 57 | WEATHERING | H | 440.00 | SqFt |

| | | | | | | | | | | | | | |
|---|-------------|----|--------------|--------------------------------|--------------------------|-------------|--------------|-----------|---------------|----|---------------|----------|---|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | Area: | 354,632 SqFt | | | | |
| Section: | 08 | of | 15 | From: | A01-05 | | | To: | A01-10 | | Last Const.: | 9/1/1980 | |
| Surface: | AAC | | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 77,012 SqFt | | Length: | 400 Ft | | Width: | 193 Ft | | | | | | |
| Slabs: | | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | |
| Shoulder: | | | Street Type: | | | Grade: | 0 | | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | | Work Type: | Base Course - Aggregate | | | Code: | BA-AG | | Is Major M&R: | True | |
| Work Date: | 9/2/1942 | | | Work Type: | New Construction - AC | | | Code: | NC-AC | | Is Major M&R: | True | |
| Work Date: | 9/1/1980 | | | Work Type: | Overlay - AC Structural | | | Code: | OL-AS | | Is Major M&R: | True | |
| Work Date: | 6/1/2001 | | | Work Type: | Crack Sealing - AC | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 9/1/2008 | | | Work Type: | Crack Seal - Wide Cracks | | | Code: | CS-WD | | Is Major M&R: | False | |
| Work Date: | 9/2/2008 | | | Work Type: | Patching - AC Deep | | | Code: | PA-AD | | Is Major M&R: | False | |
| Work Date: | 9/1/2012 | | | Work Type: | Crack Sealing - AC | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 9/1/2012 | | | Work Type: | Patching - AC Deep | | | Code: | PA-AD | | Is Major M&R: | False | |
| Work Date: | 9/1/2015 | | | Work Type: | Crack Sealing - AC | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 9/2/2015 | | | Work Type: | Patching - AC Deep | | | Code: | PA-AD | | Is Major M&R: | False | |
| Last Insp. Date: | 7/1/2022 | | | TotalSamples: | 16 | | | Surveyed: | 5 | | | | |
| Conditions: | PCI: | 45 | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | |
| Sample Number: | 05 | | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 44 | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | | |
| 48 | L & T CR | | L | 100.00 | | Ft | | | | | | | |
| 48 | L & T CR | | M | 200.00 | | Ft | | | | | | | |
| 48 | L & T CR | | M | 70.00 | | Ft | | | | | | | |
| 48 | L & T CR | | M | 138.00 | | Ft | | | | | | | |
| 50 | PATCHING | | L | 25.00 | | SqFt | | | | | | | |
| 50 | PATCHING | | L | 25.00 | | SqFt | | | | | | | |
| 50 | PATCHING | | L | 212.00 | | SqFt | | | | | | | |
| 50 | PATCHING | | L | 25.00 | | SqFt | | | | | | | |
| 50 | PATCHING | | L | 25.00 | | SqFt | | | | | | | |
| 52 | RAVELING | | M | 1000.00 | | SqFt | | | | | | | |
| 57 | WEATHERING | | M | 4000.00 | | SqFt | | | | | | | |
| Sample Number: | 06 | | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 45 | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | | |
| 48 | L & T CR | | L | 150.00 | | Ft | | | | | | | |
| 48 | L & T CR | | M | 56.00 | | Ft | | | | | | | |
| 48 | L & T CR | | M | 300.00 | | Ft | | | | | | | |
| 50 | PATCHING | | L | 25.00 | | SqFt | | | | | | | |
| 50 | PATCHING | | L | 25.00 | | SqFt | | | | | | | |
| 50 | PATCHING | | L | 25.00 | | SqFt | | | | | | | |
| 52 | RAVELING | | M | 1000.00 | | SqFt | | | | | | | |
| 57 | WEATHERING | | M | 4000.00 | | SqFt | | | | | | | |
| Sample Number: | 10 | | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 46 | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | | |
| 48 | L & T CR | | L | 100.00 | | Ft | | | | | | | |
| 48 | L & T CR | | L | 100.00 | | Ft | | | | | | | |
| 48 | L & T CR | | L | 50.00 | | Ft | | | | | | | |
| 48 | L & T CR | | L | 100.00 | | Ft | | | | | | | |
| 48 | L & T CR | | M | 20.00 | | Ft | | | | | | | |

| | | | | |
|----|------------|---|---------|------|
| 48 | L & T CR | M | 20.00 | Ft |
| 48 | L & T CR | M | 257.00 | Ft |
| 50 | PATCHING | L | 90.00 | SqFt |
| 50 | PATCHING | L | 60.00 | SqFt |
| 52 | RAVELING | M | 1000.00 | SqFt |
| 57 | WEATHERING | M | 4000.00 | SqFt |

Sample Number: 11

Type: R

Area: 5000.00 SqFt

PCI: 53

Sample Comments:

Created by Inspection Schedule

| | | | | |
|----|------------|---|---------|------|
| 48 | L & T CR | L | 200.00 | Ft |
| 48 | L & T CR | L | 50.00 | Ft |
| 48 | L & T CR | M | 20.00 | Ft |
| 48 | L & T CR | M | 137.00 | Ft |
| 50 | PATCHING | L | 60.00 | SqFt |
| 52 | RAVELING | M | 1000.00 | SqFt |
| 57 | WEATHERING | M | 4000.00 | SqFt |

Sample Number: 16

Type: R

Area: 5000.00 SqFt

PCI: 38

Sample Comments:

Created by Inspection Schedule

| | | | | |
|----|------------|---|---------|------|
| 48 | L & T CR | L | 150.00 | Ft |
| 48 | L & T CR | M | 100.00 | Ft |
| 48 | L & T CR | M | 84.00 | Ft |
| 50 | PATCHING | L | 85.00 | SqFt |
| 52 | RAVELING | M | 2500.00 | SqFt |
| 57 | WEATHERING | M | 2500.00 | SqFt |

| | | | | | | | | | | | | | | | | | | | | | | | |
|----------------------|--------------|-------------|--|--------------------------------|--|--------------------------------|--|---------------|--|--------------|--|----------------------------------|--|--------------|--|--------------|--|----------|--|---------------|--|------|--|
| Network: | | LaGrande | | Name: | | LaGrande / Union County | | | | | | | | | | | | | | | | | |
| Branch: | | A01LG | | Name: | | Apron 01 LaGrande | | Use: | | APRON | | Area: | | 354,632 SqFt | | | | | | | | | |
| Section: | | 03 | | of | | 15 | | From: | | A01-02 | | To: | | HANGARS | | Last Const.: | | 9/2/1949 | | | | | |
| Surface: | | AC | | Family: | | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | | KLGD | | Category: | | O | | Rank: | | S | | | | | |
| Area: | | 48,880 SqFt | | Length: | | 280 Ft | | Width: | | 236 Ft | | | | | | | | | | | | | |
| Slabs: | | | | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: | | | | Ft | | | | | | | |
| Shoulder: | | | | Street Type: | | | | Grade: | | 0 | | Lanes: | | 0 | | | | | | | | | |
| Section Comments: | | | | | | | | | | | | | | | | | | | | | | | |
| Work Date: | | | | 9/1/1949 | | | | Work Type: | | | | Base Course - Unknown (Major MR) | | | | Code: | | BA-UN | | Is Major M&R: | | True | |
| Work Date: | | | | 9/2/1949 | | | | Work Type: | | | | New Construction - AC | | | | Code: | | NC-AC | | Is Major M&R: | | True | |
| Last Insp. Date: | | | | 7/1/2022 | | | | TotalSamples: | | 12 | | Surveyed: | | | | 4 | | | | | | | |
| Conditions: | | | | PCI: | | | | 1 | | | | | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | | | | | | | | | | | |
| Sample Number: | | 01 | | Type: | | R | | Area: | | 4000.00 SqFt | | PCI: | | 0 | | | | | | | | | |
| Sample Comments: | | | | Created by Inspection Schedule | | | | | | | | | | | | | | | | | | | |
| 41 | ALLIGATOR CR | | | H | | 2000.00 | | SqFt | | | | | | | | | | | | | | | |
| 57 | WEATHERING | | | H | | 4000.00 | | SqFt | | | | | | | | | | | | | | | |
| Sample Number: | | 04 | | Type: | | R | | Area: | | 4900.00 SqFt | | PCI: | | 0 | | | | | | | | | |
| Sample Comments: | | | | Created by Inspection Schedule | | | | | | | | | | | | | | | | | | | |
| 41 | ALLIGATOR CR | | | H | | 2900.00 | | SqFt | | | | | | | | | | | | | | | |
| 57 | WEATHERING | | | H | | 4900.00 | | SqFt | | | | | | | | | | | | | | | |
| Sample Number: | | 08 | | Type: | | R | | Area: | | 4100.00 SqFt | | PCI: | | 5 | | | | | | | | | |
| Sample Comments: | | | | Created by Inspection Schedule | | | | | | | | | | | | | | | | | | | |
| 41 | ALLIGATOR CR | | | M | | 300.00 | | SqFt | | | | | | | | | | | | | | | |
| 41 | ALLIGATOR CR | | | H | | 100.00 | | SqFt | | | | | | | | | | | | | | | |
| 50 | PATCHING | | | H | | 1350.00 | | SqFt | | | | | | | | | | | | | | | |
| 57 | WEATHERING | | | M | | 2750.00 | | SqFt | | | | | | | | | | | | | | | |
| Sample Number: | | 11 | | Type: | | R | | Area: | | 4000.00 SqFt | | PCI: | | 0 | | | | | | | | | |
| Sample Comments: | | | | Created by Inspection Schedule | | | | | | | | | | | | | | | | | | | |
| 41 | ALLIGATOR CR | | | H | | 2000.00 | | SqFt | | | | | | | | | | | | | | | |
| 57 | WEATHERING | | | M | | 2000.00 | | SqFt | | | | | | | | | | | | | | | |
| 57 | WEATHERING | | | H | | 2000.00 | | SqFt | | | | | | | | | | | | | | | |

| | | | | | | | | | | | |
|---|--------------|---------|-------------------------------------|-------------------------|-------------|-----------|--------------|---------------|--------------|---------------|-------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | Area: | 354,632 SqFt | | |
| Section: | 05 | of | 15 | From: | A01-04 | | To: | A01-08 | Last Const.: | 9/1/1980 | |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | KLGD | Category: | O | Rank: | S | |
| Area: | 19,600 SqFt | | Length: | 245 Ft | | Width: | 80 Ft | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | |
| Shoulder: | Street Type: | | Grade: | | 0 | | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | True |
| Work Date: | 9/2/1942 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True |
| Work Date: | 9/1/1980 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True |
| Work Date: | 6/1/2001 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False |
| Work Date: | 9/1/2008 | | Work Type: Crack Seal - Wide Cracks | | | | Code: | CS-WD | | Is Major M&R: | False |
| Work Date: | 9/2/2008 | | Work Type: Patching - AC Deep | | | | Code: | PA-AD | | Is Major M&R: | False |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False |
| Work Date: | 9/1/2015 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False |
| Work Date: | 9/2/2015 | | Work Type: Patching - AC Deep | | | | Code: | PA-AD | | Is Major M&R: | False |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 4 | | Surveyed: | | | | | 3 |
| Conditions: | PCI: 47 | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 02 | | Type: | R | | Area: | 6000.00 SqFt | | PCI: | 51 | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | |
| 45 | DEPRESSION | | L | 25.00 SqFt | | | | | | | |
| 48 | L & T CR | | M | 330.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 75.00 Ft | | | | | | | |
| 57 | WEATHERING | | M | 5000.00 SqFt | | | | | | | |
| 57 | WEATHERING | | H | 1000.00 SqFt | | | | | | | |
| Sample Number: | 03 | | Type: | R | | Area: | 4000.00 SqFt | | PCI: | 48 | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | | L | 112.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 50.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 50.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 50.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 50.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 80.00 Ft | | | | | | | |
| 57 | WEATHERING | | M | 3250.00 SqFt | | | | | | | |
| 57 | WEATHERING | | H | 750.00 SqFt | | | | | | | |
| Sample Number: | 04 | | Type: | R | | Area: | 3600.00 SqFt | | PCI: | 41 | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | |
| 41 | ALLIGATOR CR | | M | 12.00 SqFt | | | | | | | |
| 48 | L & T CR | | M | 161.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 84.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 90.00 Ft | | | | | | | |
| 50 | PATCHING | | L | 84.00 SqFt | | | | | | | |
| 50 | PATCHING | | L | 138.00 SqFt | | | | | | | |
| 57 | WEATHERING | | M | 2880.00 SqFt | | | | | | | |
| 57 | WEATHERING | | H | 720.00 SqFt | | | | | | | |

| | | | | | | | | | |
|-----------------------------|--------------------------------|----------------|---|-------------------|-------------------------|------------------|------------------|--------------|--------------------------------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | Area: | 354,632 SqFt |
| Section: | 06 | of | 15 | From: | A01-08 | | To: | A01-01 | Last Const.: 9/2/2009 |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | KLGD | Category: | O | Rank: S |
| Area: | 4,529 SqFt | | Length: | 113 Ft | | Width: | 40 Ft | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: Ft |
| Shoulder: | Street Type: | | Grade: 0 | | Lanes: 0 | | | | |
| Section Comments: | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | Is Major M&R: True |
| Work Date: | 9/2/1942 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | Is Major M&R: True |
| Work Date: | 9/3/1942 | | Work Type: New Construction - AC | | | | Code: | NC-AC | Is Major M&R: True |
| Work Date: | 9/1/2009 | | Work Type: Cold Milling | | | | Code: | MI-CO | Is Major M&R: False |
| Work Date: | 9/2/2009 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | Is Major M&R: True |
| Work Date: | 9/1/2015 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | Is Major M&R: False |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 1 | | Surveyed: | 1 | | |
| Conditions: | PCI: | 83 | | | | | | | |
| Inspection Comments: | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4529.00 SqFt | | PCI: | 83 | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | | M | 56.00 Ft | | | | | |
| 57 | WEATHERING | | L | 4529.00 SqFt | | | | | |

| | | | | | | | | | | | | | |
|----------------------|-------------|-------|---------------|--------------------------------|--------------|-------------|-------|-------|---------------|----|---------------|----------|---|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | Area: | 354,632 SqFt | | | | |
| Section: | 01 | of | 15 | From: | TA-02 | | | To: | A01-02 | | Last Const.: | 9/1/2009 | |
| Surface: | AAC | | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | S |
| Area: | 11,524 SqFt | | Length: | 1,088 Ft | | Width: | 12 Ft | | | | | | |
| Slabs: | | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | |
| Shoulder: | | | Street Type: | | | Grade: | 0 | | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: | Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | True | |
| Work Date: | 9/2/1942 | | Work Type: | Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | True | |
| Work Date: | 9/3/1942 | | Work Type: | New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True | |
| Work Date: | 9/1/1974 | | Work Type: | Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True | |
| Work Date: | 9/1/2009 | | Work Type: | Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True | |
| Work Date: | 9/1/2015 | | Work Type: | Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 3 | | Surveyed: | 2 | | | | | | |
| Conditions: | PCI: 100 | | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 3151.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 3600.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |

| | | | | | | | | | | | |
|----------------------|--------------|--------------------------------|--------------------------------|-------------------|-------------------------|----------------------------------|---------------|--------|-----------------------|---------------|-------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | Area: | 354,632 SqFt | | |
| Section: | 10 | of | 15 | From: | A01-08 | | To: | A01-11 | Last Const.: 9/2/1980 | | |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | Zone: | KLGD | Category: | O | Rank: | P | | |
| Area: | 54,850 SqFt | | Length: | 255 Ft | | Width: | 215 Ft | | | | |
| Slabs: | Slab Length: | | Ft | Slab Width: | | Ft | Joint Length: | | Ft | | |
| Shoulder: | Street Type: | | Grade: | | 0 | Lanes: | | 0 | | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 9/1/1980 | | Work Type: | | | Base Course - Unknown (Major MR) | | Code: | BA-UN | Is Major M&R: | True |
| Work Date: | 9/2/1980 | | Work Type: | | | New Construction - AC | | Code: | NC-AC | Is Major M&R: | True |
| Work Date: | 6/1/2001 | | Work Type: | | | Crack Sealing - AC | | Code: | CS-AC | Is Major M&R: | False |
| Work Date: | 9/1/2008 | | Work Type: | | | Crack Seal - Wide Cracks | | Code: | CS-WD | Is Major M&R: | False |
| Work Date: | 9/2/2008 | | Work Type: | | | Surface Treatment - Slurry Seal | | Code: | SS-ST | Is Major M&R: | False |
| Work Date: | 9/1/2012 | | Work Type: | | | Crack Sealing - AC | | Code: | CS-AC | Is Major M&R: | False |
| Work Date: | 9/2/2012 | | Work Type: | | | Patching - AC Deep | | Code: | PA-AD | Is Major M&R: | False |
| Work Date: | 9/1/2015 | | Work Type: | | | Crack Sealing - AC | | Code: | CS-AC | Is Major M&R: | False |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 10 | | Surveyed: | | 4 | | | |
| Conditions: | PCI: | 66 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 6340.00 SqFt | | | PCI: | 68 | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | |
| 48 | L & T CR | L | 250.00 | Ft | | | | | | | |
| 48 | L & T CR | L | 100.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 74.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 30.00 | Ft | | | | | | | |
| 50 | PATCHING | L | 18.00 | SqFt | | | | | | | |
| 57 | WEATHERING | M | 6340.00 | SqFt | | | | | | | |
| Sample Number: | 05 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 67 | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | |
| 48 | L & T CR | L | 200.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 100.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 50.00 | Ft | | | | | | | |
| 50 | PATCHING | L | 32.00 | SqFt | | | | | | | |
| 57 | WEATHERING | M | 5000.00 | SqFt | | | | | | | |
| Sample Number: | 07 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 66 | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | |
| 48 | L & T CR | L | 100.00 | Ft | | | | | | | |
| 48 | L & T CR | L | 50.00 | Ft | | | | | | | |
| 48 | L & T CR | L | 50.00 | Ft | | | | | | | |
| 48 | L & T CR | L | 100.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 100.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 25.00 | Ft | | | | | | | |
| 50 | PATCHING | L | 28.00 | SqFt | | | | | | | |
| 57 | WEATHERING | M | 5000.00 | SqFt | | | | | | | |
| Sample Number: | 09 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 65 | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | |
| 48 | L & T CR | L | 300.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 50.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 25.00 | Ft | | | | | | | |
| 50 | PATCHING | L | 90.00 | SqFt | | | | | | | |
| 50 | PATCHING | L | 70.00 | SqFt | | | | | | | |
| 50 | PATCHING | L | 35.00 | SqFt | | | | | | | |

| | | | | |
|----|------------|---|---------|------|
| 50 | PATCHING | L | 35.00 | SqFt |
| 57 | WEATHERING | M | 5000.00 | SqFt |

| | | | | | | | | | | | |
|----------------------|------------|--------------|--------------------------------|-------------------------|-------------------------|-----------|--------|---------------|--------------|---------------|----------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | Area: | 354,632 SqFt | | |
| Section: | 13 | of | 15 | From: | A01LG-11 | | | To: | A01LG-12 | Last Const.: | 9/4/2019 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | | Zone: | | Category: | | Rank: | P |
| Area: | 7,040 SqFt | | Length: | 185 Ft | | Width: | 30 Ft | | | | |
| Slabs: | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | |
| Shoulder: | | Street Type: | | Grade: | 0 | | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 9/1/2019 | | Work Type: | Geotextile | | | Code: | FB-TX | | Is Major M&R: | False |
| Work Date: | 9/2/2019 | | Work Type: | Subbase - Aggregate | | | Code: | SB-AG | | Is Major M&R: | False |
| Work Date: | 9/3/2019 | | Work Type: | Base Course - Aggregate | | | Code: | BA-AG | | Is Major M&R: | False |
| Work Date: | 9/4/2019 | | Work Type: | New Construction - AC | | | Code: | NC-AC | | Is Major M&R: | True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 1 | | Surveyed: | 1 | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 7040.00 SqFt | | | PCI: | 100 | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |

| | | | | | | | | | | | |
|----------------------|------------|--------------|--------------------------------|-------------------------|--------------|-----------|-----------|---------------|--------------|---------------|----------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | Area: | 354,632 SqFt | | |
| Section: | 14 | of | 15 | From: | A01LG-12 | | To: | TALG-03 | | Last Const.: | 9/4/2019 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | | Category: | | Rank: | P | |
| Area: | 4,336 SqFt | | Length: | 115 Ft | | Width: | 20 Ft | | | | |
| Slabs: | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | |
| Shoulder: | | Street Type: | | Grade: | 0 | | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 9/1/2019 | | Work Type: | Geotextile | | | Code: | FB-TX | | Is Major M&R: | False |
| Work Date: | 9/2/2019 | | Work Type: | Subbase - Aggregate | | | Code: | SB-AG | | Is Major M&R: | False |
| Work Date: | 9/3/2019 | | Work Type: | Base Course - Aggregate | | | Code: | BA-AG | | Is Major M&R: | False |
| Work Date: | 9/4/2019 | | Work Type: | New Construction - AC | | | Code: | NC-AC | | Is Major M&R: | True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 1 | | Surveyed: | 1 | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4336.00 SqFt | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |

| | | | | | | | | | | | | |
|-----------------------------|---------------------|----------------|---|-------------------|-------------------------|------------------|--------------|-------------|----------------------|--------------------------------|---------------------|----------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | | Area: | 354,632 SqFt | | |
| Section: | 12 | of | 15 | From: | A01LG-11 | | | To: | A01LG-15 | | Last Const.: | 9/3/2019 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Apron | | Zone: | | | | Category: | Rank: P | | |
| Area: | 36,243 SqFt | | Length: | 370 Ft | | Width: | 95 Ft | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: | | Ft | |
| Shoulder: | Street Type: | | | | Grade: | 0 | | | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | | | | |
| Work Date: | 9/1/2019 | | Work Type: Geotextile | | | | Code: | FB-TX | | Is Major M&R: False | | |
| Work Date: | 9/2/2019 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: False | | |
| Work Date: | 9/3/2019 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: True | | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 8 | | Surveyed: | 6 | | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4764.00 SqFt | | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 4756.00 SqFt | | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 4762.00 SqFt | | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |
| Sample Number: | 05 | Type: | R | Area: | 4769.00 SqFt | | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |
| Sample Number: | 06 | Type: | R | Area: | 4890.00 SqFt | | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |
| Sample Number: | 07 | Type: | R | Area: | 4872.00 SqFt | | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |

| | | | | | | | | | | |
|-----------------------------|-------------|----------------------|--------------------------------|--------------------|--------------|----------------------|------------------|--------------------------|--------------|---|
| Network: | LaGrande | Name: | LaGrande / Union County | | | | | | | |
| Branch: | A01LG | Name: | Apron 01 LaGrande | | Use: | APRON | Area: | 354,632 SqFt | | |
| Section: | 15 | of | 15 | From: | A01LG-12 | To: | TALG-03 | Last Const.: | 9/4/2019 | |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | | Category: | | Rank: | P |
| Area: | 10,085 SqFt | Length: | 155 Ft | Width: | 40 Ft | | | | | |
| Slabs: | | Slab Length: | Ft | Slab Width: | Ft | Joint Length: | Ft | | | |
| Shoulder: | | Street Type: | | Grade: | 0 | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | |
| Work Date: | 9/1/2019 | Work Type: | Geotextile | | | Code: | FB-TX | Is Major M&R: | False | |
| Work Date: | 9/2/2019 | Work Type: | Subbase - Aggregate | | | Code: | SB-AG | Is Major M&R: | False | |
| Work Date: | 9/3/2019 | Work Type: | Base Course - Aggregate | | | Code: | BA-AG | Is Major M&R: | False | |
| Work Date: | 9/4/2019 | Work Type: | New Construction - AC | | | Code: | NC-AC | Is Major M&R: | True | |
| Last Insp. Date: | 7/1/2022 | TotalSamples: | 2 | Surveyed: | 2 | | | | | |
| Conditions: | PCI: 100 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5318.00 SqFt | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | |
| <No Distress> | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 4767.00 SqFt | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | |
| <No Distress> | | | | | | | | | | |

| | | | | | | | | | | | | | |
|----------------------|--------------------------------|----|--------------|--------------------------------|--------------------------|-------------|--------------|-----------|---------------|--------------|---------------|-------|---|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | Area: | 354,632 SqFt | | | | |
| Section: | 07 | of | 15 | From: | A01-08 | | To: | A01-01 | | Last Const.: | 9/1/2009 | | |
| Surface: | AAC | | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 12,089 SqFt | | Length: | 513 Ft | | Width: | 24 Ft | | | | | | |
| Slabs: | | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | |
| Shoulder: | | | Street Type: | | | Grade: | 0 | | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | | Work Type: | Base Course - Aggregate | | | Code: | BA-AG | | Is Major M&R: | True | |
| Work Date: | 9/2/1942 | | | Work Type: | New Construction - AC | | | Code: | NC-AC | | Is Major M&R: | True | |
| Work Date: | 9/1/1980 | | | Work Type: | Overlay - AC Structural | | | Code: | OL-AS | | Is Major M&R: | True | |
| Work Date: | 6/1/2001 | | | Work Type: | Crack Sealing - AC | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 9/1/2008 | | | Work Type: | Crack Seal - Wide Cracks | | | Code: | CS-WD | | Is Major M&R: | False | |
| Work Date: | 9/2/2008 | | | Work Type: | Patching - AC Deep | | | Code: | PA-AD | | Is Major M&R: | False | |
| Work Date: | 9/1/2009 | | | Work Type: | Overlay - AC Structural | | | Code: | OL-AS | | Is Major M&R: | True | |
| Work Date: | 9/1/2015 | | | Work Type: | Crack Sealing - AC | | | Code: | CS-AC | | Is Major M&R: | False | |
| Last Insp. Date: | 7/1/2022 | | | TotalSamples: | 2 | | | Surveyed: | 2 | | | | |
| Conditions: | PCI: | 78 | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | |
| Sample Number: | 01 | | Type: | R | | Area: | 5948.00 SqFt | | PCI: | 79 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| 48 | L & T CR | | L | 148.00 Ft | | | | | | | | | |
| 48 | L & T CR | | L | 27.00 Ft | | | | | | | | | |
| 48 | L & T CR | | M | 56.00 Ft | | | | | | | | | |
| 57 | WEATHERING | | L | 5948.00 SqFt | | | | | | | | | |
| Sample Number: | 02 | | Type: | R | | Area: | 6141.00 SqFt | | PCI: | 76 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| 48 | L & T CR | | L | 230.00 Ft | | | | | | | | | |
| 48 | L & T CR | | M | 30.00 Ft | | | | | | | | | |
| 48 | L & T CR | | M | 66.00 Ft | | | | | | | | | |
| 57 | WEATHERING | | L | 6141.00 SqFt | | | | | | | | | |

| | | | | | | | | | |
|-----------------------------|---------------------|----------------|--|-------------------|-------------------------|------------------|------------------|---------------------|-------------------------------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | Area: | 354,632 SqFt |
| Section: | 02 | of | 15 | From: | A01-01 | To: | A01-03 | Last Const.: | 9/1/2009 |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | KLGD | Category: | O | Rank: S |
| Area: | 12,600 SqFt | | Length: | 280 Ft | | Width: | 45 Ft | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: Ft |
| Shoulder: | Street Type: | | | | Grade: 0 | | Lanes: 0 | | |
| Section Comments: | | | | | | | | | |
| Work Date: | 9/1/1949 | | Work Type: Base Course - Unknown (Major MR) | | | | Code: | BA-UN | Is Major M&R: True |
| Work Date: | 9/2/1949 | | Work Type: New Construction - AC | | | | Code: | NC-AC | Is Major M&R: True |
| Work Date: | 9/1/2009 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | Is Major M&R: True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 3 | | Surveyed: | 2 | | |
| Conditions: | PCI: 72 | | | | | | | | |
| Inspection Comments: | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4500.00 SqFt | | PCI: | 71 | |
| Sample Comments: | | | | | | | | | |
| 48 | L & T CR | L | 26.00 | Ft | | | | | |
| 48 | L & T CR | L | 21.00 | Ft | | | | | |
| 48 | L & T CR | M | 50.00 | Ft | | | | | |
| 48 | L & T CR | M | 100.00 | Ft | | | | | |
| 57 | WEATHERING | L | 4500.00 | SqFt | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 4500.00 SqFt | | PCI: | 73 | |
| Sample Comments: | | | | | | | | | |
| 48 | L & T CR | L | 17.00 | Ft | | | | | |
| 48 | L & T CR | M | 50.00 | Ft | | | | | |
| 48 | L & T CR | M | 100.00 | Ft | | | | | |
| 57 | WEATHERING | L | 4500.00 | SqFt | | | | | |

| | | | | | | | | | | | | |
|---|--------------|---------|---|-------------------|-------------------------|--------|--------|---------------|-------|---------------------|--------------|----------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | | Area: | 354,632 SqFt | | |
| Section: | 11 | of | 15 | From: | A01-10 | | | To: | - | | Last Const.: | 9/2/1980 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 30,587 SqFt | | Length: | 145 Ft | | Width: | 215 Ft | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | |
| Shoulder: | Street Type: | | | | Grade: | 0 | | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | | | |
| Work Date: | 9/1/1980 | | Work Type: Base Course - Unknown (Major MR) | | | | Code: | BA-UN | | Is Major M&R: True | | |
| Work Date: | 9/2/1980 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: True | | |
| Work Date: | 6/1/2001 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | |
| Work Date: | 9/1/2008 | | Work Type: Crack Seal - Wide Cracks | | | | Code: | CS-WD | | Is Major M&R: False | | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | |
| Work Date: | 9/1/2015 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | |
| Last Insp. Date: 7/1/2022 | | | | | | | | | | | | |
| TotalSamples: | | | 7 | | Surveyed: 3 | | | | | | | |
| Conditions: | PCI: 67 | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4576.00 SqFt | | PCI: | 70 | | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | |
| 48 | L & T CR | | L | 210.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 23.00 | Ft | | | | | | | |
| 48 | L & T CR | | M | 65.00 | Ft | | | | | | | |
| 57 | WEATHERING | | M | 4576.00 | SqFt | | | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 63 | | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | |
| 48 | L & T CR | | L | 100.00 | Ft | | | | | | | |
| 48 | L & T CR | | M | 50.00 | Ft | | | | | | | |
| 48 | L & T CR | | M | 57.00 | Ft | | | | | | | |
| 48 | L & T CR | | M | 100.00 | Ft | | | | | | | |
| 48 | L & T CR | | M | 50.00 | Ft | | | | | | | |
| 48 | L & T CR | | M | 25.00 | Ft | | | | | | | |
| 57 | WEATHERING | | M | 5000.00 | SqFt | | | | | | | |
| Sample Number: | 04 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 68 | | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | |
| 48 | L & T CR | | L | 100.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 100.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 70.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 100.00 | Ft | | | | | | | |
| 48 | L & T CR | | M | 100.00 | Ft | | | | | | | |
| 57 | WEATHERING | | M | 5000.00 | SqFt | | | | | | | |

| | | | | | | | | | | | |
|----------------------|-------------|--------------------------------|---|--------------------------------|-------------------------|-------------|--------------|-------|---------------|---------------------|----------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | |
| Branch: | A01LG | | Name: | Apron 01 LaGrande | | Use: | APRON | | Area: | 354,632 SqFt | |
| Section: | 09 | of | 15 | From: | A01-10 | | To: | TA-02 | | Last Const.: | 9/1/2009 |
| Surface: | AAC | | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | KLGD | | Category: | O | |
| Area: | 17,817 SqFt | | Length: | 538 Ft | | Width: | 34 Ft | | | | |
| Slabs: | | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | |
| Shoulder: | | | Street Type: | | | Grade: | 0 | | Lanes: | 0 | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 9/1/1980 | | Work Type: Base Course - Unknown (Major MR) | | | | Code: | BA-UN | | Is Major M&R: True | |
| Work Date: | 9/2/1980 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: True | |
| Work Date: | 6/1/2001 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | |
| Work Date: | 9/1/2008 | | Work Type: Crack Seal - Wide Cracks | | | | Code: | CS-WD | | Is Major M&R: False | |
| Work Date: | 9/2/2008 | | Work Type: Surface Treatment - Slurry Seal | | | | Code: | SS-ST | | Is Major M&R: False | |
| Work Date: | 9/1/2009 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: True | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | |
| Work Date: | 9/1/2015 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 3 | | Surveyed: | | 2 | | | |
| Conditions: | PCI: 74 | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 01 | | Type: | R | | Area: | 6150.00 SqFt | | PCI: | 76 | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | |
| 48 | L & T CR | | L | 100.00 Ft | | | | | | | |
| 48 | L & T CR | | L | 100.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 100.00 Ft | | | | | | | |
| 57 | WEATHERING | | L | 6150.00 SqFt | | | | | | | |
| Sample Number: | 02 | | Type: | R | | Area: | 6920.00 SqFt | | PCI: | 73 | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | |
| 48 | L & T CR | | L | 170.00 Ft | | | | | | | |
| 48 | L & T CR | | L | 260.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 34.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 16.00 Ft | | | | | | | |
| 48 | L & T CR | | M | 93.00 Ft | | | | | | | |
| 57 | WEATHERING | | L | 6920.00 SqFt | | | | | | | |

| | | | | | | | | | | | |
|-----------------------------|---------------------|---------------------|----------------------------------|-------------------------|--------------------|------------------|---------------|----------------------|---------------------|--------------------------|-------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | AHELILG | | Name: | Apron Helipad | | Use: | HELIPAD | Area: | 2,496 SqFt | | |
| Section: | 01 | of 4 | From: | A01LG-13 | | To: | A01LG-13 | | Last Const.: | 9/4/2019 | |
| Surface: | PCC | Family: | 2022_Eastern_Cat1/2/3_AIUses_PCC | | Zone: | Category: | | Rank: | P | | |
| Area: | 400 SqFt | | Length: | 20 Ft | | Width: | 20 Ft | | | | |
| Slabs: | 4 | Slab Length: | 10 Ft | | Slab Width: | 10 Ft | | Joint Length: | 40 Ft | | |
| Shoulder: | Street Type: | | Grade: | | 0 | | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 9/1/2019 | | Work Type: | Geotextile | | | Code: | FB-TX | | Is Major M&R: | False |
| Work Date: | 9/2/2019 | | Work Type: | Subbase - Aggregate | | | Code: | SB-AG | | Is Major M&R: | False |
| Work Date: | 9/3/2019 | | Work Type: | Base Course - Aggregate | | | Code: | BA-AG | | Is Major M&R: | False |
| Work Date: | 9/4/2019 | | Work Type: | New Construction - PCC | | | Code: | NC-PC | | Is Major M&R: | True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 1 | | Surveyed: | 1 | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4.00 Slabs | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |

| | | | | | | | | | |
|-----------------------------|----------|----------------------|----------------------------------|--------------------|------------|--------------------------|------------|---------------------|----------|
| Network: | LaGrande | Name: | LaGrande / Union County | | | | | | |
| Branch: | AHELILG | Name: | Apron Helipad | Use: | HELIPAD | Area: | 2,496 SqFt | | |
| Section: | 03 | of | 4 | From: | A01LG-14 | To: | A01LG-14 | Last Const.: | 9/4/2019 |
| Surface: | PCC | Family: | 2022_Eastern_Cat1/2/3_AIUses_PCC | Zone: | | Category: | | Rank: | P |
| Area: | 400 SqFt | Length: | 20 Ft | Width: | 20 Ft | | | | |
| Slabs: | 4 | Slab Length: | 10 Ft | Slab Width: | 10 Ft | Joint Length: | 40 Ft | | |
| Shoulder: | | Street Type: | | Grade: | 0 | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | |
| Work Date: | 9/1/2019 | Work Type: | Geotextile | Code: | FB-TX | Is Major M&R: | False | | |
| Work Date: | 9/2/2019 | Work Type: | Subbase - Aggregate | Code: | SB-AG | Is Major M&R: | False | | |
| Work Date: | 9/3/2019 | Work Type: | Base Course - Aggregate | Code: | BA-AG | Is Major M&R: | False | | |
| Work Date: | 9/4/2019 | Work Type: | New Construction - PCC | Code: | NC-PC | Is Major M&R: | True | | |
| Last Insp. Date: | 7/1/2022 | TotalSamples: | 1 | Surveyed: | 1 | | | | |
| Conditions: | PCI: 100 | | | | | | | | |
| Inspection Comments: | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4.00 Slabs | PCI: | 100 | | |
| Sample Comments: | | | | | | | | | |
| <No Distress> | | | | | | | | | |

| | | | | | | | | | |
|-----------------------------|----------|----------------------|----------------------------------|--------------------|------------|--------------------------|------------|---------------------|----------|
| Network: | LaGrande | Name: | LaGrande / Union County | | | | | | |
| Branch: | AHELILG | Name: | Apron Helipad | Use: | HELIPAD | Area: | 2,496 SqFt | | |
| Section: | 02 | of | 4 | From: | A01LG-13 | To: | A01LG-13 | Last Const.: | 9/4/2019 |
| Surface: | PCC | Family: | 2022_Eastern_Cat1/2/3_AIUses_PCC | Zone: | | Category: | | Rank: | P |
| Area: | 400 SqFt | Length: | 20 Ft | Width: | 20 Ft | | | | |
| Slabs: | 4 | Slab Length: | 10 Ft | Slab Width: | 10 Ft | Joint Length: | 40 Ft | | |
| Shoulder: | | Street Type: | | Grade: | 0 | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | |
| Work Date: | 9/1/2019 | Work Type: | Geotextile | Code: | FB-TX | Is Major M&R: | False | | |
| Work Date: | 9/2/2019 | Work Type: | Subbase - Aggregate | Code: | SB-AG | Is Major M&R: | False | | |
| Work Date: | 9/3/2019 | Work Type: | Base Course - Aggregate | Code: | BA-AG | Is Major M&R: | False | | |
| Work Date: | 9/4/2019 | Work Type: | New Construction - PCC | Code: | NC-PC | Is Major M&R: | True | | |
| Last Insp. Date: | 7/1/2022 | TotalSamples: | 1 | Surveyed: | 1 | | | | |
| Conditions: | PCI: 100 | | | | | | | | |
| Inspection Comments: | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4.00 Slabs | PCI: | 100 | | |
| Sample Comments: | | | | | | | | | |
| <No Distress> | | | | | | | | | |

| | | | | | | | | | | | |
|----------------------|------------|--------------|----------------------------------|-------------------------|-------------|-----------|-----------|---------------|----------|---------------|-------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | AHELILG | Name: | Apron Helipad | | Use: | HELIPAD | Area: | 2,496 SqFt | | | |
| Section: | 04 | of | 4 | From: | A01LG-15 | To: | A01LG-15 | Last Const.: | 9/4/2019 | | |
| Surface: | PCC | Family: | 2022_Eastern_Cat1/2/3_AIUses_PCC | | Zone: | | Category: | | Rank: | P | |
| Area: | 1,296 SqFt | | Length: | 36 Ft | | Width: | 36 Ft | | | | |
| Slabs: | 9 | Slab Length: | 12 Ft | | Slab Width: | 12 Ft | | Joint Length: | 144 Ft | | |
| Shoulder: | | Street Type: | | | Grade: | 0 | | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 9/1/2019 | | Work Type: | Geotextile | | | Code: | FB-TX | | Is Major M&R: | False |
| Work Date: | 9/2/2019 | | Work Type: | Subbase - Aggregate | | | Code: | SB-AG | | Is Major M&R: | False |
| Work Date: | 9/3/2019 | | Work Type: | Base Course - Aggregate | | | Code: | BA-AG | | Is Major M&R: | False |
| Work Date: | 9/4/2019 | | Work Type: | New Construction - PCC | | | Code: | NC-PC | | Is Major M&R: | True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 1 | | Surveyed: | 1 | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 9.00 Slabs | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |

| | | | | | | | | | |
|-----------------------------|-----------------|---------------------|---|-------------------------------|--------------------|------------------|------------------|----------------------|--------------------------------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | |
| Branch: | AHTALG | | Name: | Taxiway A Hold Apron LaGrande | | Use: | APRON | Area: | 17,175 SqFt |
| Section: | 01 | of 1 | From: | Taxiway A | | | To: | End | Last Const.: 1/1/2021 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | | Category: | | Rank: P |
| Area: | 17,175 SqFt | | Length: | 170 Ft | | Width: | 100 Ft | | |
| Slabs: | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft |
| Shoulder: | | Street Type: | | Grade: | 0 | | Lanes: | 0 | |
| Section Comments: | | | | | | | | | |
| Work Date: | 1/1/2021 | | Work Type: Geotextile | | | | Code: | FB-TX | Is Major M&R: False |
| Work Date: | 1/1/2021 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | Is Major M&R: False |
| Work Date: | 1/1/2021 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | Is Major M&R: False |
| Work Date: | 1/1/2021 | | Work Type: New Construction - AC | | | | Code: | NC-AC | Is Major M&R: True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 3 | | Surveyed: | 3 | | |
| Conditions: | PCI: 100 | | | | | | | | |
| Inspection Comments: | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5725.00 SqFt | | PCI: | 100 | |
| Sample Comments: | | | | | | | | | |
| <No Distress> | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 5725.00 SqFt | | PCI: | 100 | |
| Sample Comments: | | | | | | | | | |
| <No Distress> | | | | | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 5725.00 SqFt | | PCI: | 100 | |
| Sample Comments: | | | | | | | | | |
| <No Distress> | | | | | | | | | |

| | | | | | | | | | | | |
|----------------------|--------------|--------------------------------|------------------------------------|-------------------------------|----------------------|-----------|--------|---------------|---------------------|--------------|-----------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | AHTCLG | | Name: | Taxiway C Hold Apron LaGrande | | Use: | APRON | Area: | 29,900 SqFt | | |
| Section: | 01 | of | 1 | From: | Taxiway C at R30 End | | | To: | End | Last Const.: | 10/4/2012 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Apron_AC/AAC | | Zone: | KLGD | | Category: | O | Rank: | P |
| Area: | 29,900 SqFt | | Length: | 130 Ft | | Width: | 230 Ft | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | |
| Shoulder: | Street Type: | | | | Grade: | 0 | | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 10/1/2012 | | Work Type: Geotextile | | | | Code: | FB-TX | Is Major M&R: False | | |
| Work Date: | 10/2/2012 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | Is Major M&R: False | | |
| Work Date: | 10/3/2012 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | Is Major M&R: False | | |
| Work Date: | 10/4/2012 | | Work Type: New Construction - AC | | | | Code: | NC-AC | Is Major M&R: True | | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 7 | | Surveyed: | 4 | | | | |
| Conditions: | PCI: | 81 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5250.00 SqFt | | | PCI: | 75 | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | |
| 48 | L & T CR | L | 170.00 Ft | | | | | | | | |
| 48 | L & T CR | L | 92.00 Ft | | | | | | | | |
| 48 | L & T CR | M | 44.00 Ft | | | | | | | | |
| 57 | WEATHERING | L | 5250.00 SqFt | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 89 | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | |
| 52 | RAVELING | L | 172.00 SqFt | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 SqFt | | | | | | | | |
| Sample Number: | 05 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 75 | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | |
| 48 | L & T CR | L | 376.00 Ft | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 SqFt | | | | | | | | |
| Sample Number: | 06 | Type: | R | Area: | 3200.00 SqFt | | | PCI: | 85 | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | |
| 48 | L & T CR | L | 95.00 Ft | | | | | | | | |
| 57 | WEATHERING | L | 3200.00 SqFt | | | | | | | | |

| | | | | | | | | | | | | |
|----------------------|--------------------------------|---------|------------------------------------|-----------------------|-------------------------|-------------|--------|-----------|---------------|---------------------|--------------|----------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | R12LG | | Name: | Runway 12/30 LaGrande | | Use: | RUNWAY | | Area: | 625,921 SqFt | | |
| Section: | 01 | of 3 | | From: | R12 End | | | To: | R12LG-2 | | Last Const.: | 6/1/2014 |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_RW_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 457,600 SqFt | | Length: | 4,576 Ft | | Width: | 100 Ft | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: | | Ft | |
| Shoulder: | Street Type: | | | | Grade: | 0 | | Lanes: | | 0 | | |
| Section Comments: | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: True | | |
| Work Date: | 9/2/1942 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: True | | |
| Work Date: | 9/3/1942 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: True | | |
| Work Date: | 9/1/1974 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: True | | |
| Work Date: | 9/1/1992 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: True | | |
| Work Date: | 9/1/2004 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | |
| Work Date: | 9/2/2004 | | Work Type: Surface Seal - Fog Seal | | | | Code: | SS-FS | | Is Major M&R: False | | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | |
| Work Date: | 6/1/2014 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: True | | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 92 | | Surveyed: 6 | | | | | | |
| Conditions: | PCI: 79 | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 87 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | | L | 50.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 67.00 | Ft | | | | | | | |
| 57 | WEATHERING | | L | 5000.00 | SqFt | | | | | | | |
| Sample Number: | 06 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 81 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | | L | 50.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 50.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 28.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 50.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 53.00 | Ft | | | | | | | |
| 57 | WEATHERING | | L | 5000.00 | SqFt | | | | | | | |
| Sample Number: | 36 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 76 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | | L | 30.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 155.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 50.00 | Ft | | | | | | | |
| 57 | WEATHERING | | L | 4500.00 | SqFt | | | | | | | |
| 57 | WEATHERING | | M | 500.00 | SqFt | | | | | | | |
| Sample Number: | 48 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 79 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | | L | 119.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 150.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 16.00 | Ft | | | | | | | |
| 57 | WEATHERING | | L | 5000.00 | SqFt | | | | | | | |
| Sample Number: | 85 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 77 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | | L | 100.00 | Ft | | | | | | | |

| | | | | |
|----|------------|---|---------|------|
| 48 | L & T CR | L | 15.00 | Ft |
| 48 | L & T CR | L | 19.00 | Ft |
| 48 | L & T CR | M | 50.00 | Ft |
| 57 | WEATHERING | L | 4950.00 | SqFt |
| 57 | WEATHERING | M | 50.00 | SqFt |

Sample Number: 90

Type: R

Area: 5000.00 SqFt

PCI: 72

Sample Comments: Created by Inspection Schedule

| | | | | |
|----|------------|---|---------|------|
| 48 | L & T CR | L | 64.00 | Ft |
| 48 | L & T CR | L | 350.00 | Ft |
| 57 | WEATHERING | L | 4950.00 | SqFt |
| 57 | WEATHERING | M | 50.00 | SqFt |

| | | | | | | | | | | | | | |
|---|--------------|---------|-----------------------------|-----------------------|-------------------------|-----------|--------------------------|---------------|---------|--------------|--------------|---------------|-------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | R12LG | | Name: | Runway 12/30 LaGrande | | Use: | RUNWAY | | Area: | 625,921 SqFt | | | |
| Section: | 02 | of | 3 | From: | R12LG-1 | | | To: | R30 End | | Last Const.: | 6/1/2014 | |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_RW_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P | |
| Area: | 102,400 SqFt | | Length: | 1,024 Ft | | Width: | 100 Ft | | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | | |
| Shoulder: | Street Type: | | Grade: | | 0 | | Lanes: | 0 | | | | | |
| Section Comments: | | | | | | | | | | | | | |
| Work Date: | 9/1/1991 | | Work Type: | | | | Base Course - Bituminous | | Code: | BA-BI | | Is Major M&R: | True |
| Work Date: | 9/2/1991 | | Work Type: | | | | New Construction - AC | | Code: | NC-AC | | Is Major M&R: | True |
| Work Date: | 9/1/2004 | | Work Type: | | | | Surface Seal - Fog Seal | | Code: | SS-FS | | Is Major M&R: | False |
| Work Date: | 9/1/2012 | | Work Type: | | | | Crack Sealing - AC | | Code: | CS-AC | | Is Major M&R: | False |
| Work Date: | 6/1/2014 | | Work Type: | | | | Overlay - AC Structural | | Code: | OL-AS | | Is Major M&R: | True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 21 | | Surveyed: | 5 | | | | | | |
| Conditions: | PCI: 86 | | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 89 | | | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | | |
| 48 | L & T CR | | L | 50.00 Ft | | | | | | | | | |
| 48 | L & T CR | | L | 21.00 Ft | | | | | | | | | |
| 57 | WEATHERING | | L | 5000.00 SqFt | | | | | | | | | |
| Sample Number: | 06 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 88 | | | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | | |
| 48 | L & T CR | | L | 50.00 Ft | | | | | | | | | |
| 48 | L & T CR | | L | 50.00 Ft | | | | | | | | | |
| 57 | WEATHERING | | L | 5000.00 SqFt | | | | | | | | | |
| Sample Number: | 11 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 87 | | | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | | |
| 48 | L & T CR | | L | 67.00 Ft | | | | | | | | | |
| 48 | L & T CR | | L | 50.00 Ft | | | | | | | | | |
| 57 | WEATHERING | | L | 5000.00 SqFt | | | | | | | | | |
| Sample Number: | 16 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 79 | | | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | | |
| 48 | L & T CR | | L | 50.00 Ft | | | | | | | | | |
| 48 | L & T CR | | L | 50.00 Ft | | | | | | | | | |
| 48 | L & T CR | | M | 50.00 Ft | | | | | | | | | |
| 57 | WEATHERING | | L | 5000.00 SqFt | | | | | | | | | |
| Sample Number: | 18 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 86 | | | | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | | | | |
| 48 | L & T CR | | L | 63.00 Ft | | | | | | | | | |
| 48 | L & T CR | | L | 72.00 Ft | | | | | | | | | |
| 57 | WEATHERING | | L | 5000.00 SqFt | | | | | | | | | |

| | | | | | | | | | | | |
|-----------------------------|--------------------------------|----------------|---|-------------------------|--------------------|------------------|--------------|------------------|----------------------|--------------------------|----------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | R12LG | | Name: | Runway 12/30 LaGrande | | Use: | RUNWAY | | Area: | 625,921 SqFt | |
| Section: | 03 | of 3 | From: | Section 03 | | | To: | 30 End | | Last Const.: | 6/1/2014 |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_RW_AC/AAC | | Zone: | KLGD | | Category: | O | Rank: | P |
| Area: | 65,921 SqFt | | Length: | 659 Ft | | Width: | 100 Ft | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: | Ft | |
| Shoulder: | Street Type: | | | | Grade: | 0 | | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 10/1/2012 | | Work Type: Geotextile | | | | Code: | FB-TX | | Is Major M&R: | False |
| Work Date: | 10/2/2012 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | False |
| Work Date: | 10/3/2012 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | False |
| Work Date: | 10/4/2012 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True |
| Work Date: | 6/1/2014 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 13 | | Surveyed: | 4 | | | | |
| Conditions: | PCI: | 83 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 84 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | |
| 48 | L & T CR | L | 55.00 | | Ft | | | | | | |
| 48 | L & T CR | L | 111.00 | | Ft | | | | | | |
| 57 | WEATHERING | L | 5000.00 | | SqFt | | | | | | |
| Sample Number: | 04 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 82 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | |
| 48 | L & T CR | L | 77.00 | | Ft | | | | | | |
| 48 | L & T CR | L | 50.00 | | Ft | | | | | | |
| 48 | L & T CR | L | 90.00 | | Ft | | | | | | |
| 57 | WEATHERING | L | 5000.00 | | SqFt | | | | | | |
| Sample Number: | 07 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 80 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | |
| 48 | L & T CR | L | 50.00 | | Ft | | | | | | |
| 48 | L & T CR | L | 125.00 | | Ft | | | | | | |
| 48 | L & T CR | L | 74.00 | | Ft | | | | | | |
| 57 | WEATHERING | L | 5000.00 | | SqFt | | | | | | |
| Sample Number: | 10 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 86 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | |
| 48 | L & T CR | L | 26.00 | | Ft | | | | | | |
| 48 | L & T CR | L | 100.00 | | Ft | | | | | | |
| 57 | WEATHERING | L | 5000.00 | | SqFt | | | | | | |

| | | | | | | | | | | | | | |
|----------------------|--------------------------------|---------|---|-----------------------|-------------------------|-----------|--------|-------|---------------|---------------------|--------------|----------|---|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | R16LG | | Name: | Runway 16/34 LaGrande | | Use: | RUNWAY | | Area: | 226,415 SqFt | | | |
| Section: | 03 | of | 7 | From: | R16-06 | | | To: | R34 END | | Last Const.: | 1/1/2021 | |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_RW_AC/AAC | | Zone: | KLGD | | | Category: | O | | Rank: | P |
| Area: | 168,713 SqFt | | Length: | 2,800 Ft | | Width: | 60 Ft | | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: | | Ft | | |
| Shoulder: | Street Type: | | | | Grade: | 0 | | | Lanes: | 0 | | | |
| Section Comments: | Section -07 prior to 2022 | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: True | | | |
| Work Date: | 9/2/1942 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: True | | | |
| Work Date: | 9/3/1942 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: True | | | |
| Work Date: | 9/1/1984 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: True | | | |
| Work Date: | 1/1/2004 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | | |
| Work Date: | 1/2/2004 | | Work Type: Surface Seal - Fog Seal | | | | Code: | SS-FS | | Is Major M&R: False | | | |
| Work Date: | 8/1/2008 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | | |
| Work Date: | 8/2/2008 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: True | | | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | | |
| Work Date: | 1/1/2021 | | Work Type: Cold Mill and Overlay - 3 Inches | | | | Code: | MOL-3 | | Is Major M&R: True | | | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 23 | | Surveyed: | | 6 | | | | | |
| Conditions: | PCI: 100 | | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 6000.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 05 | Type: | R | Area: | 6000.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 10 | Type: | R | Area: | 6000.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 15 | Type: | R | Area: | 6000.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 20 | Type: | R | Area: | 6000.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 25 | Type: | R | Area: | 6000.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |

| | | | | | | | | | | | | | |
|-----------------------------|--------------------------------|--------------|--|-----------------------------|-------------------------|---------------|------------------|--------|----------------------|--------------------------------|----------|--------------|---|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | R16LG | | Name: | Runway 16/34 LaGrande | | Use: | RUNWAY | | Area: | 226,415 SqFt | | | |
| Section: | 01 | of 7 | | From: | R16-04 | | To: | R16-06 | | Last Const.: | 1/1/2021 | | |
| Surface: | AAC | | Family: | 2022_Eastern_Cat3_RW_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 27,198 SqFt | | Length: | 454 Ft | | Width: | 60 Ft | | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: | | Ft | | |
| Shoulder: | Street Type: | | | | Grade: | | 0 | | Lanes: | | 0 | | |
| Section Comments: | Section -05 prior to 2022 | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: True | | | |
| Work Date: | 9/2/1942 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: True | | | |
| Work Date: | 9/3/1942 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: True | | | |
| Work Date: | 9/1/1984 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: True | | | |
| Work Date: | 1/1/2004 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | | |
| Work Date: | 1/2/2004 | | Work Type: Surface Seal - Fog Seal | | | | Code: | SS-FS | | Is Major M&R: False | | | |
| Work Date: | 8/1/2008 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | | |
| Work Date: | 8/2/2008 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: True | | | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | | |
| Work Date: | 1/1/2021 | | Work Type: Cold Mill and Overlay - 3 Inches | | | | Code: | MOL-3 | | Is Major M&R: True | | | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | | 10 | | Surveyed: | | 5 | | | | |
| Conditions: | PCI: 100 | | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 6000.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 6000.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 6000.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 04 | Type: | R | Area: | 4500.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 05 | Type: | R | Area: | 4295.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |

| | | | | | | | | | | | | |
|----------------------|--------------------------------|---------|-----------------------------|----------------------------------|--------------|-----------|--------|---------------|-------|--------------|---------------|-------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | R16LG | | Name: | Runway 16/34 LaGrande | | Use: | RUNWAY | | Area: | 226,415 SqFt | | |
| Section: | 02 | of 7 | From: | R16-05 | | | To: | R16-07 | | Last Const.: | 1/1/2021 | |
| Surface: | AC | Family: | 2022_Eastern_Cat3_RW_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 9,000 SqFt | | Length: | 150 Ft | | Width: | 60 Ft | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | |
| Shoulder: | Street Type: | | Grade: | | 0 | | Lanes: | 0 | | | | |
| Section Comments: | Section -06 prior to 2022 | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: | Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | True |
| Work Date: | 9/2/1942 | | Work Type: | Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | True |
| Work Date: | 9/3/1942 | | Work Type: | New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True |
| Work Date: | 9/1/1978 | | Work Type: | Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True |
| Work Date: | 1/1/2004 | | Work Type: | Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False |
| Work Date: | 1/2/2004 | | Work Type: | Surface Seal - Fog Seal | | | | Code: | SS-FS | | Is Major M&R: | False |
| Work Date: | 8/1/2008 | | Work Type: | Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | False |
| Work Date: | 8/2/2008 | | Work Type: | Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | False |
| Work Date: | 8/3/2008 | | Work Type: | Complete Reconstruction - AC | | | | Code: | CR-AC | | Is Major M&R: | True |
| Work Date: | 9/1/2012 | | Work Type: | Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False |
| Work Date: | 1/1/2021 | | Work Type: | Cold Mill and Overlay - 3 Inches | | | | Code: | MOL-3 | | Is Major M&R: | True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 2 | | Surveyed: | 2 | | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4500.00 SqFt | | PCI: | 100 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 4500.00 SqFt | | PCI: | 100 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |

| | | | | | | | | | | | |
|-----------------------------|-------------|---------------------|----------------------------------|----------------------|-------------------------|---------------|------------------|----------------------|---------------------|--------------------------|-------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | |
| Branch: | TAILG | | Name: | Taxiway A1 | | Use: | TAXIWAY | Area: | 23,227 SqFt | | |
| Section: | 01 | of | 1 | From: | Taxiway A | | To: | Runway 17/35 | Last Const.: | 1/1/2021 | |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | | Category: | | Rank: | P | |
| Area: | 23,227 SqFt | | Length: | 300 Ft | | Width: | 75 Ft | | | | |
| Slabs: | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | |
| Shoulder: | | Street Type: | | Grade: | 0 | | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 1/1/2021 | | | Work Type: | Geotextile | | | Code: | FB-TX | Is Major M&R: | False |
| Work Date: | 1/1/2021 | | | Work Type: | New Construction - AC | | | Code: | NC-AC | Is Major M&R: | True |
| Work Date: | 1/1/2021 | | | Work Type: | Subbase - Aggregate | | | Code: | SB-AG | Is Major M&R: | False |
| Work Date: | 1/1/2021 | | | Work Type: | Base Course - Aggregate | | | Code: | BA-AG | Is Major M&R: | False |
| Last Insp. Date: | 1/1/2022 | | | TotalSamples: | 5 | | Surveyed: | 5 | | | |
| Conditions: | PCI: | 100 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5135.00 SqFt | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 4817.00 SqFt | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 5280.00 SqFt | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |
| Sample Number: | 04 | Type: | R | Area: | 4303.00 SqFt | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |
| Sample Number: | 05 | Type: | R | Area: | 3680.00 SqFt | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |

| | | | | | | | | | | | |
|----------------------|-------------|--------------|----------------------------------|-------------------------|--------------|-----------|-----------|---------------|--------------|---------------|-------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | TA2LG | Name: | Taxiway A2 | | Use: | TAXIWAY | Area: | 11,300 SqFt | | | |
| Section: | 01 | of | 1 | From: | Taxiway A | | To: | Runway 17/35 | Last Const.: | 1/1/2021 | |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | | Category: | | Rank: | P | |
| Area: | 11,300 SqFt | Length: | 175 Ft | | Width: | 50 Ft | | | | | |
| Slabs: | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | |
| Shoulder: | | Street Type: | | | Grade: | 0 | | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 1/1/2021 | | Work Type: | Geotextile | | | Code: | FB-TX | | Is Major M&R: | False |
| Work Date: | 1/1/2021 | | Work Type: | New Construction - AC | | | Code: | NC-AC | | Is Major M&R: | True |
| Work Date: | 1/1/2021 | | Work Type: | Subbase - Aggregate | | | Code: | SB-AG | | Is Major M&R: | False |
| Work Date: | 1/1/2021 | | Work Type: | Base Course - Aggregate | | | Code: | BA-AG | | Is Major M&R: | False |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 2 | | Surveyed: | 2 | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 6514.00 SqFt | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 4783.00 SqFt | | PCI: | 100 | | | |
| Sample Comments: | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | |

| | | | | |
|--|---|--------------------------------------|-------------------------|--------------------------------|
| Network: LaGrande | | Name: LaGrande / Union County | | |
| Branch: TALG | Name: Taxiway A LaGrande | | Use: TAXIWAY | Area: 200,559 SqFt |
| Section: 01 | of 4 | From: R12 End | To: TALG-02 | Last Const.: 6/1/2014 |
| Surface: AAC | Family: 2022_Eastern_Cat3_Taxiway_AC/AAC | Zone: KLGD | Category: O | Rank: P |
| Area: 5,786 SqFt | Length: 75 Ft | Width: 70 Ft | | |
| Slabs: | Slab Length: Ft | Slab Width: Ft | Joint Length: Ft | |
| Shoulder: | Street Type: | Grade: 0 | Lanes: 0 | |
| Section Comments: | | | | |
| Work Date: 9/1/1942 | Work Type: Subbase - Aggregate | | Code: SB-AG | Is Major M&R: True |
| Work Date: 9/2/1942 | Work Type: Base Course - Aggregate | | Code: BA-AG | Is Major M&R: True |
| Work Date: 9/3/1942 | Work Type: New Construction - AC | | Code: NC-AC | Is Major M&R: True |
| Work Date: 9/1/1974 | Work Type: Overlay - AC Structural | | Code: OL-AS | Is Major M&R: True |
| Work Date: 9/1/1992 | Work Type: Overlay - AC Structural | | Code: OL-AS | Is Major M&R: True |
| Work Date: 9/1/1993 | Work Type: Surface Treatment - Slurry Seal | | Code: ST-SS | Is Major M&R: False |
| Work Date: 8/1/2008 | Work Type: Subbase - Aggregate | | Code: SB-AG | Is Major M&R: False |
| Work Date: 8/2/2008 | Work Type: Base Course - Aggregate | | Code: BA-AG | Is Major M&R: False |
| Work Date: 8/3/2008 | Work Type: Complete Reconstruction - AC | | Code: CR-AC | Is Major M&R: True |
| Work Date: 6/1/2014 | Work Type: Overlay - AC Structural | | Code: OL-AS | Is Major M&R: True |
| Last Insp. Date: 7/1/2022 | TotalSamples: 1 | Surveyed: 1 | | |
| Conditions: PCI: 80 | | | | |
| Inspection Comments: | | | | |
| Sample Number: 01 | Type: R | Area: 5786.00 SqFt | PCI: 80 | |
| Sample Comments: Created by Inspection Schedule | | | | |
| 48 | L & T CR | L | 153.00 Ft | |
| 48 | L & T CR | L | 62.00 Ft | |
| 48 | L & T CR | L | 75.00 Ft | |
| 57 | WEATHERING | L | 5786.00 SqFt | |

| | | | | | | | | | | | | | | |
|----------------------|--------------|--------------------------------|----------------------------------|----------|-------------------------|-----------|--------|---------------------------------|---------|--------------|--------------|----------|---------------|-------|
| Network: | LaGrande | | Name: | | LaGrande / Union County | | | | | | | | | |
| Branch: | TALG | | Name: | | Taxiway A LaGrande | | Use: | TAXIWAY | Area: | 200,559 SqFt | | | | |
| Section: | 03 | of 4 | | From: | TALG-02 | | | To: | TDLG-04 | | Last Const.: | 9/1/1974 | | |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P | | |
| Area: | 118,555 SqFt | | Length: | 2,711 Ft | | Width: | 50 Ft | | | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | | | |
| Shoulder: | Street Type: | | Grade: | | 0 | | Lanes: | 0 | | | | | | |
| Section Comments: | | | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: | | | | | Subbase - Aggregate | | Code: | SB-AG | | Is Major M&R: | True |
| Work Date: | 9/2/1942 | | Work Type: | | | | | Base Course - Aggregate | | Code: | BA-AG | | Is Major M&R: | True |
| Work Date: | 9/3/1942 | | Work Type: | | | | | New Construction - AC | | Code: | NC-AC | | Is Major M&R: | True |
| Work Date: | 9/1/1974 | | Work Type: | | | | | Overlay - AC Structural | | Code: | OL-AS | | Is Major M&R: | True |
| Work Date: | 9/1/1993 | | Work Type: | | | | | Surface Treatment - Slurry Seal | | Code: | ST-SS | | Is Major M&R: | False |
| Work Date: | 9/1/2015 | | Work Type: | | | | | Crack Sealing - AC | | Code: | CS-AC | | Is Major M&R: | False |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 22 | | Surveyed: | 5 | | | | | | | |
| Conditions: | PCI: 72 | | | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 75 | | | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | | | |
| 48 | L & T CR | L | 100.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | L | 5.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | L | 100.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | M | 35.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | M | 57.00 | Ft | | | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 | SqFt | | | | | | | | | | |
| Sample Number: | 05 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 73 | | | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | | | |
| 48 | L & T CR | L | 17.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | M | 100.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | M | 63.00 | Ft | | | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 | SqFt | | | | | | | | | | |
| Sample Number: | 10 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 63 | | | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | | | |
| 43 | BLOCK CR | L | 450.00 | SqFt | | | | | | | | | | |
| 48 | L & T CR | L | 85.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | L | 43.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | M | 80.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | M | 100.00 | Ft | | | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 | SqFt | | | | | | | | | | |
| Sample Number: | 15 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 79 | | | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | | | |
| 48 | L & T CR | L | 50.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | L | 10.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | M | 25.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | M | 25.00 | Ft | | | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 | SqFt | | | | | | | | | | |
| Sample Number: | 20 | Type: | R | Area: | 5000.00 SqFt | | | PCI: | 69 | | | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | | | |
| 48 | L & T CR | L | 150.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | L | 50.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | M | 25.00 | Ft | | | | | | | | | | |
| 48 | L & T CR | M | 75.00 | Ft | | | | | | | | | | |

| | | | | |
|----|------------|---|---------|------|
| 48 | L & T CR | M | 75.00 | Ft |
| 57 | WEATHERING | L | 5000.00 | SqFt |

| | | | | | | | | | |
|-----------------------------|---------------------|----------------|---|--------------------|-------------------------|------------------|------------------|--------------------------|------------------------------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | |
| Branch: | TALG | | Name: | Taxiway A LaGrande | | Use: | TAXIWAY | Area: | 200,559 SqFt |
| Section: | 04 | of | 4 | From: | TDLG - 05 | | To: | TA2LG - 01 | Last Const.: 1/1/2021 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Taxiw ay_AC/AAC | | Zone: | | Category: | | Rank: P |
| Area: | 60,718 SqFt | | Length: | 1,260 Ft | | Width: | 45 Ft | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft |
| Shoulder: | Street Type: | | | | Grade: | 0 | | Lanes: | 0 |
| Section Comments: | | | | | | | | | |
| Work Date: | 1/1/2021 | | Work Type: Geotextile | | | Code: | FB-TX | Is Major M&R: | False |
| Work Date: | 1/1/2021 | | Work Type: New Construction - AC | | | Code: | NC-AC | Is Major M&R: | True |
| Work Date: | 1/1/2021 | | Work Type: Base Course - Aggregate | | | Code: | BA-AG | Is Major M&R: | False |
| Work Date: | 1/1/2021 | | Work Type: Subbase - Aggregate | | | Code: | SB-AG | Is Major M&R: | False |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 13 | | Surveyed: | 5 | | |
| Conditions: | PCI: | 100 | | | | | | | |
| Inspection Comments: | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5906.00 SqFt | | PCI: | 100 | |
| Sample Comments: | | | | | | | | | |
| <No Distress> | | | | | | | | | |
| Sample Number: | 04 | Type: | R | Area: | 4760.00 SqFt | | PCI: | 100 | |
| Sample Comments: | | | | | | | | | |
| <No Distress> | | | | | | | | | |
| Sample Number: | 07 | Type: | R | Area: | 4500.00 SqFt | | PCI: | 100 | |
| Sample Comments: | | | | | | | | | |
| <No Distress> | | | | | | | | | |
| Sample Number: | 10 | Type: | R | Area: | 4241.00 SqFt | | PCI: | 100 | |
| Sample Comments: | | | | | | | | | |
| <No Distress> | | | | | | | | | |
| Sample Number: | 13 | Type: | R | Area: | 4284.00 SqFt | | PCI: | 100 | |
| Sample Comments: | | | | | | | | | |
| <No Distress> | | | | | | | | | |

| | | | | | | | | | |
|-----------------------------|--------------------------------|----------------|--|--------------------|-------------------------|------------------|------------------|--------------|--------------------------------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | |
| Branch: | TALG | | Name: | Taxiway A LaGrande | | Use: | TAXIWAY | Area: | 200,559 SqFt |
| Section: | 02 | of | 4 | From: | TALG-01 | | To: | TALG-03 | Last Const.: 8/3/2008 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | Zone: | KLGD | | Category: | O | Rank: P |
| Area: | 15,500 SqFt | | Length: | 310 Ft | | Width: | 50 Ft | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: Ft |
| Shoulder: | Street Type: | | Grade: 0 | | Lanes: 0 | | | | |
| Section Comments: | | | | | | | | | |
| Work Date: | 8/1/2008 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | Is Major M&R: False |
| Work Date: | 8/2/2008 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | Is Major M&R: False |
| Work Date: | 8/3/2008 | | Work Type: Complete Reconstruction - AC | | | | Code: | CR-AC | Is Major M&R: True |
| Work Date: | 9/1/2015 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | Is Major M&R: False |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 4 | | Surveyed: | 3 | | |
| Conditions: | PCI: 65 | | | | | | | | |
| Inspection Comments: | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5250.00 SqFt | | PCI: | 64 | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | L | 3.00 | Ft | | | | | |
| 48 | L & T CR | L | 75.00 | Ft | | | | | |
| 48 | L & T CR | L | 27.00 | Ft | | | | | |
| 48 | L & T CR | L | 75.00 | Ft | | | | | |
| 48 | L & T CR | M | 35.00 | Ft | | | | | |
| 48 | L & T CR | M | 75.00 | Ft | | | | | |
| 48 | L & T CR | M | 75.00 | Ft | | | | | |
| 50 | PATCHING | L | 400.00 | SqFt | | | | | |
| 57 | WEATHERING | L | 5250.00 | SqFt | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 5042.00 SqFt | | PCI: | 60 | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | L | 7.00 | Ft | | | | | |
| 48 | L & T CR | L | 75.00 | Ft | | | | | |
| 48 | L & T CR | M | 75.00 | Ft | | | | | |
| 48 | L & T CR | M | 34.00 | Ft | | | | | |
| 48 | L & T CR | M | 75.00 | Ft | | | | | |
| 48 | L & T CR | M | 68.00 | Ft | | | | | |
| 50 | PATCHING | L | 480.00 | SqFt | | | | | |
| 57 | WEATHERING | L | 5042.00 | SqFt | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 4986.00 SqFt | | PCI: | 70 | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | L | 31.00 | Ft | | | | | |
| 48 | L & T CR | L | 69.00 | Ft | | | | | |
| 48 | L & T CR | M | 75.00 | Ft | | | | | |
| 48 | L & T CR | M | 75.00 | Ft | | | | | |
| 57 | WEATHERING | L | 4986.00 | SqFt | | | | | |

| | | | | | | | | | | | | |
|-----------------------------|--------------------------------|----------------|--|--------------------|-------------------------|------------------|--------------|-------------|----------------------|--------------------------|---------------------|----------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | TBLG | | Name: | Taxiway B LaGrande | | Use: | TAXIWAY | | Area: | 93,318 SqFt | | |
| Section: | 03 | of | 3 | From: | R16LG-05 | | | To: | T01LG-2 | | Last Const.: | 1/2/2021 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | | | Category: | O | Rank: | P |
| Area: | 24,749 SqFt | | Length: | 305 Ft | | Width: | 54 Ft | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: | | Ft | |
| Shoulder: | Street Type: | | | | Grade: | 0 | | | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | | | | |
| Work Date: | 9/1/1949 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | True | |
| Work Date: | 9/2/1949 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | True | |
| Work Date: | 9/3/1949 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True | |
| Work Date: | 9/1/1993 | | Work Type: Surface Treatment - Slurry Seal | | | | Code: | ST-SS | | Is Major M&R: | False | |
| Work Date: | 8/1/2008 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | False | |
| Work Date: | 8/2/2008 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | False | |
| Work Date: | 8/3/2008 | | Work Type: Complete Reconstruction - AC | | | | Code: | CR-AC | | Is Major M&R: | True | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 9/1/2015 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 1/1/2021 | | Work Type: Cold Mill and Overlay - 3 Inches | | | | Code: | MOL-3 | | Is Major M&R: | True | |
| Work Date: | 1/2/2021 | | Work Type: Cold Mill and Overlay - 3 Inches | | | | Code: | MOL-3 | | Is Major M&R: | True | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 4 | | Surveyed: | 3 | | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 6583.00 SqFt | | | PCI: | 100 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 6638.00 SqFt | | | PCI: | 100 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 5927.00 SqFt | | | PCI: | 100 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |

| | | | | | | | | | | | | |
|----------------------|--------------|--------------------------------|------------------------------------|--------------------|-------------------------|--------------|---------|-----------|---------------|---------------------|--------------|----------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | TBLG | | Name: | Taxiway B LaGrande | | Use: | TAXIWAY | | Area: | 93,318 SqFt | | |
| Section: | 02 | of 3 | | From: | R16LG-05 | | | To: | R12LG-1 | | Last Const.: | 9/3/1993 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 48,734 SqFt | | Length: | 944 Ft | | Width: | 50 Ft | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: | | Ft | |
| Shoulder: | Street Type: | | Grade: | | 0 | | Lanes: | | 0 | | | |
| Section Comments: | | | | | | | | | | | | |
| Work Date: | 9/1/1993 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: True | | |
| Work Date: | 9/2/1993 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: True | | |
| Work Date: | 9/3/1993 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: True | | |
| Work Date: | 6/1/2001 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | |
| Work Date: | 9/1/2004 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | |
| Work Date: | 9/2/2004 | | Work Type: Surface Seal - Fog Seal | | | | Code: | SS-FS | | Is Major M&R: False | | |
| Work Date: | 9/1/2008 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | |
| Work Date: | 9/1/2015 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: False | | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 10 | | Surveyed: | | 4 | | | | |
| Conditions: | PCI: | 73 | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 68 | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | |
| 48 | L & T CR | M | 118.00 Ft | | | | | | | | | |
| 48 | L & T CR | M | 150.00 Ft | | | | | | | | | |
| 48 | L & T CR | M | 12.00 Ft | | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 SqFt | | | | | | | | | |
| Sample Number: | 03 | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 79 | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | |
| 48 | L & T CR | L | 50.00 Ft | | | | | | | | | |
| 48 | L & T CR | L | 10.00 Ft | | | | | | | | | |
| 48 | L & T CR | L | 90.00 Ft | | | | | | | | | |
| 48 | L & T CR | L | 25.00 Ft | | | | | | | | | |
| 48 | L & T CR | M | 25.00 Ft | | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 SqFt | | | | | | | | | |
| Sample Number: | 06 | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 74 | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | |
| 48 | L & T CR | L | 9.00 Ft | | | | | | | | | |
| 48 | L & T CR | L | 119.00 Ft | | | | | | | | | |
| 48 | L & T CR | M | 100.00 Ft | | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 SqFt | | | | | | | | | |
| Sample Number: | 07 | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 71 | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | |
| 48 | L & T CR | L | 19.00 Ft | | | | | | | | | |
| 48 | L & T CR | L | 25.00 Ft | | | | | | | | | |
| 48 | L & T CR | M | 75.00 Ft | | | | | | | | | |
| 48 | L & T CR | M | 50.00 Ft | | | | | | | | | |
| 50 | PATCHING | L | 50.00 SqFt | | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 SqFt | | | | | | | | | |

| | | | | | | | | | | | | |
|----------------------|--------------------------------|---------|--------------------------------------|-------------------------|--------------|-----------|---------|---------------|-------|---------------|----------|---|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | TBLG | | Name: | Taxiway B LaGrande | | Use: | TAXIWAY | | Area: | 93,318 SqFt | | |
| Section: | 01 | of 3 | From: | R16LG-05 | | | To: | TBLG-02 | | Last Const.: | 6/1/2014 | |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_Taxiw ay_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 19,835 SqFt | | Length: | 215 Ft | | Width: | 50 Ft | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | |
| Shoulder: | Street Type: | | Grade: | | 0 | | Lanes: | 0 | | | | |
| Section Comments: | | | | | | | | | | | | |
| Work Date: | 9/1/1993 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | True | |
| Work Date: | 9/2/1993 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | True | |
| Work Date: | 9/3/1993 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True | |
| Work Date: | 6/1/2001 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 9/1/2004 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 9/2/2004 | | Work Type: Surface Seal - Fog Seal | | | | Code: | SS-FS | | Is Major M&R: | False | |
| Work Date: | 9/1/2008 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 6/1/2014 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 4 | | Surveyed: | 3 | | | | | |
| Conditions: | PCI: 76 | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 4990.00 SqFt | | PCI: | 85 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | L | 34.00 | Ft | | | | | | | | |
| 48 | L & T CR | L | 109.00 | Ft | | | | | | | | |
| 57 | WEATHERING | L | 4990.00 | SqFt | | | | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 5280.00 SqFt | | PCI: | 70 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | M | 100.00 | Ft | | | | | | | | |
| 48 | L & T CR | M | 16.00 | Ft | | | | | | | | |
| 48 | L & T CR | M | 100.00 | Ft | | | | | | | | |
| 48 | L & T CR | M | 37.00 | Ft | | | | | | | | |
| 57 | WEATHERING | L | 5280.00 | SqFt | | | | | | | | |
| Sample Number: | 04 | Type: | R | Area: | 3558.00 SqFt | | PCI: | 73 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | M | 50.00 | Ft | | | | | | | | |
| 48 | L & T CR | M | 80.00 | Ft | | | | | | | | |
| 57 | WEATHERING | L | 3558.00 | SqFt | | | | | | | | |

| | | | |
|--|--|--------------------------------------|--|
| Network: LaGrande | | Name: LaGrande / Union County | |
| Branch: TC1LG | Name: Taxiway C1 LaGrande | Use: TAXIWAY | Area: 14,223 SqFt |
| Section: 02 of 2 | From: TC!LG-01 | To: TCLG-03 | Last Const.: 9/2/1984 |
| Surface: AC | Family: 2022_Eastern_Cat3_Taxiway_AC/AAC | Zone: KLGD | Category: O Rank: P |
| Area: 5,650 SqFt | Length: 113 Ft | Width: 50 Ft | |
| Slabs: | Slab Length: Ft | Slab Width: Ft | Joint Length: Ft |
| Shoulder: | Street Type: | Grade: 0 | Lanes: 0 |
| Section Comments: | | | |
| Work Date: 9/1/1984 | Work Type: Base Course - Unknown (Major MR) | | Code: BA-UN Is Major M&R: True |
| Work Date: 9/2/1984 | Work Type: New Construction - AC | | Code: NC-AC Is Major M&R: True |
| Work Date: 9/1/1986 | Work Type: Crack Sealing - AC | | Code: CS-AC Is Major M&R: False |
| Last Insp. Date: 7/1/2022 | TotalSamples: 1 | Surveyed: 1 | |
| Conditions: PCI: 33 | | | |
| Inspection Comments: | | | |
| Sample Number: 01 | Type: R | Area: 5650.00 SqFt | PCI: 33 |
| Sample Comments: Created by Inspection Schedule | | | |
| 48 | L & T CR | M | 12.00 Ft |
| 50 | PATCHING | L | 113.00 SqFt |
| 50 | PATCHING | L | 40.00 SqFt |
| 50 | PATCHING | M | 113.00 SqFt |
| 50 | PATCHING | M | 113.00 SqFt |
| 50 | PATCHING | M | 113.00 SqFt |
| 50 | PATCHING | M | 113.00 SqFt |
| 50 | PATCHING | M | 160.00 SqFt |
| 50 | PATCHING | M | 113.00 SqFt |
| 57 | WEATHERING | H | 5650.00 SqFt |

| | | | | | | | | | |
|----------------------|--------------------------------|---|----------------------------------|-------------------------|--------------|---------------|---------|---------------|----------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | |
| Branch: | TC1LG | Name: | Taxiway C1 LaGrande | | Use: | TAXIWAY | Area: | 14,223 SqFt | |
| Section: | 01 | of | 2 | From: | T05LG-1 | To: | R12LG-1 | Last Const.: | 6/1/2014 |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | Zone: | KLGD | Category: | O | Rank: | P |
| Area: | 8,573 SqFt | Length: | 150 Ft | Width: | 50 Ft | | | | |
| Slabs: | | Slab Length: | Ft | Slab Width: | Ft | Joint Length: | Ft | | |
| Shoulder: | | Street Type: | | Grade: | 0 | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | |
| Work Date: | 9/1/1984 | Work Type: Base Course - Unknown (Major MR) | | | | Code: | BA-UN | Is Major M&R: | True |
| Work Date: | 9/2/1984 | Work Type: New Construction - AC | | | | Code: | NC-AC | Is Major M&R: | True |
| Work Date: | 9/1/1986 | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | Is Major M&R: | False |
| Work Date: | 9/1/1991 | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | Is Major M&R: | True |
| Work Date: | 9/2/2004 | Work Type: Surface Seal - Fog Seal | | | | Code: | SS-FS | Is Major M&R: | False |
| Work Date: | 9/1/2008 | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | Is Major M&R: | False |
| Work Date: | 9/1/2012 | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | Is Major M&R: | False |
| Work Date: | 6/1/2014 | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | Is Major M&R: | True |
| Last Insp. Date: | 7/1/2022 | TotalSamples: | 2 | Surveyed: | 2 | | | | |
| Conditions: | PCI: 92 | | | | | | | | |
| Inspection Comments: | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4823.00 SqFt | PCI: | 90 | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | L | 9.00 | Ft | | | | | |
| 48 | L & T CR | L | 20.00 | Ft | | | | | |
| 57 | WEATHERING | L | 4823.00 | SqFt | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 3750.00 SqFt | PCI: | 94 | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | |
| 57 | WEATHERING | L | 3750.00 | SqFt | | | | | |

| | | | | | | | | | |
|-----------------------------|--------------------------------|----------------|---|---------------------|-------------------------|------------------|------------------|---------------|--------------------------------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | |
| Branch: | TC2LG | | Name: | Taxiway C2 LaGrande | | Use: | TAXIWAY | Area: | 38,359 SqFt |
| Section: | 02 | of | 2 | From: | TCLG-01 | | To: | Taxiway C | |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | Category: | O | Rank: P |
| Area: | 24,798 SqFt | | Length: | 200 Ft | | Width: | 70 Ft | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: Ft |
| Shoulder: | Street Type: | | | | Grade: | 0 | | Lanes: | 0 |
| Section Comments: | | | | | | | | | |
| Work Date: | 10/1/2012 | | Work Type: Geotextile | | | | Code: | FB-TX | Is Major M&R: False |
| Work Date: | 10/2/2012 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | Is Major M&R: False |
| Work Date: | 10/3/2012 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | Is Major M&R: False |
| Work Date: | 10/4/2012 | | Work Type: New Construction - AC | | | | Code: | NC-AC | Is Major M&R: True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 5 | | Surveyed: | 3 | | |
| Conditions: | PCI: 74 | | | | | | | | |
| Inspection Comments: | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5289.00 SqFt | | PCI: | 77 | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | | L | 55.00 Ft | | | | | |
| 48 | L & T CR | | L | 70.00 Ft | | | | | |
| 48 | L & T CR | | L | 29.00 Ft | | | | | |
| 48 | L & T CR | | M | 70.00 Ft | | | | | |
| 57 | WEATHERING | | L | 5289.00 SqFt | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 5302.00 SqFt | | PCI: | 77 | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | | L | 28.00 Ft | | | | | |
| 48 | L & T CR | | L | 38.00 Ft | | | | | |
| 48 | L & T CR | | L | 50.00 Ft | | | | | |
| 48 | L & T CR | | L | 50.00 Ft | | | | | |
| 48 | L & T CR | | M | 75.00 Ft | | | | | |
| 57 | WEATHERING | | L | 5302.00 SqFt | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 3485.00 SqFt | | PCI: | 63 | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | | L | 146.00 Ft | | | | | |
| 48 | L & T CR | | L | 150.00 Ft | | | | | |
| 48 | L & T CR | | L | 150.00 Ft | | | | | |
| 48 | L & T CR | | M | 71.00 Ft | | | | | |
| 57 | WEATHERING | | L | 3485.00 SqFt | | | | | |

| | | | | | | | | | | | | |
|----------------------|--------------------------------|---------|----------------------------------|-------------------------|--------------|-------------|-----------|---------|---------------|--------------|---------------|-------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | TC2LG | | Name: | Taxiway C2 LaGrande | | Use: | TAXIWAY | Area: | 38,359 SqFt | | | |
| Section: | 01 | of | 2 | From: | RW 30 End | | To: | TCLG-02 | | Last Const.: | 6/1/2014 | |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | Category: | O | | Rank: | P | |
| Area: | 13,561 SqFt | | Length: | 125 Ft | | Width: | 70 Ft | | | | | |
| Slabs: | | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | |
| Shoulder: | | | Street Type: | | | Grade: | 0 | | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | | | | |
| Work Date: | 10/1/2012 | | Work Type: | Geotextile | | | | Code: | FB-TX | | Is Major M&R: | False |
| Work Date: | 10/2/2012 | | Work Type: | Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | False |
| Work Date: | 10/3/2012 | | Work Type: | Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | False |
| Work Date: | 10/4/2012 | | Work Type: | New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True |
| Work Date: | 6/1/2014 | | Work Type: | Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 3 | | Surveyed: | 2 | | | | | |
| Conditions: | PCI: 76 | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 5302.00 SqFt | | PCI: | 76 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | | L | 119.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 70.00 | Ft | | | | | | | |
| 48 | L & T CR | | L | 46.00 | Ft | | | | | | | |
| 48 | L & T CR | | M | 51.00 | Ft | | | | | | | |
| 57 | WEATHERING | | L | 5302.00 | SqFt | | | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 3534.00 SqFt | | PCI: | 74 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | | L | 101.00 | Ft | | | | | | | |
| 48 | L & T CR | | M | 71.00 | Ft | | | | | | | |
| 57 | WEATHERING | | L | 3534.00 | SqFt | | | | | | | |

| | | | | | | | | | | |
|---|-------------|---------|------------------------------------|--------------------|-------------------------|-------------|-----------|------------|---------------------|----------|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | |
| Branch: | TCLG | | Name: | Taxiway C LaGrande | | Use: | TAXIWAY | Area: | 241,832 SqFt | |
| Section: | 04 | of | 5 | From: | TC1LG-01 | | To: | Section 05 | Last Const.: | 9/3/1991 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | Category: | O | Rank: | P |
| Area: | 44,975 SqFt | | Length: | 927 Ft | | Width: | 50 Ft | | | |
| Slabs: | | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft |
| Shoulder: | | | Street Type: | | | Grade: | 0 | | Lanes: | 0 |
| Section Comments: | | | | | | | | | | |
| Work Date: | 9/1/1991 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | Is Major M&R: True | |
| Work Date: | 9/2/1991 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | Is Major M&R: True | |
| Work Date: | 9/3/1991 | | Work Type: New Construction - AC | | | | Code: | NC-AC | Is Major M&R: True | |
| Work Date: | 9/1/2004 | | Work Type: Surface Seal - Fog Seal | | | | Code: | SS-FS | Is Major M&R: False | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | Is Major M&R: False | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 9 | | Surveyed: | 4 | | | |
| Conditions: | PCI: 94 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 94 | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | |
| 57 | WEATHERING | | L | | 5000.00 SqFt | | | | | |
| Sample Number: | 04 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 94 | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | |
| 57 | WEATHERING | | L | | 5000.00 SqFt | | | | | |
| Sample Number: | 06 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 94 | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | |
| 57 | WEATHERING | | L | | 5000.00 SqFt | | | | | |
| Sample Number: | 08 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 94 | | |
| Sample Comments: Created by Inspection Schedule | | | | | | | | | | |
| 57 | WEATHERING | | L | | 5000.00 SqFt | | | | | |

| | | | | | | | | | | | | | | | | | | | |
|----------------------|------------|--------------------------------|---|---------------|--------------|----------------------------------|--|-----------|--|---------------|--|---------------|--|--------------|--|--------------|--|----------|--|
| Network: | | LaGrande | | Name: | | LaGrande / Union County | | | | | | | | | | | | | |
| Branch: | | TCLG | | Name: | | Taxiway C LaGrande | | Use: | | TAXIWAY | | Area: | | 241,832 SqFt | | | | | |
| Section: | | 01 | | of | | 5 | | From: | | TBBL-01 | | To: | | TDLG-01 | | Last Const.: | | 9/3/1991 | |
| Surface: | | AC | | Family: | | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | | KLGD | | Category: | | O | | Rank: | | P | |
| Area: | | 122,032 SqFt | | Length: | | 2,204 Ft | | Width: | | 50 Ft | | | | | | | | | |
| Slabs: | | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: | | Ft | | | | | | | |
| Shoulder: | | Street Type: | | Grade: | | 0 | | Lanes: | | 0 | | | | | | | | | |
| Section Comments: | | | | | | | | | | | | | | | | | | | |
| Work Date: | | 9/1/1991 | | Work Type: | | Subbase - Aggregate | | Code: | | SB-AG | | Is Major M&R: | | True | | | | | |
| Work Date: | | 9/2/1991 | | Work Type: | | Base Course - Aggregate | | Code: | | BA-AG | | Is Major M&R: | | True | | | | | |
| Work Date: | | 9/3/1991 | | Work Type: | | New Construction - AC | | Code: | | NC-AC | | Is Major M&R: | | True | | | | | |
| Work Date: | | 9/1/2004 | | Work Type: | | Surface Seal - Fog Seal | | Code: | | SS-FS | | Is Major M&R: | | False | | | | | |
| Work Date: | | 9/1/2012 | | Work Type: | | Crack Sealing - AC | | Code: | | CS-AC | | Is Major M&R: | | False | | | | | |
| Work Date: | | 9/1/2015 | | Work Type: | | Crack Sealing - AC | | Code: | | CS-AC | | Is Major M&R: | | False | | | | | |
| Last Insp. Date: | | 7/1/2022 | | TotalSamples: | | 25 | | Surveyed: | | 5 | | | | | | | | | |
| Conditions: | | PCI: 90 | | | | | | | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | | | | | | | |
| Sample Number: | | 03 | | Type: | | R | | Area: | | 5216.00 SqFt | | PCI: | | 91 | | | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | | | | | | | | |
| 48 | L & T CR | | L | | 8.00 Ft | | | | | | | | | | | | | | |
| 57 | WEATHERING | | L | | 5216.00 SqFt | | | | | | | | | | | | | | |
| Sample Number: | | 08 | | Type: | | R | | Area: | | 5000.00 SqFt | | PCI: | | 94 | | | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | | | | | | | | |
| 57 | WEATHERING | | L | | 5000.00 SqFt | | | | | | | | | | | | | | |
| Sample Number: | | 13 | | Type: | | R | | Area: | | 5000.00 SqFt | | PCI: | | 94 | | | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | | | | | | | | |
| 57 | WEATHERING | | L | | 5000.00 SqFt | | | | | | | | | | | | | | |
| Sample Number: | | 18 | | Type: | | R | | Area: | | 5000.00 SqFt | | PCI: | | 94 | | | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | | | | | | | | |
| 57 | WEATHERING | | L | | 5000.00 SqFt | | | | | | | | | | | | | | |
| Sample Number: | | 23 | | Type: | | R | | Area: | | 5000.00 SqFt | | PCI: | | 78 | | | | | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | | | | | | | | | | |
| 48 | L & T CR | | L | | 15.00 Ft | | | | | | | | | | | | | | |
| 48 | L & T CR | | L | | 57.00 Ft | | | | | | | | | | | | | | |
| 48 | L & T CR | | M | | 57.00 Ft | | | | | | | | | | | | | | |
| 57 | WEATHERING | | L | | 5000.00 SqFt | | | | | | | | | | | | | | |

| | | | | | | | | | | | | |
|----------------------|--------------------------------|---------|------------------------------------|-------------------------|--------------|-----------|---------|---------------|--------------|---------------|----------|---|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | TCLG | | Name: | Taxiway C LaGrande | | Use: | TAXIWAY | Area: | 241,832 SqFt | | | |
| Section: | 02 | of 5 | From: | TDLG-01 | | | To: | TC1LG-01 | | Last Const.: | 9/3/1991 | |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 30,453 SqFt | | Length: | 566 Ft | | Width: | 50 Ft | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | |
| Shoulder: | Street Type: | | | | Grade: | 0 | | Lanes: | 0 | | | |
| Section Comments: | | | | | | | | | | | | |
| Work Date: | 9/1/1991 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | True | |
| Work Date: | 9/2/1991 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | True | |
| Work Date: | 9/3/1991 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True | |
| Work Date: | 9/1/2004 | | Work Type: Surface Seal - Fog Seal | | | | Code: | SS-FS | | Is Major M&R: | False | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 9/1/2015 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 7 | | Surveyed: | 3 | | | | | |
| Conditions: | PCI: 89 | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5215.00 SqFt | | PCI: | 100 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 78 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 42 | BLEEDING | N | 10.00 | SqFt | | | | | | | | |
| 48 | L & T CR | L | 12.00 | Ft | | | | | | | | |
| 48 | L & T CR | L | 73.00 | Ft | | | | | | | | |
| 48 | L & T CR | M | 16.00 | Ft | | | | | | | | |
| 48 | L & T CR | M | 28.00 | Ft | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 | SqFt | | | | | | | | |
| Sample Number: | 05 | Type: | R | Area: | 5000.00 SqFt | | PCI: | 89 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | |
| 48 | L & T CR | L | 45.00 | Ft | | | | | | | | |
| 57 | WEATHERING | L | 5000.00 | SqFt | | | | | | | | |

| | | | | | | | | | | |
|---------------------------|-------------|--------------------------------|------------------------------------|--------------|--------------------|-------------------------|-------|-----------|---------------------|------------------------|
| Network: | | LaGrande | | Name: | | LaGrande / Union County | | | | |
| Branch: | TCLG | | Name: | | Taxiway C LaGrande | | Use: | TAXIWAY | Area: | 241,832 SqFt |
| Section: | 05 | of 5 | | From: | Section 04 | | | To: | Taxiway C2 | Last Const.: 10/4/2012 |
| Surface: | AC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | | Category: | O | Rank: P |
| Area: | 33,710 SqFt | | Length: | 680 Ft | | Width: | 50 Ft | | | |
| Slabs: | | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft |
| Shoulder: | | | Street Type: | | | Grade: | 0 | | Lanes: | 0 |
| Section Comments: | | | | | | | | | | |
| Work Date: | 10/1/2012 | | Work Type: Geotextile | | | | Code: | FB-TX | Is Major M&R: False | |
| Work Date: | 10/2/2012 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | Is Major M&R: False | |
| Work Date: | 10/3/2012 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | Is Major M&R: False | |
| Work Date: | 10/4/2012 | | Work Type: New Construction - AC | | | | Code: | NC-AC | Is Major M&R: True | |
| Last Insp. Date: 7/1/2022 | | | | | | | | | | |
| | | | TotalSamples: | 7 | | Surveyed: 4 | | | | |
| Conditions: | PCI: 68 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 75 | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | L | | 18.00 Ft | | | | | | |
| 48 | L & T CR | M | | 73.00 Ft | | | | | | |
| 57 | WEATHERING | L | | 4500.00 SqFt | | | | | | |
| 57 | WEATHERING | M | | 500.00 SqFt | | | | | | |
| Sample Number: | 02 | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 74 | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | L | | 50.00 Ft | | | | | | |
| 48 | L & T CR | L | | 50.00 Ft | | | | | | |
| 48 | L & T CR | M | | 50.00 Ft | | | | | | |
| 57 | WEATHERING | L | | 4500.00 SqFt | | | | | | |
| 57 | WEATHERING | M | | 500.00 SqFt | | | | | | |
| Sample Number: | 04 | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 69 | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | L | | 174.00 Ft | | | | | | |
| 48 | L & T CR | M | | 100.00 Ft | | | | | | |
| 57 | WEATHERING | L | | 4500.00 SqFt | | | | | | |
| 57 | WEATHERING | M | | 500.00 SqFt | | | | | | |
| Sample Number: | 06 | Type: | R | | Area: | 5000.00 SqFt | | PCI: | 55 | |
| Sample Comments: | | Created by Inspection Schedule | | | | | | | | |
| 48 | L & T CR | L | | 143.00 Ft | | | | | | |
| 48 | L & T CR | L | | 100.00 Ft | | | | | | |
| 48 | L & T CR | L | | 185.00 Ft | | | | | | |
| 48 | L & T CR | M | | 100.00 Ft | | | | | | |
| 48 | L & T CR | M | | 134.00 Ft | | | | | | |
| 48 | L & T CR | M | | 100.00 Ft | | | | | | |
| 57 | WEATHERING | L | | 4500.00 SqFt | | | | | | |
| 57 | WEATHERING | M | | 500.00 SqFt | | | | | | |

| | | | | | | | | | | | |
|-----------------------------|--------------------------------|----------------|---|-------------------------|--------------------|------------------|--------------|------------------|----------------------|--------------------------|----------|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | |
| Branch: | TCLG | | Name: | Taxiway C LaGrande | | Use: | TAXIWAY | | Area: | 241,832 SqFt | |
| Section: | 03 | of 5 | From: | TC1LG | | | To: | Intersection | | Last Const.: | 9/1/2012 |
| Surface: | AAC | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | | Category: | O | Rank: | P |
| Area: | 10,662 SqFt | | Length: | 113 Ft | | Width: | 50 Ft | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | | Ft | | Joint Length: | Ft | |
| Shoulder: | Street Type: | | | | Grade: | 0 | | Lanes: | 0 | | |
| Section Comments: | | | | | | | | | | | |
| Work Date: | 9/1/1984 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | False |
| Work Date: | 9/2/1984 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True |
| Work Date: | 9/1/2012 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True |
| Work Date: | 9/1/2015 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 2 | | Surveyed: | 2 | | | | |
| Conditions: | PCI: | 74 | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 5600.00 SqFt | | PCI: | 63 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | |
| 48 | L & T CR | L | 6.00 | Ft | | | | | | | |
| 48 | L & T CR | L | 6.00 | Ft | | | | | | | |
| 48 | L & T CR | L | 16.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 110.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 66.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 13.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 32.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 38.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 110.00 | Ft | | | | | | | |
| 48 | L & T CR | M | 32.00 | Ft | | | | | | | |
| 57 | WEATHERING | L | 5600.00 | SqFt | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 5061.00 SqFt | | PCI: | 87 | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | |
| 48 | L & T CR | L | 94.00 | Ft | | | | | | | |
| 48 | L & T CR | L | 27.00 | Ft | | | | | | | |
| 57 | WEATHERING | L | 5061.00 | SqFt | | | | | | | |

| | | | | | | | | | | | | | |
|-----------------------------|--------------------------------|--------------|--|--------------------------------------|-------------------------|------------------|---------------|----------------------|------------------|--------------------------|---------------------|--------------|---|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | TDLG | | Name: | Taxiway D LaGrande | | Use: | TAXIWAY | | Area: | 121,895 SqFt | | | |
| Section: | 01 | of 5 | | From: | TDLG-01 | | | To: | TDLG-03 | | Last Const.: | 1/1/2021 | |
| Surface: | AAC | | Family: | 2022_Eastern_Cat3_Taxiw ay_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 93,045 SqFt | | Length: | 2,165 Ft | | Width: | 40 Ft | | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | | |
| Shoulder: | Street Type: | | Grade: | | 0 | | Lanes: | 0 | | | | | |
| Section Comments: | Section -02 prior to 2022c | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | True | | |
| Work Date: | 9/2/1942 | | Work Type: Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | True | | |
| Work Date: | 9/3/1942 | | Work Type: New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True | | |
| Work Date: | 9/1/1978 | | Work Type: Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True | | |
| Work Date: | 9/1/2009 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | | |
| Work Date: | 9/2/2009 | | Work Type: Surface Treatment - Slurry Seal | | | | Code: | SS-ST | | Is Major M&R: | False | | |
| Work Date: | 9/1/2012 | | Work Type: Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | | |
| Work Date: | 1/1/2021 | | Work Type: Cold Mill and Overlay - 3 Inches | | | | Code: | MOL-3 | | Is Major M&R: | True | | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 16 | | Surveyed: | 5 | | | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 6000.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 03 | Type: | R | Area: | 6000.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 06 | Type: | R | Area: | 6000.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 10 | Type: | R | Area: | 6000.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 14 | Type: | R | Area: | 6000.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |

| | | | | | | | | | | | | | |
|----------------------|--------------------------------|-------|---------------|----------------------------------|--------------|-------------|---------|-------|---------------|----|---------------|----------|---|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | | | |
| Branch: | TDLG | | Name: | Taxiway D LaGrande | | Use: | TAXIWAY | Area: | 121,895 SqFt | | | | |
| Section: | 02 | of | 5 | From: | TDLG-02 | | | To: | R16LG | | Last Const.: | 1/1/2021 | |
| Surface: | AAC | | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 4,844 SqFt | | Length: | 94 Ft | | Width: | 40 Ft | | | | | | |
| Slabs: | | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | |
| Shoulder: | | | Street Type: | | | Grade: | 0 | | Lanes: | 0 | | | |
| Section Comments: | Section -03 prior to 2022 | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: | Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | True | |
| Work Date: | 9/2/1942 | | Work Type: | Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | True | |
| Work Date: | 9/3/1942 | | Work Type: | New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True | |
| Work Date: | 9/1/1978 | | Work Type: | Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True | |
| Work Date: | 9/1/2012 | | Work Type: | Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 9/1/2015 | | Work Type: | Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 1/1/2021 | | Work Type: | Cold Mill and Overlay - 3 Inches | | | | Code: | MOL-3 | | Is Major M&R: | True | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 1 | | Surveyed: | 1 | | | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 4844.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |

| | | | | | | | | | | | | | |
|-----------------------------|---------------------------|--------------|----------------------|----------------------------------|-------------------------|--------------------|---------|--------------|----------------------|--------------|--------------------------|--------------|---|
| Network: | LaGrande | | | Name: | LaGrande / Union County | | | | | | | | |
| Branch: | TDLG | | Name: | Taxiway D LaGrande | | Use: | TAXIWAY | | Area: | 121,895 SqFt | | | |
| Section: | 04 | of | 5 | From: | TDLG-04 | | | To: | TALG-04 | | Last Const.: | 1/1/2021 | |
| Surface: | AAC | | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 15,923 SqFt | | Length: | 263 Ft | | Width: | 40 Ft | | | | | | |
| Slabs: | | | Slab Length: | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | |
| Shoulder: | | | Street Type: | | | Grade: | 0 | | Lanes: | 0 | | | |
| Section Comments: | Section -05 prior to 2022 | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: | Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | True | |
| Work Date: | 9/2/1942 | | Work Type: | Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | True | |
| Work Date: | 9/3/1942 | | Work Type: | New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True | |
| Work Date: | 9/1/1974 | | Work Type: | Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True | |
| Work Date: | 9/1/1993 | | Work Type: | Surface Treatment - Slurry Seal | | | | Code: | ST-SS | | Is Major M&R: | False | |
| Work Date: | 9/1/2009 | | Work Type: | Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True | |
| Work Date: | 9/1/2015 | | Work Type: | Crack Sealing - AC | | | | Code: | CS-AC | | Is Major M&R: | False | |
| Work Date: | 1/1/2021 | | Work Type: | Cold Mill and Overlay - 3 Inches | | | | Code: | MOL-3 | | Is Major M&R: | True | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 2 | | Surveyed: | 2 | | | | | | |
| Conditions: | PCI: 100 | | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 7304.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |
| Sample Number: | 02 | Type: | R | Area: | 8617.00 SqFt | | | PCI: | 100 | | | | |
| Sample Comments: | | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |

| | | | | | | | | | | | | | |
|----------------------|--------------------------------|-------|---------------|----------------------------------|--------------|-----------|---------|---------------|--------------|--------------|---------------|-------|---|
| Network: | LaGrande | | Name: | LaGrande / Union County | | | | | | | | | |
| Branch: | TDLG | | Name: | Taxiway D LaGrande | | Use: | TAXIWAY | Area: | 121,895 SqFt | | | | |
| Section: | 03 | of | 5 | From: | R16LG | | To: | TDLG-05 | | Last Const.: | 1/1/2021 | | |
| Surface: | AAC | | Family: | 2022_Eastern_Cat3_Taxiway_AC/AAC | | Zone: | KLGD | | Category: | O | | Rank: | P |
| Area: | 2,746 SqFt | | Length: | 30 Ft | | Width: | 40 Ft | | | | | | |
| Slabs: | Slab Length: | | Ft | | Slab Width: | Ft | | Joint Length: | Ft | | | | |
| Shoulder: | Street Type: | | Grade: | | 0 | | Lanes: | 0 | | | | | |
| Section Comments: | Section -04 prior to 2022 | | | | | | | | | | | | |
| Work Date: | 9/1/1942 | | Work Type: | Subbase - Aggregate | | | | Code: | SB-AG | | Is Major M&R: | True | |
| Work Date: | 9/2/1942 | | Work Type: | Base Course - Aggregate | | | | Code: | BA-AG | | Is Major M&R: | True | |
| Work Date: | 9/3/1942 | | Work Type: | New Construction - AC | | | | Code: | NC-AC | | Is Major M&R: | True | |
| Work Date: | 9/1/1974 | | Work Type: | Overlay - AC Structural | | | | Code: | OL-AS | | Is Major M&R: | True | |
| Work Date: | 9/1/1993 | | Work Type: | Surface Treatment - Slurry Seal | | | | Code: | ST-SS | | Is Major M&R: | False | |
| Work Date: | 1/1/2021 | | Work Type: | Cold Mill and Overlay - 3 Inches | | | | Code: | MOL-3 | | Is Major M&R: | True | |
| Last Insp. Date: | 7/1/2022 | | TotalSamples: | 1 | | Surveyed: | 1 | | | | | | |
| Conditions: | PCI: | 100 | | | | | | | | | | | |
| Inspection Comments: | | | | | | | | | | | | | |
| Sample Number: | 01 | Type: | R | Area: | 2746.00 SqFt | | PCI: | 100 | | | | | |
| Sample Comments: | Created by Inspection Schedule | | | | | | | | | | | | |
| <No Distress> | | | | | | | | | | | | | |

APPENDIX F

Work History Report

4/13/2023

Work History Report

Page 1 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

Network: LaGrande / Union Co **Branch:** A01LG **Apron 01 LaGrand** **Section:** 01 **Surface:** AAC
L.C.D. 9/1/2009 **Use:** APRON **Rank:** S **Length:** 1,088.00 (Ft) **Width:** 12.00 (Ft) **True Area:** 11524 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|-------------------------|------|----------------|-------------------------------------|----------|
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2009 | OL-AS | Overlay - AC Structural | 0.00 | 3.00 | <input checked="" type="checkbox"/> | |
| 9/1/1974 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | |

Network: LaGrande / Union Co **Branch:** A01LG **Apron 01 LaGrand** **Section:** 02 **Surface:** AAC
L.C.D. 9/1/2009 **Use:** APRON **Rank:** S **Length:** 280.00 (Ft) **Width:** 45.00 (Ft) **True Area:** 12600.00015 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|----------------------------------|------|----------------|-------------------------------------|----------------|
| 9/1/2009 | OL-AS | Overlay - AC Structural | 0.00 | 3.00 | <input checked="" type="checkbox"/> | |
| 9/2/1949 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/1/1949 | BA-UN | Base Course - Unknown (Major MR) | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |

Network: LaGrande / Union Co **Branch:** A01LG **Apron 01 LaGrand** **Section:** 03 **Surface:** AC
L.C.D. 9/2/1949 **Use:** APRON **Rank:** S **Length:** 280.00 (Ft) **Width:** 236.00 (Ft) **True Area:** 48880 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|----------------------------------|------|----------------|-------------------------------------|----------------|
| 9/2/1949 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/1/1949 | BA-UN | Base Course - Unknown (Major MR) | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |

Network: LaGrande / Union Co **Branch:** A01LG **Apron 01 LaGrand** **Section:** 04 **Surface:** AC
L.C.D. 9/2/1949 **Use:** APRON **Rank:** S **Length:** 93.00 (Ft) **Width:** 80.00 (Ft) **True Area:** 7440.000034 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|----------------------------------|------|----------------|-------------------------------------|---------------|
| 9/2/1949 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk.thickness |
| 9/1/1949 | BA-UN | Base Course - Unknown (Major MR) | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk.thickness |

Network: LaGrande / Union Co **Branch:** A01LG **Apron 01 LaGrand** **Section:** 05 **Surface:** AAC
L.C.D. 9/1/1980 **Use:** APRON **Rank:** S **Length:** 245.00 (Ft) **Width:** 80.00 (Ft) **True Area:** 19599.99992 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|--------------------------|------|----------------|-------------------------------------|--------------------------------|
| 9/2/2015 | PA-AD | Patching - AC Deep | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/2/2008 | PA-AD | Patching - AC Deep | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 9/1/2008 | CS-WD | Crack Seal - Wide Cracks | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 6/1/2001 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2001 Maint. Program |
| 9/1/1980 | OL-AS | Overlay - AC Structural | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1980, unk. thickness |
| 9/2/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | BA-AG | Base Course - Aggregate | 0.00 | 10.00 | <input checked="" type="checkbox"/> | |

4/13/2023

Work History Report

Page 2 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

Network: LaGrande / Union Co Branch: A01LG Apron 01 LaGrand Section: 06 Surface: AAC
 L.C.D. 9/2/2009 Use: APRON Rank: S Length: 113.00 (Ft) Width: 40.00 (Ft) True Area: 4529 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|-------------------------|------|----------------|-------------------------------------|----------|
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/2/2009 | OL-AS | Overlay - AC Structural | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/1/2009 | MI-CO | Cold Milling | 0.00 | 2.00 | <input type="checkbox"/> | |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | |

Network: LaGrande / Union Co Branch: A01LG Apron 01 LaGrand Section: 07 Surface: AAC
 L.C.D. 9/1/2009 Use: APRON Rank: P Length: 513.00 (Ft) Width: 24.00 (Ft) True Area: 12089 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|--------------------------|------|----------------|-------------------------------------|--------------------------------|
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2009 | OL-AS | Overlay - AC Structural | 0.00 | 3.00 | <input checked="" type="checkbox"/> | |
| 9/2/2008 | PA-AD | Patching - AC Deep | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 9/1/2008 | CS-WD | Crack Seal - Wide Cracks | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 6/1/2001 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2001 Maint. Program |
| 9/1/1980 | OL-AS | Overlay - AC Structural | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1980, unk. thickness |
| 9/2/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | BA-AG | Base Course - Aggregate | 0.00 | 10.00 | <input checked="" type="checkbox"/> | |

Network: LaGrande / Union Co Branch: A01LG Apron 01 LaGrand Section: 08 Surface: AAC
 L.C.D. 9/1/1980 Use: APRON Rank: P Length: 400.00 (Ft) Width: 193.00 (Ft) True Area: 77012 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|--------------------------|------|----------------|-------------------------------------|--------------------------------|
| 9/2/2015 | PA-AD | Patching - AC Deep | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2012 | PA-AD | Patching - AC Deep | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/2/2008 | PA-AD | Patching - AC Deep | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 9/1/2008 | CS-WD | Crack Seal - Wide Cracks | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 6/1/2001 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2001 Maint. Program |
| 9/1/1980 | OL-AS | Overlay - AC Structural | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1980, unk. thickness |
| 9/2/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | BA-AG | Base Course - Aggregate | 0.00 | 10.00 | <input checked="" type="checkbox"/> | |

4/13/2023

Work History Report

Page 3 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

| Network: LaGrande / Union Co | | Branch: A01LG | Apron 01 LaGrand | | Section: 09 | Surface: AAC |
|-------------------------------------|-------------------|----------------------------------|----------------------------|--------------------------|--------------------------------------|--------------------------------|
| L.C.D. 9/1/2009 | Use: APRON | Rank: P | Length: 538.00 (Ft) | Width: 34.00 (Ft) | True Area: 17817.00000 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2009 | OL-AS | Overlay - AC Structural | 0.00 | 3.00 | <input checked="" type="checkbox"/> | |
| 9/2/2008 | SS-ST | Surface Treatment - Slurry Seal | 0.00 | 0.00 | <input type="checkbox"/> | circa 2008 |
| 9/1/2008 | CS-WD | Crack Seal - Wide Cracks | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 6/1/2001 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2001 Maint. Program |
| 9/2/1980 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1980, unk. thickness |
| 9/1/1980 | BA-UN | Base Course - Unknown (Major MR) | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1980, unk. thickness |

| Network: LaGrande / Union Co | | Branch: A01LG | Apron 01 LaGrand | | Section: 10 | Surface: AC |
|-------------------------------------|-------------------|----------------------------------|----------------------------|---------------------------|-------------------------------------|--------------------------------|
| L.C.D. 9/2/1980 | Use: APRON | Rank: P | Length: 255.00 (Ft) | Width: 215.00 (Ft) | True Area: 54850 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/2/2012 | PA-AD | Patching - AC Deep | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/2/2008 | SS-ST | Surface Treatment - Slurry Seal | 0.00 | 0.00 | <input type="checkbox"/> | circa 2008 |
| 9/1/2008 | CS-WD | Crack Seal - Wide Cracks | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 6/1/2001 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2001 Maint. Program |
| 9/2/1980 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1980, unk. thickness |
| 9/1/1980 | BA-UN | Base Course - Unknown (Major MR) | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1980, unk. thickness |

| Network: LaGrande / Union Co | | Branch: A01LG | Apron 01 LaGrand | | Section: 11 | Surface: AC |
|-------------------------------------|-------------------|----------------------------------|----------------------------|---------------------------|--------------------------------------|--------------------------------|
| L.C.D. 9/2/1980 | Use: APRON | Rank: P | Length: 145.00 (Ft) | Width: 215.00 (Ft) | True Area: 30587.00000 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2008 | CS-WD | Crack Seal - Wide Cracks | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 6/1/2001 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2001 Maint. Program |
| 9/2/1980 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1980, unk. thickness |
| 9/1/1980 | BA-UN | Base Course - Unknown (Major MR) | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1980, unk. thickness |

| Network: LaGrande / Union Co | | Branch: A01LG | Apron 01 LaGrand | | Section: 12 | Surface: AC |
|-------------------------------------|-------------------|-------------------------|----------------------------|--------------------------|--------------------------------------|--------------------|
| L.C.D. 9/3/2019 | Use: APRON | Rank: P | Length: 370.00 (Ft) | Width: 95.00 (Ft) | True Area: 36243.00001 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 9/3/2019 | NC-AC | New Construction - AC | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/2/2019 | BA-AG | Base Course - Aggregate | 0.00 | 8.00 | <input type="checkbox"/> | |
| 9/1/2019 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | |

4/13/2023

Work History Report

Page 4 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

| Network: LaGrande / Union Co | | Branch: A01LG | | Apron 01 LaGrand | | Section: 13 | Surface: AC |
|-------------------------------------|-------------------|-------------------------|----------------------------|--------------------------|--------------------------------------|--------------------|--------------------|
| L.C.D. 9/4/2019 | Use: APRON | Rank: P | Length: 185.00 (Ft) | Width: 30.00 (Ft) | True Area: 7040.000002 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 9/4/2019 | NC-AC | New Construction - AC | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/3/2019 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | | |
| 9/2/2019 | SB-AG | Subbase - Aggregate | 0.00 | 8.00 | <input type="checkbox"/> | | |
| 9/1/2019 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | | |

| Network: LaGrande / Union Co | | Branch: A01LG | | Apron 01 LaGrand | | Section: 14 | Surface: AC |
|-------------------------------------|-------------------|-------------------------|----------------------------|--------------------------|--------------------------------------|--------------------|--------------------|
| L.C.D. 9/4/2019 | Use: APRON | Rank: P | Length: 115.00 (Ft) | Width: 20.00 (Ft) | True Area: 4336.000001 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 9/4/2019 | NC-AC | New Construction - AC | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/3/2019 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | | |
| 9/2/2019 | SB-AG | Subbase - Aggregate | 0.00 | 8.00 | <input type="checkbox"/> | | |
| 9/1/2019 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | | |

| Network: LaGrande / Union Co | | Branch: A01LG | | Apron 01 LaGrand | | Section: 15 | Surface: AC |
|-------------------------------------|-------------------|-------------------------|----------------------------|--------------------------|--------------------------------------|--------------------|--------------------|
| L.C.D. 9/4/2019 | Use: APRON | Rank: P | Length: 155.00 (Ft) | Width: 40.00 (Ft) | True Area: 10085.00000 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 9/4/2019 | NC-AC | New Construction - AC | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/3/2019 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | | |
| 9/2/2019 | SB-AG | Subbase - Aggregate | 0.00 | 8.00 | <input type="checkbox"/> | | |
| 9/1/2019 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | | |

| Network: LaGrande / Union Co | | Branch: AH01LG | | Apron Helipad | | Section: 01 | Surface: PCC |
|-------------------------------------|---------------------|-------------------------|---------------------------|--------------------------|--------------------------------------|--------------------|---------------------|
| L.C.D. 9/4/2019 | Use: HELIPAD | Rank: P | Length: 20.00 (Ft) | Width: 20.00 (Ft) | True Area: 400.0000001 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 9/4/2019 | NC-PC | New Construction - PCC | 3,200.00 | 10.00 | <input checked="" type="checkbox"/> | | |
| 9/3/2019 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input type="checkbox"/> | | |
| 9/2/2019 | SB-AG | Subbase - Aggregate | 0.00 | 8.00 | <input type="checkbox"/> | | |
| 9/1/2019 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | | |

| Network: LaGrande / Union Co | | Branch: AH01LG | | Apron Helipad | | Section: 02 | Surface: PCC |
|-------------------------------------|---------------------|-------------------------|---------------------------|--------------------------|--------------------------------------|--------------------|---------------------|
| L.C.D. 9/4/2019 | Use: HELIPAD | Rank: P | Length: 20.00 (Ft) | Width: 20.00 (Ft) | True Area: 400.0000001 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 9/4/2019 | NC-PC | New Construction - PCC | 3,200.00 | 10.00 | <input checked="" type="checkbox"/> | | |
| 9/3/2019 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input type="checkbox"/> | | |
| 9/2/2019 | SB-AG | Subbase - Aggregate | 0.00 | 8.00 | <input type="checkbox"/> | | |
| 9/1/2019 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | | |

4/13/2023

Work History Report

Page 5 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

| Network: LaGrande / Union Co | | Branch: AHELILG | | Apron Helipad | | Section: 03 | Surface: PCC |
|-------------------------------------|---------------------|-------------------------|---------------------------|--------------------------|--------------------------------------|--------------------|---------------------|
| L.C.D. 9/4/2019 | Use: HELIPAD | Rank: P | Length: 20.00 (Ft) | Width: 20.00 (Ft) | True Area: 400.0000001 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 9/4/2019 | NC-PC | New Construction - PCC | 3,200.00 | 10.00 | <input checked="" type="checkbox"/> | | |
| 9/3/2019 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input type="checkbox"/> | | |
| 9/2/2019 | SB-AG | Subbase - Aggregate | 0.00 | 8.00 | <input type="checkbox"/> | | |
| 9/1/2019 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | | |

| Network: LaGrande / Union Co | | Branch: AHELILG | | Apron Helipad | | Section: 04 | Surface: PCC |
|-------------------------------------|---------------------|-------------------------|---------------------------|--------------------------|---------------------------------------|--------------------|---------------------|
| L.C.D. 9/4/2019 | Use: HELIPAD | Rank: P | Length: 36.00 (Ft) | Width: 36.00 (Ft) | True Area: 1296.0000000 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 9/4/2019 | NC-PC | New Construction - PCC | 10,368.00 | 10.00 | <input checked="" type="checkbox"/> | | |
| 9/3/2019 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input type="checkbox"/> | | |
| 9/2/2019 | SB-AG | Subbase - Aggregate | 0.00 | 8.00 | <input type="checkbox"/> | | |
| 9/1/2019 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | | |

| Network: LaGrande / Union Co | | Branch: AHTALG | | Taxiway A Hold A | | Section: 01 | Surface: AC |
|-------------------------------------|-------------------|-------------------------|----------------------------|---------------------------|---------------------------------------|--------------------|--------------------|
| L.C.D. 1/1/2021 | Use: APRON | Rank: P | Length: 170.00 (Ft) | Width: 100.00 (Ft) | True Area: 17175.000000 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 1/1/2021 | NC-AC | New Construction - AC | 0.00 | 4.00 | <input checked="" type="checkbox"/> | P-401 | |
| 1/1/2021 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | P-208 | |
| 1/1/2021 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | | |
| 1/1/2021 | SB-AG | Subbase - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | P-154 | |

| Network: LaGrande / Union Co | | Branch: AHTCLG | | Taxiway C Hold A | | Section: 01 | Surface: AC |
|-------------------------------------|-------------------|-------------------------|----------------------------|---------------------------|---------------------------------------|--------------------|--------------------|
| L.C.D. 10/4/2012 | Use: APRON | Rank: P | Length: 130.00 (Ft) | Width: 230.00 (Ft) | True Area: 29900.000000 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 10/4/2012 | NC-AC | New Construction - AC | 0.00 | 9.00 | <input checked="" type="checkbox"/> | p401 | |
| 10/3/2012 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input type="checkbox"/> | P209 | |
| 10/2/2012 | SB-AG | Subbase - Aggregate | 0.00 | 5.00 | <input type="checkbox"/> | | |
| 10/1/2012 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | | |

| Network: LaGrande / Union Co | | Branch: R12LG | | Runway 12/30 La | | Section: 01 | Surface: AAC |
|-------------------------------------|--------------------|-------------------------|------------------------------|---------------------------|--------------------------------------|------------------------|---------------------|
| L.C.D. 6/1/2014 | Use: RUNWAY | Rank: P | Length: 4,576.00 (Ft) | Width: 100.00 (Ft) | True Area: 457600.0114 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 6/1/2014 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | P401 | |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 | |
| 9/2/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2004 Maint. | |
| 9/1/2004 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2004 Maint. | |
| 9/1/1992 | OL-AS | Overlay - AC Structural | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness | |
| 9/1/1974 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | | |

4/13/2023

Work History Report

Page 6 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

Network: LaGrande / Union Co Branch: R12LG Runway 12/30 La Section: 02 Surface: AAC
 L.C.D. 6/1/2014 Use: RUNWAY Rank: P Length: 1,024.00 (Ft) Width: 100.00 (Ft) True Area: 102400.0004 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|--------------------------|------|----------------|-------------------------------------|------------------------|
| 6/1/2014 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | P401 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2004 Maint. |
| 9/2/1991 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/1/1991 | BA-BI | Base Course - Bituminous | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |

Network: LaGrande / Union Co Branch: R12LG Runway 12/30 La Section: 03 Surface: AAC
 L.C.D. 6/1/2014 Use: RUNWAY Rank: P Length: 659.00 (Ft) Width: 100.00 (Ft) True Area: 65921 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|-------------------------|------|----------------|-------------------------------------|----------|
| 6/1/2014 | OL-AS | Overlay - AC Structural | 0.00 | 0.00 | <input checked="" type="checkbox"/> | P401 |
| 10/4/2012 | NC-AC | New Construction - AC | 0.00 | 9.00 | <input checked="" type="checkbox"/> | P401 |
| 10/3/2012 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input type="checkbox"/> | P209 |
| 10/2/2012 | SB-AG | Subbase - Aggregate | 0.00 | 5.00 | <input type="checkbox"/> | |
| 10/1/2012 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | |

Network: LaGrande / Union Co Branch: R16LG Runway 16/34 La Section: 01 Surface: AAC
 L.C.D. 1/1/2021 Use: RUNWAY Rank: P Length: 454.00 (Ft) Width: 60.00 (Ft) True Area: 27198.00000 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|----------------------------------|------|----------------|-------------------------------------|----------------|
| 1/1/2021 | MOL-3 | Cold Mill and Overlay - 3 Inches | 0.00 | 3.00 | <input checked="" type="checkbox"/> | P-401 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 8/2/2008 | OL-AS | Overlay - AC Structural | 0.00 | 3.00 | <input checked="" type="checkbox"/> | |
| 8/1/2008 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | |
| 1/2/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.10 | <input type="checkbox"/> | |
| 1/1/2004 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | |
| 9/1/1984 | OL-AS | Overlay - AC Structural | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | |

4/13/2023

Work History Report

Page 7 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

Network: LaGrande / Union Co Branch: R16LG Runway 16/34 La Section: 02 Surface: AC
 L.C.D. 1/1/2021 Use: RUNWAY Rank: P Length: 150.00 (Ft) Width: 60.00 (Ft) True Area: 9000.000114 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|----------------------------------|------|----------------|-------------------------------------|----------|
| 1/1/2021 | MOL-3 | Cold Mill and Overlay - 3 Inches | 0.00 | 3.00 | <input checked="" type="checkbox"/> | P-401 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 8/3/2008 | CR-AC | Complete Reconstruction - AC | 0.00 | 5.00 | <input checked="" type="checkbox"/> | P401 |
| 8/2/2008 | BA-AG | Base Course - Aggregate | 0.00 | 7.00 | <input type="checkbox"/> | P209 |
| 8/1/2008 | SB-AG | Subbase - Aggregate | 0.00 | 12.00 | <input type="checkbox"/> | |
| 1/2/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.10 | <input type="checkbox"/> | |
| 1/1/2004 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | |
| 9/1/1978 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | |

Network: LaGrande / Union Co Branch: R16LG Runway 16/34 La Section: 03 Surface: AAC
 L.C.D. 1/1/2021 Use: RUNWAY Rank: P Length: 2,800.00 (Ft) Width: 60.00 (Ft) True Area: 168713.0000 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|----------------------------------|------|----------------|-------------------------------------|----------------|
| 1/1/2021 | MOL-3 | Cold Mill and Overlay - 3 Inches | 0.00 | 3.00 | <input checked="" type="checkbox"/> | P-401 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 8/2/2008 | OL-AS | Overlay - AC Structural | 0.00 | 3.00 | <input checked="" type="checkbox"/> | |
| 8/1/2008 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | |
| 1/2/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.10 | <input type="checkbox"/> | |
| 1/1/2004 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | |
| 9/1/1984 | OL-AS | Overlay - AC Structural | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | |

Network: LaGrande / Union Co Branch: TAILG Taxiway A1 Section: 01 Surface: AC
 L.C.D. 1/1/2021 Use: TAXIWAY Rank: P Length: 300.00 (Ft) Width: 75.00 (Ft) True Area: 23227.00000 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|-------------------------|------|----------------|-------------------------------------|----------|
| 1/1/2021 | NC-AC | New Construction - AC | 0.00 | 4.00 | <input checked="" type="checkbox"/> | P-401 |
| 1/1/2021 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | P-208 |
| 1/1/2021 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | |
| 1/1/2021 | SB-AG | Subbase - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | P-154 |

4/13/2023

Work History Report

Page 8 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

| Network: LaGrande / Union Co | | Branch: TA2LG | Taxiway A2 | Section: 01 | Surface: AC | |
|------------------------------|--------------|-------------------------|---------------------|-------------------|-------------------------------------|----------|
| L.C.D. 1/1/2021 | Use: TAXIWAY | Rank: P | Length: 175.00 (Ft) | Width: 50.00 (Ft) | True Area: 11300.00000 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 1/1/2021 | NC-AC | New Construction - AC | 0.00 | 4.00 | <input checked="" type="checkbox"/> | P-401 |
| 1/1/2021 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | P-208 |
| 1/1/2021 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | |
| 1/1/2021 | SB-AG | Subbase - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | P-154 |

| Network: LaGrande / Union Co | | Branch: TALG | Taxiway A LaGran | Section: 01 | Surface: AAC | |
|------------------------------|--------------|---------------------------------|--------------------|-------------------|-------------------------------------|----------------|
| L.C.D. 6/1/2014 | Use: TAXIWAY | Rank: P | Length: 75.00 (Ft) | Width: 70.00 (Ft) | True Area: 5786 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 6/1/2014 | OL-AS | Overlay - AC Structural | 0.00 | 2.50 | <input checked="" type="checkbox"/> | P401 |
| 8/3/2008 | CR-AC | Complete Reconstruction - AC | 0.00 | 5.00 | <input checked="" type="checkbox"/> | P401 |
| 8/2/2008 | BA-AG | Base Course - Aggregate | 0.00 | 7.00 | <input type="checkbox"/> | P209 |
| 8/1/2008 | SB-AG | Subbase - Aggregate | 0.00 | 12.00 | <input type="checkbox"/> | |
| 9/1/1993 | ST-SS | Surface Treatment - Slurry Seal | 0.00 | 0.50 | <input type="checkbox"/> | |
| 9/1/1992 | OL-AS | Overlay - AC Structural | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/1/1974 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | |

| Network: LaGrande / Union Co | | Branch: TALG | Taxiway A LaGran | Section: 02 | Surface: AC | |
|------------------------------|--------------|------------------------------|---------------------|-------------------|-------------------------------------|----------|
| L.C.D. 8/3/2008 | Use: TAXIWAY | Rank: P | Length: 310.00 (Ft) | Width: 50.00 (Ft) | True Area: 15500.00000 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 8/3/2008 | CR-AC | Complete Reconstruction - AC | 0.00 | 5.00 | <input checked="" type="checkbox"/> | P401 |
| 8/2/2008 | BA-AG | Base Course - Aggregate | 0.00 | 7.00 | <input type="checkbox"/> | P209 |
| 8/1/2008 | SB-AG | Subbase - Aggregate | 0.00 | 12.00 | <input type="checkbox"/> | |

| Network: LaGrande / Union Co | | Branch: TALG | Taxiway A LaGran | Section: 03 | Surface: AAC | |
|------------------------------|--------------|---------------------------------|-----------------------|-------------------|-------------------------------------|----------|
| L.C.D. 9/1/1974 | Use: TAXIWAY | Rank: P | Length: 2,711.00 (Ft) | Width: 50.00 (Ft) | True Area: 118555 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/1993 | ST-SS | Surface Treatment - Slurry Seal | 0.00 | 0.50 | <input type="checkbox"/> | |
| 9/1/1974 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | |

4/13/2023

Work History Report

Page 9 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

| Network: LaGrande / Union Co | | Branch: TALG | Taxiway A LaGran | Section: 04 | Surface: AC | |
|------------------------------|--------------|-------------------------|-----------------------|-------------------|-------------------------------------|----------|
| L.C.D. 1/1/2021 | Use: TAXIWAY | Rank: P | Length: 1,260.00 (Ft) | Width: 45.00 (Ft) | True Area: 60718.00001 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 1/1/2021 | NC-AC | New Construction - AC | 0.00 | 4.00 | <input checked="" type="checkbox"/> | P-401 |
| 1/1/2021 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | P-208 |
| 1/1/2021 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | |
| 1/1/2021 | SB-AG | Subbase - Aggregate | 0.00 | 6.00 | <input type="checkbox"/> | P-154 |

| Network: LaGrande / Union Co | | Branch: TBLG | Taxiway B LaGran | Section: 01 | Surface: AAC | |
|------------------------------|--------------|-------------------------|---------------------|-------------------|-------------------------------------|--------------------------------|
| L.C.D. 6/1/2014 | Use: TAXIWAY | Rank: P | Length: 215.00 (Ft) | Width: 50.00 (Ft) | True Area: 19835 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 6/1/2014 | OL-AS | Overlay - AC Structural | 0.00 | 3.50 | <input checked="" type="checkbox"/> | P401 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2008 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 9/2/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2004 Maint. |
| 9/1/2004 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2004 Maint. |
| 6/1/2001 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2001 Maint. Program |
| 9/3/1993 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/2/1993 | BA-AG | Base Course - Aggregate | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/1/1993 | SB-AG | Subbase - Aggregate | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |

| Network: LaGrande / Union Co | | Branch: TBLG | Taxiway B LaGran | Section: 02 | Surface: AC | |
|------------------------------|--------------|-------------------------|---------------------|-------------------|-------------------------------------|--------------------------------|
| L.C.D. 9/3/1993 | Use: TAXIWAY | Rank: P | Length: 944.00 (Ft) | Width: 50.00 (Ft) | True Area: 48734 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2008 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 9/2/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2004 Maint. |
| 9/1/2004 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2004 Maint. |
| 6/1/2001 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2001 Maint. Program |
| 9/3/1993 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/2/1993 | BA-AG | Base Course - Aggregate | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/1/1993 | SB-AG | Subbase - Aggregate | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |

4/13/2023

Work History Report

Page 10 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

| Network: LaGrande / Union Co | | Branch: TBLG | Taxiway B LaGran | | Section: 03 | Surface: AC |
|------------------------------|--------------|----------------------------------|---------------------|-------------------|-------------------------------------|-------------|
| L.C.D. 1/2/2021 | Use: TAXIWAY | Rank: P | Length: 305.00 (Ft) | Width: 54.00 (Ft) | True Area: 24749.00000 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 1/2/2021 | MOL-3 | Cold Mill and Overlay - 3 Inches | 0.00 | 3.00 | <input checked="" type="checkbox"/> | P-401 |
| 1/1/2021 | MOL-3 | Cold Mill and Overlay - 3 Inches | 0.00 | 3.00 | <input checked="" type="checkbox"/> | P-401 |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 8/3/2008 | CR-AC | Complete Reconstruction - AC | 0.00 | 5.00 | <input checked="" type="checkbox"/> | P401 |
| 8/2/2008 | BA-AG | Base Course - Aggregate | 0.00 | 7.00 | <input type="checkbox"/> | P209 |
| 8/1/2008 | SB-AG | Subbase - Aggregate | 0.00 | 12.00 | <input type="checkbox"/> | |
| 9/1/1993 | ST-SS | Surface Treatment - Slurry Seal | 0.00 | 0.50 | <input type="checkbox"/> | |
| 9/3/1949 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/2/1949 | BA-AG | Base Course - Aggregate | 0.00 | 6.00 | <input checked="" type="checkbox"/> | |
| 9/1/1949 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | |

| Network: LaGrande / Union Co | | Branch: TC1LG | Taxiway C1 LaGra | | Section: 01 | Surface: AAC |
|------------------------------|--------------|----------------------------------|---------------------|-------------------|-------------------------------------|----------------------------|
| L.C.D. 6/1/2014 | Use: TAXIWAY | Rank: P | Length: 150.00 (Ft) | Width: 50.00 (Ft) | True Area: 8573 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 6/1/2014 | OL-AS | Overlay - AC Structural | 0.00 | 6.00 | <input checked="" type="checkbox"/> | P401 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2008 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2008 |
| 9/2/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.00 | <input type="checkbox"/> | Oregon DOA 2004 Maint. |
| 9/1/1991 | OL-AS | Overlay - AC Structural | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1991, unk. thickness |
| 9/1/1986 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | circa 1986 |
| 9/2/1984 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1984, unk. thickness |
| 9/1/1984 | BA-UN | Base Course - Unknown (Major MR) | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1984, unk. thickness |

| Network: LaGrande / Union Co | | Branch: TC1LG | Taxiway C1 LaGra | | Section: 02 | Surface: AC |
|------------------------------|--------------|----------------------------------|---------------------|-------------------|-------------------------------------|----------------------------|
| L.C.D. 9/2/1984 | Use: TAXIWAY | Rank: P | Length: 113.00 (Ft) | Width: 50.00 (Ft) | True Area: 5649.999999 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 9/1/1986 | CS-AC | Crack Sealing - AC | 0.00 | 0.10 | <input type="checkbox"/> | circa 1986 |
| 9/2/1984 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1984, unk. thickness |
| 9/1/1984 | BA-UN | Base Course - Unknown (Major MR) | 0.00 | 0.00 | <input checked="" type="checkbox"/> | circa 1984, unk. thickness |

| Network: LaGrande / Union Co | | Branch: TC2LG | Taxiway C2 LaGra | | Section: 01 | Surface: AAC |
|------------------------------|--------------|-------------------------|---------------------|-------------------|-------------------------------------|--------------|
| L.C.D. 6/1/2014 | Use: TAXIWAY | Rank: P | Length: 125.00 (Ft) | Width: 70.00 (Ft) | True Area: 13561 (SqFt) | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
| 6/1/2014 | OL-AS | Overlay - AC Structural | 0.00 | 2.50 | <input checked="" type="checkbox"/> | P401 |
| 10/4/2012 | NC-AC | New Construction - AC | 0.00 | 9.00 | <input checked="" type="checkbox"/> | P401 |
| 10/3/2012 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input type="checkbox"/> | P209 |
| 10/2/2012 | SB-AG | Subbase - Aggregate | 0.00 | 5.00 | <input type="checkbox"/> | |
| 10/1/2012 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | |

4/13/2023

Work History Report

Page 11 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

Network: LaGrande / Union Co Branch: TC2LG Taxiway C2 LaGra Section: 02 Surface:AC
 L.C.D. 10/4/2012 Use: TAXIWAY Rank: P Length: 200.00 (Ft) Width: 70.00 (Ft) True Area: 24798 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|-------------------------|------|----------------|-------------------------------------|----------|
| 10/4/2012 | NC-AC | New Construction - AC | 0.00 | 9.00 | <input checked="" type="checkbox"/> | P401 |
| 10/3/2012 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input type="checkbox"/> | P209 |
| 10/2/2012 | SB-AG | Subbase - Aggregate | 0.00 | 5.00 | <input type="checkbox"/> | |
| 10/1/2012 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | |

Network: LaGrande / Union Co Branch: TCLG Taxiway C LaGran Section: 01 Surface:AC
 L.C.D. 9/3/1991 Use: TAXIWAY Rank: P Length: 2,204.00 (Ft) Width: 50.00 (Ft) True Area: 122032.0000 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|-------------------------|------|----------------|-------------------------------------|------------------------|
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2004 Maint. |
| 9/3/1991 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/2/1991 | BA-AG | Base Course - Aggregate | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/1/1991 | SB-AG | Subbase - Aggregate | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |

Network: LaGrande / Union Co Branch: TCLG Taxiway C LaGran Section: 02 Surface:AC
 L.C.D. 9/3/1991 Use: TAXIWAY Rank: P Length: 566.00 (Ft) Width: 50.00 (Ft) True Area: 30453.00000 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|-------------------------|------|----------------|-------------------------------------|------------------------|
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2004 Maint. |
| 9/3/1991 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/2/1991 | BA-AG | Base Course - Aggregate | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/1/1991 | SB-AG | Subbase - Aggregate | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |

Network: LaGrande / Union Co Branch: TCLG Taxiway C LaGran Section: 03 Surface:AAC
 L.C.D. 9/1/2012 Use: TAXIWAY Rank: P Length: 113.00 (Ft) Width: 50.00 (Ft) True Area: 10662 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|-------------------------|------|----------------|-------------------------------------|---------------------------|
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2012 | OL-AS | Overlay - AC Structural | 0.00 | 0.00 | <input checked="" type="checkbox"/> | Unknown LCD and thickness |
| 9/2/1984 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | Unknown LCD and thickness |
| 9/1/1984 | BA-AG | Base Course - Aggregate | 0.00 | 0.00 | <input type="checkbox"/> | Unknown LCD and thickness |

Network: LaGrande / Union Co Branch: TCLG Taxiway C LaGran Section: 04 Surface:AC
 L.C.D. 9/3/1991 Use: TAXIWAY Rank: P Length: 927.00 (Ft) Width: 50.00 (Ft) True Area: 44975 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|-------------------------|------|----------------|-------------------------------------|------------------------|
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2012 |
| 9/1/2004 | SS-FS | Surface Seal - Fog Seal | 0.00 | 0.10 | <input type="checkbox"/> | Oregon DOA 2004 Maint. |
| 9/3/1991 | NC-AC | New Construction - AC | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/2/1991 | BA-AG | Base Course - Aggregate | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |
| 9/1/1991 | SB-AG | Subbase - Aggregate | 0.00 | 0.00 | <input checked="" type="checkbox"/> | unk. thickness |

4/13/2023

Work History Report

Page 12 of 14

Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM

| Network: LaGrande / Union Co | | Branch: TCLG | | Taxiway C LaGran | | Section: 05 | Surface: AC |
|-------------------------------------|---------------------|-------------------------|----------------------------|--------------------------|-------------------------------------|--------------------|--------------------|
| L.C.D. 10/4/2012 | Use: TAXIWAY | Rank: P | Length: 680.00 (Ft) | Width: 50.00 (Ft) | True Area: 33710 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 10/4/2012 | NC-AC | New Construction - AC | 0.00 | 9.00 | <input checked="" type="checkbox"/> | | |
| 10/3/2012 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input type="checkbox"/> | | |
| 10/2/2012 | SB-AG | Subbase - Aggregate | 0.00 | 5.00 | <input type="checkbox"/> | | |
| 10/1/2012 | FB-TX | Geotextile | 0.00 | 0.00 | <input type="checkbox"/> | | |

| Network: LaGrande / Union Co | | Branch: TDLG | | Taxiway D LaGran | | Section: 01 | Surface: AAC |
|-------------------------------------|---------------------|----------------------------------|------------------------------|--------------------------|--------------------------------------|-----------------------|---------------------|
| L.C.D. 1/1/2021 | Use: TAXIWAY | Rank: P | Length: 2,165.00 (Ft) | Width: 40.00 (Ft) | True Area: 93045.00002 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 1/1/2021 | MOL-3 | Cold Mill and Overlay - 3 Inches | 0.00 | 3.00 | <input checked="" type="checkbox"/> | P-401 PMP 2012 | |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | | |
| 9/2/2009 | SS-ST | Surface Treatment - Slurry Seal | 0.00 | 0.00 | <input type="checkbox"/> | | |
| 9/1/2009 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | | |
| 9/1/1978 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | | |

| Network: LaGrande / Union Co | | Branch: TDLG | | Taxiway D LaGran | | Section: 02 | Surface: AAC |
|-------------------------------------|---------------------|----------------------------------|---------------------------|--------------------------|-------------------------------------|-----------------------------------|---------------------|
| L.C.D. 1/1/2021 | Use: TAXIWAY | Rank: P | Length: 94.00 (Ft) | Width: 40.00 (Ft) | True Area: 4844 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 1/1/2021 | MOL-3 | Cold Mill and Overlay - 3 Inches | 0.00 | 3.00 | <input checked="" type="checkbox"/> | P-401 PMP 2015 PMP 2012 | |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | | |
| 9/1/2012 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | | |
| 9/1/1978 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | | |

| Network: LaGrande / Union Co | | Branch: TDLG | | Taxiway D LaGran | | Section: 03 | Surface: AAC |
|-------------------------------------|---------------------|----------------------------------|---------------------------|--------------------------|-------------------------------------|--------------------|---------------------|
| L.C.D. 1/1/2021 | Use: TAXIWAY | Rank: P | Length: 30.00 (Ft) | Width: 40.00 (Ft) | True Area: 2746 (SqFt) | | |
| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments | |
| 1/1/2021 | MOL-3 | Cold Mill and Overlay - 3 Inches | 0.00 | 3.00 | <input checked="" type="checkbox"/> | P-401 | |
| 9/1/1993 | ST-SS | Surface Treatment - Slurry Seal | 0.00 | 0.50 | <input type="checkbox"/> | | |
| 9/1/1974 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input checked="" type="checkbox"/> | | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | | |

4/13/2023

Work History Report

Page 13 of 14

*Pavement Database: ODA_WOC3_4-10-2023_PostWHEdits_4PM***Network:** LaGrande / Union Co**Branch:** TDLG

Taxiway D LaGran

Section: 04**Surface:** AAC**L.C.D.** 1/1/2021**Use:** TAXIWAY**Rank:** P**Length:** 263.00 (Ft)**Width:** 40.00 (Ft)**True Area:** 15923.00000 (SqFt)

| Work Date | Work Code | Work Description | Cost | Thickness (in) | Major M&R | Comments |
|-----------|-----------|----------------------------------|------|----------------|-------------------------------------|----------|
| 1/1/2021 | MOL-3 | Cold Mill and Overlay - 3 Inches | 0.00 | 3.00 | <input checked="" type="checkbox"/> | P-401 |
| 9/1/2015 | CS-AC | Crack Sealing - AC | 0.00 | 0.00 | <input type="checkbox"/> | PMP 2015 |
| 9/1/2009 | OL-AS | Overlay - AC Structural | 0.00 | 3.00 | <input checked="" type="checkbox"/> | |
| 9/1/1993 | ST-SS | Surface Treatment - Slurry Seal | 0.00 | 0.50 | <input type="checkbox"/> | |
| 9/1/1974 | OL-AS | Overlay - AC Structural | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/3/1942 | NC-AC | New Construction - AC | 0.00 | 2.00 | <input checked="" type="checkbox"/> | |
| 9/2/1942 | BA-AG | Base Course - Aggregate | 0.00 | 4.00 | <input checked="" type="checkbox"/> | |
| 9/1/1942 | SB-AG | Subbase - Aggregate | 0.00 | 4.50 | <input checked="" type="checkbox"/> | |

Summary:

| Work Description | Section Count | Area Total (SqFt) | Thickness Avg (in) | Thickness STD (in) |
|----------------------------------|---------------|-------------------|--------------------|--------------------|
| Base Course - Unknown (Major MR) | 8 | 186,397.00 | 0.00 | 0.00 |
| Base Course - Aggregate | 43 | 1,725,149.01 | 4.74 | 2.53 |
| Base Course - Bituminous | 1 | 102,400.00 | 0.00 | 0.00 |
| Cold Mill and Overlay - 3 Inches | 9 | 370,967.00 | 3.00 | 0.00 |
| Cold Milling | 1 | 4,529.00 | 2.00 | 0.00 |
| Complete Reconstruction - AC | 4 | 55,035.00 | 5.00 | 0.00 |
| Crack Seal - Wide Cracks | 6 | 211,955.00 | 0.00 | 0.00 |
| Crack Sealing - AC | 58 | 3,373,402.02 | 0.03 | 0.04 |
| Geotextile | 17 | 340,510.00 | 0.00 | 0.00 |
| New Construction - AC | 44 | 1,956,415.01 | 2.48 | 2.73 |
| New Construction - PCC | 4 | 2,496.00 | 10.00 | 0.00 |
| Overlay - AC Structural | 33 | 2,450,325.04 | 2.47 | 1.76 |
| Patching - AC Deep | 7 | 337,175.00 | 0.00 | 0.00 |
| Subbase - Aggregate | 38 | 1,569,543.01 | 5.57 | 3.16 |
| Surface Seal - Fog Seal | 11 | 1,039,513.01 | 0.09 | 0.03 |
| Surface Treatment - Slurry Seal | 8 | 333,471.00 | 0.31 | 0.24 |