Building Type	County
School	Jackson

Street
333 Holmes Ave

City	State	Zip
Medford	OR	97501

Latitude	Longitude
42.30865	122.86948

Tracking Code	Inspection Date
RVS in 2006	7/21/2006

Seismicity Zone: Moderate

FEMA 154 Rapid Visual Screening Score Card

	Type	Basic Score	Vert Irreg	Plan Irreg	Pre-Code	Post-Bench	Soil C	Soil D	Soil E	RVS Score
Primary	RM1	3.6	-2	-0.5	0	0	-0.8	0	0	0.3
Secondary		0	0	0	0	0	0	0	0	0
Tertiary		0	0	0	0	0	0	0	0	0

Jefferson Elementary School

Final RVS Score

Final Type	Final Score
RM1	0.3

FEMA-154 Collapse Potential

High (>10%)

Enrollment	Year Built (Field Verified)	Year Built (Alt. Source)	Est. Decade Built
543		1955	1970

Total Area (square ft)	Number of Stories	Basement	Pounding Potential
38185	1	No	Yes

Plan Irregularities	Vertical Irregularities
Reentrant Corners: Other	Steps in Elevation View: Single Change
Reentrant Corners: Other	None
None	None

Falling Hazards	Poor Conditions
Unreinforced Chimneys	None
None	None
None	None

E   Plan Irregularity Primary

N   Vertical Irregularity Primary

W   Falling Hazard

W   Vertical Irregularity Primary

W   Plan Irregularity Secondary
Joint to newer building

Building Type	County
School	Jackson

Street
333 Holmes Ave

City	State	Zip
Medford	OR	97501

Latitude	Longitude
42.3084	122.86948

Tracking Code	Inspection Date
RVS in 2006	7/21/2006

Seismicity Zone: Moderate

FEMA 154 Rapid Visual Screening Score Card

	Type	Basic Score	Vert Irreg	Plan Irreg	Pre-Code	Post-Bench	Soil C	Soil D	Soil E	RVS Score
Primary	RM1	3.6	0	0	0	0	-0.8	0	0	2.8
Secondary		0	0	0	0	0	0	0	0	0
Tertiary		0	0	0	0	0	0	0	0	0

Jefferson Elementary School

Final RVS Score

Final Type	Final Score
RM1	2.8

FEMA-154 Collapse Potential

Low (<1%)

Jack_sch28

Enrollment	Year Built (Field Verified)	Year Built (Alt. Source)	Est. Decade Built
543		1955	1980

Total Area (square ft)	Number of Stories	Basement	Pounding Potential
38185	1	No	Yes

Plan Irregularities	Vertical Irregularities
Reentrant Corners:Other (Adjacent Build/Entity)	None
None	None
None	None

Falling Hazards	Poor Conditions
None	None
None	None
None	None

SE   Plan Irregularity Primary

Jefferson Elementary School

Medford SD 549C

Building Type	County
School	Jackson

Street
333 Holmes Ave

City	State	Zip
Medford	OR	97501

Latitude	Longitude
42.30866	122.86916

Tracking Code	Inspection Date
RVS in 2006	7/21/2006

Seismicity Zone: Moderate

FEMA 154 Rapid Visual Screening Score Card

	Type	Basic Score	Vert Irreg	Plan Irreg	Pre-Code	Post-Bench	Soil C	Soil D	Soil E	RVS Score
Primary	RM1	3.6	0	-0.5	0	0	-0.8	0	0	2.3
Secondary		0	0	0	0	0	0	0	0	0
Tertiary		0	0	0	0	0	0	0	0	0

Jefferson Elementary School

Final RVS Score

Final Type	Final Score
RM1	2.3

FEMA-154 Collapse Potential

Low (<1%)

![Jack_sch28](aerial map)

OregonGeology

Jefferson Elementary School

Jack_sch28C

Enrollment	Year Built (Field Verified)	Year Built (Alt. Source)	Est. Decade Built
543		1955	1980

Total Area (square ft)	Number of Stories	Basement	Pounding Potential
38185	1	No	Yes

Plan Irregularities	Vertical Irregularities
Reentrant Corners:Other (Adjacent Build/Entity)	None
None	None
None	None

Falling Hazards	Poor Conditions
None	None
None	None
None	None

E   Pounding Potential
Joint

Jefferson Elementary School

Jack_sch28D

Medford SD 549C

Building Type	County
School	Jackson

Street	
333 Holmes Ave	

City	State	Zip
Medford	OR	97501

Latitude	Longitude
42.30852	122.86856

Tracking Code	Inspection Date
RVS in 2006	7/21/2006

Seismicity Zone: Moderate

FEMA 154 Rapid Visual Screening Score Card

	Type	Basic Score	Vert Irreg	Plan Irreg	Pre-Code	Post-Bench	Soil C	Soil D	Soil E	RVS Score
Primary	RM1	3.6	0	0	0	0	-0.8	0	0	2.8
Secondary		0	0	0	0	0	0	0	0	0
Tertiary		0	0	0	0	0	0	0	0	0

Jefferson Elementary School

Final RVS Score

Final Type	Final Score
RM1	2.8

FEMA-154 Collapse Potential

Low (<1%)

OregonGeology

Rapid Visual Screening - Senate Bill #2 - Seismic Needs Assessment
Oregon Department of Geology and Mineral Industries

Jefferson Elementary School

Enrollment	Year Built (Field Verified)	Year Built (Alt. Source)	Est. Decade Built
543		1955	1970
Total Area (square ft)	Number of Stories	Basement	Pounding Potential
38185	1	No	No

Plan Irregularities	Vertical Irregularities
None	None
None	None
None	None

Falling Hazards	Poor Conditions
None	None
None	None
None	None

OregonGeology

Building Type	County
School	Jackson

Street
333 Holmes Ave

City	State	Zip
Medford	OR	97501

Latitude	Longitude
42.30856	122.86824

Tracking Code	Inspection Date
RVS in 2006	7/21/2006

Seismicity Zone: Moderate

FEMA 154 Rapid Visual Screening Score Card

	Type	Basic Score	Vert Irreg	Plan Irreg	Pre-Code	Post-Bench	Soil C	Soil D	Soil E	RVS Score
Primary	RM1	3.6	0	0	0	0	-0.8	0	0	2.8
Secondary		0	0	0	0	0	0	0	0	0
Tertiary		0	0	0	0	0	0	0	0	0

Jefferson Elementary School

Final RVS Score

Final Type	Final Score
RM1	2.8

FEMA-154 Collapse Potential

Low (<1%)

Jefferson Elementary School

Enrollment	Year Built (Field Verified)	Year Built (Alt. Source)	Est. Decade Built
543		1955	1970

Total Area (square ft)	Number of Stories	Basement	Pounding Potential
38185	1	No	No

Plan Irregularities	Vertical Irregularities
None	None
None	None
None	None

Falling Hazards	Poor Conditions
None	None
None	None
None	None

OregonGeology

Rapid Visual Screening - Senate Bill #2 - Seismic Needs Assessment
Oregon Department of Geology and Mineral Industries