SECTION 00963 - SIGNAL SUPPORT DRILLED SHAFTS

(Follow all instructions. If there are no instructions above a subsection, paragraph, sentence, or bullet, then include it in the project. The specifications may be modified to include project specific specifications, but all additions, deletions, or modifications must be sent to the ODOT Technical Resource and State Specifications Engineer for review and approval.)

Comply with Section 00963 of the Standard Specifications modified as follows:

00963.10 Materials - Replace the "Reinforcement" line with the following line:

Reinforcement..... 02510

00963.47(a) Concrete Placement - Replace the paragraph that begins "Unless otherwise approved, allow…" with the following paragraph:

Allow a maximum of 60 minutes between concrete placements and use no concrete older than 90 minutes from batch time. Use procedures for concrete placement which ensure that the concrete within the shaft becomes a monolithic, homogeneous unit.