

SECTION 00310 - REMOVAL OF STRUCTURES AND OBSTRUCTIONS

(Follow all instructions and make all edits with "Track Changes" turned on. If there are no instructions [purple text] above a subsection, paragraph, sentence, or bullet, then include it in the Project. Delete all purple text before preparing the final document. All other modifications to this Section will require ODOT Technical Resource and State Specifications Engineer approval.)

(Note: Only include the "Asphalt Pavement Sawcutting" and "Concrete Sawcutting" Pay Items in the Schedule of Items when the estimated quantity is greater than 100 feet.)

(Note: Include Pay Item for "Removal of Concrete Barrier" when removal of concrete barrier work is included on the Project. Use either Lump Sum or Length unit of measurement. If Section 00820 "Remove and Reinstall Concrete Barrier" is also included in the Project, do not include that quantity of barrier removal in this Section.)

(Use the following lead-in paragraph when none of the following subsections are included in the Project.)

Comply with Section 00310 of the Standard Specifications.

(Use the following lead-in paragraph when any of the following subsections are included in the Project.)

Comply with Section 00310 of the Standard Specifications modified as follows:

(Use the following subsection .45 when historical marker installation is included in 00759.52.)

Add the following subsection:

00310.45 Salvaging Markers - Salvage the historical marker(s) and reinstall as shown or directed according to 00759.52.

(Use the following subsection .80 when the Schedule of Items includes Asphalt Pavement Sawcutting or Concrete Sawcutting or both.)

00310.80 Measurement - Replace the bullet "Length and Area..." with the following bullet:

- **Length and Area** - The length or area of the Structure or item actually removed, will be measured along the line and grade of the Structure or item for each continuous Structure or item removed. Measurement will be on the length or area basis, limited to the Neat Lines shown or directed.

(Asphalt Pavement Sawcutting) (and) (Concrete Sawcutting) will be measured by the linear foot of sawcut, limited to the Neat Lines shown or directed unless otherwise specified. Methods other than sawcutting will not be measured.

Additional concrete sawcutting beyond what is shown or directed by the Engineer will not be measured.

(Use the following subsection .90 when historical marker installation is included in 00759.52.)

00310.90 Payment - Add the following paragraph to the end of this subsection.

No separate or additional payment will be made for the salvaging historical markers.

(Use the following subsection .92 if any of the Pay Item(s) below apply.)

00310.92 Separate Item Basis -

(Use the following Pay Item and item (g) paragraph if Asphalt Pavement Sawcutting Pay Items in the Schedule of Items when the estimated quantity is greater than 100 feet. If the sawcutting is in a composite pavement section, choose the thicker of the two materials for the Pay Item, either asphalt or concrete, and use the total thickness.)

Replace the Pay Item Asphalt Pavement Sawcutting with the following Pay Item:

Pay Item	Unit of Measurement
----------	---------------------

(g) Asphalt Pavement Sawcutting, _____ Inches Deep.....	Foot
---	------

Replace the paragraph that begins “Item (g) applies...” with the following paragraph:

In item (g), “less than 6”, “6 to 14”, or “greater than 14” is inserted in the blank.

(Use the following Pay Item and item (i) paragraph if Concrete Sawcutting Pay Items in the Schedule of Items when the estimated quantity is greater than 100 feet. If the sawcutting is in a composite pavement section, choose the thicker of the two materials for the Pay Item, either asphalt or concrete, and use the total thickness.)

Add the following Pay Item to the Pay Item list:

(i) Concrete Sawcutting, _____ Inches Deep.....	Foot
---	------

Add the following paragraph after the paragraph that begins “Item (g) applies...”

In item (i), “less than 6”, “6 to 14”, or “greater than 14” is inserted in the blank.

(Use the following two paragraphs if sawcutting Pay Item(s) are included.)

Add the following paragraph to the end of the subsection:

No separate or additional payment will be made when methods other than sawcutting are utilized where sawcutting is shown or directed.

(Use the following Pay Item on Projects that have more than 8 curb ramps that are not included in Section 00330, otherwise (8 curb ramps or less not in Section 00330) curb ramp removal work will be included in the lump sum Removal of Structures and Obstructions. Include Pay Item for asphalt pavement sawcutting and concrete sawcutting when removing curb ramps. Do not include Pay Items for items (b), (c), and (d) when using item (j), unless approved by the State Specification Engineer.)

Add the following Pay Item to the Pay Item list:

(j) Removal of Surfacings for Curb Ramp Construction Square Yard

Add the following to the end of this subsection:

Item (j) includes all removal of curb ramp, walk, curb, driveway, Pavement, and other Work associated with curb ramp construction, including but not limited to walk and driveway construction between or beyond curb ramps. Item (j) does not include asphalt pavement sawcutting or concrete sawcutting.