

## SECTION 00811 - CABLE BARRIER

*(Follow all instructions and make all edits with "Track Changes" turned on. If there are no instructions [purple text] above a subsection, paragraph, sentence, or bullet, then include it in the Project. Delete all purple text before preparing the final document. All other modifications to this Section will require ODOT Technical Resource and State Specifications Engineer approval.)*

Comply with Section 00811 of the Standard Specifications modified as follows:-

**00811.10 Cable Barrier** - Replace this subsection, except for the subsection number and title, with the following:

Furnish cable barrier from the QPL. Furnish all cable barriers on the Project from the same manufacturer regardless of the number of runs of cable barrier required and regardless of the types of cable barrier required.

**00811.40 Cable Barrier** – Replace the paragraph that begins "Keep a tension log ..." with the following paragraph:

Keep a tension log and give it to the Engineer upon completion of installation. The tension log includes the time, date, location, ambient temperature, and the final tension readings, and is signed by the person performing the tension readings. Provide a copy of the manufacturer's recommended tension chart along with the tension log.

**00811.90 Payment** - Replace the paragraph that begins "Payment will be payment ..." with the following paragraph:

Payment will be payment in full for furnishing and placing all Materials, and for providing all Equipment, labor, and Incidentals necessary to complete the Work as specified.