

SECTION 00224 - TEMPORARY TRAFFIC CHANNELIZING DEVICES

(Follow all instructions and make all edits with "Track Changes" turned on. If there are no instructions [purple text] above a subsection, paragraph, sentence, or bullet, then include it in the Project. Delete all purple text before preparing the final document. All other modifications to this Section will require ODOT Technical Resource and State Specifications Engineer approval.)

Comply with Section 00224 of the Standard Specifications modified as follows:-

00224.00 Scope - Replace this subsection, except for the subsection number and title, with the following:

In addition to requirements of Section 00221, this Work consists of providing, installing, moving, maintaining, inspecting, and removing channelizing devices including, but not limited to, tubular markers, conical markers, surface mounted tubular markers, plastic drums, and delineators throughout the Project area as shown or specified.

00224.14 Delineators - Replace the paragraph that begins "Use new delineators from ..." with the following paragraph:

Use new delineators from the QPL or salvaged reflectorized delineators (W-1) or (Y-1), as appropriate, and according to the requirements of Section 00840 and the following:

00224.90 Payment - Replace the paragraph that begins "Item (a) includes ..." with the following paragraph:

Item (a) includes providing and installing the complete assembly of each device in its initial location and for removing the device from the surface.

Replace the paragraph that begins "Item (b) includes ..." with the following paragraph:

Item (b) includes providing new or refurbished devices to replace damaged or missing devices.

Replace the paragraph that begins "In item (e), the type ..." with the following paragraph:

In item (e), the type of barricade is inserted in the blank.

Replace the paragraph that begins "Payment will be payment ..." with the following paragraph:

Payment will be payment in full for furnishing, installing, moving, operating, maintaining, inspecting, and removing the Materials and TCD, and for providing all Equipment, labor, and Incidentals necessary to complete the Work as specified, except as covered in 00221.90(b).

