



# **Erosion & Sediment Control Manager Training Manual**

#### **INSERT TAB**

# Welcome to the Erosion and Sediment Control Manager (ESCM) Certification Training



1

#### **Training Presenters**

- Bob Marshall
  - 00280's / Permits
  - RoadsideDevelopment
- Cory Engel
  - Turbidity Monitoring
- Jim Gunter
  - ConstructionResources





2

#### Housekeeping Items

- Restrooms
- Scheduled breaks
- Refreshments provided
- Lunch on your own
- Turn cell phone ringers off
- Construction Training Team <u>odotconstructiontraining@odot.oregon.gov</u> 503-508-4444






2

#### **Resources Used during Training**

- ESCM Training Manual (provided)
- 2024 Standard Specifications (Student)
- Calculator (Student)





4

# **Erosion and Sediment Control Manager Certification Program**

#### **Certification Process**

- Pass an examination
- Training available, but not required
- Challenge any exam without taking the class



 Challenge Exam Info: <a href="https://www.oregon.gov/ODOT/Construction/Pages/Inspector-Certification-Program.aspx">https://www.oregon.gov/ODOT/Construction/Pages/Inspector-Certification-Program.aspx</a>



5


#### **Certification Exam**

- Exam after lunch
- Open book
- Maximum 3 hours
- 80% passing
- Results in ~2 weeks
- Certification is good for 3 years
- ESCM certification is only for ODOT projects!





6



#### **Introductions**

- Name
- Organization
- Years of experience as an Erosion and Sediment Control Manager





8

# AASHTOWare Project



odoteconstruction@odot.oregon.gov AWPAdmin@odot.oregon.gov



9

#### What type of data will Inspectors input?

#### Civil Rights & Labor

- Field Interviews
  - Employee Interviews

#### **Construction & Materials**

- Daily Work Report (DWR)
  - Formerly General Daily Progress Reports
  - Weigh memos attachments
- Pay notes generated from DWR
- Sample Tests



10

#### What type of data will Externals input?

#### Civil Rights & Labor

Certified Payrolls

Primes have ability to review data submitted by subs and technicians in AWP prior to ODOT's review.



#### **Construction & Materials**

- Subcontracts
- Daily Source Reports (DSR)
  - Updating production quantity
  - Identify how much material has been produced
- Submit mix designs
- Managing testing labs testers
- Sample Records access to create records and enter test data
- View Sources and source material

11

#### **AASHTOWare Project**



#### Visit the APOST Website:

https://www.oregon.gov/odot/Construction/Pages/AW-Construction.aspx

#### **Subscribe to The APOST Times:**

https://public.govdelivery.com/accounts/ORDOT/subscriber/new?topic\_id=ORDOT\_863



12

#### **INSERT TAB**

Unit 1 280s / Permit

# Erosion & Sediment Control: Specifications, Contract Compliance & Permit Requirements





1

#### **Topics of Discussion**

- Erosion Control is important. it is environmental protection and a Contract Requirement
- Regulations, Regulatory Agencies and Permits the 1200-CA is updated, and eagerly enforced
- Specifications:

Section 00280 – Erosion & Sediment Control Section 01030 - Seeding

- Erosion & Sediment Control BMPs & Standard Drawings
  - The what and how of erosion and sediment control



#### **Summary of Terms**

- BMP Best Management Practice
- ESCP Erosion and Sediment Control Plan
- ESCM Erosion and Sediment Control Manager
- ESC Erosion and Sediment Control
- EMP Environmental Management Plan
- NPDES National Pollution Discharge Elimination System
- PCP Pollution Control Plan
- **DEQ** Department of Environmental Quality
- USACE US Army Corps of Engineers



2

#### **00280.00 Scope – Specs are Contract Conditions**

- This work consists of providing effective functioning erosion and sediment control until the site is permanently stabilized.
- This work consists of...compliance with NPDES 1200-CA Permit when the permit is applicable
- Contractor is responsible to comply with all specification conditions.

ESCM directs Contractor in ESC work

Inspector verifies Contractor performs work.



#### **Regulations and Regulatory Agencies**

- National Pollutant Discharge Elimination System (NPDES) is a stormwater discharge permit for construction activities.
- 1200-CA is ODOT's NPDES permit, covers multiple projects of similar type – Having this permit in-hand eliminates months of onerous work during Project development.
- Oregon DEQ administers 1200-CA permit.
- FAHP Federal Aid Highway Program
  - Ties Federal funding to compliance with Endangered Species Act (ESA).
  - Sedimentation can damage critical habitat of Endangered Species.
  - FAHP compliance is monitored by ODOT Environmental



5

#### **Good Permit Compliance Benefits ODOT**

- ODOT is a trusted partner, with the native Tribes and multiple regulatory agencies. These agencies regulate impacts to fish, wildlife, natural landscapes, clean water and clean air.
- ODOT's reputation as a trusted partner is reinforced by our compliance with permit requirements.
- Each of ODOT's 5 Regions hold a1200-CA Permit.
   Federal Funding is enabled by the FAHP. These established permits are enabled by our trusted-partner relationship with other agencies.

This is a sweet deal. Let's not mess this up.



# ALL projects must comply with the 00280 Section

Projects with areas of disturbance one acre or more must comply with the 1200-CA permit.

Areas of disturbance in staging areas are added to Project areas of disturbance in determining 1200-CA coverage




7

# On Projects covered by the 1200-CA permit: Contractor Must Revise ESCP Prior to Beginning Construction to Provide the following:


- ESCP is posted as Bid Reference Document
- List Sub-Contractors working on Project site,
- List of potential polluting activities/materials,
- Provide name & position for all personnel involved with every aspect of ESC during construction, including ESCM with name, title, contact information & certification,
- Show staging area, stockpile area, materials processing area with appropriate ESC BMPs,
- EMP if applicable,





Sediment leaving the site









# 1200-CA Stormwater Discharge Permit and 00280 Section: In place to prevent...

#### **Evidence of erosion**





MATERIALS & INSPECTION

Evidence indicates there was turbid discharge

### 1200-CA Stormwater Discharge Permit In place to <u>prevent</u> from leaving site, or entering water...

- Visually turbid discharge or sediment or discharge that result in exceedances of water quality standards (10% above background
- Fuels, oils or solvents used with vehicles or equipment
- Wastewater from washing construction materials from tools or equipment, or wastewater containing soaps or solvents used in washing equipment or vehicles.
- Wheel wash wastewater
- Saw cut slurry and toxic or hazardous substances

Specifications support these permit requirements



11

#### **ODOT 1200-CA Permit**

- Contractor is provided a copy of the permit to the at the pre-con meeting.
- A copy of the permit must be kept on an active site.
- Local permits may also be required. (Local regulations may be more stringent.)



#### Recent 1200-CA Update fully in Effect

The 1200-CA Permit and the suite of related documents are located in the ODOT Erosion & Sediment Control web page under **Guidance Materials** 

Read the 1200-CA permit and Appendices A and B
They are written in plain language & it defines
requirements

00280.00 requires compliance with NPDES 1200-CA
Permit



13

### **Erosion & Sediment Control Plan (ESCP)** consists of:

- The Contract Erosion & Sediment Control Plan
- Implementation of the ESCP
- Monitoring (ESC) features and filling out monitoring report
- Monitoring receiving waters With submittals to DEQ
- Maintenance & repair of ESC features With submittals to DEQ
- Environmental Management Plan (EMP) attachment (When required)
- Updates to ESCP to keep document representative of current Project status With submittals to DEQ
- **Submittals to DEQ** reporting updates, maintenance & repair actions, non-compliance & violations and clean-ups and BMP repair.



#### **ESCM Duties Include:**

- Read 1200-CA Permit & keep site permit compliant
- Visually Monitor site as follows:
- · On initial date
- Every 14 days
- Within 24 hours of storm events that results in stormwater runoff
- · Within 24 hours of snow melt that results in runoff
- Monitor receiving waters
- Mobilize crews to provide corrective actions
- Fill out monitoring report form (ORS-012-0055: Failing to collect monitoring data is a Class 1 penalty)



15

# **Contractor Shall Revise BMPs to address and ESCP to Reflect Current Site Conditions**





#### **ESCM Must Revise ESCP Within 7 Days of:**

- Changes in Construction Plans that impact ESC,
- Changes in BMPs including type, design, locations or additions,
- Expansion of Construction area.
- Changes resulting from Corrective Actions.
- Changes required by DEQ or Agency,
- Changes of contractors or ESC subcontractors
- Changes in personnel involved in any aspect of ESC,
- Change of ESCM

ESCM provides ESCP updates to Agency for submittal to DEQ W/in 30 days



17

#### Required to have available on site:

- Monitoring reports in chronological order
- ESCP <u>current revision</u> electronic access is OK (some locations may not have internet access!)
- Names and contact information of all personnel involved in all aspects of ESC and complying with the 1200-CA permit.
- All updates, revisions, corrective actions, monitoring and reporting is the responsibility of ESCM



# 1200-CA (Appendix A) Include with ESCP – EMP when applicable

- ESC POR, with Region HazMat, identifies contamination type and location on ESC Plans and develops EMP.
- Contractor owns Means & Methods & may develop own EMP for submittal and approved by DEQ prior to beginning work on areas of contamination.
- When contamination is found during construction, stop work in area of contamination. Contractor develops EMP and gets DEQ approval for EMP prior to resuming work in that area.
- Agency Responsible Official (RO) submits EMP to DEQ and pays EMP review fee.
- On Projects <u>NOT</u> covered by 1200-CA, comply with 00290.30-Pollution Control

17

19

# Natural and undisturbed 50' Buffer Zones required between work and waters of the State

(Appendix B provides guidance)

- Protect and preserve riparian vegetation and Buffer Zone.
- When conditions do not provide 50' natural buffer, POR will design erosion & sediment controls to protect inadequate buffer & provide the protection equivalent to a 50' buffer.
- Respect Buffer Zones the same as any no-work-area



#### Monitoring – 00280.62: ESCM fills out form 734-2361

- Confirm all BMPs are installed correctly and are providing effective function
- Confirm conditions that could release pollutants (leaks, spills etc.) are addressed
- Identify areas where new BMPs or maintenance of BMPs are needed,
- Identify areas of visible erosion or sedimentation,
- Document all findings and provide photos.





21

## Monitoring is required within 24 hours after <u>all</u> storms that generate runoff.



Discharge shown is <u>not</u> cause by storm. Paying attention to what occurs on project site is required



#### 10/11/16 (note the date)



00280.30 – ESCM must report permit violations to Agency.
Self reporting is foundation with ODOT's trusted reputation

23


#### Install <u>all</u> BMPs shown on ESCP! Here perimeter control Was Specified:



#### 00280.40

"...Install these ESC before performing clearing, grading, or other land altering activities."

ESCM leads on erosion & sediment control. ODOT verifies risk is addressed & contracted work is done



25

# Non-Compliance Requires Self Reporting by Permittee & Corrective Actions by Contractor

- Mistakes happen. Self-Reporting sediment discharge to DEQ actually builds trust,
- DEQ would be suspicious if conditions were always perfect,
- Within 24 hours ODOT does the following:
  - Provide narrative of non-compliance,
  - · Provide photos of discharge,
  - Clean up sediment or discharge,
  - Provide plans for correcting ESC failure,
- Follow non-compliance report with corrective action.



### Non-Compliance Require Immediate Corrective Actions by Contractor

- Address conditions that caused discharge
- Clean up sediment contamination left by discharge
- Complete minor corrective actions by close of next business day
- Install new or replacement BMPs, required by Corrective actions, within 24 hours
- If completion of corrective actions within 24 hours is not feasible, document the schedule for implementing the corrective action
- Revise ESCP to reflect corrective action repairs within 7 days

days MATERIALS & INSPECTION

27

#### **Corrective Action Report Include:**

- Site name and Project's Permit ID number
- Description and cause of non-compliance
- Photos of discharge and [NTU] of receiving water
- Period of non-compliance
- Names of person(s) conducting monitoring
- Corrective steps taken and timeline of the corrective action
- Note of weather that may have contributed to the discharge
- Revisions of ESCP to show corrective action BMPs



#### **Prompt Corrective Action Result:**

When non-compliance is promptly self reported, the discharge cleaned up, the cause of the discharge repaired and a Corrective Action Report submitted, the event will <u>not</u> result in penalties.





29

#### 1200-CA Conditions

- Active Treatment (flocculants, electro-coagulation, etc.) require an EMP & must be stamped by engineer – Baker Tank providers can provide acceptable engineering
- Permittee must obtain approval for EMP prior to using Active Treatments (other than C02 sparging)
- Concrete wash out only in designated and protected areas
- Concrete wash water shall not adversely affect groundwater
- Concrete wash out area and concrete waste management must be maintained as functional at all times
- Concrete spillage or discharge to surface waters is prohibited

Concrete wash water is a pollutant - 00290.30



#### **Submissions to DEQ**

- Provide ESCP revisions, & corrective action submittals as required by 1200-CA
- Submissions to DEQ are our communication with them about the project.
- Missing submissions are communication breakdowns.
- Missing, late, inaccurate or incomplete submissions tell DEQ that Project team does not take erosion & sediment control seriously
- Use "Your DEQ Online" (YDO) electronic portal for submissions
  - · Monitoring reports are not a required submittal



31

#### **Consultant Inspected Project**

Consultant inspectors represent ODOT

All inspectors must use their authority and verify that contractors satisfy contract conditions





# 0280.04 – Erosion and Sediment Control Plan on Agency Controlled Lands

- ESCP –Required to cover all construction phases!
   Address temporary soil cover? Storm water runoff?
   Perimeter sediment control? Effective functioning?
   Look at the ESCP critically.
- Using Agency ESCP is not an excuse to overlook issues on a job site. Agency ESCPs will require updates and revision during construction.
- DEQ may request modifications to the ESCP at any time.
   ODOT may require ESCP modifications at any time.
- ODOT's 1200-CA permit does not cover non-Agency controlled land (00280.05). (Contractor's 3<sup>rd</sup> party staging areas likely to require individual 1200-C)




33


#### **BREAK**





Wayfinding overlook at Battle Rock











#### Inspector Responsibilities

- Have thorough understanding of the project, the ESCP, the natures of erosion and sedimentation and knowledge of BMPs.
- Ensure that the Contractor installs ESCP identified BMPs and updates the ESCP as construction progresses.
- Ensure that the Contractor maintains the erosion control facilities as to provide effective functioning.
- Ensure the Contractor keeps the project in administrative Permit compliance, including keeping ESCP updated and Monitoring Reports accurate and current.
- Sign monitoring forms verifying honest monitoring & submit to DEQ through YDO



39

#### 00280.06 & 00280.30 Erosion and Sediment Control Manager (ESCM) as required by 1200-CA

Contractor shall provide a person experienced in all disciplines of highway construction and certified as qualified, as the Erosion and Sediment Control Manager (ESCM).

- **00280.30**, Special Provisions list **30** duties of ESCM.
- Contractor and ESCM are the erosion and sediment control lead.
- ODOT owns the risk and enforces the contract so to provide effective functioning ESC.



#### **Duties of ESCM (continued)**

- Inspect ESC and monitor receiving waters on active construction site on initial date and every 14 Days for effective functioning.
- Inspect ESC on inactive areas every 14 Days for effective functioning.
- Inspect ESC for effective functioning and monitor receiving waters, on all active and inactive sites at least within 24 hours of rainfall events sufficient to result in runoff.
- Ensure that ESC are regularly cleaned and maintained.



41

#### **Duties of ESCM (continued)**

- Mobilize crews to make immediate repairs to ESC during working and non-working hours.
- Record actions taken to clean up discharged of sediment.
- Report potential permit violations to the Agency immediately upon discovery.
- Revise the ESCP within 7 days after ESC modifications are implemented in the field & provide to Agency
- Agency submits ESCP revisions to DEQ within 30 days after making revisions.
- Prepare submittals for corrective actions for Agency review and submittal to regulatory agencies.



#### **Revise ESCP When:**

- Changes to the construction plans that impact erosion and sediment control measures.
- Changes to the stormwater control BMPs, their location, maintenance required, and any other revisions necessary to prevent and control erosion and sediment runoff;
- Other activities at the site that are no longer accurately reflected in the ESCP. This includes changes to personnel involved in ESC made in response to corrective actions triggered;
- Any change to active treatment system
- When requested by Agency or DEQ



43





#### 00280.14 - 00280.16 Materials

- 00280.14 Erosion Prevention This Section lists materials that cover soil and prevent erosion.
- 00280.15 Runoff Control This Section lists BMPs and materials to control stormwater runoff.
- 00280.16 Sediment Control This Section lists BMPS and materials that prevent untreated sediment from leaving the project site.
- Find approved products on Qualified Products List.



# **Erosion Prevention**A good place to start is...

#### 00280.41(d)

"Limit the amount of disturbed area to that which can be effectively controlled."






47


# 00280.44 – Erosion Prevention BMPs







**Vegetation – 01030.13** 

















See RD1055





55

### **Erosion Prevention –Slope Matting**



Absorbs rain splash energy, retains moisture and covers soil, provides runoff control (depending on matting type)

# Erosion Prevention (continued) 00280.14(d) – Straw Mulch

### Straw mulch

- covers soil
- absorbs rain splash
- retains moisture
- slows runoff

No control for concentrated flow





Straw mulch is good temporary cover

57

### Erosion Prevention (continued) 00280.14(d) – Hydraulically applied Type A Matting

### Hydromulch

- covers soil
- absorbs rain splash
- retains moisture
- slows runoff
- not for concentrated flow
- usually used with seeding





### **Erosion Prevention**

# Bonded Fiber Matrix (BFM) Mulch

- should be about 3/16" thickness
- inadequate coverage (00280.44(e)4)





59

# Erosion Prevention (continued) Compost Blanket, 00280.14(f) – DETAIL 6017

- use medium compost
- absorbs rain splash
- retains moisture reducing runoff
- slows runoff
- good seed bed
- introduces soil biology
- dark color captures heat which aids germination
- not for concentrated flows
- install at spec'd thickness



# **Erosion Prevention Compost Blanket**

Can stick to 1:1 slopes and it helps plant growth.

Problems obtaining compost products? Report to Program Coordinators. Compost suppliers can and will screen coarse compost meeting ODOT spec, on request, if given advanced notice.






61


### Erosion Prevention – Runoff Control 00280.15 Runoff Control BMPs (also sediment control)








**Check Dams:** Allow runoff velocity and allow sediment to fall out of suspension

















Runoff Control
Check Dams require maintenance when 1/3 full

















# Sediment Control BMPs – 00280.16(a) Construction Entrance – ANY Track Out is NonCompliance





Tire Wa

**Construction** – Standard Drawing RD1000 **Tire Wash** – Standard Drawing RD1060

75

# Sediment Control - Sediment Fence Standard Drawing RD1040 — 00280.16(c) FRONT VIEW SECTION A-A SECTION A-A SEDIMENT FENCE AND GEOTEXTILE EIRTY DETAIL - TYPE 1 ALTERNATE SEDIMENT FENCE AND GEOTEXTILE EIRTY DETAIL - TYPE 1 ALTERNATE SEDIMENT FENCE (1) in the property of the propert

### Sediment Control – Sediment Fence Section (280.46(c)), Standard Drawing RD1040







Install plumb & on-contour Embed bottom 6"

77

# Sediment Control Sediment Fence – Required embedment







### Sediment Control – Sediment Fence Robust & effective sediment control

Requires maintenance when at 1/3 capacity





79


### **Sediment Control – Sediment Fence**


Requires maintenance/ replacement if damaged by rollers.


(And, the ESC contractor saw this then seeded right over it!)














### Unusual issues require creative solutions

Sediment fence fabric in a field fabricated inlet insert





85


### Sediment Control – Sediment Barriers Fiber Rolls – 00280.15(a) & RD1030



Correct embedment, but no overlap at ends



Plumb and on contour, but no embedment



### 00280.16(h) - Sediment Trap - RD1065

Sediment Trap design must be stamped by a qualified engineer or landscape architect

- 2 year, 24 hour storm is model for sed. trap design or 3,600 Cu. Ft. per acre
- Sediment Trap outlet structure must draw from surface water.
- Sediment Trap discharge point(s) must use energy dissipater
- Where sediment trap site will become WQ facility after construction, remove top 18" of material and replace with material which can infiltrate & treat stormwater






### Sediment Control - Flocculent - 00280.16(k)



Flocculent use is active treatment & requires EMP & DEQ approval

89

# Sediment Control "Dirt Bag" Sediment Filter Bag



### **Haul Routes -**

- Make mud slurry
- Generate thick turbid runoff
- Can track offsite

### 1200-CA -

"All unpaved roads located on-site shall be graveled" (exemptions apply)





91

# **00280.41 Construction – Work Restrictions** (Required Actions)

- Delineate clearing limits and No Work Areas, including Buffer Zones with high visibility markings such as orange plastic mesh fence. Respect those No Work Areas.
- Update the ESCP and schedule for wet season to ensure appropriate controls are implemented and maintained.

**Wet Season Work:** Oct. 1 – May 31 (00280.02)

 Temporary work suspension during wet season is an appropriate BMP. (It is not a suspension of monitoring.)



### Construction – Stabilization – 00280.42

**Stabilization** – Measures to prevent erosion and keep sediments from leaving the project site. Stabilization means <u>covering soil</u> using mulch (compost, straw, rock, wood chip or hydromulch), plastic sheeting, matting or vegetation

### 00280.42 (a) Soil Exposure Limitations

 Statewide (Entire Year) – Stabilize within seven days of exposure, all areas within 100 ft. of waterways, wetlands or other sensitive areas using methods that do not rely solely upon germination to control erosion



93

# Construction – Stabilization – 00280.42 (continued)

### **1200-CA Soil Exposure Limitations** (continued)

- Stabilize soil within 14 days of suspension of work in areas of exposed soil.
- ESCM documents the beginning of work suspension in areas of exposed soil on monitoring form.
- Complete stabilization of exposed soil as soon as practicable and within 7 days of initiation of stabilization work



### **Construction – Stabilization (continued)**

### **00280.42 Soil Exposure Limitations** (continued)

- 00280.42 (b) Temporary Stabilization
  - · Every 14 days or more frequently as needed
  - 1 day <u>prior</u> to anticipated rain events
  - · When sediments leave site
  - At the end of each day during wet periods
  - · As emergency measure when rain is falling
  - When actions or weather cause dust



95

### **Construction (continued)**

### 00280.43 Area Preparation

- Prepare areas as per 01040.48(d)
- Track walk all fill slopes
  - Steeper than 1V:3H
  - Flatter than 1V:1.5H
  - Parallel to slope contours






### **Construction (continued)**

### 00280.48 Emergency Materials

- Should/will be listed in the Special Provisions
- Deploy Emergency Materials quickly without waiting to mobilize ESC subcontractors
- Replenish emergency materials to be prepared for unanticipated erosion/sedimentation conditions.





97

### **Maintenance**

### 00280.63 Sediment Removal

- Catch Basins-storage capacity <50%</li>
- Sediment Controls-filtering capacity <33%</li>
- Construction Entrances Maintain proper function of entrances – any track out is non-compliance
- Paved Areas keep them clean
  - Vacuum sweeper and dirt removal is best
  - Never intentionally wash untreated sediment be into storm sewers or drainage ways



### **Construction – Stabilization**

### 00280.42 (c) Permanent Stabilization

- Provide permanent stabilization when earthwork to establish finish grades is complete. – ... "at the earliest practicable time"
- Apply mulch or matting with seeding to provide stabilization during seed germination and establishment.
- If seed is not established, or soil not protected, provide additional BMP's that do not rely on germination to provide stabilization.



99

### Finishing and Clean-up

### 00280.70 Removal of temporary ESC devices

- No later than 30 days from acceptance of stabilization
- Permanently stabilize areas affected by removal process (within 2 days)

### 00280.71 Sediment Disposal

- Regrade removed sediment into slopes
- Dispose according to **00290.20**
- Do not flush sediments into drainage systems This requirement supports **1200-CA**, **A.4.b.**



# **00280.80 – Measurement** Multiple methods for calculation

- Lump Sum Basis (no measurement)
- Unit Basis
- Length Basis
- Area Basis
- Limitations



101

### **QUESTIONS?**





July 6, 2018

Mr. PE
ODOT Corvallis
Via DocExpress

Dear ,

Construction Co. hereby submits this correspondence to satisfy the requirements of 00280.04, for Erosion and Sediment Control Plan (ESCP).

will use the ODOT ESCP as shown on Contract Plan Sheets FB01 through FB04 without modification.

As actual conditions on the jobsite warrant, and in consultation with the Engineer, modify the ESCP and to implement additional BMP's determined to be necessary.

will update the ESCP as appropriate and keep a copy of the updated ESCP onsite.

ESCP implementation will be detailed in weekly "look ahead" schedules.


If you have any questions or need additional information, please contact me at by phone at (541)


Sincerely,


Construction Company


Project Manager

c: 3574.06 Submittal - ESCP









### **INSERT TAB**

1200-CA Permit

Permit Number: 1200-CA Effective Date: September 15, 2022 Expiration Date: September 14, 2027



## **GENERAL PERMIT** NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM

### STORMWATER DISCHARGE PERMIT

Oregon Department of Environmental Quality 700 NE Multnomah St. Suite 600, Portland, OR 97232 Telephone: (503) 229-5279 or 1-800-452-4011 (toll free in Oregon) Issued pursuant to ORS 468B.050 and The Federal Clean Water Act

### ISSUED TO:

All public agencies responsible for construction activities with stormwater discharges that are covered by this permit. The submittal of an approved application and payment of applicable fees are required.

### PERMIT AREA

This 1200-CA Stormwater General Discharge Permit authorizes discharges in Oregon excluding tribal trust and reservation lands.

### SOURCES COVERED BY THIS PERMIT

Permit coverage is required under this General Permit if the following activities under the authority or jurisdiction of a public entity have the potential to discharge to surface waters or to a conveyance system that leads to surface waters of the state in Oregon and do not have coverage under another NPDES permit:

- a) Any construction activity, materials or equipment staging and stockpiling that will disturb one or more acres of land; or
- b) Any construction activity, materials or equipment staging and stockpiling that will disturb less than one acre of land but is part of a common plan of development or sale that will ultimately disturb one or more acres of land;
- c) Any construction activity that results in the disturbance of less than one acre of land that is a necessary and required component (e.g., utilities, structure or infrastructure) of a final project that will ultimately disturb one or more acres of land; or
- d) Any construction activity that may discharge stormwater to surface waters of the state that may be a significant contributor of pollutants to waters of the state or may cause an exceedance of a water quality standard.

Water Quality Administrator

Expiration Date: September 14, 2027

Permit Number: 1200-CA Effective Date: September 15, 2022 Expiration Date: September 14, 2027

### LIMITATIONS OF COVERAGE

This permit does not authorize:

- a. In-water work or projects that may result in the discharge of fill or dredged material into waters of the U.S. and the state.
  - i. DEQ recommends permit registrants identify, apply for and resolve any state (Department of State Lands) or federal (US Army Corps of Engineers) and DEQ 401 water quality certification requirements before obtaining 1200-CA NPDES permit coverage to prevent unintended non-compliance situations with other regulatory programs. If additional regulatory requirements, such as those listed in above, are deemed necessary by other regulatory jurisdictions for the construction activity identified in the erosion and sediment control plan, the permit registrants may be required to significantly alter the project and erosion and sediment controls to accommodate other regulatory jurisdiction requirements.
- b. Stormwater discharges associated with industrial activities [as defined in 40 CFR §122.26(b)(14)] or stormwater associated with municipal separate storm sewer systems [as defined in 40 CFR §122.26(b)(8) and (b)(16)]. Such discharges are regulated through DEQ's NPDES Industrial Stormwater General Permits (1200-A/Z) or DEQ's NPDES MS4 Stormwater Permits; or another appropriate NPDES permit.
- c. Post-construction stormwater discharges that originate from the site after completion of construction activities and the site is stabilized.
- d. Stormwater discharges to underground injection control (UIC) systems.

Unless specifically authorized by this permit, by another NPDES or WPCF permit, or by Oregon Administrative Rule, any other direct or indirect discharge to waters of the state is prohibited.

### **Permitted Activities**

Until this permit expires or is modified or revoked, the permit registrant is authorized to construct, install, modify, and operate erosion and sediment control measures and storm water treatment and control facilities, and to discharge storm water to public waters in conformance with all the requirements, limitations and conditions set forth in the attached schedules as follows:

### **Table of Contents**

SCHEDULE A	1
CONTROLS AND EFFLUENT LIMITATIONS	1
1. Application requirements for obtaining permit coverage	1
2. Discharge authorization	1
3. Annual fee	1
4. Multiphase development	1
5. Construction projects that disturb five or more acres	1
6. Environmental Management Plan	2
7. Procedures for denial or revocation of coverage	2
8. Renewal application for permit coverage	2
9. Electronic system use requirement	3
10. Authorized discharges under this permit	3
10.1 Stormwater discharge including stormwater runoff, snowmelt runoff, and surface water	
10.2. Stormwater discharge from construction support activities at the construction site when:	3
11. Authorized non-stormwater discharges	3
11.1. Combined discharges	4
12. Prohibited discharges	4
13. Technology based effluent limitations/control measures	4
13.1. General stormwater control design installation, and maintenance requirements	4
13.2. Erosion prevention and sediment control and treatment requirements	6
13.3. Pollution prevention controls	
13.4. Construction dewatering requirements	16
14. Water quality based effluent limitations and associated requirements for stormwater discharges	17
14.1. General effluent limitations to meet applicable instream water quality standards	17
14.2. Water quality limited streams.	17
15. Erosion and Sediment Control Plan (ESCP)	17
15.1. Qualifications to develop ESCP	17
15.2. Design the ESCP to meet the objectives	18
15.3. ESCP for each phase of construction activity	18
15.4. ESCP contents	18
15.5. ESCP certification	22
15.6. ESCP attachments	23
15.7. On-site availability of the ESCP	
15.8. ESCP revisions	23
15.9. Submission of ESCP revision to DEQ	23

	Expiration	Date:	September	14.	2027
--	------------	-------	-----------	-----	------

15.10. Prior to commencement of construction activities.	24
15.11. Permit Registrant is responsible for ensuring that all activities on the site comply with the requirements of the permit	24
16. Corrective Actions	24
16.1. Corrective action timelines	25
16.2. Corrective action documents	25
16.3. Submit a corrective action report to DEQ	26
SCHEDULE B	. 27
MINIMUM MONITORING AND RECORDKEEPING REQIREMENTS	27
17. Visual monitoring of site and reporting requirements	27
17.1. Person(s) responsible for visually monitoring the project site	27
17.2. Frequency of visual monitoring inspections	27
17.3 Reductions in visual monitoring frequency	27
17.4. Requirements for visual monitoring	28
17.5. Visual monitoring inspection report	29
17.6. Monitoring requirements	
17.7. Inspections by DEQ	30
SCHEDULE D	. 31
SPECIAL CONDTIONS	
4. Permit Specific Definitions:	31
SCHEDULE F	. 35
NPDES GENERAL CONDITIONS	35
Section A. Standard Conditions	35
1. Duty to Comply	35
2. Penalties for Water Pollution and Permit Condition Violations	
3. Duty to Mitigate	35
4. Duty to Reapply	35
5. Permit Actions	35
6. Toxic Pollutants	36
7. Property Rights	36
8. Permit References	36
SECTION C. MONITORING AND RECORDS	36
1. Inspection and Entry	36
SECTION D. REPORTING REQUIREMENTS	36
1. Planned Changes	36
2. Anticipated Noncompliance	36

3. Transfers	37
4. Compliance Schedule	37
5. Twenty-Four Hour Reporting	37
6. Other Noncompliance	37
6. Other Noncompliance	38
8. Signatory Requirements	38
9. Falsification of Reports	38

## **SCHEDULE A**

### **CONTROLS AND EFFLUENT LIMITATIONS**

# 1. Application requirements for obtaining permit coverage

A complete and accurate application from a public entity must be submitted to DEQ at least sixty (60) days prior to any planned land disturbing construction activities. Construction activities are not authorized until DEQ issues discharge authorization.

The application must include the items below and be submitted to DEQ on Your DEQ Online:

- a. A complete and accurate DEQ approved application form; and
- b. The application fee and annual fee for the first year of permit coverage according to OAR 340-045-0075, Table 70G.

# 2. Discharge authorization

Permit coverage for permit registrants that were issued permit coverage prior to August 11, 2022, the issuance date of this permit, begins on September 15, 2022, the effective date of this permit.

Permit registrants issued permit coverage before August 11, 2022, must comply with all conditions in Section 16 by September 15, 2022, the effective date. Permit registrants issued permit coverage before August 11, 2022, must comply with the remainder of the permit conditions by April 1, 2023.

Permit coverage for new applicants begins when the registrant receives documented notice from DEQ that registration is approved. Permit registrants issued permit coverage after September 15, 2022, must comply with all permit conditions the date permit coverage is issued by DEQ.

#### 3. Annual fee

Registrants must pay the annual fee until DEQ approves termination of permit coverage.

# 4. Multiphase development

A map and description of each phase of the multiphase development for which land use approvals are approved with the intent of development or maintenance that requires the performing of construction activities must be included in the Erosion and Sediment Control Plan (ESCP). Construction activities, including stockpiling and staging, cannot commence within a phase unless that phase has a developed ESCP that has been submitted to DEQ.

# 5. Construction projects that disturb five or more acres

Permit registrants that conduct any project under this permit that includes construction activities that disturb or are likely to disturb five or more acres are subject to a 14-calendar day public review period of the Erosion and Sediment Control Plan (ESCP) that meets all permit requirements before any construction activities begin. The permit registrant will post all required and necessary project documents (i.e., site map and ESCP) for the mandatory 14-day public comment period or send to DEQ for posting.

If construction activities expand beyond five acres after construction activities are initiated, a 14-calendar day public review period will be required. During the 14-calendar day public review period, registrants are not authorized to

conduct construction activities in the area expanded beyond the boundaries of the originally submitted ESCP in accordance with 340-045-0033(6)(b). After the public comment period is over, the finalized ESCP must be submitted to DEQ.

# 6. Environmental Management Plan

The permit registrant must complete an Environmental Management Plan (EMP, see Appendix A), pay the review fee, and submit the required DEQ documents for projects when the following conditions exist or are anticipated. The EMP must be submitted to and approved by DEQ before work may commence on the project site. If these conditions are discovered after registering for permit coverage, the EMP must be approved by DEQ before work is initiated in the area of contamination. The approved EMP becomes a component of the erosion and sediment control plan. An EMP must be submitted for the following:

- a. Contaminated soils, contaminated groundwater or hazardous materials that will or have the potential to be encountered during construction activities. Provide detailed information with the Contaminated Media Management Plan (CMMP) on the nature and extent of the contamination (concentration, location, and depth) as well as pollution prevention and/or treatment BMPs proposed to control the discharge of impacted soil, groundwater or hazardous building materials debris in stormwater. In the event that undocumented contamination, underground storage tanks, or other potentially hazardous conditions are encountered that are not addressed in the Environmental Management Plan, discharges exposed to the contaminated media must cease and DEQ must be notified within 48 hours. The discharges exposed to the contaminated media may not occur until DEQ approves the CMMP.
- b. Construction dewatering for the purpose of lowering non-contaminated groundwater will be or is performed, and an Active Chemical Treatment System is to be utilized before discharge. An EMP is not required for dewatering accumulated water due to shallow excavation activities, except for when an Active Chemical Treatment System is utilized before discharge from the permitted site (See Section 13.4).
- c. An Active Chemical Treatment System (e.g., cationic treatment chemicals, electro-coagulation, flocculants, filtration, anionic polyacrylamide, polymers, hydrochloric or sulfuric acid) for sediment, pH neutralization, or other pollutant removal is planned or implemented at the project site. When "treatment chemicals" are proposed, the permit registrants must demonstrate to DEQ that appropriate controls and implementation procedures are used to ensure that the use of treatment chemicals will not lead to discharges that cause an exceedance of water quality standards or harm aquatic life.

DEQ will determine if the project can have coverage under this permit after the permit registrant has included appropriate controls and implementation procedures designed to ensure that the above activities will not lead to discharges that cause an exceedance of water quality standards. In the absence of authorization, the registrant must apply for and receive coverage under the 1200-C construction stormwater general permit or an individual permit prior to discharging from the site.

An EMP is not required on 1200-CA permit covered projects that began construction activities prior to the effective date of this permit, except for when unknown contaminants are discovered during construction activities performed after the effective date of this permit.

# 7. Procedures for denial or revocation of coverage

DEQ may refuse to authorize or revoke coverage under this general permit and require the responsible public entity to apply for an individual NPDES permit in accordance with the procedures in OAR 340-045-0033(10). If that occurs, DEQ will notify the registrant in writing that an individual permit is required.

# 8. Renewal application for permit coverage

Permit Number: 1200-CA

Effective Date: September 15, 2022 Expiration Date: September 14, 2027

If a registrant intends to continue coverage under this permit after the permit expiration date, a complete renewal application must be submitted to DEQ along with any other required documents at least 180 days prior to permit expiration to ensure uninterrupted permit coverage unless DEQ grants permission to submit an application less than 180 days in advance.

# 9. Electronic system use requirement

Permit registrants must submit all required documents and payments using DEQ's electronic reporting system, Your DEQ Online (YDO).

# 10. Authorized discharges under this permit

The following is a list of stormwater discharges that are authorized under this permit provided that all stormwater controls are designed, installed, and maintained as required by this permit:

# 10.1 Stormwater discharge including stormwater runoff, snowmelt runoff, and surface water.

These stormwater discharges also include drainage associated with construction activity described in the Sources Covered section of this permit.

# 10.2. Stormwater discharge from construction support activities at the construction site when:

- a. The support activity is directly related to the construction site covered by this NPDES permit;
- b. The support activity is not a commercial operation, nor does it serve multiple unrelated construction projects;
- c. The support activity does not operate beyond the completion of the construction activity at the last construction project it supports; and
- d. The appropriate control measures are implemented to ensure compliance with the discharge and water quality requirements of this permit.

# 11. Authorized non-stormwater discharges

The following non-stormwater discharges from construction sites are authorized if the terms and conditions of this permit are met, all necessary controls are implemented to minimize sediment transport, the discharge is not a significant source of pollutants and not contaminated and the discharge is not prohibited by local ordinance:

- a. Water and associated discharges from emergency firefighting activities;
- b. Fire hydrant flushing;
- c. Properly managed landscape irrigation;
- d. Water used to wash equipment and vehicles (excluding the engine, undercarriage, and wheels/tires) provided there is no discharge of soaps, solvents or detergents used;
- e. Water used to control dust;
- f. Potable water including uncontaminated water line flushing as approved;
- g. External building washdown, provided soaps, solvents, and detergents are not used, and external surfaces do not contain hazardous substances:

- h. Pavement wash waters, provided spills or leaks of toxic or hazardous substances have not occurred (unless all spill material has been removed) and where soaps, solvents, and detergents are not used. Directing pavement wash waters into any surface water, storm drain inlet, or stormwater conveyance is prohibited, unless the conveyance is connected to a sediment basin, sediment trap, or similarly effective control for the pollutants present. The hosing of accumulated sediments on pavement into any stormwater conveyance is prohibited;
- i. Uncontaminated air conditioning or compressor condensate;
- j. Uncontaminated, non-turbid discharges of groundwater or spring water;
- k. Foundation or footing drains where flows are not contaminated with process materials such as solvents or contaminated groundwater; and
- 1. Construction dewatering activities (including non-contaminated groundwater dewatering and well drilling discharge associated with the registered construction activity), provided that:
  - i. The water is land applied in a way that results in complete infiltration with no potential to discharge to a surface water of the state, or the use of a sanitary or combined sewer discharge is authorized with local sewer district approval; or
  - ii. Best Management Practices and a treatment system approved by DEQ (see Section 6) are used to ensure compliance with discharge and water quality requirements.

# 11.1. Combined discharges

Discharges of stormwater listed in Sections 10.1 and 10.2 combined with authorized non-stormwater discharges in Section 11 into a common conveyance system are allowed.

# 12. Prohibited discharges

The following discharges are not authorized by this permit:

- a. Visually turbid discharge or discharge of sediment (see Section 13.2.11) from the construction site to surface waters or a conveyance system that leads to waters of the state;
- b. A discharge that causes or contributes to an exceedance of any applicable water quality standard;
- c. Concrete wastewater from washing tools and vehicles after pouring, prepping or finishing concrete;
- d. Wastewater from washing and cleanout of stucco, paint, form release oils, curing compounds and other construction materials;
- e. Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance;
- f. Soaps, solvents, or detergents used in vehicle and equipment washing or external building washdown;
- g. Wheel/tire wash wastewater, unless the discharge of wheel wash or tire bath wastewater is to a separate treatment system that prevents discharge to surface water, such as closed-loop recirculation or upland land application or to the sanitary sewer with approval from the local jurisdiction;
- h. Hydro-demolition water and saw-cutting slurry; and
- i. Toxics or hazardous substances from a spill or other release.

# 13. Technology based effluent limitations/control measures

The control measures in this section are technology-based effluent limitations (TBELs).

## 13.1. General stormwater control design installation, and maintenance requirements.

Expiration Date: September 14, 2027

The permit registrant must implement erosion and sediment control measures at all times to prevent any visibly turbid discharges or sediment from leaving the project site from initial soil disturbance until project completion. Failure to implement any of the required erosion and sediment control measures or practices, or the discharge of visibly turbid water and/or sediment from the project site is prohibited. The permit registrant must ensure that the erosion and sediment control plan is revised as necessary to reflect site conditions in accordance with the requirements of this permit.

Prior to and during the discharge of stormwater and authorized non-stormwater discharges to surface waters of the state, the registrant must design, install, and maintain effective stormwater control and treatment methods required in this section to prevent the discharge of pollutants in stormwater from construction activities that may cause or contribute to a violation of water quality standards. To meet this requirement, the registrant must perform the following:

#### 13.1.1. Factors to consider when designing stormwater controls

Consider the following factors when designing stormwater controls:

- a. The expected amount, frequency, intensity, and duration of precipitation;
- b. The nature of stormwater runoff and run-on (See Schedule D.4 Permit Specific Definitions) at the site, including factors such as expected flow from impervious surfaces, slopes and site drainage features; and
- c. The soil type and range of soil particle sizes expected to be present on the site.

# 13.1.2. Design and install all stormwater controls in accordance with engineering and professional practices

Design and install all stormwater controls in accordance with appropriate, recognized and generally accepted engineering and professional practices, including applicable design specifications and manufacturer's instructions.

#### 13.1.3. Installation of stormwater controls

Permit registrant must complete the installation of stormwater controls before each phase of construction activities begin as follows:

- a. Install and implement any downgradient sediment controls (e.g., buffers, perimeter controls, discharge point controls, storm drain inlet protection) before construction activity in any portion of the site begins;
- b. Install erosion prevention measures (e.g., matting, straw mulch, compost blankets) on areas with exposed soil that will not be worked for 14 days; and
- c. Following the installation of stormwater controls for initial construction activities the registrant must adjust stormwater controls and management strategies throughout the project site to meet and match the needs of each phase of construction as the project is implemented.

#### 13.1.4. Ensure that all stormwater controls are maintained and remain effective

Permit registrant must ensure that all stormwater controls are maintained and remain effective during construction activities until project completion and are protected from activities that would reduce their effectiveness including:

a. Follow maintenance recommendations from the manufacturer and utilize appropriate recognized and generally accepted engineering and professional based on-site conditions. The

registrant must document deviations from manufacturer recommendations in the inspection report;

- Comply with any specific maintenance requirements for the stormwater controls implemented as required in this permit and in the ESCP. Regular maintenance is required and is not limited to response actions that result from inspections or identified problems;
- c. Initiate repairs and replacements of stormwater controls when maintenance issues are discovered; and
- d. Record any stormwater controls installed (where none had previously been), repaired, replaced or removed as required in Sections 16.2 and 17.5.

### 13.1.5. Maintaining erosion and sediment controls

Maintain specific erosion and sediment controls as follows:

- a. Inspect and maintain erosion control measures (e.g., reseed, apply additional mulch, address blanket malformation and soil sloughing underneath);
- b. Remove trapped sediment from sediment fence before it reaches one third of the above ground fence height;
- c. Remove sediment before it reaches one third of the above ground height of sediment barriers such as straw wattles and biobags;
- d. Clean catch basins and inserts before sediment retention capacity is reduced by 50 percent; and
- e. Remove sediments from sediment basins before design capacity is reduced by 50 percent.

# 13.2. Erosion prevention and sediment control and treatment requirements

The registrant must implement erosion prevention and sediment control and treatment methods in accordance with the following requirements to prevent the discharge of pollutants in stormwater from construction activities. Registrant must ensure that soils are stable during all rain events throughout the year.

#### 13.2.1. Activities before construction commences

Before construction activities commence, the permit registrant must identify and protect any:

- a. Riparian areas and vegetation including trees and associated root zones, and vegetation areas to be preserved;
- b. Vegetated buffer zones between the site and sensitive areas (e.g., wetlands, springs, groundwater seeps, etc.) and other areas required to be preserved, especially in perimeter areas; and
- c. Existing and post-construction stormwater facilities constructed during 1200-CA permit coverage that are designed and engineered to infiltrate or filter stormwater. In addition to physical protection, stormwater runoff discharge from areas where construction activities are performed may not be conveyed to existing or post-construction facilities during construction. The following exceptions are allowed:
  - i. Existing post-construction stormwater facilities may receive stormwater runoff from construction activities performed on site if the ESCP states that upon project completion and final stabilization, the top 18" of soil is excavated from the entire surface of the facility and replaced with suitable growth media capable of infiltrating the runoff

Expiration Date: September 14, 2027

volume from the drainage area of a 2-year 24-hour storm event or satisfying the hydraulic conductivity criteria specified in the stormwater management requirements of the local regulatory agency.

ii. Post-construction stormwater facilities constructed during 1200-CA permit coverage may receive stormwater runoff from construction activities on site if upon project completion and final stabilization, accumulated sediment and temporary control measures, such as rip rap, velocity dissipating pads or impermeable liners are removed before the facility is constructed to design specifications.

### 13.2.2. Sequence clearing, grading, and other land disturbing activities

Permit registrant must sequence clearing, grading and other land disturbing actives to the maximum extent practicable to prevent exposed inactive areas from causing erosion as per Section 13.2.20.

#### 13.2.3. Prevent bypass and ponding

Create smooth surfaces between the soil surface and erosion and sediment controls, when possible, to prevent stormwater from bypassing erosion and sediment controls or ponding.

# 13.2.4. Establish and maintain natural buffer zones and/or equivalent erosion and sediment controls.

When a surface water of the state is located within 50 feet of the projected site's land disturbance:

- a. The permit registrant must comply with local natural buffer zone requirements before proposing the following compliance alternatives. For any discharges to surface waters of the state located within 50 feet of the site's land disturbances, the permit registrant must comply with one of the following alternatives:
  - i. Maintain a 50-foot undisturbed natural buffer zone (See Section 13.2.4.b to determine natural buffer zone encroachment authorization on 401 Water Quality Certification projects); or
  - ii. Maintain an undisturbed natural buffer that is less than 50 feet and is supplemented by erosion and sediment controls that achieve, in combination, the sediment load reduction equivalent to a 50-foot undisturbed natural buffer (See Appendix B); or
  - iii. If infeasible to provide and maintain an undisturbed natural buffer zone of any size, implement erosion and sediment controls to achieve the sediment load reduction equivalent to a 50-foot undisturbed natural buffer zone.
- b. If DEQ determines that the project requires a 401 Water Quality Certification, construction activities, including stockpiling and staging of materials, are authorized to encroach into the existing 50-foot natural buffer zone of any water of the state as conditioned in the 401 Water Quality Certification. Projects with 1200-CA permit authorization and a 401 Water Quality Certification are not required to comply with the natural buffer zone requirements of Appendix B.
- c. If a registrant's project has the potential to discharge to a waterbody that is listed as impaired and requiring a Total Daily Maximum Load (TMDL) for turbidity or sedimentation on the most recently approved Oregon 303(d) list (found on the "Water Quality Assessment" page of DEQ's website), or has an established TMDL for turbidity or sedimentation, the permit registrant must maintain established vegetated buffers sized at 50 feet (horizontally) plus an

additional 25 feet (horizontally) per five degrees of slope or propose control measures of equal effectiveness to DEQ for approval.

d. Sediment and erosion control measures installed for any natural buffer zone requirement must be maintained and disposed of appropriately before project completion.

See Appendix B for natural buffer zone guidance, additional conditions applicable to each compliance alternative, and for exceptions to the compliance alternatives.

For permit registrants that began construction activities prior to the effective date of this permit, the approved natural buffer zone width and approved erosion and sediment controls are deemed appropriate.

### 13.2.5. Utilize existing vegetation as control and stabilization measures as follows:

- a. When possible, preserve existing vegetation;
- b. Direct stormwater to vegetated areas to maximize stormwater infiltration and filtering to reduce pollutant discharges where feasible;
- c. Re-vegetate open areas as soon as the site is no longer active; and
- d. Identify the composition of seed mix (percentage of annuals, perennials and clover) and other plantings used to establish temporary cover in the ESCP.

# 13.2.6. Install sediment controls along all perimeter areas of the site that may potentially discharge stormwater runoff from disturbed areas identified in the ESCP

For areas at "linear construction sites" (See Schedule D.4 Permit Specific Definitions) where perimeter controls are infeasible (e.g., due to a limited or restricted right-of-way), implement other practices to prevent pollutant discharges from perimeter areas of the site.

#### 13.2.7. Prevent sediment track-out

To prevent sediment track-out onto public or private roads do the following:

- a. Establish graveled or paved exits and parking areas prior to any land disturbance;
- b. Restrict vehicle use to properly designated entry and exit points. Use appropriate stabilization techniques at all points that exit onto paved roads (e.g., aggregate stone with an underlying geotextile or non-woven filter fabric and turf mats);
  - i. Exception: Stabilization is not required for exit points at linear utility construction sites that are used only episodically and for very short durations over the life of the project, provided other exit point controls are implemented to prevent sediment track-out.
- c. Implement additional track-out controls as necessary to ensure that sediment removal occurs prior to vehicle exit (e.g., wheel and tire washing, rumble strips and rattle plates);
- d. Gravel all unpaved roads located onsite unless temporary or permanent stabilization measures are not required (see Section 13.2.20);
- e. Cover all sediment loads leaving the site;
- f. When trucking saturated soils from the site, use water-tight trucks or drain loads on site;
- g. Where sediment has been tracked-out from the site onto paved roads, sidewalks, or other paved areas outside of the site, remove the sediment by the end of the same business day that the track-out occurs or by the end of the next business day if track-out occurs on a non-

Expiration Date: September 14, 2027

business day. Track-out must be removed by sweeping, shoveling, or vacuuming these surfaces or by using other similarly effective means of sediment removal; and

h. Hosing or sweeping tracked-out sediment into any stormwater conveyance, storm drain inlet or water of the state is prohibited.

# 13.2.8. Manage stockpiles or land clearing debris piles composed, in whole or in part, of sediment and/or soil as follows:

- a. Locate the piles outside of any natural buffers established under Section 13.2.1 and away from any stormwater conveyances, drain inlets and areas where stormwater flow is concentrated;
- b. Install a sediment barrier (e.g., berms, dikes, fiber rolls, silt fences, sandbags, gravel bags or straw bale) along all downgradient perimeter areas;
- c. Soil stockpiles must be stabilized or covered at the end of each workday and before weekends, holidays or extended breaks of construction activities if a storm event is forecast that may result in any discharge from the project site or wind speeds (typically 10 mph or greater) capable of soil erosion that may result in fugitive dust;
- d. Provide cover (e.g., tarps, blown straw or hydroseed) or appropriate temporary stabilization consistent with Section 13.2.20) for any piles not in use; and
- e. Hosing down or sweeping soil or sediment accumulated on pavement or other impervious surfaces into any stormwater conveyance, storm drain inlet or water of the state is prohibited.

#### 13.2.9. Prevent wind erosion and control dust

Prevent wind-blown soil and dust from areas with exposed soil through the appropriate application of water or other dust suppression techniques to control the generation of pollutants that could be discharged in stormwater from the site. Federal regulation 40 CFR Part 279 prohibits the use of used oil as a dust suppressant.

# 13.2.10. Steep slope (See Schedule D.4 Permit Specific Definitions) disturbances in areas where construction activities are not occurring or projected are prohibited

# 13.2.11. Prevent the discharge of sediment to surface waters or conveyance systems leading to surface waters of the state

The following conditions indicate that sediment has left or is likely to leave the site and are prohibited:

- a. Required stabilization has not been initiated or completed.
- b. Earth slides or mud flows.
- c. Concentrated flows of stormwater such as rills, rivulets, gullies or channels that cause erosion when such flows are not filtered, settled or otherwise treated to remove sediment.
- d. Sediment laden or turbid flows of stormwater that are not filtered or settled to remove sediment and turbidity.
- e. Deposits of sediment at the construction site in areas that drain to unprotected stormwater inlets or to catch basins that discharge to surface waters. Inlets and catch basins with failing sediment controls due to a lack of maintenance or inadequate design are considered unprotected.

f. Sediment basins or traps without adequate wet or dry storage volume or sediment basins or traps that allow discharge of stormwater from below the surface of the wet storage portion of the basin or trap.

- g. Deposits of sediment from the project site on any property (including public and private streets) outside of the construction activity covered by this general permit.
- h. Deposits of sediment from the project site at discharge locations or the banks of any waters flowing within or immediately adjacent to the site.

### 13.2.12. Prevent soil compaction

In areas of the site where final vegetative stabilization will occur or where post-construction infiltration practices will be installed (See Section 13.2.1.c) the registrant must:

- a. Preserve suitable native topsoil by stockpiling for reuse or transferring to other locations, unless infeasible;
- b. Restrict vehicle and equipment use in designated areas (e.g., haul roads, staging and stockpiling or laydown) to their stated purpose to avoid soil compaction; and
- c. Before seeding or planting areas of exposed soil that have been compacted, use techniques that rehabilitate and condition the soils as necessary to support vegetative growth.

#### 13.2.13. Protect storm drain inlets

The following storm drain inlet protection measures are required:

- a. Install inlet protection measures that remove sediment from discharges prior to entry into any storm drain inlet that conveys stormwater flow, provided the registrant has authority to access the storm drain inlet; and
- b. Clean, or remove and replace, the protection measures as sediment accumulates, the filter becomes clogged and/or performance is compromised. Where there is evidence of sediment accumulation adjacent to the inlet protection measure, remove the deposited sediment by the end of the same business day in which it is found or by the end of the following business day if removal by the same business day is not feasible.

# 13.2.14. For projects involving concrete, establish concrete truck and other concrete equipment washout area before beginning concrete work

When performing construction activities involving concrete, the following control measures are required:

- a. Wash concrete trucks and equipment in an appropriately protected area or in designated concrete washout areas only;
- b. Direct all concrete wash water into an impermeable-lined pit or leak-proof container designed so that overflows will not occur due to inadequate sizing or precipitation;
- c. Locate activities away from waters of the state and stormwater inlets or conveyances so that stormwater coming into contact with areas where these activities are performed cannot reach waters of the state;
- d. Concrete wash may not adversely affect groundwater;
- e. Concrete washout and waste concrete management areas must be maintained and functional;

Permit Number: 1200-CA

Effective Date: September 15, 2022 Expiration Date: September 14, 2027

f. Handle (e.g., through disposal, reuse or recycle) wash water as waste. Do not dispose of concrete wash water or wash out concrete trucks onto the ground, or into storm drains, open ditches, streets or streams;

- g. Do not dump excess concrete on site, except in designated concrete washout areas;
- h. Handle (e.g., through disposal, reuse or recycle) hardened concrete waste consistent with handling of other construction wastes; and
- i. Concrete spillage or concrete discharge to surface waters of the state is prohibited.

# 13.2.15. Establish material and waste storage areas, and other non-stormwater controls before construction activities commence

#### 13.2.16. Control stormwater discharges

Control all stormwater discharges, including both peak flowrates and total stormwater volume, to prevent channel and streambank erosion and scour in the immediate vicinity of discharge points as follows:

- a. Use erosion controls and velocity dissipation devices within and along the length of any stormwater conveyance channel and at any outlet to slow down runoff to prevent erosion; and
- b. Protect stream banks from concentrated flows by constructing runoff control measures (e.g., check dams, outlet protection (riprap), pipe slope drains, swales/dikes, surface roughening).

## 13.2.17. Engineer sediment basin or similar impoundment installed

If an engineered sediment basin or similar impoundment is installed the following must take place:

- a. The design must be prepared and stamped by an Oregon Registered Professional Engineer or an Oregon Registered Landscape Architect per Section 15.1.b;
- b. The basin or impoundment must be situated outside of any water of the state, any natural water quality buffers, and any post-construction stormwater facility designed and engineered to infiltrate established under Section 13.2.1;
- c. The basin or impoundment must be designed to avoid collecting water from wetlands;
- d. The basin or impoundment must be designed to provide storage for either of the following:
  - i. Find the site's estimated 2-year, 24-hour precipitation. The 2-year, 24-hour precipitation can be found using the Precipitation Frequency Data Server (PFDS) developed by the National Oceanic and Atmospheric Administration's (NOAA) National Weather Service (NWS) or the Oregon Department of Transportation (ODOT) Precipitation Data Viewer;
  - ii. 3,600 cubic feet per acre drained; or
  - iii. A site-specific alternative capable of ensuring that water quality violations do not occur through a combination of storage (e.g., Baker tanks), retention, infiltration or other means of stormwater runoff control;
- e. The design must utilize outlet structures that withdraw water from the surface of the sediment basin or similar impoundment, unless infeasible;
- f. The design must use erosion controls and velocity dissipation devices to prevent erosion at inlets and outlets; and

g. Follow maintenance requirements per Sections 13.1.4 and 13.1.5.

The approved sediment basin is deemed appropriate on 1200-CA permit covered projects that began construction activities prior to the effective date of this permit.

# 13.2.18. Engineered sediment basin or similar impoundment must be installed when engineered soils used on site

An engineered sediment basin or similar impoundment must be installed on sites with engineered soils as follows:

- a. For construction activity involving the use of engineered soils (soil amendments including, but not limited to Portland cement-treated base [CTB], cement kiln dust [CKD], or fly ash), the registrant must install an engineered sediment basin or similar impoundment in accordance with Section 13.2.17 (e.g., trap, pond) to treat high pH runoff (i.e., above 8.5 standard units) before discharge. The registrant is required to determine the acceptable pH water quality criteria range of site discharge based on criteria of the receiving waterbody according to OAR 340-041-0021. If necessary, the registrant must adjust or neutralize the high pH water until it is in the range of pH Standard Units (SU) using an appropriate treatment BMP such as carbon dioxide (CO2) sparging or dry ice.
- b. The permittee must obtain written approval from DEQ or Agent before using any form of chemical treatment other than CO2 sparging or dry ice (see Section 6). See Section 17.6.1 for pH monitoring requirements.

## 13.2.19. The registrant must maintain site as follows:

- a. Clean up sediment that leaves the site and place sediment back on the site and stabilize or dispose of sediment properly within 24 hours. In addition, the source(s) of the sediment must be controlled to prevent continued or additional discharge within 24 hours of being identified, and a corrective action report submitted to DEQ per Section 16.3. Until the sediment or turbidity are no longer visually detectable, immediate corrective actions or the implementation of additional and appropriate BMPs is required to ensure the registrant is not causing or contributing to a violation of water quality standards. Any instream cleanup of sediment may require authorization from the Oregon Department of State Lands; and
- b. Do not intentionally wash sediment into storm sewers or drainage ways. Methods such as vacuuming, dry mechanical sweeping, or manual sweeping must be used to cleanup released sediments.

# 13.2.20. The registrant must stabilize exposed portions of the site as follows:

- a. Implement and maintain the stabilization measures (e.g., seeding protected by erosion controls until vegetation is established, sodding, mulching, erosion control blankets, hydromulch, gravel) that prevent erosion from exposed portions of the site;
- b. Document the day that construction activities cease in an area and the location on site in the visual monitoring report (see Section 17.5.e);
- c. Initiate the installation of temporary stabilization measures (e.g., blown straw and a tackifier, loose straw, compost mulch, temporary vegetative cover, crushed rock or gravel base), final vegetation cover or permanent stabilization measures immediately whenever any land

Expiration Date: September 14, 2027

disturbing activities have permanently ceased or will be temporarily inactive on any portion of the site for 14 or more calendar days; and

d. Complete the installation of stabilization measures as soon as practicable, but no later than seven calendar days after stabilization has been initiated.

# 13.2.21. Final Stabilization Criteria (for any areas not covered by permanent structures). To achieve project completion, registrants must:

- Establish uniform (i.e., evenly distributed, without large bare areas) perennial vegetation that provides 70 percent or more cover on all exposed areas. Limited allowable exceptions include:
  - i. For sites where it is difficult to establish 70 percent coverage (e.g., arid, semiarid or drought-stricken areas), the registrant must cover exposed soil between planted or seeded areas with bio or photo degradable controls designed to prevent erosion without active maintenance or propose a site-specific plan to DEQ for approval.
  - ii. Disturbed areas on farm use land as defined in ORS 308A.056 (e.g., pipelines across crop or range land, or staging areas for highway construction) that are restored to their preconstruction farm use are not subject to final vegetative stabilization criteria.
  - iii. Stabilization may not be required if the intended function of a specific area of the site necessitates that it remains disturbed, and only the minimum area needed remains disturbed (e.g., dirt access roads, utility pole pads, areas being used for storage of vehicles, equipment, materials);
- b. Implement temporary bio or photo-degradable non-vegetative stabilization measures (e.g., mulch or rolled erosion control products) to provide effective cover while vegetation is being established to prevent erosion of the seeded or planted area;
- c. Ensure that final vegetative cover or permanent stabilization is established before temporary sediment controls are removed unless doing so conflicts with local requirements;
- d. Ensure there is no discharge from the site of construction-related sediment or turbidity to surface waters:
- e. Remove and properly dispose of all construction materials, waste and waste handling devices, and remove all equipment and vehicles that were used during construction, unless intended for long-term use;
- f. Remove all temporary stormwater controls that were installed and maintained during construction, except those that are intended for long-term use;
- g. Remove sediment from permanent (post-construction) structural stormwater facilities by over excavating and replacing with growth media before vegetating; and
- h. Remove all potential pollutants, including any sediment being retained by temporary erosion and sediment controls, and discontinued pollutant-generating activities associated with construction, unless needed for long-term use.

#### 13.3. Pollution prevention controls

The registrant must implement pollution prevention controls in accordance with the following requirements to prevent the discharge of pollutants to stormwater and to prevent the discharge of pollutants from spilled or leaked materials from construction activities, such as building materials, building products, construction

Permit Number: 1200-CA

Effective Date: September 15, 2022 Expiration Date: September 14, 2027

wastes, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste, fuels, lubricants and other material present.

The registrant must provide written spill prevention and response procedures, employee training on spill prevention and proper disposal procedures, spill kits available on site, regularly maintained vehicles and machinery, material delivery and storage controls, signage and covered storage areas for waste and supplies.

#### 13.3.1. General conditions

Provide an effective means of eliminating the discharge of any waste from any activities performed on site by implementing the following:

- a. Locate activities away from waters of the state and stormwater inlets or conveyances so that stormwater coming into contact with areas where waste generating activities are performed cannot reach waters of the state;
- b. Ensure adequate supplies are available at all times to handle spills, leaks and disposal of liquids, and provide secondary containment (e.g., spill berms, decks, spill containment pallets);
- c. Have a spill kit available on site and ensure personnel are available to respond expeditiously in the event of a leak or spill;
- d. Clean up spills or contaminated surfaces immediately using dry clean up measures (do not clean contaminated surfaces by hosing the area down) and eliminate the source of the spill to prevent a discharge or a continuation of an ongoing discharge; and
- e. Store materials in a covered area (e.g., plastic sheeting, temporary roofs), or in secondary containment to prevent the exposure of these containers to precipitation or stormwater runoff, or a similarly effective means designed to prevent the discharge of pollutants from these areas.

#### 13.3.2. Equipment and vehicle fueling and maintenance

- a. Use drip pans and absorbents under or around vehicles;
- b. Dispose of or recycle oil and oily wastes in accordance with other federal, state, tribal, or local requirements;
- c. To the extent possible perform equipment fueling and maintenance off-site at authorized facilities; and
- d. If allowed by the local fire department, fit fuel dispensing nozzles with "hold-open latches" with an automatic shutoff.

### 13.3.3. Equipment and vehicle washing

- a. Ensure there is no discharge of soaps, solvents, or detergents in equipment and vehicle wash water; and
- b. Prevent the discharge of turbid vehicle wash water to waters of the state or conveyances that lead to waters of the state.

### 13.3.4. Building materials and building products

Expiration Date: September 14, 2027

Minimize material exposure in cases where the exposure to precipitation or to stormwater will result in a discharge of pollutants (e.g., elevate materials from soil to prevent leaching of pollutants).

#### 13.3.5. Pesticides, herbicides, insecticides, and fertilizer

Comply with all application and disposal requirements included on the registered pesticide, herbicide, insecticide, and fertilizer label (see also Section 13.3.6). When applying fertilizers, registrants must:

- a. Apply at a rate and in amounts consistent with manufacturer's specifications;
- b. Apply at the appropriate time of year for the location, and preferably timed to coincide as closely as possible to the period of maximum vegetation uptake and growth;
- c. Avoid applying before heavy rains that could cause excess nutrients to be discharged;
- d. Never apply to frozen ground;
- e. Never apply to stormwater conveyance channels; and
- f. Follow all other federal, state and local requirements regarding fertilizer application.

#### 13.3.6. Hazardous or toxic waste

- a. Separate hazardous or toxic waste from construction and domestic waste;
- b. Store waste in sealed containers, which are constructed of suitable materials to prevent leakage and corrosion, and which are clearly labeled with their contents in accordance with all applicable federal, state, tribal or local requirements;
- c. Store all outside containers within appropriately sized secondary containment (e.g., spill berms, decks, spill containment pallets) to prevent spills from being discharged or provide a similarly effective means designed to prevent the discharge of pollutants from these areas (e.g., storing chemicals in a covered area, having a spill kit available on site); and
- d. Dispose of hazardous or toxic waste in accordance with the manufacturer's recommended method of disposal and in compliance with federal, state, tribal, and local requirements.

#### 13.3.7. Construction and domestic wastes

- a. Provide waste containers (e.g., dumpster, trash receptacle) that provide ground separation and are of sufficient size and number to contain construction and domestic wastes;
- b. Keep waste container lids closed when not in use and close lids at the end of the business day for those containers that are actively used throughout the day. For waste containers that do not have lids, provide either (1) cover (e.g., a tarp, plastic sheeting, temporary roof) to prevent exposure of wastes to precipitation, or (2) a similarly effective means designed to prevent the discharge of pollutants (e.g., secondary containment);
- c. Clean up and dispose of waste in designated waste containers; and
- d. Clean up immediately if containers overflow.

### 13.3.8. Sanitary waste

Position portable toilets so that they are secure and will not be tipped or knocked over and located away from waters of the state and stormwater inlets or conveyances.

## 13.3.9. Washing applicators and containers

When construction activities involve washing applicators and containers used for stucco, paint, concrete, form release oils, curing compounds, or other materials, the following measures are required:

- a. No discharge of these liquid wastes is allowed in storm sewers or waters of the state;
- b. Dispose of liquid wastes in accordance with applicable requirements;
- c. Remove and dispose of hardened concrete waste consistent with the handling of other construction wastes in Section 13.3.7; and
- d. Locate any washout or cleanout activities as far away as possible from waters of the state and stormwater inlets or conveyances, and, to the extent feasible, designate areas to be used for these activities with signs and in the ESCP and conduct such activities only in these areas.

## 13.3.10. Emergency spill notification requirements

Discharges of toxic or hazardous substances from a spill or other release are prohibited, consistent with Section 12. Where a leak, spill, or other release containing a hazardous substance or oil occurs during a 24-hour period, the registrant must notify the Oregon Emergency Response System at (800) 452-0311 as soon as the registrant has knowledge of the release. Contact information must be in locations that are readily accessible and available to all employees.

## 13.4. Construction dewatering requirements

This section pertains to accumulated water from precipitation and uncontaminated groundwater seepage due to shallow excavation activities, not for the lowering of contaminated groundwater (see Section 6). Registrant must comply with the following requirements to prevent the discharge of pollutants in groundwater or accumulated stormwater that is removed from excavations, trenches, foundations, vaults, or other similar points of accumulation, in accordance with Section 12-Prohibited Discharges:

- a. To the extent feasible, use vegetated, upland areas of the site to infiltrate dewatering water before discharge. The registrant is prohibited from using waters of the state as part of the treatment area;
- b. Implement the appropriate control measures for dewatering discharges to prevent the discharge of pollutants;
- c. Do not discharge visible floating solids or foam;
- d. Use an oil-water separator or suitable filtration device (such as a cartridge filter) that is designed to remove oil, grease or other products if dewatering water is found to contain these materials;
- e. At all points where dewatering water is discharged, comply with the velocity dissipation requirements of Section 13.2.16;
- f. With backwash water, either haul it away for disposal or return it to the beginning of the treatment process;
- g. Replace and clean the filter media used in dewatering devices when the pressure differential equals or exceeds the manufacturer's specifications;
- h. If there is no alternative option, the use of a sanitary or combined sewer discharge is authorized with local sewer district approval; and
- i. Active chemical treatment systems for turbidity or any other pollutants must be designed and stamped by an Oregon Registered Professional Engineer and be approved by DEQ.

# 14. Water quality based effluent limitations and associated requirements for stormwater discharges

Discharges must be controlled to meet all applicable water quality standards. In addition, DEQ expects compliance with the permit conditions is compliance with applicable water quality standards. As soon as the registrant becomes aware or DEQ determines that discharges do not meet applicable water quality standards, corrective actions must be undertaken as required in Section 16.1.

### 14.1. General effluent limitations to meet applicable instream water quality standards

Discharges must be controlled and may not cause or contribute to an exceedance of the applicable water quality standards as established in OAR 340-041; specifically, OAR 340-041-0036: Turbidity (Nephelometric Turbidity Units, NTU); No more than a 10% (ten percent) cumulative increase in natural stream turbidities may be allowed, as measured relative to a control point immediately upstream of the turbidity causing activity.

## 14.2. Water quality limited streams

DEQ may establish additional controls on construction activities that discharge stormwater runoff to water quality limited streams if Total Maximum Daily Loads are established and construction activities are determined to be a significant contributor to these loads. DEQ may also require application for individual permit or develop a watershed-based general permit for the activity.

# 15. Erosion and Sediment Control Plan (ESCP)

Before any project under this permit begins, the ESCP must be submitted to DEQ. The registrant must implement the ESCP at all times, from initial soil disturbance until project completion. Failure to implement any of the control measures or practices described in the ESCP is a permit violation. The ESCP must be kept up to date throughout the term of coverage under this permit. The registrant must ensure that an ESCP is revised as necessary to reflect site conditions and submit revisions to DEQ in accordance with the requirements of this permit.

Permit registrants of projects covered under the 1200-CA permit prior to the effective date of this permit must revise and update the ESCP content and site map to ensure that the ESCP is compliant with the requirements of this permit and must submit the revised ESCP to DEQ in YDO by April 1, 2023.

# 15.1. Qualifications to develop ESCP

- a. For construction activities disturbing twenty or more acres, the ESCP must be developed and stamped by a professional with one of the following credentials, and their name and credentials must be included in the ESCP as a preparer:
  - i. Certified Professional in Erosion and Sediment Control.
  - ii. Certified Professional in Stormwater Quality.
  - iii. Oregon Registered Professional Engineer.
  - iv. Oregon Registered Landscape Architect.
  - v. Oregon Certified Engineering Geologist.
- b. If engineered facilities such as sedimentation basins or diversion structures for erosion and sediment control are required, these portions of the ESCP must be designed and stamped by an Oregon Registered Professional Engineer or an Oregon Registered Landscape Architect (see Section 13.2.17).

## 15.2. Design the ESCP to meet the objectives

The ESCP must be designed to meet the following objectives:

- a. To implement best management practices (BMPs) in accordance with appropriate, recognized and generally accepted engineering practices to prevent erosion and sedimentation, and to identify, reduce, eliminate or prevent contamination of stormwater and water pollution from construction activities;
- b. To prevent violations of water quality standards, erosion and sediment transport from the project site and meet 1200-CA permit technology-based effluent limitations and treatment requirements; and
- c. To control peak volumetric flow rates and velocities of stormwater discharges to prevent scouring by means such as diverting, collecting, conveying and/or controlling flows.

## 15.3. ESCP for each phase of construction activity

Sediment and erosion controls must be clearly depicted for each of the following four distinct phases of construction activities within the ESCP. In addition, a site description and site map must be developed for the following construction phases:

- a. Demolition, clearing, grading, excavating and land development;
- b. Street and utilities;
- c. Vertical construction; and
- d. Final landscaping and site stabilization.

Linear construction projects must have an ESCP that clearly defines and addresses each distinct phase of construction. An ESCP including the site description and site map for each construction phase must be submitted to DEQ before construction activities may be initiated on the subsequent construction phase.

#### 15.4. ESCP contents

At a minimum the ESCP must include the applicable information specified below:

- a. Clearly identify the ESCP preparer and their credentials or stamp within the ESCP per Section 15.1;
- b. Name and location of the site;
- c. All contractors to perform work on site as follows:
  - i. Once known, include a list of all contractors that will engage in construction activities on site, and the areas of the site where the contractor(s) will engage in construction activities. Revise the list as appropriate until project completion.
  - ii. Include a list of all personnel (by name and position) that are responsible for the design, installation and maintenance of stormwater control measures (e.g., ESCP developer, BMP installer (see Section 15.10), as well as their individual responsibilities.
  - iii. Personnel conducting visual monitoring must be identified in the ESCP. Provide the following for all personnel conducting visual monitoring of the project site:
    - 1. Name and title
    - 2. Contact information
    - 3. A description of certification per Section 17.1, along with any certification numbers and expiration date;
- d. Environmental Management Plan per Section 6 if applicable;

Expiration Date: September 14, 2027

- e. Site description must include the following:
  - i. A description of the construction activities, including structures that are planned for demolition.
  - ii. The size of the property (in acres and length in miles if a linear construction site).
  - iii. A statement that clearly identifies the 303 (d) category 4 and 5 impairments status of each receiving water body (when the discharge enters an impaired watershed unit the listing will only be applied if there is a hydrologic connection between the receiving water and assessment water body causing the impairment);
  - iv. Any waterbody to be impacted by the construction activities and reference in 401 water quality certifications, USACE permit, DSL permit, and/or any other applicable agency authorization;
  - v. The total area expected to be disturbed by the construction activities (to the nearest quarter acre or quarter mile if a linear construction site);
  - vi. A description of any on-site and off-site construction support activity areas covered by this permit (see Section 10.2) such as staging areas;
  - vii. The maximum area expected to be disturbed at any one time, including on-site and offsite construction support activity areas;
  - viii. A description and projected schedule for the following:
    - 1. Start dates of construction activities in each portion of the site, site preparation (i.e., excavating, cutting and filling), final grading, and creation of soil vegetation stockpiles requiring stabilization.
    - 2. Temporary or permanent stop dates of construction activities in each portion of the site.
    - 3. Dates of temporary or final stabilization of exposed area for each portion of site.
    - 4. Dates of removal of temporary stormwater controls and construction equipment or vehicles, and the final end date of construction related pollutant generating activities;
    - ix. Type of fill material to be used, and of soils prior to disturbance;
    - x. Composition of seed mix and other planting used to establish temporary cover;
    - xi. A statement indicating engineered soil will be used per Section 17.6, and pH monitoring is required of sedimentation basins;
  - xii. Identify all authorized non-stormwater discharges in section 11 that will or may occur;
  - xiii. A list and description of all pollutant-generating activities on the site. For each pollutant generating activity include an inventory of pollutants or pollutant constituents (e.g., sediment, fertilizers, pesticides, paints, caulks, sealants, fluorescent light ballasts, contaminated substrates, solvents, fuels, associated with that activity, which could be discharged in stormwater from the construction site. The registrant must consider where potential spills and leaks could occur that contribute pollutants to stormwater discharges, and nay known hazardous or toxic substances, such as PCBs and asbestos, that will be disturbed, removed, or used on site during construction;
  - xiv. Description of stormwater controls. For each of the Section 13.2 Erosion Prevention and Sediment Control and Treatment Requirements, Section 13.3 Pollution Prevention Controls, and Section 13.4 Construction Dewatering Requirements, as applicable to the site, registrant must include the following in detail design sheet of the ESCP:
    - 1. A description of the specific controls(s) to be implemented to comply with the requirements of this permit.

- 2. Any applicable stormwater control design specifications (including references to any manufacturer specifications and/or erosion and sediment control manuals/ordinances relied upon).
- 3. Routine stormwater control maintenance specifications.
- 4. Proposed timetable indicating when each sediment and control BMP is to be installed/implemented and duration that it is to remain in place;
- xv. Natural buffer zone and/or equivalent sediment controls (see Section 13.2.4, and Appendix B). The registrant must include the following in the narrative site description:
  - 1. The compliance alternative to be implemented.
  - 2. If complying with alternative 1, the width of natural buffer retained.
  - 3. If complying with alternative 2 or 3, the erosion and sediment control(s) the registrant will use to achieve an equivalent sediment reduction, and any information the registrant relied upon to demonstrate the equivalency.
  - 4. If complying with alternative 3, a description of why it is infeasible for the registrant to provide and maintain an undisturbed natural buffer of any size.
  - 5. For "linear construction sites" where it is infeasible to implement compliance alternative 1, 2, or 3, a rationale for this determination, and a description of any buffer width retained and/or supplemental erosion and sediment controls installed.
  - 6. A description of any disturbances that are exempt under Section 13.2.1 that occur within 50 feet of a water of the state.
  - 7. A description of the vegetated buffers, sized at 50 feet (horizontally) plus an additional 25 feet (horizontally) per five degrees of slope or DEQ approved control measures of equal effectiveness for any waterbody that is listed as impaired and requiring a TMDL for turbidity or sedimentation on the most recently approved Oregon 303(d) list, or has an established TMDL for turbidity or sedimentation;
- xvi. Perimeter controls for a "linear construction site" (see Section 13.2.6). For areas where perimeter controls are not feasible, include documentation to support this determination and a description of the other practices that will be implemented to prevent discharges of pollutants in stormwater associated with construction activities;
  - 1. Note: Routine maintenance specifications for perimeter controls documented in the ESCP must include Sections 13.1.5.a, and 13.2.6 requirement that sediment be removed before it has accumulated to one-third of the above-ground height of any perimeter control.
- xvii. Sediment track-out controls (see Section 13.2.7). Document the specific stabilization techniques and/or controls that will be implemented to remove sediment prior to vehicle exit;
- xviii. Sediment basins (see Section 13.2.17). The registrant must include the design storm method and calculations, and other design details in the ESCP. In circumstances where it is infeasible to utilize outlet structures that withdraw water from the surface of the sediment basin, include documentation to support this determination, including the specific conditions or time periods when this exception will apply;
- xix. Treatment chemicals (see Section 6). The registrant must include the specific controls and implementation procedures designed to ensure that the use of cationic treatment chemicals will not lead to an exceedance of water quality standards;
- xx. Stabilization measures (see Sections 13.2.20 and 13.2.21). The registrant must include the specific vegetative and/or non-vegetative practices that will be used;

Expiration Date: September 14, 2027

xxi. Spill Prevention Procedures (see Section 13.3.10). The following must be included:

- 1. Procedures for expeditiously stopping, containing, and cleaning up spills, leaks, and other releases.
- 2. The ESCP may also reference the existence of oil Spill Prevention Control and Countermeasure (SPCC) plans developed for the construction activity (see Section 13.3.2.a), provided that the registrant keeps a copy of the SPCC on site or electronically available.
- 3. Waste management procedures (see Sections 13.3.1 and 13.3.4).
- 4. The location of fertilizers applied on site (see Section 13.3.5);
- xxii. Staff Training. Include documentation that the required personnel are trained in accordance with section 17.1; and
- xxiii. Planned business days and hours for the project known at the time.
- f. Site Map. Include a legible map, or series of maps, showing the following features of the site if applicable:
  - i. Roads and features for DEQ to locate and access the site;
  - ii. Boundaries of the property;
  - iii. Depict the drainage patterns of stormwater and authorized non-stormwater before and after major grading activities;
  - iv. Locations where land disturbing activities will occur including:
    - 1. Locations where land disturbing activities will occur (note any phasing), including any demolition activities
    - 2. Approximate slopes before and after major grading activities (pre- and post-elevation contours).
    - 3. For steep slopes (see Schedule D.4 Permit Specific Definitions), clearly label with the words "Steep Slope" and include the percentage grade.
    - 4. Locations where sediment, soil, or other construction materials will be stockpiled
    - 5. Clearly label any water of the state crossings with words "water crossing".
    - 6. Designated points where vehicles will exit onto paved roads.
    - 7. Locations of structures and other impervious surfaces upon completion of construction.
    - 8. Locations of on-site and off-site construction support activity areas covered by this permit (see Section 10.2);
  - v. Locations of springs, wetlands, surface waters, and all waters of Oregon within and one mile downstream of the site's discharge point. Also identify if any surface waters are 303(d) Category 4 and 5 listed as impaired (when the discharge enters an impaired watershed unit, the listing will only be applied if there is a hydrologic connection between the receiving water and assessment water body causing the impairment);
  - vi. Riparian areas and vegetation including trees and associated rooting zones, and vegetation areas to be preserved;
  - vii. Vegetated buffer zones and/or equivalent sediment controls (see Section 13.2.4 and Appendix B) between the site and sensitive areas (e.g., wetlands), and other areas to be preserved, clearly label with the words "Natural Buffer Zone";

Permit Number: 1200-CA

Effective Date: September 15, 2022 Expiration Date: September 14, 2027

ii Clearly label the type and extent of pre-construction cover on the site (e.g. vegetative cover

- viii. Clearly label the type and extent of pre-construction cover on the site (e.g., vegetative cover, forest, pasture, pavement, structures);
- ix. Temporary and permanent stormwater conveyance systems;
- x. Location of concrete wash out;
- xi. Location of sanitary facilities;
- xii. Location of nearest official rain gauge, or if used, location of the registrant's onsite rain gauge;
- xiii. Onsite water disposal locations (e.g., for dewatering);
- xiv. Onsite drain catch basin depicting inlet protections, and a description of the type of catch basins used (e.g., field inlet, curb inlet, grated drain, and combination);
- xv. Septic drain field;
- xvi. Existing or proposed drywells or other UICs;
- xvii. Drinking water wells on site or adjacent to the site;
- xviii. Stormwater planters;
- xix. Detention ponds, storm drain piping, and inflow and outflow details (e.g., bottom elevations and inverts);
- xx. Post-construction stormwater facilities designed and engineered to infiltrate or filter stormwater and associated access restriction control measures (Section 13.2.12);
- xxi. Locations of all potential pollutant-generating activities identified in Section 15.4.e. xiii;
- xxii. Locations of stormwater controls, including any shared controls utilized to comply with this permit;
- xxiii. Any other applicable features or controls that are associated with pollution prevention in stormwater discharges;
- xxiv. Locations where polymers, flocculants, or other treatment chemicals will be used and stored;
- xxv. Locations of engineered soils (see Section 13.2.18);
- xxvi. Locations of engineered sediment basins (see Section 13.2.17);
- xxvii. Receiving water(s). Stormwater and authorized non-stormwater discharge point locations, including:
  - 1. Locations where stormwater and/or authorized non-stormwater will be discharged to storm drain inlets; and
  - 2. Locations where stormwater or authorized non-stormwater will be discharged directly to surface waters of the state;
- xxviii. Perimeter controls for a "linear construction site" (see Section 13.2.6);
- xxix. Sediment track-out controls (see Section 13.2.7); and
- xxx. Stabilization measures (see Sections 13.2.20 and 13.2.21). The registrant must include the specific vegetative and/or non-vegetative practices that will be used.

## 15.5. ESCP certification

The ESCP must be signed and dated by the preparer and in accordance with Section 15.1 if applicable.

Expiration Date: September 14, 2027

#### 15.6. ESCP attachments

The registrant must include a copy of the DEQ approved Environmental Management Plan if applicable (see Section 6).

### 15.7. On-site availability of the ESCP

The registrant must keep a current copy of the ESCP at the site and be available for inspections or upon request by DEQ. The ESCP can be stored electronically as long as the personnel on-site can access it and make it available for inspector review.

#### 15.8. ESCP revisions

The ESCP and the site maps must be revised, within seven days of any of the following to accurately reflect site conditions and BMPs used onsite, if any of the following occurs:

- a. Changes to the construction plans that impact erosion and sediment control measures.
- b. Changes to the stormwater control BMPs, their location, maintenance required, and any other revisions necessary to prevent and control erosion and sediment runoff.
- c. An increase in construction activities to adjacent lots.
- d. Other activities at the site that are no longer accurately reflected in the ESCP. This includes changes made in response to corrective actions triggered under Section 16. The ESCP does not need to be modified if the estimated dates in Section 15.4.e.viii change during the course of construction.
- e. To reflect areas on the site map where operational control has been transferred (and the date of transfer) since initiating permit coverage.
- f. If inspections by DEQ determine that ESCP revisions are necessary for compliance with this permit.
- g. Where DEQ determines it is necessary to install and/or implement additional controls at the site in order to meet the requirements of this permit, the following must be included in the ESCP:
  - i. A copy of any correspondence describing such measures and requirements; and
  - ii. A description of the controls that will be used to meet such requirements.
- h. Change of contractors that will engage in construction activities on site, and the areas of the site where the contractor(s) will engage in construction activities.
- i. Change of any personnel (by name and position) that are responsible for the design, installation and maintenance of stormwater control measures (see Section 15.10).
- j. Change of the Certified Erosion and Sediment Control Inspector, or of their contact information and any applicable certification and training experience.
- k. To reflect any revisions to applicable federal, state, tribal or local requirements that affect the stormwater controls implemented at the site.
- 1. If a change in chemical treatment systems or chemically enhanced stormwater control is made, including use of a different treatment chemical, different dosage rate or different area of application as applicable.

### 15.9. Submission of ESCP revision to DEQ

Revisions to the ESCP that require submission are a reporting requirement. The registrant must submit a revised version of the complete ESCP to DEQ within 30 calendar days of the revision. If the registrant does

not receive a response to the revisions from DEQ within ten calendar days of receipt, the proposed revisions are deemed accepted.

- a. ESCP revisions must be submitted if they are made for the following reasons:
  - i. Part of a corrective action requirement in Section 16.
  - ii. An increase or decrease of the project size.
  - iii. An increase or decrease of the size or location of disturbed areas.
  - iv. Change to BMPs (e.g., type, design, or location).
  - v. Change of the certified visual monitoring inspector.
- b. The registrant must maintain records showing the dates of all ESCP revisions. The records must include the name of the person authorizing each change (see Section 15.8 above) and a brief summary of all changes.
- c. All revisions made to the ESCP consistent with Section 15.8 must be authorized by a person identified in Section 15.1 if applicable.
- d. Approval of the revisions by DEQ prior to implementation is not required, however the addition of an Active Chemical Treatment System must be approved by DEQ before operating and requires submission of an Environmental Management Plan (see Section 6.c).

#### 15.10. Prior to commencement of construction activities.

The registrant must document the names and contact information of personnel that have responsibilities for implementing stormwater control measures and complying with the permit and ESCP requirements at the project site. The list of personnel should be kept with the ESCP.

If new or additional contractors are hired to implement control measures identified in the ESCP after construction has commenced, the contact information must be updated. The registrant must ensure that the following personnel are informed of the permit and ESCP requirements and their specific responsibilities:

- a. Personnel who are responsible for the installation, maintenance, and/or repair of stormwater controls (including pollution prevention controls);
- b. Personnel responsible for the application and storage of treatment chemicals (if applicable);
- c. Personnel who are responsible for conducting inspections as required in Section 17.1; and
- d. Personnel who are responsible for taking corrective actions as required in Section 16.

# 15.11. Permit Registrant is responsible for ensuring that all activities on the site comply with the requirements of the permit

The registrant must make subcontractors and outside service providers aware of any permit requirements that apply to the work they are subcontracted to perform. The permit registrant must provide subcontractors and outside service providers easy access to an electronic or paper copy of applicable portions of this permit, the most updated copy of the ESCP and other relevant documents or information that must be kept with the ESCP.

#### 16. Corrective Actions

Permit registrants issued permit coverage prior to August 11, 2022, the issuance date of this permit, must comply with all conditions of Section 16-Corrective Actions as of September 15, 2022, the permit effective date.

The registrant must take corrective action(s) to comply with permit conditions, and must take immediate corrective action if any of the following conditions exist:

- a. The discharges are causing an exceedance of applicable water quality standards.
- b. Sediment or turbidity (as described in Section 13.2.11) are visible in discharge from the permitted site within:
  - i. A conveyance system leading to surface waters.
  - ii. Surface waters from the discharge point.
- c. If DEQ requires the registrant to take corrective actions to prevent or control the discharge of significant amounts of sediment or turbidity to surface waters or to conveyance systems that discharge to surface waters, or as the result of a permit violations found during an inspection.
- d. A stormwater control needs repair or replacement (beyond routine maintenance required under Section 13.1.4).
- e. A stormwater control necessary to comply with the requirements of this permit was never installed or was installed incorrectly.
- f. A prohibited discharge has occurred (see Section 12), including visibly turbid discharge.

#### 16.1. Corrective action timelines

If any corrective action is required per Section 16 above, the registrant must immediately implement that action according to the following:

- a. Take all necessary steps to address the condition, including cleaning up any contaminated surfaces so the material will not discharge in subsequent storm events;
- b. Complete the corrective action by the close of the next business day when the problem does not require a new or replacement control or significant repair; and
- c. When the problem requires a new or replacement control or significant repair, install the new or modified control and make it operational, or complete the repair, by no later than 24 hours from the time of discovery to ensure that the requirements of Section 14.1 are met. If it is infeasible to complete the installation or repair within 24 hours, the registrant must document in the records why it is infeasible to complete the installation or repair within the 24-hour timeframe and document the schedule for installing the stormwater control(s) and making it operational as soon as feasible after the 24-hour timeframe. Where these actions result in changes to any of the stormwater controls or procedures documented in the ESCP, the registrant must revise the ESCP in accordance with Section 15.8.

#### 16.2. Corrective action documents

Within 24 hours of each corrective action implemented, the registrant must document the corrective actions in a report that includes:

- a. The site common name;
- b. Identification of discharge locations that were out of compliance;
- c. The period of noncompliance;
- d. Names, titles and contact information of personnel conducting inspections;
- e. The specific condition and the date and time it was identified;
- f. Describe the noncompliance and evaluate the stormwater control measures and practices to determine the cause of noncompliance;

g. Within 24 hours of completing the corrective action (in accordance with the timelines of Section 16.1), document the actions taken to address the condition, and steps taken to prevent the reoccurrence of the noncompliance including whether any ESCP revisions are required. Where these actions result in changes to any of the stormwater controls or procedures documented in the ESCP, the registrant must revise the ESCP in accordance with Section 15.8;

- h. Each corrective action report must be signed by the permit registrant;
- i. The corrective action reports must be kept at the site or at an easily accessible location and made available to DEQ upon request; and
- j. The corrective action reports must be retained for three years after project completion.

## 16.3. Submit a corrective action report to DEQ

Within 48 hours of taking Corrective Action(s) that prevent an exceedance of water quality standards, sediment from leaving the site or visibly turbid discharge as required in Sections 16.a, 16.b or 16.c above the registrant must submit a corrective action report to DEQ. This report must include:

- a. The site common name and permit identification number;
- b. A description of the noncompliance and its cause;
- c. Identification of outfalls that were out of compliance;
- d. The NTU of the turbid discharge before and after corrective actions or photo of discharge before and after corrective action(s) implementation;
- e. The period of noncompliance;
- f. Names of personnel conducting visual monitoring;
- g. Steps taken or planned to reduce, eliminate and prevent recurrence of the noncompliance (such as specific BMPs that will be implemented or increased inspection frequency);
- h. A timeline of corrective action events: From identifying the need to take corrective action to submission of a corrective action report showing that the required steps were taken in the time allotted per Sections 16.1, 16.2 and 16.3. If allotted time is exceeded, state the cause for the delay;
- i. Weather conditions that varied from predicted storm events and may have contributed to prohibited discharge occurrence; and
- j. ESCP revisions if revisions were required to prevent and control erosion and sediment discharges.

If the registrant performs appropriate corrective actions and reporting in accordance with Sections 16, 16.1, 16.2 and 16.3, DEQ will consider these efforts to correct and/or mitigate the violation in deciding whether to initiate an enforcement action.

Expiration Date: September 14, 2027

## **SCHEDULE B**

## MINIMUM MONITORING AND RECORDKEEPING REQIREMENTS

# 17. Visual monitoring of site and reporting requirements

## 17.1. Person(s) responsible for visually monitoring the project site

All sites one or more acres in size must be visually monitored by a Certified Erosion and Sediment Control or Storm Water Quality Visual Monitoring Inspector (Inspector). The Visual Monitoring Inspector must be certified in one of the following sediment and erosion control programs, or any other course approved at a future date by DEQ. DEQ has approved the following programs:

- a. Certified Professional in Erosion and Sediment Control,
- b. Certified Professional in Storm Water Quality,
- c. Certified Inspector of Sediment and Erosion Control,
- d. Washington State Certified Erosion and Sediment Control Lead,
- e. Rogue Valley Sewer Services Erosion and Sediment Control Certification, or
- f. Oregon Department of Transportation Erosion and Sediment Control Manager Certification (ODOT projects only).

## 17.2. Frequency of visual monitoring inspections

At a minimum, the Inspector must document the initial date of any construction staging, construction activities or land clearing, and conduct and document a visual monitoring inspection of the project site per the following frequency:

- a. On the initial date;
- b. Once every 14 calendar days; and
- c. Daily within 24 hours of any storm event, including snowmelt that results in discharge from the site.

Storm event information can be derived from weather stations that are representative of the site location, rain gauges and other appropriate documentation can be used in the inspection reports. Note, in many parts of Western Oregon, a storm event of 0.10 inches will result in a discharge from construction sites.

# 17.3 Reductions in visual monitoring frequency

The Inspector must inspect stabilized areas no more than 14 days prior to a site becoming inactive to ensure that erosion and sediment control measures are in working order. For the following scenarios, the Inspector must clearly document the following conditions have begun in the written visual monitoring reports:

- a. The Inspector may reduce the frequency of inspections in any area of the site where the temporary stabilization steps in accordance with Section 13.2.20 have been completed to twice per month for the first month, no less than 14 calendar days apart, then once per month. If construction activity resumes on a stabilized area of the site at a later date, the inspection frequency must immediately increase to that required in Section 17.2, as applicable. The Inspector must document the beginning and ending dates of site inactivity in the visual monitoring reports.
- b. For "linear construction sites" where disturbed portions have achieved final stabilization criteria at the same time active construction continues on others, the inspection frequency may be reduced to twice

per month for the first month, no less than 14 calendar days apart, in any area of the site where the temporary stabilization steps have been completed. After the first month, inspect once more within 24 hours of any storm event leading to discharge from the site. If there are no issues or evidence of stabilization problems (e.g., failure to establish 70% vegetative cover), inspections may be discontinued. If "wash-out" of stabilization materials and/or sediment is observed, following restabilization, inspections must resume at the inspection frequency required in Section 17.2. Inspections must continue until final stabilization is visually confirmed following a storm event leading to discharge from the site.

#### Frozen conditions:

- a. If construction activities are suspended due to frozen conditions, visual monitoring inspections may be temporarily suspended on the site until thawing conditions (See Schedule D.4 Permit Specific Definitions) exist if:
  - i. Runoff is unlikely due to continuous frozen conditions. If unexpected weather conditions (such as above freezing temperatures or rain events) make discharges likely, the Inspector must immediately resume the regular inspection frequency as described in Section 17.2, as applicable;
  - ii. Land disturbances have been suspended; and
  - iii. All disturbed areas of the site have been temporarily stabilized in accordance with Section 13.2.20.
- b. If construction activities are conducted during frozen conditions, the visual monitoring inspection frequency may be reduced to once per month if:
  - Runoff is unlikely due to continuous frozen conditions. If unexpected weather conditions (such as above freezing temperatures or rain events) results in likely discharges, the Inspector must immediately resume the regular inspection frequency as described in Section 17.2, as applicable; and
  - ii. Disturbed areas of the site have been temporarily stabilized in accordance with Section 13.2.20.

# 17.4. Requirements for visual monitoring

Visual Monitoring should be conducted during safe conditions and evaluate all elements of the ESCP including:

- a. Confirmation that all stormwater controls are properly installed and are working as intended to prevent pollutant discharges;
- b. Confirmation that the presence of conditions that could lead to spills, leaks, or other accumulations of pollutants on the site are addressed;
- c. Identify any locations where new or modified stormwater controls are necessary to meet the erosion and sediment control requirements of Sections 13, 14 and 15;
- d. Check for the presence of visible erosion and sedimentation as outlined in Section 13.2.11 and document any indication of sediment that has left or is likely to leave the project site;
- e. If a discharge is occurring during the inspection:
  - i. Identify all stormwater discharge locations at the site; and
  - ii. Document the visual quality of the discharge and take note of the characteristics of the stormwater discharge, including color, odor, suspended solids, foam, oil sheen and any other indicators of stormwater pollutants;

Expiration Date: September 14, 2027

f. If no discharge occurred from site within 24 hours of a storm event, the inspector must document (e.g., date stamped photos of all points of discharge from the site) that no discharge from the site occurred:

- g. Identify any portion of the project site where land disturbing activities have permanently ceased or will be temporarily inactive for 14 or more calendar days and note the initial date of cessation; and
- h. Complete any necessary maintenance, corrective actions or stabilization measures.

The Inspector is not required to visually monitor areas that, at the time of the inspection, are considered unsafe. Nearby downstream locations of any receiving waterbodies must be inspected to the extent that such inspections are safe, accessible and practical.

# 17.5. Visual monitoring inspection report

The inspection report must be completed within 48 hours of all site inspections. Inspection reports must include the following as applicable to the site:

- a. The inspection date;
- b. The name of the site and the identification number provided by the permit registrant;
- c. Names, titles and contact information of the inspector;
- d. A summary of the inspection, including the observations of the elements made in Section 17.4, the location of BMPs in need of any necessary maintenance or corrective actions, the location of any BMPs that failed to operate as designed or proved inadequate for a particular application, the location of where additional BMPs are needed that did not exist at the time of inspection, visual observations of the stormwater discharges from the site, or if a discharge from the site did not occur within 24 hours of a storm event (attach date stamped photos to report);
- e. Any unauthorized discharges from the site;
- f. Any portion(s) of the site where land disturbing activities have permanently ceased or will be temporarily inactive for 14 or more calendar days;
- g. If complying with stabilization schedules for sites affected by unforeseen circumstances that delay the initiation and/or completion of vegetative stabilization, document the circumstances and the schedule for initiating and completing stabilization;
- h. If complying with the stabilization schedules in arid, and semi-arid sites typical of Eastern Oregon (climate determination of the project site can be found on the National Climatic Data Center website), or drought-stricken areas, the beginning and ending dates of the seasonally dry period and the schedule the permit registrant will follow for initiating and completing vegetative stabilization;
- i. All pH sampling results conducted per Section 17.6.1;
- j. The alternative erosion and sediment control measures and the inspection frequency (see Section 17.3.b) for linear construction projects;
- k. Reasons for changes or modifications to the ESCP;
- 1. Start and end dates subject to alternative inspection frequencies listed in Section 17.3
- m. If the Inspector is inspecting the site at the frequency specified in Section 17.2 or Section 17.3, the applicable rain gauge, weather station readings or other source of information that triggered the inspection (e.g., weather conditions during the inspection, the approximate amount of precipitation since the last inspection, and approximate amount of precipitation during the last 24 hours);

n. If the Inspector determines that it is unsafe to inspect a portion of the site or the inclement weather makes the site, or portions of the site inaccessible, the reasoning and the locations to which this condition applies must be documented;

- o. Each inspection report must be signed by the Inspector with the following statement: "I certify that this report is true, accurate, and complete to the best of my knowledge, abilities, and belief";
- p. All inspection reports should be kept in chronological order at the site or at an easily accessible location (electronically is acceptable), and made available at the time of inspection or within three days upon request by DEQ; and
- q. All visual monitoring notes, sampling records and inspection reports must be kept for three years from project completion.

## 17.6. Monitoring requirements

# 17.6.1. Monitoring pH of stormwater captured in sediment basins/impoundments when engineered soils are used

If construction activity involves the use of engineered soils (soil amendments including, but not limited to Portland cement-treated base, cement kiln dust, or fly ash), the permit registrant must conduct, and document pH monitoring of stormwater captured in the sediment impoundment as described below:

- a. The permit registrant must begin the pH monitoring period when the engineered soils are first exposed to precipitation and must continue every 7 calendar days and within 24 hours of the occurrence of discharge from the site, or the occurrence of a storm event of 0.10 inches or greater until final stabilization of the area of engineered soils is established;
- b. Document date soil amendments are added, and final stabilization achieved in the Inspection Report per Section 17.5;
- c. The permit registrant must monitor the pH of stormwater in the sediment basins/impoundments immediately before the stormwater discharge to surface waters and at discharge point locations that receive stormwater runoff from the area of engineered soils;
- d. The benchmark value for pH is defined in Standard Units (SU) and determined by the river basin containing the receiving waterbody according to OAR 340-041-0021. Anytime monitoring indicates that the pH is the maximum allowed SU or greater, the permit registrant must either:
  - i. Prevent the high pH water from entering storm sewer systems or surface waters; or
  - ii. If necessary, adjust or neutralize the high pH water until it is in the range of pH SU acceptable for discharge to the river basin containing the receiving waterbody by using an appropriate treatment BMP such as carbon dioxide (CO2) sparging or dry ice. The permit registrant must obtain written permission from DEQ before using any form of chemical treatment other than CO2 sparging or dry ice per Section 6; and
- e. The permit registrant must perform pH monitoring on site within 15 minutes of sample collection with an accurately calibrated pH meter. The permit registrant must record the pH monitoring results and any pH adjustment treatments in the inspection report.

# 17.7. Inspections by DEQ

The permit registrant must allow and make arrangements for DEQ to have access to the site at all reasonable times.

# **SCHEDULE D**

## SPECIAL CONDTIONS

- 1. Issuance of this permit coverage does not relieve the permit registrant from all other permitting and licensing requirements. Prior to beginning construction activities, all other necessary approvals must be obtained.
- 2. Permit coverage will remain in effect after the expiration date or until another permit is issued if the permittee has paid all fees and has filed a renewal application.
- **3.** Any permit registrant that does not want to be covered or limited by this general permit may make application for an individual NPDES permit in accordance with the procedures in OAR 340-45-030.

# 4. Permit Specific Definitions:

- a. Active Chemical Treatment System-the use of chemicals (e.g., cationic treatment chemicals, electro-coagulation, flocculants, filtration, anionic polyacrylamide, polymers, hydrochloric or sulfuric acid) to remove pollutants from water (stormwater runoff or from dewatering) before discharge from a permitted site.
- b. Active Treatment System-the use of pumps or other non-passive means to facilitate the removal of pollutants from water (stormwater runoff or from dewatering) before discharge from a permitted site.
- c. Backwash Water (per Section 13.4.f)-refers to pumping water backwards through the filter media, sometimes including intermittent use of compressed air during the process. Backwashing is a form of preventive maintenance so that the filter media can be reused.
- d. Best Management Practices or BMPs-schedules of activities, prohibitions of practices, maintenance procedures, and other physical, structural or managerial practices to prevent or reduce the pollution of waters of the state.
   BMPs include treatment systems, erosion and sediment control, source control, and operating procedures and practices to control site runoff, spillage or leaks, and waste disposal.
- e. Clean Water Act or CWA-the Federal Water Pollution Control Act enacted by Public Law 92-500, as amended by Public Laws 95-217, 95-576, 96-483, and 97-117; USC 1251 et seq.
- f. Common Plan of Development or Sale-is a plan to subdivide a parcel of land into separate parts for separate sale. This can be for residential, commercial, or industrial development. A construction activity is part of a larger common plan of development if it is completed in one or more of the following ways: in separate stages, in separate phases, and/or in combination with other construction activities.
- g. Construction Activities-including but not limited to, clearing, grading, excavating, grubbing, stumping, demolition, and land disturbing activities. Construction activity does not include routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of the facility as defined in 40 CFR 122.26(b)(15).
- h. Construction Support Activity-a construction-related activity that specifically supports the construction activity and involves earth disturbance or pollutant-generating activities of its own and can include activities associated with concrete or asphalt batch plants, equipment staging yards, materials storage areas, excavated material disposal areas, and borrow areas.
- i. Contamination-for the purposes of this permit, are generally understood to be caused by a known or unknown "Release", as defined by ORS 465.200 (22), from a known or suspected source.
- j. Conveyance System-for the purposes of this permit, a sewer, ditch, pipe, channel, swale or similar component that is designed to carry water or any combination of such components.

- k. CO<sub>2</sub> Sparging (per Sections 13.2.18 and 17.6.1)-is a technique in which carbon dioxide gas, sometimes introduced by dry ice, is bubbled through a liquid in order to lower the pH of the liquid.
- 1. DEQ-the Oregon Department of Environmental Quality.
- m. Detention-the temporary storage of stormwater to improve quality or reduce the volumetric flow rate of discharge or both.
- n. Dewatering-the removal and disposal of surface water or groundwater during site construction.
- o. Discharge Point-the location where stormwater leaves the site. It includes the location where stormwater is discharged to surface water or a stormwater conveyance system.
- p. Earth Disturbance-actions taken to alter the existing vegetation and/or underlying soil of a site, such as clearing, grading, site preparation (e.g., excavating, cutting, and filling), soil compaction, and movement and stockpiling of topsoil.
- q. Encroach(ing)-to intrude beyond a specified boundary without right or permission.
- r. Engineered Soils (per Section 17.6.1)-soils on site amended with cementitious compounds.
- s. Erosion-the movement of soil particles or rock fragments by water or wind.
- t. Erosion and Sediment Control BMPs-BMPs that are intended to prevent erosion and sedimentation, such as preserving natural vegetation, seeding, mulching and matting, plastic covering, sediment fences, and sediment traps and ponds. Erosion and sediment control BMPs are synonymous with stabilization and structural BMPs.
- u. Farm Use Land-cropland, grassland, rangeland, pasture, and other land on which agricultural or forest-related products or livestock are produced. Agricultural lands include cropped woodland, marshes, incidental areas included in the agricultural operation, and other types of land used for the production of livestock.
- v. Hazardous Materials-the materials defined in 40 CFR part 302 Designation, Reportable Quantities, and Notification.
- w. Linear Construction Site-examples of linear construction projects include, but are not limited to, pipeline projects, highway construction, highway resurfacing and maintenance, airport runway construction and resurfacing tunnels, mass transit systems, and railroads.
- x. Local Government-any county, city, town, or service district.
- y. National Pollutant Discharge Elimination System or NPDES-the national program under Section 402 of the Clean Water Act for regulation of point source discharges of pollutants to waters of the United States.
- z. Native Topsoil (per Section 13.2.12)-top layer of soil on site.
- aa. Natural Buffer Zone-for the purposes of this permit, an area of undisturbed natural cover surrounding surface waters within which construction activities are restricted. Natural cover includes the natural vegetation, exposed rock, and barren ground that existed prior to commencement of land disturbing activities.
- bb. Natural Vegetation-vegetation that occurs spontaneously without regular management, maintenance, or species introductions or removals. For purposes of this permit, this includes invasive species.
- cc. Non-Stormwater Pollution Controls-general site and materials management measures that directly or indirectly aid in minimizing the discharge of sediment and other construction related pollutants from the construction site.
- dd. Owner-for the purposes of this permit, any person with a legal interest in the permitted activities or the property on which the permitted activities occur.
- ee. Permit Registrant-for the purposes of this permit, the public entity performing the construction activity regulated by this permit that has submitted an application and received notice of registration under this general permit by DEQ.

- ff. Person-not only individuals, but also includes corporations, associations, firms, partnerships, joint stock companies, public and municipal corporations, political subdivisions, the state and any agencies thereof and the federal government and any agencies thereof.
- gg. pH Neutralization (per Section 17.6)-to bring the pH between 6.5 and 8.5 standard units.
- hh. Pollutant as defined in 40 CFR §122.2-dredged spoil, solid waste, incinerator residue, filter backwash, sewage, garbage, domestic sewage sludge (biosolids), munitions, chemical wastes, biological materials, radioactive materials, heat, wrecked or discarded equipment, rock, sand, soil, cellar dirt and industrial, municipal, and agricultural waste discharge into water. It does not mean sewage from vessels within the meaning of section 312 of the FWPCA, nor does it include dredge or fill material discharged in accordance with a permit issued under section 404 of the FWPCA.
- ii. Pollution or Water Pollution as defined by ORS 468B.005(3)-such alteration of the physical, chemical or biological properties of any waters of the state, including change in temperature, taste, color, turbidity, silt or odor of the waters, or such discharge of any liquid, gaseous, solid, radioactive or other substance into any waters of the state, which will or tends to, either by itself or in connection with any other substance, create a public nuisance or which will or tends to render such waters harmful, detrimental or injurious to public health, safety or welfare, or to domestic, commercial, industrial, agricultural, recreational or other legitimate beneficial uses or to livestock, wildlife, fish or other aquatic life or the habitat thereof.
- jj. Project Completion-for the purposes of this permit, it means that construction activities are completed on the 1200-CA permit covered project site and that final stabilization criteria listed in the permit conditions are met.
- kk. Runoff Controls-BMPs that are designed to control the peak volume and flow rate or to prevent scour due to concentrated flows.
- 11. Sediment-mineral or organic matter, typically deposited by water, air or ice.
- mm. Sediment Basin/Impoundment (also includes traps/ponds)-a sediment basin is a temporary pond built on a construction site to capture eroded or disturbed soil that is washed off during storm events, and protect the water quality of a nearby stream, river, lake or bay. The sediment-laden soil settles in the pond before the runoff is discharged.
- nn. Sequence-the phased order that land disturbing activities are performed.
- oo. Shared Control-a stormwater control, such as a sediment basin or pond, used by two or more operators that is installed and maintained for the purpose of minimizing and controlling pollutant discharges from a construction site with multiple registrants associated with a common plan of development or sale.
- pp. Steep Slope-defined as those that are 70 percent or greater in grade.
- qq. Site-the area where the construction activity is physically located or conducted.
- rr. Storm Event-EPA defines a storm event at 40 CFR 122.21(g)(7)(ii) as a rainfall event with greater than 0.1 inch of rainfall.
- ss. Stormwater as defined by 40 CFR §122.26(b)(13)-stormwater runoff, snow melt runoff and surface runoff and drainage.
- tt. Stormwater Conveyance-a sewer, ditch, or swale that is designed to carry stormwater; a stormwater conveyance may also be referred to as a storm drain or storm sewer.
- uu. Stumping-For the purposes of this permit, "stumping" is defined as "to clear the land of stumps."
- vv. Surface Runoff-that portion of stormwater that does not infiltrate into the ground or evaporate, but instead flows onto adjacent land or watercourses or is routed to stormwater conveyance systems.
- ww. Surface Water-all water naturally open to the atmosphere; for example, rivers, lakes, reservoirs, ponds, streams, impoundments, oceans, estuaries, springs, etc.

- xx. Thawing Conditions-when frozen water onsite melts and creates runoff that may possibly discharge.
- yy. Total Maximum Daily Load or TMDL-a calculation of the maximum amount of a pollutant that a waterbody can receive and still meet state water quality standards. It is the sum of the allowable loads of a single pollutant from all contributing point and nonpoint sources. Percentages of the TMDL are allocated by DEQ to the various pollutant sources.
- zz. Toxic Substances-are materials that are poisonous to living organisms.
- aaa. Treatment Chemicals-polymers, flocculants or other chemicals that, among other things, are used to reduce turbidity in stormwater discharges by chemically bonding to the suspended silts and other soil materials and causing them to bind together and settle out. Common examples of treatment chemicals are chitosan, cationic PAM and anionic polyacrylamide.
- bbb. Turbidity-the optical condition of waters caused by suspended or dissolved particles or colloids that scatter and absorb light rays instead of transmitting light in straight lines through the water column. Turbidity may be expressed as nephelometric turbidity units (NTUs) measured with a calibrated turbidity meter.
- ccc. Underground Injection Control-any system, structure, or activity that is created to place fluid below the ground or sub-surface (e.g., sumps, infiltration galleries, drywells, trench drains, drill holes, etc.).
- ddd. Visibly Turbid Discharge-refers to the cloudiness in the water discharged caused by sediment and other matter in the water column.
- eee. Water or Waters of the State as defined by ORS 468B.005(10)-lakes, bays, ponds, impounding reservoirs, springs, wells, rivers, streams, creeks, wetlands, estuaries, marshes, inlets, canals, the Pacific Ocean within the territorial limits of the State of Oregon and all other bodies of surface or underground waters, natural or artificial, inland or coastal, fresh or salt, public or private (except those private waters which do not combine or effect a junction with natural surface or underground waters), which are wholly or partially within or bordering the state or within its jurisdiction.

Expiration Date: September 14, 2027

## **SCHEDULE F**

## NPDES GENERAL CONDITIONS

#### Section A. Standard Conditions

### 1. Duty to Comply

The permittee must comply with all conditions of this permit. Any permit noncompliance constitutes aviolation of Oregon Revised Statutes (ORS) 468B.025 and is grounds for enforcement action; for permit termination, suspension, or modification; or for denial of a permit renewal application.

#### 2. Penalties for Water Pollution and Permit Condition Violations

Oregon Law (ORS 468.140) allows the Director to impose civil penalties up to \$10,000 per day for violation of a term, condition, or requirement of a permit.

Under ORS 468.943, unlawful water pollution, if committed by a person with criminal negligence, is punishable by a fine of up to \$25,000 or by imprisonment for not more than one year, or by both. Each day on which a violation occurs or continues is a separately punishable offense.

Under ORS 468.946, a person who knowingly discharges, places or causes to be placed any waste into the waters of the state or in a location where the waste is likely to escape into the waters of the state, is subject to a Class B felony punishable by a fine not to exceed \$200,000 and up to 10 years in prison.

## 3. Duty to Mitigate

The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit which has a reasonable likelihood of adversely affecting human health or the environment. In addition, upon request of the Department, the permittee shall correct any adverse impact on the environment or human health resulting from noncompliance with this permit, including such accelerated or additional monitoring as necessary to determine the nature and impact of the noncomplying discharge.

# 4. Duty to Reapply

If the permittee wishes to continue an activity regulated by this permit after the expiration date of this permit, the permittee must apply for and have the permit renewed. The application shall be submitted at least 180 days before the expiration date of this permit.

The Director may grant permission to submit an application less than 180 days in advance but no later than the permit expiration date.

#### 5. Permit Actions

This permit may be modified, suspended, revoked and reissued, or terminated for cause including, but not limited to, the following:

- a. Violation of any term, condition, or requirement of this permit, a rule, or a statute;
- b. Obtaining this permit by misrepresentation or failure to disclose fully all material facts; or
- c. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.

Permit Number: 1200-CA Effective Date: September 15, 2022 Expiration Date: September 14, 2027

The filing of a request by the permittee for a permit modification or a notification of planned changes or anticipated noncompliance, does not stay any permit condition.

### 6. Toxic Pollutants

The permittee shall comply with any applicable effluent standards or prohibitions established under Section307(a) of the Clean Water Act for toxic pollutants within the time provided in the regulations that establish those standards or prohibitions, even if the permit has not yet been modified to incorporate the requirement.

# 7. Property Rights

The issuance of this permit does not convey any property rights of any sort, or any exclusive privilege.

### 8. Permit References

Except for effluent standards or prohibitions established under Section 307(a) of the Clean Water Act for toxic pollutants and standards for sewage sludge use or disposal established under Section 405(d) of the Clean Water Act, all rules and statutes referred to in this permit are those in effect on the date this permit is issued.

### SECTION C. MONITORING AND RECORDS

# 1. Inspection and Entry

The permittee shall allow the Director, or an authorized representative upon the presentation of credentials to:

- a. Enter upon the permittee's premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of this permit;
- b. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this permit;
- c. Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this permit, and
- d. Sample or monitor at reasonable times, for the purpose of assuring permit compliance or as otherwise authorized by state law, any substances or parameters at any location.

## SECTION D. REPORTING REQUIREMENTS

## 1. Planned Changes

The permittee shall comply with Oregon Administrative Rules (OAR) 340, Division 52, "Review of Plans and Specifications". Except where exempted under OAR 340-52, no construction, installation, or modification involving disposal systems, treatment works, sewerage systems, or common sewers shall be commenced untilthe plans and specifications are submitted to and approved by the Department. The permittee shall give notice to the Department as soon as possible of any planned physical alternations or additions to the permitted facility.

# 2. Anticipated Noncompliance

The permittee shall give advance notice to the Director of any planned changes in the permitted facility oractivity which may result in noncompliance with permit requirements.

Permit Number: 1200-CA Effective Date: September 15, 2022 Expiration Date: September 14, 2027

### 3. Transfers

This permit may be transferred to a new permittee provided the transferee acquires a property interest in the permitted activity and agrees in writing to fully comply with all the terms and conditions of the permit and therules of the Commission. No permit shall be transferred to a third party without prior written approval from the Director. The permittee shall notify the Department when a transfer of property interest takes place.

# 4. Compliance Schedule

Reports of compliance or noncompliance with, or any progress reports on interim and final requirements contained in any compliance schedule of this permit shall be submitted no later than 14 days following each schedule date. Any reports of noncompliance shall include the cause of noncompliance, any remedial actions taken, and the probability of meeting the next scheduled requirements.

# 5. Twenty-Four Hour Reporting

The permittee shall report any noncompliance which may endanger health or the environment. Any information shall be provided orally (by telephone) within 24 hours, unless otherwise specified in this permit, from the time the permittee becomes aware of the circumstances. During normal business hours, the Department's Regional office shall be called. Outside of normal business hours, the Department shall be contacted at 1-800-452-0311 (Oregon Emergency Response System).

A written submission shall also be provided within 5 days of the time the permittee becomes aware of the circumstances. If the permittee is establishing an affirmative defense of upset or bypass to any offense underORS 468.922 to 468.946, and in which case if the original reporting notice was oral, delivered written notice must be made to the Department or other agency with regulatory jurisdiction within 4 (four) calendar days. The written submission shall contain:

- a. A description of the noncompliance and its cause;
- b. The period of noncompliance, including exact dates and times;
- c. The estimated time noncompliance is expected to continue if it has not been corrected;
- d. Steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance; and
- e. Public notification steps taken, pursuant to General Condition B.7.

The following shall be included as information which must be reported within 24 hours under this paragraph:

- a. Any unanticipated bypass which exceeds any effluent limitation in this permit.
- b. Any upset which exceeds any effluent limitation in this permit.
- c. Violation of maximum daily discharge limitation for any of the pollutants listed by the Director in this permit.

The Department may waive the written report on a case-by-case basis if the oral report has been received within 24 hours.

# 6. Other Noncompliance

The permittee shall report all instances of noncompliance not reported under General Condition D.4 or D.5, at the time monitoring reports are submitted. The reports shall contain:

- a. A description of the noncompliance and its cause;
- b. The period of noncompliance, including exact dates and times;

Permit Number: 1200-CA Effective Date: September 15, 2022 Expiration Date: September 14, 2027

- c. The estimated time noncompliance is expected to continue if it has not been corrected; and
- d. Steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.

# 7. Duty to Provide Information

The permittee shall furnish to the Department, within a reasonable time, any information which the Department may request to determine compliance with this permit. The permittee shall also furnish to the Department, upon request, copies of records required to be kept by this permit.

Other Information: When the permittee becomes aware that it failed to submit any relevant facts in a permit application or submitted incorrect information in a permit application or any report to the Department, it shall promptly submit such facts or information.

# 8. Signatory Requirements

All applications, reports or information submitted to the Department shall be signed and certified inaccordance with 40 CFR 122.22.

# 9. Falsification of Reports

Under ORS 468.953, any person who knowingly makes any false statement, representation, or certification in any record or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or noncompliance, is subject to a Class C felony punishable by a fine not to exceed \$100,000 per violation and up to 5 years in prison.

# **INSERT TAB**

# Unit 2 Turbidity Monitoring

# Turbidity Monitoring During Construction



# **Cory Engel**




Water Resources Program Coordinator 503-508-0764
Cory.C.Engel@odot.oregon.gov

1

# What is turbidity?

Turbidity is a calibrated measurement of the degree to which a material suspended in water scatters and absorbs light.





# Why does turbidity matter?

- Warms water
- Reduces oxygen
- Impedes photosynthesis
- Clogs fish gills
- Affects fish reproduction and growth
- Interferes with predation
- Affects recreation & drinking





2

# The contractor's ESCM is required to monitor turbidity:

# As part of Erosion & Sediment Control

Standard 280.62(c)

(NPDES 1200-CA)



# On MATERIALS & MINSPECTION

# **During work in water**

Special 290.30(a)(8)

(Clean Water Act Section 401 Water Quality Certifications)



4

# **Turbidity Monitoring Contract Specifications**

# As part of Erosion & Sediment Control

(NPDES 1200-CA)

# 00280.62 Inspection and Monitoring

# **(c) Monitor Receiving Stream**Observe and record color and

turbidity or clarity within 30 feet upstream and downstream of locations where surface waters from the construction site enter the receiving stream....

# **During work in water**

(Clean Water Act Section 401 Water Quality Certifications)

### SP00290.30(a)(8) Turbidity Monitoring

During Work in waters, implement BMPs to minimize turbidity and monitor turbidity...



5

# Turbidity Monitoring as part of Erosion & Sediment Control Monitoring



# Turbidity Monitoring for ESC: WHEN DO WE DO IT?

- When site's runoff drains to a stream (most sites)
- On active sites:
  - · On the initial date of staging or clearing
  - · At least once every 14 days
  - Within 24 hours after any storm event or snowmelt that results in discharge from the site.
- On sites that are inactive, stabilized, or continuously frozen, twice per month for the first month, then once per month.



7

# Turbidity Monitoring for ESC: HOW DO WE DO IT?

Although a turbidity meter can be used to measure turbidity, <u>visual monitoring</u> for erosion and sediment control is generally more convenient and appropriate because other pollutants like color, sheen, and litter are being visually monitored at the same time.



# **Turbidity Monitoring for ESC:** WHERE DO WE DO IT?

At the point of discharge





9

# Turbidity Monitoring for ESC: WHAT IS THE COMPLIANCE STANDARD?


■ 10% increase over background. When monitoring visually, any noticeable increase in turbidity above background (regardless of severity) should be presumed to exceed the standard.







10



11

# Turbidity Monitoring During Work In Water



# Turbidity Monitoring During Work In Water: WHEN DO WE DO IT?

**Per SP00290.30(a)(8):** Meter: 2-hr / Visual: 4-hr intervals





13

# **Turbidity Monitoring During Work In Water**

# "Work In Water" means:

- Work within actual water
- Work that would be within actual water were it not for artificial dewatering





# Turbidity Monitoring During Work In Water: HOW DO WE DO IT?

- We do it in the manner SP00290.30(a)(8) directs.
- Metered measurements of water samples are usually required during work in water.
- On some projects, SP00290.30(a)(8) will allow the contractor to decide whether they want to use visual or meter monitoring.



15

# Turbidity Monitoring During Work In Water: WHERE DO WE DO IT?

- Meter required: Upcurrent approx. 100' from the work; downcurrent approx. 100' from the work, mid-depth of the stream, and within any plume.
- Meter not required: Upcurrent outside the influence of the project, and downcurrent within any plume.





# Turbidity Monitoring During Work In Water: WHAT IS THE VISUAL COMPLIANCE STANDARD?

- A visible plume is an indicator that the 10% threshold has been exceeded.
  - Repair or upgrade in-water BMPs.
  - If a plume is still present at the next 4-hour observation interval, repair or upgrade in-water BMPs and stop work until there is no longer a visible plume or metered samples indicate turbidity is no longer more than 10% above the background level.



17

# Turbidity Monitoring During Work In Water: WHAT IS THE METER COMPLIANCE STANDARD?

Turbidity Level	Restrictions to Duration of Activity
< 5 NTU above background	No restrictions. Continue to monitor every 2 hours.
≥ 5 & < 30 NTU above background	Modify BMPs & continue for <u>4</u> hours. If turbidity is still ≥ 5 above background, stop. Modify BMPs. Resume when NTU is < 5 above background.
≥ 30 & < 50 NTU above background	Modify BMPs & continue for <u>2</u> hours. If turbidity is still ≥ 5 above background, stop. Modify BMPs. Resume when NTU is < 5 above background.
<b>50 NTU</b> or more above background	Stop turbidity-causing work immediately. Contractor notifies the ODOT inspector, and ODOT notifies DEQ.



VUEKE	: Al	RE O	BS	BERV	ATIC	DNS	RECORDE
Oregon Department of Transportation		IN-V	VATER W	ORK TURBIDITY	MONITORIN	G REPORT	
PROJECT NAME						KEY NUMBER	CONTRACT NUMBER
For ODOT use							
DSL permit no.					Samp	pling/Observati	on Locations
Army Corps of Engineers	permit no.			distance of upcurrer	nt and downcurr	ent sampling o	r observations from the in-water work:
Instream work start date					if there is no 401	Water Quality (	Certification)
Instream work end date				☐ 100 feet (typically if there is a 401 Water Quality Certification)			
Extension date (if applica	ible)			Other: Text	Reason: Text		
2. For Contractor/Insp		PRANCE 20/-	\/9\ for nro	anibad bushidibe ma	nitering method		
2. For Contractorninsp	ector use. S			g – First monitoring t			o hours.
Check here to affirm	that the turbic	Sity meter used by	as been mai	intained and calibrate	d according to th	e manufacturer's	s specifications
MONITORED BY	DATE	MONITORING START TIME	TIDAL STA	GE UPGURRENT	DOWNCURRENT NTU	STOP TIME	COMMENTS (DESCRIBE CORRECTIVE ACTION IF DOWNCURRENT NT IS 7 S.00 NTU ABOVE BACKOROUND, DESCRIBE ANY SPEC CIRCUMSTANCES AT THE TIME OF SAMPLING.)
				•			
		Visual turbidity	monitorin	g – First monitoring t	efore work begir	ns, then every fo	ur hours.
MONITORED BY	DATE	MONITORING START TIME	TIDAL STA		STOPTIME	FROM BACK	COMMENTS ECTIVE ACTION IF A PLUME IS OBSERVED THAT IS DISTING ROROUND TURBICITY LEVELS, DESCRIBE ANY SPECIAL MISTANCES AT THE TIME OF THE OBSERVATIONS.
				-			
Signature and subm PRINTED NAME	nission	SIONATURE		DAT	Ε	TITLE	PHONE
Submit according to Se	ection 00290	.30(a)(8).					
Distribution: Original to	Agency Pro	lect Manager, K	еер а сору	y on site during on-	site work.		orm 734-2755

19

# Turbidity Monitoring General Considerations

20

# **General Considerations: Safety First!**

Move the monitoring site or revert to visual monitoring if conditions are sketchy.









21

# **General Considerations: Non-Project Turbidity**

- Try to choose a monitoring location that excludes the non-project turbidity source.
- Record on the monitoring form and take a photograph.





# **General Considerations: Sampling Point**

- In a well-mixed stream, take sample away from the shore line
- Mid-depth of the stream
- If there's a visible plume resulting from project work, take sample from within it
- If in the stream, take sample upstream from your feet (avoid sample contamination by stirring up bed sediment)






23

# **General Considerations: Sample Handling**

- Take upstream and downstream samples as close to the same time as possible
- Rinse sample container thoroughly with sample water before filling with the sample to be tested
- Invert the container when submerging and turn it upright in the mid-point of the water column
- Follow meter's maintenance and calibration instructions
- Average multiple readings for each sample
- Avoid pouring from one container to another
- Before metering, gently agitate to resuspend sediments





25

# **General Considerations: Regulator Reporting**

# **Self-reporting exceedances**

- Things go better with regulators when they trust us.
- Trust is built by transparency.
- Consistently perfect reports are unrealistic & suspicious.



# **INSERT TAB**

**401 Certification** 



# Department of Environmental Quality Northwest Region

700 NE Multnomah Street, Suite 600 Portland, OR 97232 (503) 229-5263 FAX (503) 229-6945 TTY 711

Month XX, 2021

APPLICANT NAME
COMPANY/ORG NAME
STREET ADDRESS
CITY, STATE ZIP

RE: 401 Water Quality Certification Approval for Project Number, Project Name

The US Army Corps of Engineers (USACE) has determined that your project will be authorized under Nationwide Permit (NWP) category #XX. As described in the application package received and reviewed by the Oregon Department of Environmental Quality (DEQ), the project qualifies for the expedited 401 Water Quality Certification (WQC), subject to the conditions outlined below. If you cannot meet all conditions of this 401 WQC, you may apply for a standard individual certification. A standard individual certification will require additional information, a public notice, and a higher review fee.

**Certification Decision:** Based on information provided by the USACE and the Applicant, DEQ has determined that implementation eligible activities under the proposed NWP will be consistent with water quality requirements including applicable provisions of Sections 301, 302, 303, 306, and 307 of the federal Clean Water Act, state water quality standards set forth in Oregon Administrative Rules Chapter 340 Division 41, and other appropriate requirements of state law, provided the following conditions are incorporated into the federal permit and strictly adhered to by the Applicant.

**Duration of Certificate:** This 401 WQC for impacts to waters, including dredge and fill activities, is valid for the duration of the USACE Section 404 permit. A new 401 WQC must be requested with any modification of the USACE 404 permit.

In addition to all USACE national and regional permit conditions, the following 401 WQC conditions apply to all NWP categories that qualify for the Nationwide 401 WQC.

## **401 GENERAL CERTIFICATION CONDITIONS**

1) **Responsible parties:** This 401 WQC applies to the Applicant. The Applicant is responsible for the work of its contractors and sub-contractors, as well as any other entity that performs work related to this WQC.

Rule: 40 CFR 121, OAR 340-048-0015

**Justification:** DEQ must be aware of responsible parties to ensure compliance.

2) **Work Authorized:** Work authorized by this 401 WQC is limited to the work described in the Permit Application and additional application materials (hereafter "the permit application")

materials"), unless otherwise authorized by DEQ. If the project is operated in a manner not consistent with the project description contained in the permit application materials, the Applicant is not in compliance with this 401 WQC and may be subject to enforcement.

Rule: OAR 340-048-0015

**Justification:** To ensure the project will comply with water quality standards, DEQ must understand all work involved in the construction and operation of the project.

401 WQC on Site: A copy of this 401 WQC must be kept on the job site and readily available for reference by the Applicant and its contractors and subcontractors, as well as by DEQ, USACE, National Marine Fisheries Service (NMFS), Oregon Department of Fish and Wildlife (ODFW), and other state and local government inspectors.

Rule: OAR 340-012

**Justification:** All parties must be aware of and comply with the 401 WQC, including on-site contractors.

4) **Project Changes:** DEQ may modify or revoke this 401 WQC, in accordance with OAR 340-048-0050, if the project changes or project activities are having an adverse impact on state water quality or beneficial uses, or if the Applicant is otherwise in violation of the conditions of this certification.

Rule: OAR 340-048-0050

**Justification:** To ensure the project will comply with water quality standards, DEQ must understand all work involved in the construction and operation of the project.

- 5) Land Use Compatibility Statement: In accordance with OAR 340-048-0020(2) (i), each Applicant must submit findings prepared by the local land use jurisdiction that demonstrates the activity's compliance with the local comprehensive plan. Such findings can be submitted using Section 11 of the Joint Permit Application, signed by the appropriate local official and indicating:
  - a. "This project is consistent with the comprehensive plan and land use regulations;" or,
  - b. "This project will be consistent with the comprehensive plan and land use regulations when the following local approvals are obtained," accompanied by the obtained local approvals.
  - c. Rarely, such as for federal projects on federal land, "this project is not regulated by the comprehensive plan" will be acceptable.

In lieu of submitting the appropriate section of the USACE & Department of State Lands (DSL) Joint Permit Application, the Applicant may use DEQ's Land Use Compatibility Statement form found at: http://www.oregon.gov/deg/FilterDocs/lucs.pdf

Rule: OAR 340-048-0020(2) (i), OAR 340-018

Justification: DEQ must ensure compliance with water quality land use laws at the local level.

- 6) Access: The Applicant and its contractors must allow DEQ access to the project site with or without prior notice, including staging areas, and mitigation sites to monitor compliance with these 401 WQC conditions, including:
  - Access to any records, logs, and reports that must be kept under the conditions of this 401 WQC;
  - b. To inspect best management practices (BMPs), monitoring or equipment or methods; and

c. To collect samples or monitor any discharge of pollutants.

Rule: OAR 340-012

Justification: DEQ must inspect facilities for compliance with all state rules and laws.

7) Failure of any person or entity to comply with this Order may result in the issuance of civil penalties or other actions, whether administrative or judicial, to enforce its terms.

Rule: OAR 340-012

Justification: If the project is not being constructed or operated as proposed, it may not be consistent with water quality

requirements.

# FOR PROJECTS THAT PROPOSE CONSTRUCTION, THE FOLLOWING GENERAL **CONDITIONS APPLY**

8) Erosion and Sediment Control: During construction, erosion control measures must be implemented to prevent or control movement of soil into waters of the state. The Applicant is required to develop and implement an effective erosion and sediment control plan. Any project that disturbs more than one acre is required to obtain a National Pollutant Discharge Elimination System (NPDES) 1200-C construction stormwater permit from DEQ. Contact DEQ for more information. Contact information can be found at: https://www.oregon.gov/deg/wg/wgpermits/Pages/Stormwater-Construction.aspx

In addition, the Applicant (or responsible party) must:

- a. Maintain an adequate supply of materials necessary to control erosion at the project construction site.
- b. Prohibit erosion of stockpiles. Deploy compost berms, impervious materials, or other effective methods during rain events or when stockpiles are not moved or reshaped for more than 48 hours.
- c. Inspect erosion control measures daily and maintain erosion control measures as often necessary to ensure the continued effectiveness of measures. Erosion control measures must remain in place until all exposed soil is stabilized;
  - i. If monitoring or inspection shows that the erosion and sediment controls are ineffective, Applicant must mobilize immediately to make repairs, install replacements, or install additional controls as necessary.
  - ii. If sediment has reached 1/3 of the exposed height of a sediment or erosion control, Applicant must remove the sediment to its original contour.
- d. Use removable pads or mats to prevent soil compaction at all construction access points through, and staging areas in, riparian or wetland areas to prevent soil compaction, unless otherwise authorized by DEQ.
- e. Flag or fence off wetlands not specifically authorized to be impacted to protect from disturbance and/or erosion.
- f. Place dredged or other excavated material on upland areas with stable slopes to prevent materials from eroding back into waterways or wetlands.

g. Place clean aggregate at all construction entrances, and utilize other BMPs, including, but not limited to as truck or wheel washes, when earth moving equipment is leaving the site and traveling on paved surfaces. The tracking of sediment off site by vehicles is prohibited.

Rule: OAR 340-041-0007(8), ORS 468B.050, CWA Section 402, OAR 340-045 Justification: DEQ must ensure that pollution does not enter waterways.

9) **Deleterious Waste Materials:** The Applicant is prohibited from placing biologically harmful materials and construction debris where they could enter waters of the state, including wetlands (wetlands are waters of the state). This includes, but is not limited to: petroleum products; chemicals; cement cured less than 24 hours; welding slag and grindings; concrete saw cutting by-products; sandblasted materials; chipped paint; tires; wire; steel posts; asphalt; and waste concrete.

The following specific requirements apply:

- a. Cure concrete, cement, or grout for at least 24 hours before any contact with flowing waters:
- b. Use only clean fill, free of waste and polluted substances;
- c. Employ all practicable controls to prevent discharges of spills of harmful materials to surface or groundwater;
- d. Maintain at the project construction site, and deploy as necessary, an adequate supply of materials needed to contain deleterious materials during a weather event;
- e. Remove all foreign materials, refuse, and waste from the project area

Rule: OAR 340-041-0007(8), ORS 468B.050, CWA Section 402

Justification: DEQ must ensure that pollution does not enter waterways.

10) **Spill Prevention:** The Applicant must fuel, operate, maintain and store vehicles, and must store construction materials, in areas that will not disturb habitat directly or result in potential discharges.

Rule: ORS 468B.025(1)(a)

Justification: DEQ must ensure that pollution does not enter waterways.

### 11) Spill & Incident Reporting:

- a. In the event that deleterious materials are discharged into state waters, or onto land with a potential to enter state waters, the discharge must be promptly reported to the Oregon Emergency Response Service (OERS, 1-800-452-0311). Containment and cleanup must begin immediately and be completed as soon as possible.
- b. If the project operations cause a water quality problem that results in distressed or dying fish, the operator must immediately: cease operations; take appropriate corrective measures to prevent further environmental damage; collect fish specimens and water samples; and notify DEQ, ODFW, NMFS, and US Fish and Wildlife Service (USFW).

Rule: ORS 466.645(1); OAR 340-142-0030(1)(b)(B), OAR 340-041

**Justification:** DEQ must ensure that pollution does not enter waterways and must be protective of beneficial uses, including fish.

## 12) **Vegetation Protection and Site Restoration:**

- a. The Applicant must protect riparian, wetland, and shoreline vegetation in the authorized project area from disturbance through one or more of the following:
  - i. Minimization of project and impact footprint;
  - ii. Designation of staging areas and access points in open, upland areas;
  - iii. Fencing and other barriers demarking construction areas; and
  - iv. Use of alternative equipment (e.g., spider hoe or crane).
- b. If authorized work results in vegetative disturbance and the disturbance has not been accounted for in planned mitigation actions, the Applicant must successfully reestablish vegetation to a degree of function equivalent or better than before the disturbance.
- c. Pesticides (including herbicides) and fertilizers must be applied per manufacturer's instructions by a professionally licensed applicator. If chemical treatment is necessary, the Applicant is responsible for ensuring that pesticide application laws, including with the NPDES System 2300-A general permit, are met. Please review the information on the following website for more information: https://www.oregon.gov/deg/wg/wgpermits/Pages/Pesticide.aspx
  - i. For pesticide application within stormwater treatment facilities or within 150 feet of waters of the state, the Applicant must adopt an Integrated Pest Management (IPM) plan that describes pest prevention, monitoring and control techniques with a focus on prevention of inputs to waters of the state, or coverage under an NPDES permit, if required.
  - ii. Pesticide application should be applied during the dry season and avoid direct water application;
  - iii. Unless otherwise approved in writing by DEQ, applying surface fertilizer within stormwater treatment facilities or within 50 feet of any stream channel is prohibited.

**Rule:** OAR 340-041, OAR 340-012, OAR 340-041-0033

**Justification:** Riparian, wetland, and shoreline vegetation help ensure excess sediment does not enter a waterway, and helps offset potential temperature impacts. DEQ must ensure that pollution does not enter waterways.

Buffers: The Applicant shall avoid and protect from harm, all wetlands and provide a 50 foot buffer to waters of the state, unless proposed, necessary, and approved as part of the project. If a local jurisdiction has a more stringent buffer requirement, that requirement will take the place of this certification requirement.

Rule: OAR 340-041, OAR 340-012

**Justification:** Riparian, wetland, and shoreline buffers help ensure excess sediment does not enter a waterway, and helps offset potential temperature impacts. DEQ must ensure that pollution does not enter waterways.

Previously Contaminated Soil and Groundwater: If any contaminated soil or groundwater is encountered, it must be handled and disposed of in accordance with the soil and groundwater management plan for the site, as well as local, state and federal regulations. The Applicant must notify the Environmental Cleanup Section of DEQ at 1-800-452-4011 Ex.6258.

Rule: OAR 340-041, OAR 340-012, OAR 340-122, OAR 340-040

**Justification:** DEQ must ensure that pollution does not enter waterways. As sediments are disturbed, pollutants could become redistributed.

# FOR PROJECTS THAT PROPOSE IN-STREAM WORK IN JURISDICTIONAL WATERS

Fish protection/ Oregon Department of Fish and Wildlife timing: The Applicant must perform in-water work only within the ODFW preferred time window as specified in the *Oregon Guidelines for Timing of In-Water Work to Protect Fish and Wildlife Resources*, or as authorized otherwise under a USACE permit and/or DSL removal/fill permit. Exceptions to the timing window must be recommended by ODFW, NMFS and/or the USFW as appropriate, and approved by DSL when applicable.

Rule: OAR 340-041-0011

Justification: DEQ must be protective of all water quality standards, including beneficial uses such as fish.

Aquatic life movements: Any activity that may disrupt the movement of aquatic life living in the water body, including those species that normally migrate through the area, is prohibited. The Applicant must provide unobstructed fish passage at all times during any authorized activity, unless otherwise approved in the approved application.

Rule: OAR 340-041-0016; OAR 340-041-0028

Justification: DEQ must be protective of all water quality standards, including beneficial uses such as fish.

17) **Isolation of in-water work areas:** The Applicant must isolate in-water work areas from the active flowing stream, unless otherwise authorized as part of the approved application, or authorized by DEQ.

Rule: OAR 340-041, OAR 340-012, OAR 340-045

Justification: DEQ must ensure that pollution does not enter waterways.

18) **Cessation of Work:** The Applicant must cease project operations under high-flow conditions that will result in inundation of the project area. Only efforts to avoid or minimize turbidity or other resource damage as a result of inundation of the exposed project area are allowed during high-flow conditions.

Rule: OAR 340-041, OAR 340-012

Justification: DEQ must ensure that pollution does not enter waterways.

- 19) **Turbidity**: The Applicant must implement BMPs to minimize turbidity during in-water work. Any activity that causes turbidity to exceed 10% above natural stream turbidities is prohibited except as specifically provided below:
  - a. **Monitoring**: Turbidity monitoring must be conducted and recorded as described below. Monitoring must occur at two-hour intervals each day when in-water work is being conducted. A properly calibrated turbidimeter is required **unless another monitoring method is proposed and authorized by DEQ.** 
    - i. Representative Background Point: The Applicant must take and record a turbidity measurement every two hours during in-water work at an undisturbed area. A background location shall be established at a representative location approximately 100 feet up-current of the in water activity unless otherwise authorized by DEQ. The background turbidity, location, date, tidal stage (if applicable) and time must be recorded immediately prior to monitoring down-current at the compliance point described below.
    - ii. <u>Compliance Point</u>: The Applicant must monitor every two hours. A compliance location shall be established at a representative location approximately 100 feet down-current from the disturbance at approximately mid-depth of the waterbody

and within any visible plume. The turbidity, location, date, tidal stage (if applicable) and time must be recorded for each measurement.

b. **Compliance**: The Applicant must compare turbidity monitoring results from the compliance points to the representative background levels taken during each two – hour monitoring interval. Pursuant to OAR 340-041-0036, short term exceedances are allowed as followed:

MONITORING WITH A TURBIDIMETER EVERY 2 HOURS			
TURBIDITY LEVEL	Restrictions to Duration of Activity		
0 to 4 NTU above background	No Restrictions		
5 to 29 NTU above background	Work may continue maximum of 4 hours. If turbidity remains 5-29 NTU above background, stop work and modify BMPs. Work may resume when NTU is 0-4 above background.		
30 to 49 NTU above background	Work may continue maximum of 2 hours. If turbidity remains 30-49 NTU above background, stop work and modify BMPs. Work may resume when NTU is 0-4 above background.		
50 NTU or more above background	Stop work immediately and inform DEQ		

### c. Reporting:

- Record all turbidity monitoring required by subsections (a) and (b) above in daily logs which must include: calibration documentation; background NTUs; compliance point NTUs; comparison of the points in NTUs; and location; date; time; and tidal stage (if applicable) for each reading.
- ii. A narrative must be prepared discussing all exceedances with subsequent monitoring, actions taken, and the effectiveness of the actions. Applicant must make available copies of daily logs for turbidity monitoring to regulatory agencies including DEQ, USACE, NMFS, USFWS, and ODFW upon request.
- iii. Keep records on file for the duration of the permit cycle.
- d. **BMPs to Minimize In-stream Turbidity:** The Applicant must implement the following BMPs, unless accepted in writing by DEQ:
  - i. Sequence/Phasing of work The Applicant must schedule work activities so as to minimize in-water disturbance and duration of in-water disturbances.
  - ii. Bucket control All in-stream digging passes by excavation machinery and placement of fill in-stream using a bucket must be completed so as to minimize turbidity. All practicable techniques such as employing an experienced equipment operator, not dumping partial or full buckets of material back into the wetted stream, adjusting the volume, speed, or both of the load, or using a closed-lipped environmental bucket must be implemented;

- iii. The Applicant must limit the number and location of stream-crossing events. Establish temporary crossing sites as necessary at the least sensitive areas and amend these crossing sites with clean gravel or other temporary methods as appropriate;
- iv. Machinery may not be driven into the flowing channel, unless authorized in writing by DEQ; and
- Excavated material must be placed so that it is isolated from the water edge or wetlands, and not placed where it could re-enter waters of the state uncontrolled.
- vi. Containment measures such as silt curtains, geotextile fabric, and silt fences must be in place and properly maintained in order to minimize in-stream sediment suspension and resulting turbidity.

Rule: OAR 340-041-0036, OAR 340-041

Justification: DEQ must ensure that pollution does not enter waterways.

# SPECIFIC CONDITIONS FOR POST-CONSTRUCTION STORMWATER MANAGEMENT

Post Construction Stormwater Management: For projects which propose new impervious surfaces or the redevelopment of existing surfaces, the Applicant must submit a post-construction stormwater management plan to DEQ. The plan must be reviewed and approved prior to construction to ensure compliance with water quality standards. The Applicant must implement BMPs as proposed in the stormwater management plan, including operation and maintenance. If proposed stormwater facilities change due to site conditions, the Applicant must notify DEQ in writing.

In lieu of a complete stormwater management plan, the Applicant may submit documentation of acceptance of the stormwater into a DEQ permitted NPDES Phase I Municipal Separate Storm Sewer System (MS4).

Rule: ORS 468B.050, OAR 340-045, OAR 340-041

Justification: DEQ must ensure that pollution does not enter waterways.

21) **Stormwater Management & System Maintenance:** The Applicant is required to implement effective operation and maintenance practices for the lifetime of the proposed facility. Long-term operation and maintenance of stormwater treatment facilities will be the responsibility of the applicant or the entity listed in the approved post-construction stormwater management plan.

Maintenance of stormwater treatment facilities subject to an MS4 permit is regulated by the permit.

Rule: OAR 340-041, OAR 340-012, OAR 340-045

Justification: DEQ must ensure that pollution does not enter waterways.

22) **Corrective Action May Be Required:** DEQ retains the authority to require corrective action in the event the stormwater management facilities are not built or performing as described in the plan.

Rule: OAR 340-041, OAR 340-012

**Justification:** DEQ must ensure that pollution does not enter waterways.

### **CATEGORY SPECIFIC CONDITIONS**

In addition to all national and regional conditions of the USACE permit and the 401 Water Quality Certification general conditions above, the following conditions apply to the noted specific categories of authorized activities.

### NWP 42 - Recreational Facilities:

42.1) For facilities that include turf maintenance actions, the permittee must develop and implement an Integrated Pest Management Plan (IPM) that describes pest prevention, monitoring and control techniques with a focus on prevention of chemical and nutrient inputs to waters of the state, including maintenance of adequate buffers for pesticide application near salmonid streams, or coverage under an NPDES permit, if required (information is available at: <a href="http://www.oregon.gov/deg/wg/wgpermits/Pages/Pesticide.aspx">http://www.oregon.gov/deg/wg/wgpermits/Pages/Pesticide.aspx</a>).

Rule: OAR 340-041-0033, OAR 340-041

Justification: DEQ must ensure that pollution does not enter waterways, including excess pesticides and fertilizers.

### **NWP 43 – Stormwater Management Facilities:**

- 43.1) Projects that propose the following elements are denied expedited certification:
  - a. In-stream stormwater facilities:
  - b. Discharge outfalls not subject to an MS4 NPDES permit; and,
  - c. Proposals that do not demonstrate pollutant removal to meet water quality standards prior to discharge to waters of the state.

Rule: OAR 340-041, OAR 340-012, OAR 340-048

Justification: DEQ must ensure that pollution does not enter waterways; stormwater is considered a pollutant.

43.2) To apply for certification for a project with in-stream stormwater facilities, without an NPDES permit, or without submittal of an approvable stormwater management plan per DEQ's Guidelines (at: <a href="http://www.oregon.gov/deq/FilterDocs/401wqcertPostCon.pdf">http://www.oregon.gov/deq/FilterDocs/401wqcertPostCon.pdf</a>), the Applicant must submit complete project information and water quality impacts analysis directly to DEQ in order to undergo individual 401 WQC evaluation and fulfill public participation requirements.

\*\*Rule: OAR 340-041-0059\*\*

Justification: DEQ must ensure that pollution does not enter waterways; stormwater is considered a pollutant.

### NWP 44 – Mining Activities:

44.1) Projects that do not obtain an NPDES 700-PM or Individual permit are denied expedited certification.

Rule: OAR 340-045-0033, OAR 340-041

**Justification:** DEQ must ensure that pollution does not enter waterways. Excess turbidity can be considered pollution.

44.2) To apply for certification for a project without an NPDES permit, the Applicant must submit complete project information and water quality impacts analysis directly to DEQ in order to undergo individual 401 WQC evaluation and fulfill public participation requirements.

**Rule:** OAR 340-041-0059

Justification: DEQ must ensure that pollution does not enter waterways.

44.3) The State of Oregon requires an In-Water Blasting Permit be obtained per OAR, 635-425-0000. Permittee is advised to contact the nearest ODFW office for further information at: <a href="https://www.dfw.state.or.us/lands/inwater/">https://www.dfw.state.or.us/lands/inwater/</a>

Rule: OAR 340-041-0011

Justification: DEQ must be protective of all water quality standards, including beneficial uses such as fish.

## **NWP 51 – Land-Based Renewable Energy Generation Facilities:**

51.1) For associated utility lines with directionally-bored stream or wetland crossings proposed, condition D.1 must be applied.

Rule: OAR 340-041, OAR 340-012, OAR 340-048

Justification: DEQ must ensure that pollution does not enter waterways.

### NWP 58 – Utility Lines:

- 58.1) For proposals that include directionally-bored stream or wetland crossings:
  - a. All drilling equipment, drill recovery and recycling pits, and any waste or spoil produced, must be completely isolated, recovered, then recycled or disposed of to prevent entry into waters of the state. Recycling using a tank instead of drill recovery/recycling pits is preferable;
  - b. In the event that drilling fluids enter a water of the state, the equipment operator must stop work, immediately initiate containment measures and report the spill to the Oregon Emergency Response System (OERS) at 1-800-452-0311.
  - c. An adequate supply of materials needed to control erosion and to contain drilling fluids must be maintained at the project construction site and deployed as necessary.
  - d. The Applicant must have a contingency plan in place prior to construction for the inadvertent return of drilling lubricant.

Rule: OAR 340-142-0030, OAR 340-142-0040(1)

Justification: Drilling equipment and fluids that enter a waterbody would likely cause contamination of that waterbody.

58.2) For proposals that include utility lines through wetlands, include anti-seep collars or equivalent technology to prevent draining the wetlands.

Rule: OAR 340-041, OAR 340-012, OAR 340-048

Justification: DEQ must ensure that pollution does not enter waterways.

If the Applicant is dissatisfied with the conditions contained in this certification, a hearing may be requested. Such request must be made in writing to DEQ's Office of Compliance and Enforcement at 700 NE Multnomah St, Suite 600, Portland Oregon 97232, within 20 days of the mailing of this certification.

The DEQ hereby certifies that this project complies with the Clean Water Act and state rules, with the above conditions. If you have any questions, please contact Haley Teach at 503-229-5051, by email at <a href="mailto:Haley.Teach@deq.state.or.us">Haley.Teach@deq.state.or.us</a>, or at the address on this letterhead.

Sincerely,

Steve Mrazik, Water Quality Manager Northwest Region

ec:

, USACE , DSL , NOAA

Deanna Caracciolo, DLCD (If project is in coastal zone)



# **INSERT TAB**

# Unit 3 Roadside Development

# Right of Way Development and Control

**Environmental Inspector** 



ODOT Flickr im



1

# Right of Way Development is unlike Construction

- Materials are perishable, living things.
- Site preparation healthy soil
- Healthy seeds
- Mulch
- Seed establishment



2

# Section 01000 – Right of Way Development and Control

# ■ 01030.00 Scope

This work consists of **seeding and associated tasks** to develop plant growth for **erosion control**, environmental mitigation and Roadside Development.

# ■ 01040.00 Scope

This work consists of planting but has sections that pertain to seeding too! (i.e., soil conditioners, amendments, bio-amendments, soil testing, topsoil and Wetland soil)



3

# Section 01030 - Seeding

### 01030.02 Definitions

- Certified Seed commercially available, named varieties of seeds; certified by OSU Seed Certification Service, will have a blue tag. Native plants are not usually certified.
- Pure Live Seed (PLS) The amount of viable seed in the total quantity of seed



# Section 01030 - Seeding

## 01030.02 Definitions

Noxious Weed – identified by ODA as harmful or a threat to economy and ecology of the state;

- Type A Of economic importance, with infestations small enough to eradicate or contain
- Type B Of economic importance, with regional abundance but may have limited distribution

Weed Management Area – identified on Plans, usually noxious weeds present



5

# **Noxious Weeds**



Type A: Giant Hogweed /
Heracleum mantagazzianum
(Sap can cause burning, blisters
& long lasting scars)



Type B: Butterfly Bush /





### Soil

Soil quality affects both seeding (01030) and planting (01040).

Specifications discuss soil in one location – Section 01040

- 01030.11 Topsoil Refer to 01040.14
- 01030.12 Soil Modifiers Refer to 01040.16, 01040.17
   & 01040.18
- 01030.45 Soil Testing Refer to 01040.13



7

- Soils defined in Section 01040.14
- Healthy soil includes mineral material, organic matter including soil biology and pore space





## **Soil Biology**




Many varieties of Nematodes exist Bacteria, Fungi, Protozoa, Nematodes, Arthropods and Earthworms decompose organic materials, sequester carbon, take nitrogen from the air & fix it to the soil. These micro-critters, enhance soil aggregation and porosity, prey on crop pests and are food for above-ground animals

a

## 01040.17 Soil Biology - Mycorrhizal Fungi

- Symbiotic relationship: Mycorrhizae take inexpensive sugars from host plant and help uptake water and nutrients from soil that would otherwise be unavailable.
- Mycorrhizae release chemicals into the soil that unbind nutrients from soil
- Microscopic filaments of Mycorrhizal hyphae (roots) may comprise several miles per cubic inch.
- Soil Bio-Amendments discussed in Section 01040.17





Mycorrhizal fungi on roots

11

### 01040: Materials - Soil

- 01040.13 Soil Testing and Amendment Report
   For soil fertility by a qualified testing lab. Should identify amendments, bio-amendments and fertilizer needed in a report.
- 01040.14 Topsoil
   3 types (plus water quality mixture identified in Sections 01012, 01011 & 01014)
- 01040.15-.17 Soil Conditioners, Amendments and Bio-Amendment

Conditioners modify soil structure; amendments improve soil nutrition; fertilizers increase availability of specific elements necessary for plant growth, Bio-Amendments introduce soil biology into the soil.



# Roadside soils are frequently poor quality:

Stripped of topsoil layer or compacted mineral soil with little pore space or soil biology

## Retain existing vegetation wherever possible!

Section
01040.48
describes site
preparation
required for
seeding





13


# Section 01030 - Seeding


01030.13 Seed – Labels, Quality, Pure Live Seed, Inspection, Mixes

#### Look for:

- Compliance with Oregon and Federal Seed Regs
- Testing date Within 18 months of planting
- Not sprouted, moldy, wet or damaged







16

# Calculation of Amount of Seed (lbs / ac)

Specified Seeding Rate = <u>10 PLS / Ac</u>

Actual Seeding Rate = 10 PLS / AC
Seed Purity 80% x Germination 90%

 $(0.80 \times 0.90 = 0.72)$ 

Actual Seeding Rate = <u>10</u> 0.72

Actual Seeding Rate = 13.88 pounds per acre



17

# Verify seed sack contains project specified seeds (01030.13)



MATERIALS & INSPECTION

#### Fertilizer 01030.14

- Type and quantity based upon Soil Testing and Amendment Report
- Not typically used on Wetland Mitigation sites or water quality plantings
- Use slow-release types when fertilizers are used
- Use low phosphorus types near water bodies when used
- Stockpiled (select) topsoil, compost and/or mycorrhizae can reduce the need for fertilizer and improve overall soil quality



19

### **Fertilizer**

- Labeled to document content of Nitrogen (N), Phosphorus (P) and Potassium (K)
- Always listed in order (N-P-K)


Example: a 5-10-5 fertilizer =

5% by weight nitrogen

10% by weight phosphorus

5% by weight potassium






# 01030.15 - Mulch for seeding

- Hydro-mulch Wood pulp, BFM or High Performance Growth Media (usually include tackifier & color tracer)
- Straw Use only certified weed free straw
- Compost See Erosion Control 00280.14(f) for Compost Blanket. Provide additional tackifier with compost blanket.





# **Materials Specifications**

- 01030.16 Tackifier
   Liquid or dry powder. Plant based (Guar or Plantain) or chemical (Polyacrylamide)
- 01030.17 Pesticides
   Contractor must get approval for use of pesticides before using.



### Construction

- 01030.40 General Retain all existing desirable vegetation!
  - · Notify Agency 24 hours prior to seeding
  - No seeding in adverse weather



25

## **Site Preparation**

01030.41 - References 01040.48

- 5 site prep methods for 8 seeding types
- Seeding areas are made weed free
- Stockpile selected topsoils as briefly as possible.
- Loosen subsoils, roughen cut slopes, texture fill slopes
- Haul and spread selected topsoils without compacting.

01030.42 – Weed Control Plan (WCP)

- Where specified WCP can be part of Planting Work Plan (PWP)
- Weed control inspections: Frequencies listed
- Weed Removal: Work and required documentation
- Applicable when included in Schedule list of items



### 01030.43 - Seeding

- a) Temporary (used for erosion control 00280)
- b) Permanent Seeding (defined in Specials)(permanent seeding can be used for erosion control)
- West of the Cascades
   (March 1 May 15 & September 1 October 31)

   Extra time for irrigated areas
- East of the Cascades
   (October 1 February 1) Unless in irrigated areas.
- Wetland (East and West)
   (September 1 October 31 & March 1 April 30)



27

# Seeding Timing – 01030.43

- Apply temporary seeding to stabilize disturbed soils and slopes that will be exposed for 2 months or longer. Do not count solely on temporary seeding for immediate erosion control!
- Apply permanent seeding on areas to be left dormant for 1 year or more.
- 3 weeks to achieve required coverage







30



## **Establishment**

## 01030.60 General, 01030.61 Establishment

- Temporary Seeding: min 70% cover no timeframe
- Permanent Seeding: min 90% cover either 45 days after seeding, or no timeframe for erosion control
- East of the Cascades 30% cover
- Water Quality Seeding 100% cover



# Construction 01040.43 & 01040.44 – Soils

#### 01040.43 Topsoil

- Excavate and install or stockpile < 28 days.</li>
- Prepare subsoil eliminate compaction
- Haul, spread and finish grade and cleanup.

#### 01040.44 Select Wetland Topsoil

- Excavate first, then place selected wetland topsoils directly to site. Or stockpile < 28 days.</li>
- Sub-excavate to grade, seek Agency approval.
- Haul, spread carefully, seek Agency approval.




33

## 01040.48 Area Preparation

Incorporate soil amendments (01040.45), soil bioamendments (01040.46), fertilizers (01040.47) as recommended by soil test results.







# **Measurement & Payment**

## 01030.80, .90 Seeding

- Unit, Area Basis (mulch is measured by area basis)
- Partial Payments: 70% at seeding, 30% at completion

Your roadsides are now seeded!



## 03020 Compost

- Many applications in Erosion Control, Soil Conditioning, and Mulching.
- Watch for appropriate particle sizes, debris bits and state of decomposition of organics.
- Certified at the source, not by the load.
- Check Lab results for analysis




37

### Communication

- Pre-Construction Conference the best opportunity to answer questions before they become issues. Bring forward Roadside priorities.
- Professional of Record (POR) on-call to Resident Engineer / Inspector if issues arise. Must be kept apprised of contract change orders.
- Regular Inspections and Enforcement of Contract Documents are Key to Success!
- Post-Construction Conference / Resident Engineer narrative – the best opportunity for learning how to improve next time. Include POR.



SEEDING							
Due Section What							
precon	01030.30(a)	Certification that weed control coordinator meets requirements of 01030.30(a)					
precon	01030.42(a)	Weed control work plan					
within 60 days of execution of contract	01030.13(g)	List of seed sources for all specified seeds. Verify that all specified seed has been located and will be available.					
before using	01030.17	Submit proposed pesticides and receive approval. Submit a copy of manufacturers federal registered label. If requested, submit MSDS sheet.					
before using	01030.30(b)	Certification that pesticide applicator possesses an Oregon Commercial Pesticide Applicators License (each individual applicator who will be performing work)					



### **Plant Establishment**

### 01040.72 Periodic Inspections

- Typically, 3 inspections: Spring, Summer and Fall.
   Inspectors go with Contractor on inspections
- Inspector will provide Contractor with list of corrective work

#### 01040.73 Corrective Work

 Contractor is required to replace dead plants 15 days after receiving list of corrective work.



41

#### Floodplain Planting using contract grown native wetland sod



Much of ODOT's plantings are required as permit conditions. If success is not achieved during the Project, ODOT pays until success is achieved – Failure is not an option.

## **Presenter Information**

## **Bob Marshall**

Roadside Development and Erosion Control Program Leader

(503) 986-3512

robert.r.marshall@odot.oregon.gov



43



# Premixed Seed Blends Adjusted Rates of Application

Form Example

Project Name (Section)

Enter Contractor or Subcontractor Name

(Sub)Contractor

Seed Mix Type

Contract No.

L03/SL1

Lot/Batch No.

COLUMN

I	II	III	IV	V		VI	VII	VIII
Seed	Specified (lb./acre)	Purity %	Germ. %	Adjusted PLS (lb. per acre)		% of Seed (this lot#/mix)	lb. of Seed per 1 lb (this lot#/mix)	lb. of this Seed Blend Needed per Acre (this lot#/mix)
Spike Bentgrass	0.5	99.66%	90.00%	0.6	0.6	1.50%	0.015	40.0
California Brome	24.5	98.83%	88.00%	28.2	##	27.00%	0.270	104.4
Camas Grass	3.5	97.75%	88.00%	4.1	4.1	3.50%	0.035	117.1
Slough Sledge	3.5	99.69%	91.00%	3.9	3.9	3.50%	0.035	111.4
Tufted Hairgrass	1.8	99.07%	91.00%	1.9	1.9	5.00%	0.050	38.0
Meadow Barley	37.0	95.18%	93.00%	41.8	##	38.00%	0.380	110.0
Path Rush	0.1	97.32%	98.00%	0.1	0.1	0.50%	0.005	20.0
Sickle Keeled Lupine	17.5	99.95%	90.00%	19.5	##	19.00%	0.190	102.6
					##			
					##			
					##			
					##			
					##			
					##			
					##			
					##			
					##			
					##			
					##			
					##			

RESULTS	
Greatest Amount Calc. (from column VIII) =	117.1
Premeasured Acre =	1.9
Greatest Amount Calc. x Premeasured Acre =	222.6

Seed %	98.00%
Other Crop Seed %	1.40%
Weed Seed %	0.55%
Inert Material %	0.05%
Total %*	100.00%

<sup>\*</sup>should be close to 100%

## **INSERT TAB**

Unit 4
Construction

# **Construction Resources**



1

# **Learning Objectives Review**

- Understand ODOT Specifications and 1200-CA Permit
- Implement Erosion and Sediment Control Plan (ESCP) to comply with Standard Specifications, 1200-CA Permit and Contract requirements
- Identify Best Management Practices (BMPs)
- Recognize when BMPs are not being effective and upgrade and document changes in ESCP to comply with contract requirements



2

OREGON STANDARD

SPECIFICATIONS FOR CONSTRUCTION

2024


<u>APWA</u>

## **Standard Specifications**

- 00100.00's
  - Order of Precedence and before On-site Work can begin
- 00280.00's
  - Erosion Control
- 290.00's
  - Environmental Protection
- 01030.00's
  - Seeding



2



4

# Standard Specifications – 100.00's 00150.10(a) – Order of Precedence

Contract Change Orders

Special Provisions

Project Plans

Reviewed Stamped Working Drawings

3D Engineered Models

Standard Drawings

Approved Unstamped Working Drawings

Supplemental Specifications

Standard Specifications

All other contract documents not listed above.

5

## Standard Specifications - 100.00's

# 00180.40 Limitation of Operations: (b) On-Site Work:

The contractor shall not begin on-site work until the Contractor has:

- Received a Notice to Proceed
- An accepted Project Work schedule
- An approved Erosion and Sediment Control Plan
- An approved Pollution Control Plan
- Met with the Agency at the required preconstruction conference



6

# Standard Specifications – 290.00's Pollution Control Plan

#### 00290.00 scope

- All penalties assessed against the Agency because of the Contractor's violation of Laws referenced above, or permits applicable to the Project, will be withheld from the progress or final payments according to 00195.50(e).
- No condition of the Contract releases the Contractor from any responsibility or requirement under any environmental or other Law.



7

# Standard Specifications – 290.00's Pollution Control Plan

00290.30(b)

**(b) Pollution Control Plan** - Develop a PCP using ODOT Form 734-2445 and submit it for approval at least **10 Calendar Days before the preconstruction conference.** Maintain a copy of the PCP on-site at all times during construction activities, readily available to employees and Inspectors. Ensure that all employees comply with the provisions of the PCP.



8

# Standard Specifications – 290.00's Pollution Control Plan

#### 00290.30(a)(1) - General

- Allow no pollutant of any kind (e.g., petroleum products or fresh "green" concrete) to come in contact with an active flowing stream or waters of the State and U.S.
- Comply with the erosion prevention and sediment control requirements of Section 00280 and all applicable DEQ NPDES 1200 Permit requirements.
- Do not cause turbidity to waters of the State and U.S. outside of regulated levels.




Q

# **Special Provisions**

Check for language that replaces, adds, and/or eliminates Standard Specification language.

The Agency's NPDES 1200-CA Permit applying to this project is an example of added language:



#### **SECTION 00280 - EROSION AND SEDIMENT CONTROL**

Comply with Section 00280 of the Standard Specifications modified as follows: **00280.00 Scope** – Add the following paragraph to the end of this subsection: The Agency's NPDES 1200-CA Permit is applicable to the Project.



10



The special provisions is where you will find the criteria for **Metered Turbidity Monitoring** and the list of **Emergency Materials per 280.48**.



00280.48 Emergency Materials - Add the following paragraphs after the paragraph that begins "Provide, stockpile, and protect...":

Provide and stockpile the following emergency Materials on the Project site:



11

# **Special Provisions (continued)**

Example of added language:

00280.16(a) Construction Entrances - Add the following paragraphs to the beginning of this subsection:

Provide construction entrances, Type 1.

With prior approval from the Engineer, the Contractor may use prefabricated construction entrances.

Example of added non-standard specification:

**SECTION 00294 - CONTAMINATED MEDIA** 

Section 00294, which is not a Standard Specification, is included in this Project by Special Provision.



12

## 01030.13 Seed - Special Provision

Use the PLS specified rate listed in 01030.13(f) for determining PLS application rates. Ensure the PLS application rate meets the PLS specified rate. Apply pre blended seed mixes, with multiple species, at a PLS application rate ensuring all species meet or exceed the PLS specified rate for each species in the seed mix.



13

## 01030.13 Seed - Special Provision

- PLS application rate for an individual seed species is determined as follows:
  - PLS specified rate is listed in 01030.13(f)
  - PLS factor is obtained by multiplying the seed label germination percentage times the seed label purity percentage. Use the purity and germination percentages from the label on actual bags of seed to be used on the Project.
  - PLS application rate is obtained by dividing the PLS specified rate by the PLS factor.



14

## 01030.13 Seed – Special Provision

- For a seed mix, make this calculation for each seed species in the mix and then adjust as follows:
  - Using the seed tag, determine the weight of each seed species in the bag and use this information to find the percentage, by weight, of each seed species is in 1 pound for the pre-blended mix.
  - Divide the percentage by weight of each seed species, per pound, for the pre-blended mix, by the PLS application rate for that specific seed species.

Determine the highest application rate in the seed mix and apply the seed mix at that application rate.



15

# **Special Provisions (continued)**

The Standard Specifications might refer to the Special Provisions for project specific information:

Standard Specification 01030.13(f)

(f) Types of Seed Mixes - Seed mixes, quantities, standards, seeding rates, and other information will be included in the Special Provisions for each type of seed mix.

Special Provisions 01030.13(f) page 212/278

01030.13(f) Types of Seed Mixes - Add the following to the end of this subsection:


Provide the following seed mix formulas:

Temporary Seeding:

Botanical Name (Common Name)	PLS Specified Rate (lb/acre)
Triticum aestivum x elytrigia elonga	ata 36.0
(Sterile wheat nurse crop) Poa secunda (Sandberg Bluegrass)	3.0
Hordeum brachyantherum	26.0
(Meadow Barley) Bromus Carinatus	24.0
(California Brome) Festuca roemeri var. roemeri	5.0
(Roemer's Fescue) Trifolium repens (White Clover)	3.0




16




17


opoolal i i	Ονι	sions (conti	nued	)				
Bid item List	SCHEDULE OF ITEMS  1-5: AURORA DONALD INTERCHANGE (EXIT 278) PHASE 2 (C15498)  HP CIVIL INC							
	ITEM NO	ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE (IN FIGURES)	TOTAL (IN FIGURES)		
	0600	0290-0102000A WORK CONTAINMENT PLAN	LUMP SUM	ALL	500.00	500.00		
	0610	0290-0200000A TURBIDITY MONITORING	LUMP SUM	ALL	2,500.00	2,500.00		
	0620	0294-0100000A HEALTH AND SAFETY PLAN	LUMP SUM	ALL	1,500.00	1,500.00		
	0630	0294-0200010M CONTAMINATED SOIL DISPOSAL	TON	12,952.00	40.00	518,080.00		
	0640	0294-0700000E SOIL SAMPLE COLLECTION AND ANALYTICAL TESTING	EACH	3.00	4,500.00	13,500.00		
	0650	1999-9Z90000J CONSTRUCTION MATS	SQFT	4,500.00	10.00	45,000.00		
	SECT	ION 0002 ROADWORK						
	0660	0305-0100000A CONSTRUCTION SURVEY WORK	LUMP SUM	ALL	500,000.00	500,000.00		
MATERIALS & INSPECTION	0670	0310-0106000A REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LUMP SUM	ALL	375,000.00	375,000.00		


18






20





22



23

<u>Category</u> <u>Sub Category</u> <u>Erosion Prevention Materials</u>	Section
Erosion Prevention Materials	<u>occion</u>
Erosion Prevention Materials	
Matting – Slope Type A - Slopes 1V:3H or flatter - Clay Soll Type B - Slopes 1V:3H or flatter - Sandy Soll Type C - Slopes steeper than 1V:3H - Clay Soll Type D - Slopes steeper than 1V:3H - Sandy Soll	00280.14e
Matting – Flexible Channel Liner         Type E-Shear Stress Range         2 lbs/ft²           Type F-Shear Stress Range         4 lbs/ft²           Type G-Shear Stress Range         6 lbs/ft²           Type H-Shear Stress Range         8 lbs/ft²	
Runoff Control Materials	
Check Dam Type 5 – Prefabricated System	00280.15a
Compost Filter Sock Filter Sock Material	00280.15f (1)
Sediment Control Materials	
Inlet Protection Type 3 – Prefabricated Filter Inserts	00280.16d
Sediment Barrier	

24

			ODOT CONSTRUCTION / MATERIALS SECTION QUALIFIED PRODUCTS LIST APPROVED LIST - NO SAMPLES OR TESTS REQUIRED' QUALIFIED LIST - ADDITIONAL REQUIREMENTS** JANUARY 2024				Page 37		
STANDARD SPEC#	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS		
00280.14E	MATTING - TYPE A SLOPE	EROSION CONTROL BLANKET SC 32 BO	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/13/15	4940	A			
00280.14E	MATTING - TYPE A SLOPE	EROSION CONTROL BLANKET S 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4845	A			
00280.14E	MATTING - TYPE A SLOPE	EXCEL CS-3 ALL NATURAL	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3397	A	70% WHEAT STRAW & 30% COCONUT. WITH JUTE SCRIM		
00280.14E	MATTING - TYPE A SLOPE	FLEXTERRA HP-FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-6462 ACF WEST 803/878-5115	02/10/11	4205	A	FLEXIBLE GROWTH MEDIUM HYDRAULCALLY APPLIED. RECYCLED THERMALLY REFINED WOOD FIBERS.		
00280.14E	MATTING - TYPE A SLOPE	FUSION	LSC ENVIRONMENTAL PRODUCTS 800/900-7671 HANES GEOCOMPONENTS 800/426-4976	06/19/19	5199	A	HYDRO, APPLIED, GAR, PAM STABILIZER SOIL BIO-AMENDMENTS		
00280.14E	MATTING - TYPE A SLOPE	GEOLUTE	BELTON INDUSTRIES 800/225-4099 BOB MORAN ACF WEST 800/878-5115	10/11/01	2490	A	WOVEN JUTE. BIODEGRADEABLE.		
00280.14E	MATTING - TYPE A SLOPE	HYDRA CX2	NORTH AMERICAN GREEN 800/772-2040	05/14/09	3532	A			
00280.14E	MATTING - TYPE A SLOPE	HYDROSTRAW BONDED FIBER MATRIX	HYDROSTRAW 800/545-1755 ED LEE	11/11/10	4164	A			
00280.14E	MATTING - TYPE A SLOPE	KANSAS EROSION KEP-C100 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	6367	A	BIODEGRADABLE COIR & JUTE NETTING		

25

### **NFTMG**

OREGON DEPARTMENT OF TRANSPORTATION CONSTRUCTION SECTION

#### NONFIELD-TESTED MATERIALS ACCEPTANCE GUIDE

2024 STANDARD SPECIFICATIONS

January 2024 UPDATE




Updated versions of this guide are available by printing from the web address listed below. This document is to be used as a guide for documentation required for acceptance of Materials on ODOT Construction projects and does not relieve the user of requirements specified in the Construction Project Documents. Please notify the Contract Administration Unit, in the Construction Section at the ODOT Materials Laboratory, of any changes in Standard Drawings, Special Provisions, or Standard Specifications, etc., which would require additions to, deletions from, or changes to this listing.

 $Internet\ Address: \underline{https://www.oregon.gov/ODOT/Construction/Pages/Structure-Services.aspx}$ 

Contact 541-784-7721 to have correction made to this guide. A summary of changes since last publication is found at the end of this document.

\*Special Provisions, Contract Plans, and Standard Specifications take precedence over this guide per 00150.10(a). Refer to the Contract for documentation requirements.

26



27

# **NFTMG** (continued) F. QPL QPL" is for hyd 00280.14(e) I" is seed lab test results for weed seed or I" is STA lab analysis of compost T, Q, P/R "Q" is from Supplier according to 03020.10 and 00165.35 P/R" is copy of the DEQ permit or registration of cor 00280.16(d) F. OPL Sediment Barrier – Cereal Straw 00280.16(e) F. OPL Sediment Barriers, Sediment Mat Straw Bales " must document visual verification 00280.16(a)

28

#### **INSERT TAB**

QPL

# OREGON DEPARTMENT OF TRANSPORTATION CONSTRUCTION SECTION

#### QUALIFIED PRODUCTS LIST

PUBLISHING DATE: JANUARY 2024



The Qualified Products List is updated every six months or amended as needed.

#### QUALIFIED PRODUCTS LIST OREGON DEPARTMENT OF TRANSPORTATION

The "QUALIFIED PRODUCTS LIST" (QPL) is a comprehensive list of all finished products which have been evaluated and/or used by the Oregon DOT.

The "QUALIFIED PRODUCTS LIST" is made up of two types of lists:

- 1. The **QUALIFIED LIST** "Q" is for products that have been reviewed and found to be suitable for use in a specific category. <u>Job control testing may still be necessary</u>. Consult the <u>ODOT Nonfield-Tested Materials Acceptance Guide</u>", the "ODOT Field-Tested Materials Acceptance Guide", and the Project Specifications. Certificate of materials origin might be required.
- 2. The **APPROVED LIST "A"** is for commercially available products having a low consequence of failure. These products are only usable for appropriate applications. May Require a Field Inspection Report. State existence on the Approved List and recognition of the product. No additional sampling or testing is needed.

Specific questions regarding products on the un-published **CONDITIONAL LIST** can be answered by calling **503/986-3059**.

"Conditionally Approved" products need specific, prior approval for each project. Approval is given for one project at a time.

The use of all products is restricted to the category in which they are listed. Products should be used and installed as the manufacturer recommends. The QPL does not distinguish between domestic and foreign steel. Use of this list by **ODOT Maintenance** Personnel as an *information resource* is encouraged not required.

Note: Any change to a product on the QPL, without prior approval, will be cause for rejection of the product.

<u>Description</u>	<u> Page #</u>
Index by Category, for Spec #Traffic Control Devices	
Erosion Control Devices Pavement Markings	V - VI
Qualified & Approved Listby Spec Number	
Reinforcing Steel	A1-A15

The "QPL" and submittal forms are accessible from the Internet:

#### **Qualified Products Web Page**

Although the products listed are approved for use, they are not exempt from State Purchasing Rules, practices and guidelines, or manufacturer's warrantees or guarantees.

If you have questions, contact:

Oregon Department of Transportation 800 Airport Rd SE, Salem, OR 97301-4798 Dean Chess, Phone: 503/986-3059

E-Mail: dean.m.chess@odot.oregon.gov



#### OREGON DEPARTMENT OF TRANSPORTATION

"QPL" INDEX BY CATEGORY TO GET SPECIFICATION NUMBERS

PAGE I

CATEGORY	SPEC#
ANTI-GRAFFITI COATING - SIGNS	02910.70
ASPHALT COLD PATCH - HI PERF	00745.00
ASPHALT RELEASE AGENT	00745.22
AUTOMATED FLAGGER ASSIST. DEVICE	00223.23
BACKER ROD	02440.14
BARRICADE, TEMPORARY	00224.15
BARRIER PANELS, REFLECTIVE	00226.11B
BARRIER, CABLE	00811.00
BEARINGS, BRIDGE	00582.10
BICYCLE CHANNELIZING DEVICES	00228.12
BIRD SPIKES	00907.10
BOLT GRADE ADJUSTMENT SYSTEM	00470.42
BONDING AGENT, EPOXY	02070.10
BONDING AGENT, NON-EPOXY	02070.20
CEMENT, BLENDED	02010.20
CEMENT, PORTLAND	02010.10
CEMENTITIOUS PIPE LINER	00414.10
CFRP STRENGTHENING WET LAY UP	00565.00
CHEMICAL ADMIXTURES	02040.10
CHLORIDE REMOVER	00594.13
CONCRETE & CRACK SEALER HIGH MOD	. 02060.20
CONCRETE & CRACK SEALER LOW MOD.	02060.10

CATEGORY	SPEC#
CONCRETE BARRIER GATE	00820.00
CONCRETE MODIFIER - LATEX	02035.00
CONCRETE SCM - BLENDED	02030.60
CONCRETE SCM - FLY ASH	02030.10
CONCRETE SCM - GGBF SLAG	02030.40
CONCRETE SCM - METAKAOLIN	02030.50
CONCRETE SCM - SILICA FUME	02030.20
CONCRETE SEALER - WATER REPELLENT	02060.30
CONCRETE SURFACE RETARDER	02055.10
CRACK INJECTION, EPOXY	00538.10
CURING BLANKET, CONCRETE	02050.30
CURING COMPOUND, CONCRETE	02050.10
DAMP PROOFING, CLEAR	00597.11
DELINEATORS - (TYPES 2, 3 & 5)	00840.10
DELINEATORS, TEMP	00224.14
DETECTABLE WARNING DEVICES	00759.12
DRAINS, TRENCH (PREFORMED)	00446.00
ELASTOMERIC CONCRETE	00584.10
ELECTRONIC CUTTABLE FILM	02910.60
EROSION CONTROL	00280.00
EXPANSION JOINTS, BRIDGE	00585.10
FENCING, WORKZONE	00221.13

CATEGORY	SPEC#
FLAGGER STATION LIGHTING	00223.22
FLAGGER STOP/SLOW PADDLE	00223.21
FLY ASH	02030.10
GALVANIZING REPAIR OF HOT-DIP	02530.71
GEOGRIDS - SUBGRADE REINFORCEMENT	02320.10
GEOGRIDS - TYPE I MSEW	02320.10
GEOSYNTHETICS	02320.10B
GLARE SHIELDS	00822.00
GLARESCREEN TEMPORARY	00226.11
GROUT, EPOXY	02080.10
GROUT, KEYWAY	02080.30
GROUT, NON-EPOXY (NON SHRINK)	02080.20
GROUT, STRUCTURAL	02080.60
GROUT, TENDON	02080.50
GUARDRAIL BLOCKS, PLASTIC	02110.20
GUARDRAIL TERMINALS	00810.10
HOT APPLIED JOINT SEALANT	02440.30
MPACT ATTENUATOR, PERM.	00830.00
MPACT ATTENUATOR, TEMP.	00226.12
MPACT ATTENUATOR, TRUCK MTD	00226.23
OINT FILLER, PREFORMED	02440.10
ATEX EMULSION PAINT	02210.30

#### OREGON DEPARTMENT OF TRANSPORTATION

"QPL" INDEX BY CATEGORY TO GET SPECIFICATION NUMBERS

PAGE II

CATEGORY	SPEC#
LOOP SEALANTS, TRAFFIC	00990.43
LUBE FOR FASTENERS	02560.70
LUBE FOR GALV FASTENERS	02560.70
LUBE FOR STAINLESS FASTENERS	02560.70
MAILBOX SUPPORTS	01070.00
MANHOLE RISER RINGS	00470.00
MANHOLE STEPS	02450.30
MARKERS, CONICAL	00224.11
MARKERS, TUBULAR	00224.10
MARKERS, TUBULAR, SURF. MTD, PERM.	00856.10
MARKERS, TUBULAR, SURF. MTD, TEMP.	00224.12
MARKINGS, LONGITUDINAL - DURABLE	00865.00
MARKINGS, LONGITUDINAL - HIGH PERF	00866.00
MARKINGS, LONGITUDINAL - PAINT	00860.00
MARKINGS, TRANSVERSE	00867.00
MECHANICAL ANCHOR SYSTEM	00535.10B
MEMBRANE, SPRAY WATERPROOFING	00591.00
METAKAOLIN	02030.50
MOISTURE RETENTION CHEM FOR SOIL	01040.22
MPCO AGGREGATE	00556.10B
MULTI - LAYER POLY. CON. OVERLAY	00556.10A
PAINT STRIPING BEADS, TEMP	00225.12B

CATEGORY	SPEC#
PAINT STRIPING BEADS, TEMP	00225.12B
PAINT STRIPING, TEMP	00225.12A
PAVEMENT MARKER ADHESIVE	00855.00
PAVEMENT MARKER, FLEXIBLE	00225.10
PAVEMENT MARKER, PERMANENT	00855.00
PCC REPAIR	02015.20
PCC REPAIR POLYMER MODIFIED	02015.30
PCC REPAIR, RESURFACER	02015.60
PCC REPAIR, SURFACE	02015.50
PCMS / PVMS - CHNGABLE MESSAGE SIGN	00222.15B
PEDESTRIAN CHANNELIZING DEVICE	00228.10
PERFORATED STEEL SQ TUBE - ANCHORS	00930.00
PERFORATED STEEL SQ TUBE - SLIP BASE	00930.00
PERFORATED STEEL SQ TUBE - SUPPORTS	00930.00
PILE TIPS	02520.10E
PIPE - POLYETHYLENE	02415.10
PIPE - POLYPROPYLENE	02415.40
PIPE - PVC	02415.50
PIPE- SOLID WALL POLYETHYLENE	02415.20
PIPE, MASTIC	00445.12
PIPE, POLYMER COATINGS FOR METAL PIPE	02420.20
PIPE-STEEL REINFORCED POLYETHYLENE	02415.30

CATEGORY	SPEC#
PLASTIC DRUMS, TEMPORARY	00224.13
POROUS PAVER	00760.00
POURED SEALANT, SILICONE (2 PART)	02440.11
PRECOMPRESSED FOAM SILICONE JOINT	02440.23
PREFORMED COMPRESSION JOINT SEAL	02440.22
PSST SIGN SUPPORTS, TEMP	00222.11E
RADAR SPEED TRAILER	00222.15C
RAMPS, TEMPORARY SIDEWALK	00228.13
RAPID SET CEMENT	02011.10
REBAR MANUFACTURERS	02510.10
REBAR SPLICE, MECHANICAL	02510.20
REFLECTIVE ELEMENTS FOR MARKINGS	00850.00
REINFORCEMENT, HEADED BAR	02510.25
RESIN BONDED ANCHOR SYSTEM	00535.10A
ROCK BOLTS	00398.00
SEQUENTIAL ARROW SIGN	00222.15A
SIGN COVERS, TEMPORARY	00222.12A
SIGN SHEETING, TYPES 1 - X	02910.20
SIGN SHEETING, WORKZONE RIGID	00222.10B
SIGN SHEETING, WORKZONE ROLL-UP	00222.10D
SIGN SUPPORTS, PORTABLE	00222.11B
SILICA FUME	02030.20

#### OREGON DEPARTMENT OF TRANSPORTATION

"QPL" INDEX BY CATEGORY TO GET SPECIFICATION NUMBERS

Page I	II
raue	

CATEGORY	SPEC#
SLAG (GGBFS)	02030.40
SMART WORK ZONE SYSTEM VENDOR	00229.10
SOIL BIO AMENDMENT	01040.17
SOIL STERILIZATION	01040.21
STORMWATER CONTROL FACILITIES	01010.03
STRIP SEALS	02440.20
STRUCTURAL STEEL CAULKING	00594.12
STRUCTURAL STEEL COATINGS	00594.10
SYNTHETIC FIBER, MACRO, MICRO, BLEND	02045.00
SYNTHETIC SLURRY	00512.14
TAPE, NON-REFLECTIVE	00225.11
TAPE, TEMPORARY	00225.11
TEMPORARY BARRIER	00226.11A
TEMPORARY WALKS	00228.14
TIMBER COATING	02210.20
TRAFFIC SIGNAL, PORTABLE	00227.13
TRANSVERSE RUMBLE STRIPS, TEMP.	00225.14
WATERPROOFING - CAP	00597.11
WOOD PRESERVATIVE, FIELD	02190.30

<u>Category</u>	Sub Category	<u>Section</u>
Erosion Prevention Ma	uterials	
	Matting – Slope Type A - Slopes 1V:3H or flatter - Clay Soil Type B - Slopes 1V:3H or flatter - Sandy Soil Type C - Slopes steeper than 1V:3H - Clay Soil Type D - Slopes steeper than 1V:3H - Sandy Soil	00280.14e
	Matting – Flexible Channel Liner  Type E-Shear Stress Range 2 lbs/ft²  Type F-Shear Stress Range 4 lbs/ft²  Type G-Shear Stress Range 6 lbs/ft²  Type H-Shear Stress Range 8 lbs/ft²	
Runoff Control Materia		
	Check Dam  Type 5 – Prefabricated System	00280.15a
	Compost Filter Sock Filter Sock Material	00280.15f (1)
Sediment Control Mate	<u>erials</u>	
	Inlet Protection  Type 3 – Prefabricated Filter Inserts	00280.16d
	Sediment Barrier Type 7 – Prefabricated Barrier System	00280.16e
Pay 1 2022	Sediment Mat	00280.16f

#### **Erosion Control**

<u>Category</u>	Sub Category	<u>Section</u>
Sediment Control Materials Cont.		
Flocculants		00280.16k
Hydro-mulch		01030.15a
Moisture Retention Chemicals		01040.22b
Miscellaneous Items		01040.23

STANDARD SPEC#	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00226.23	IMPACT ATTENUATOR, TL-3 TRUCK MOUNTED NCHRP 350 TL-3	VORTEQ TL-3	VALTIR LLC JIM CROWLEY 312/467-6750 DAN MCCARTHY 760/518-9929 CORAL SALES 800/538-7245	07/10/08	3644	А	TRAILER MOUNTED. MUST USE SUPPORT TRUCKS APPROX 20K LBS GVW OR HIGHER.
00227.13	TRAFFIC SIGNAL, PORTABLE TRAILER MOUNT	ADDCO PTS-2000	JOHN THOMAS, INC. 888/447-7263 ANNE BROUSIL 815/288-2343 TRAFFIC SAFETY 800/547-8518	01/12/06	1586	Q	PROJECT MUST INCLUDE SPECS FOR PORTABLE SIGNALS. APPROVAL NEEDED PRIOR TO USE.
00227.13	TRAFFIC SIGNAL, PORTABLE TRAILER MOUNT	HORIZON SQ-3TS	HORIZON SIGNAL 800/852-8796 HIGHWAY SPECIALTIES 503/390-1113	01/12/06	2646	Q	PROJECT MUST INCLUDE SPECS FOR PORTABLE SIGNALS. APPROVAL NEEDED PRIOR TO USE.
00227.13	TRAFFIC SIGNAL, PORTABLE TRAILER MOUNT	MODEL PTL 2.4X	NORTH AMERICA TRAFFIC 877/352-4626	10/09/08	3683	Q	PROJECT MUST INCLUDE SPECS FOR PORTABLE SIGNALS. APPROVAL NEEDED PRIOR TO USE.
00227.13	TRAFFIC SIGNAL, PORTABLE TRAILER MOUNT	RC FLAGMAN PTL 2.4	NORTH AMERICA TRAFFIC 877/352-4626	02/08/07	3297	Q	PROJECT MUST INCLUDE SPECS FOR PORTABLE SIGNALS. APPROVAL NEEDED PRIOR TO USE.
00227.13	TRAFFIC SIGNAL, PORTABLE TRAILER MOUNT	STS PST-1000 & STS PST-1000A	SUPERIOR TRAFFIC SERVICES, LLC JEFF HOLLENBECK 406/531-9914 MIKE DAVIS 509/220-0339	02/21/18	5013	Q	PROJECT MUST INCLUDE SPECS FOR PORTABLE SIGNALS. APPROVAL NEEDED PRIOR TO USE.
00228.10	PEDESTRIAN CHANNELIZING DEVICE (PCD)	PLASTICADE PATHCADE BARRICADE SYSTEM ANTI-TRIP FOOT RECESSED WHEN USED AS PCD	PLASTICADE 800/772-0355	05/10/22	5426	Α	384 SQ IN OF SHEETING PER SIDE SHEETING WILL MATCH THE COLOR OF THE BODY. WHITE TYPE III OR IV ORANGE TYPE VIII OR IX
00228.10	PEDESTRIAN CHANNELIZING DEVICE (PCD)	SAFETY WALL SW-3674	PLASTIC SAFETY SYSTEMS INC 216/231/8590	06/13/11	4402	Α	384 SQ IN OF SHEETING PER SIDE SHEETING WILL MATCH THE COLOR OF THE BODY. WHITE TYPE III OR IV ORANGE TYPE VIII OR IX
00228.10	PEDESTRIAN CHANNELIZING DEVICE (PCD)	STRONGWALL ADA PEDESTRIAN BARRICADE	PLASTICADE 800/772-0355	06/23/14	4748	Α	384 SQ IN OF SHEETING PER SIDE SHEETING WILL MATCH THE COLOR OF THE BODY. WHITE TYPE III OR IV ORANGE TYPE VIII OR IX

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00228.10	PEDESTRIAN CHANNELIZING DEVICE (PCD)	TRAFFIX URBANITE WALL SHALL HAVE ADA COMPLIANT LEGS	TRAFFIX DEVICES INC. 801/9797099 TRAFFIC SAFETY SUPPLY COMPANY 503/235-8531	03/14/17	5031	Α	384 SQ IN OF SHEETING PER SIDE SHEETING WILL MATCH THE COLOR OF THE BODY. WHITE TYPE III OR IV ORANGE TYPE VIII OR IX
00228.10	PEDESTRIAN CHANNELIZING DEVICE (PCD)	YODOCK 2001	YODOCK 888/496-3625 CORAL SALES 800/538-7245	01/26/12	4561	Α	384 SQ IN OF SHEETING PER SIDE SHEETING WILL MATCH THE COLOR OF THE BODY. WHITE TYPE III OR IV ORANGE TYPE VIII OR IX
00228.10	PEDESTRIAN CHANNELIZING DEVICE (PCD)	YODOCK 2001M	YODOCK 888/496-3625 CORAL SALES 800/538-7245	06/11/13	2652	Α	384 SQ IN OF SHEETING PER SIDE SHEETING WILL MATCH THE COLOR OF THE BODY. WHITE TYPE III OR IV ORANGE TYPE VIII OR IX
00228.10	PEDESTRIAN CHANNELIZING DEVICE (PCD)  MASH TL-3 2016	TPAR	PEXCO LLC- DAVIDSON TRAFFIC 877/335-4638 STEVE LOOP 253/284-8000 CRAIG SCHULZ 253/284-8005 TRAFFIC SAFETY 800/547-8518	06/10/13	4604	Α	384 SQ IN OF SHEETING PER SIDE SHEETING WILL MATCH THE COLOR OF THE BODY. WHITE TYPE III OR IV ORANGE TYPE VIII OR IX
00228.12	BICYCLE CHANNELIZING DEVICE (BCD)	YODOCK 2001SL SLIMLINE CHANNELIZER	YODOCK 888/496-3625 CORAL SALES 800/538-7245	05/11/16	4659	Α	72 SQ IN WHITE SHEETING PER SIDE TYPE III OR IV
00228.13	TEMPORARY CURB RAMPS	BOARDWALK PLATFORM 2	PSS 800/662-6338	05/22/17	5046	Α	RAMP AND PLATFORM
00228.13	TEMPORARY CURB RAMPS	BOARDWALK RAMP	PSS 800/662-6338	03/24/17	5043	Α	RAMP
00229.10	SMART WORK ZONE SYSTEM VENDOR	ASTI	ASTI TRANSPORTATION SYSTEMS 302/328-3220	09/09/10	4071	Α	ELEVATED, TRAILER-MOUNTED, MICROWAVE / BLUETOOTH SENSORS.
00229.10	SMART WORK ZONE SYSTEM VENDOR	ICONE	ICONE PRODUCTS 315/626-6800	05/12/11	3674	Α	GROUND-MOUNTED, DOPPLER RADAR SENSORS WITHIN PORTABLE TRAFFIC DRUMS.

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00229.10	SMART WORK ZONE SYSTEM VENDOR	JAMLOGIC PTS	VER-MAC 888/488-7446	08/11/11	4075	Α	ELEVATED, TRAILER-MOUNTED, DOPPLER/ MICROWAVE/ BLUETOOTH SENSORS.
00229.10	SMART WORK ZONE SYSTEM VENDOR	SALANDER SOFTWARE SERVICES	SALANDER LLC 612/964-6004	03/06/17	4947	Α	
00229.10	SMART WORK ZONE SYSTEMS VENDOR	SAWS-SOLAR ADVANCED WARNING SYSTEM	SOLAR ADVANCED WARNING SYSTEMS INC. DARIO ALVAREZ 512/810-6989	11/02/22	5431	Α	CONFLICT MONITORING-TRUCKS ENTERING/CROSSING/EXITING WARNING
00280.14E	MATTING - TYPE A SLOPE	AIRTROL GEOBINDER	USG CORPORATION 916/417-5048 HANES GEO COMP. 800/324-4594	07/09/09	3905	Α	
00280.14E	MATTING - TYPE A SLOPE	BIONET S75BN	WESTERN GREEN 800/582-4005 CASCADE GEOS 971/339-1020	12/02/21	5385	Α	STRAW AND JUTE NETTING
00280.14E	MATTING - TYPE A SLOPE	EARTHGUARD FIBER MATRIX	LSC ENVIRONMENTAL PRODUCTS 800/800-7671 HANES GEOCOMPONENTS 800/426-4976	01/08/09	2972	Α	SPRAY W/ WOOD CELLULOSE FIBER GUAR TACKIFIER, PAM STABILIZER & STARCH BIO-DEGRADABLE
00280.14E	MATTING - TYPE A SLOPE	ENVIRO-SHIELD BONDED FIBER MTX	USG CORPORATION 916/417-5048 HANES GEO COMP. 800/324-4594	07/09/09	3533	Α	
00280.14E	MATTING - TYPE A SLOPE	EROSION CONTROL BLANKET C 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	05/01/15	4848	Α	
00280.14E	MATTING - TYPE A SLOPE	EROSION CONTROL BLANKET S 31 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4843	Α	

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE A SLOPE	EROSION CONTROL BLANKET SC 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/13/15	4846	Α	
00280.14E	MATTING - TYPE A SLOPE	EROSION CONTROL BLANKET S 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4845	Α	
00280.14E	MATTING - TYPE A SLOPE	EXCEL CS-3 ALL NATURAL	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3397	Α	70% WHEAT STRAW & 30% COCONUT. WITH JUTE SCRIM
00280.14E	MATTING - TYPE A SLOPE	FLEXTERRA HP-FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	02/10/11	4205	Α	FLEXIBLE GROWTH MEDIUM HYDRAULICALLY APPLIED. RECYCLED THERMALLY REFINED WOOD FIBERS.
00280.14E	MATTING - TYPE A SLOPE	FUSION	LSC ENVIRONMENTAL PRODUCTS 800/800-7671 HANES GEOCOMPONENTS 800/426-4976	06/19/19	5199	Α	HYDRO. APPLIED, GAR, PAM STABILIZER SOIL BIO-AMENDMENTS
00280.14E	MATTING - TYPE A SLOPE	GEOJUTE	BELTON INDUSTRIES 800/225-4099 BOB MORAN ACF WEST 800/878-5115	10/11/01	2490	Α	WOVEN JUTE. BIODEGRADEABLE.
00280.14E	MATTING - TYPE A SLOPE	HYDRA CX2	NORTH AMERICAN GREEN 800/772-2040	05/14/09	3532	Α	
00280.14E	MATTING - TYPE A SLOPE	HYDROSTRAW BONDED FIBER MATRIX	HYDROSTRAW 800/545-1755 ED LEE	11/11/10	4164	Α	
00280.14E	MATTING - TYPE A SLOPE	KANSAS EROSION KEP-C100 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5357	Α	BIODEGRADABLE COIR & JUTE NETTING

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE A SLOPE	KANSAS EROSION KEP-S2 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5358	Α	BIODEGRADABLE WHEAT STRAW & JUTE NETTING
00280.14E	MATTING - TYPE A SLOPE	KANSAS EROSION KEP-SC2 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5359	Α	BIODEGRADABLE WHEAT STRAW & COIR, JUTE NETTING
00280.14E	MATTING - TYPE A SLOPE	NORTH AMERICAN GREEN S150BN	NORTH AMERICAN GREEN 800/772-2040 OR 812/687-6632 ACF WEST 800/878-5115	07/10/97	1381	Α	STRAW FIBER COVERED WITH TWISTED PAPER YARN NETTING. 100% BIO-DEGRADABLE.
00280.14E	MATTING - TYPE A SLOPE	NORTH AMERICAN GREEN S75BN	NORTH AMERICAN GREEN 800/772-2040 OR 812/687-6632 ACF WEST 800/878-5115	07/10/97	1380	Α	STRAW FIBER CONVERED WITH BIO- DEGRADABLE NETTING. 100% BIO-DEGRADABLE.
00280.14E	MATTING - TYPE A SLOPE	SOIL GUARD	MAT, INC. 888/477-3028 (WAS WEYERHAEUSER UNTIL 12/99)	11/09/95	1403	Α	MADE OF FIR AND HEMLOCK. BONDED FIBER MATRIX. HYDRAULICALLY APPLIED.
00280.14E	MATTING - TYPE A SLOPE HYDRAULICALLY APPLIED	BINDEX BFM	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	12/10/12	4563	Α	HYDRAULICALLY APPLIED WOOD FIBER
00280.14E	MATTING - TYPE A SLOPE HYDRAULICALLY APPLIED	FLEXTERRA FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	11/09/06	3319	Α	HYDRAULICALLY APPLIED WOOD FIBER
00280.14E	MATTING - TYPE A SLOPE HYDRAULICALLY APPLIED	PROMATRIX ENGINEERED FIBER MATRIX	PROFILE PRODUCTS, LLC 847/215-3454 ACF WEST 503/771-5115	09/19/12	4506	Α	HYDRAULICALLY APPLIED WOOD FIBER
00280.14E	MATTING - TYPE B SLOPE	BIONET S75BN	WESTERN GREEN 800/582-4005 CASCADE GEOS 971/339-1020	12/02/21	5385	Α	STRAW AND JUTE NETTING

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE B SLOPE	EARTHGUARD FIBER MATRIX/VERTEX	LSC ENVIRONMENTAL PRODUCTS 800/800-7671 HANES GEOCOMPONENTS 800/426-4976	01/08/09	2972	Α	SPRAY W/ WOOD CELLULOSE FIBER GUAR TACKIFIER, PAM STABILIZER & STARCH BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE	EROSION CONTROL BLANKET C 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	05/01/15	4848	A	BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE	EROSION CONTROL BLANKET SC 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/13/15	4846	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE	EROSION CONTROL BLANKET S 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4845	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE	EROSION CONTROL BLANKET S 31 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4843	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE	EXCEL CS-3 ALL NATURAL	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3397	Α	70% WHEAT STRAW & 30% COCONUT. WITH JUTE SCRIM BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE	FLEXTERRA HP-FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	02/10/11	4205	Α	FLEXIBLE GROWTH MEDIUM HYDRAULICALLY APPLIED. RECYCLED THERMALLY REFINED WOOD FIBERS BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE	FUSION	LSC ENVIRONMENTAL PRODUCTS 800/800-7671 HANES GEOCOMPONENTS 800/426-4976	06/19/19	5199	Α	HYDRO. APPLIED, GAR, PAM STABILIZER SOIL BIO-AMENDMENTS BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE	GEOJUTE PLUS	BELTON INDUSTRIES INC 800/225/4099 ACF WEST INC 503/771/5115	06/30/11	2490	Q	NOT FOR USE AS TYPE A & C

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE B SLOPE	HYDRA CX2	NORTH AMERICAN GREEN 800/772-2040	05/14/09	3532	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE	KANSAS EROSION KEP-C100 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5357	Α	BIODEGRADABLE COIR & JUTE NETTING
00280.14E	MATTING - TYPE B SLOPE	KANSAS EROSION KEP-S2 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5358	Α	BIODEGRADABLE WHEAT STRAW & JUTE NETTING
00280.14E	MATTING - TYPE B SLOPE	KANSAS EROSION KEP-SC2 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5359	Α	BIODEGRADABLE WHEAT STRAW & COIR, JUTE NETTING
00280.14E	MATTING - TYPE B SLOPE	SOIL GUARD	MAT, INC. 888/477-3028 (WAS WEYERHAEUSER UNTIL 12/99)	11/09/95	1403	Α	MADE OF FIR AND HEMLOCK. BONDED FIBER MATRIX. HYDRAULICALLY APPLIED. BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE HYDRAULICALLY APPLIED	BINDEX BFM	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	12/10/12	4563	Α	HYDRAULICALLY APPLIED WOOD FIBER
00280.14E	MATTING - TYPE B SLOPE HYDRAULICALLY APPLIED	FLEXTERRA FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	11/09/06	3319	Α	HYDRAULICALLY APPLIED WOOD FIBER BIODEGRADABLE
00280.14E	MATTING - TYPE B SLOPE HYDRAULICALLY APPLIED	PROMATRIX ENGINEERED FIBER MATRIX	PROFILE PRODUCTS, LLC 847/215-3454 ACF WEST 503/771-5115	09/19/12	4506	Α	HYDRAULICALLY APPLIED WOOD FIBER BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	AIRTROL GEOBINDER	USG CORPORATION 916/417-5048 HANES GEO COMP. 800/324-4594	07/09/09	3905	Α	

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE C SLOPE	BIONET S150BN	WESTERN GREEN 800/582-4005 CASCADE GEOS 971/339-1020	12/02/21	5386	Α	STRAW AND JUTE NETTING
00280.14E	MATTING - TYPE C SLOPE	COCOFLEX ET-FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	03/12/09	3803	Α	EXTENDED TERM FLEXIBLE GROWTH MEDIUM. WOOD & COCONUT. BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	EARTHGUARD FIBER MATRIX	LSC ENVIRONMENTAL PRODUCTS 800/800-7671 HANES GEOCOMPONENTS 800/426-4976	08/13/09	2972	Α	SPRAY W/ WOOD CELLULOSE FIBER GUAR TACKIFIER, PAM STABILIZER & STARCH BIO-DEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	ENVIRO-SHIELD BONDED FIBER MTX	USG CORPORATION 916/417-5048 HANES GEO COMP. 800/324-4594	07/09/09	3533	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	EROSION CONTROL BLANKET SC 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/13/15	4846	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	EROSION CONTROL BLANKET S 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4845	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	EROSION CONTROL BLANKET C 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	05/01/15	4848	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	EXCEL CS-3 ALL NATURAL	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3397	Α	70% WHEAT STRAW & 30% COCONUT. WITH JUTE SCRIM BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	FLEXTERRA HP-FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	02/10/11	4205	Α	FLEXIBLE GROWTH MEDIUM HYDRAULICALLY APPLIED. RECYCLED THERMALLY REFINED WOOD FIBERS BIODEGRADABLE

<sup>\*</sup>LIST 'A' = APPROVED. MAY BE USED WITHOUT SAMPLES, TESTING, OR QUALITY COMPLIANCE CERTIFICATIONS. MAY NEED A FIELD INSPECTION REPORT.

\*\*LIST 'Q' = QUALIFIED. USE WITH SAMPLING, TESTING, &/OR QUALITY COMPLIANCE CERTIFICATIONS AS NEEDED. NEEDS A FIELD INSPECTIONS REPORT. CHECK SPECS AND NFTMAG.
LIST PUBLISHED BY: ODOT MATERIALS LAB; 800 AIRPORT RD SE; SALEM, OR 97301-4798; (503) 986-3059. PLEASE REPORT ANY PROBLEMS USING THESE PRODUCTS.

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE C SLOPE	FUSION	LSC ENVIRONMENTAL PRODUCTS 800/800-7671 HANES GEOCOMPONENTS 800/426-4976	06/19/19	5199	Α	HYDRO. APPLIED, GAR, PAM STABILIZER SOIL BIO-AMENDMENTS BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	GEOJUTE	BELTON INDUSTRIES 800/225-4099 BOB MORAN ACF WEST 800/878-5115	10/11/01	2490	Α	WOVEN JUTE. BIODEGRADEABLE.
00280.14E	MATTING - TYPE C SLOPE	HYDRA CM STEEP SLOPE MATRIX	NORTH AMERICAN GREEN 800/772-2040	11/11/10	4265	Α	70% STRAW & 20% RECLAIMED COTTON FIBER. BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	HYDRA CX2	NORTH AMERICAN GREEN 800/772-2040	05/14/09	3532	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	HYDROSTRAW ALL IN 1 BONDED FIBER MATRIX	HYDROSTRAW 800/545-1755 RON EDWARDS	07/09/15	4899	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	HYDROSTRAW BONDED FIBER MATRIX	HYDROSTRAW 800/545-1755 ED LEE	11/11/10	4164	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE	KANSAS EROSION KEP-C100 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5357	Α	BIODEGRADABLE COIR & JUTE NETTING
00280.14E	MATTING - TYPE C SLOPE	KANSAS EROSION KEP-S2 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5358	Α	BIODEGRADABLE WHEAT STRAW & JUTE NETTING
00280.14E	MATTING - TYPE C SLOPE	KANSAS EROSION KEP-SC2 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5359	Α	BIODEGRADABLE WHEAT STRAW & COIR, JUTE NETTING

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE C SLOPE	SOIL GUARD	MAT, INC. 888/477-3028 (WAS WEYERHAEUSER UNTIL 12/99)	11/09/95	1403	Α	MADE OF FIR AND HEMLOCK. BONDED FIBER MATRIX. HYDRAULICALLY APPLIED. BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE HYDRAULICALLY APPLIED	BINDEX BFM	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	12/10/12	4563	Α	HYDRAULICALLY APPLIED WOOD FIBER BIODEGRADABLE
00280.14E	MATTING - TYPE C SLOPE HYDRAULICALLY APPLIED	FLEXTERRA FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	11/09/06	3319	Α	HYDRAULICALLY APPLIED WOOD FIBER BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	BIONET S150BN	WESTERN GREEN 800/582-4005 CASCADE GEOS 971/339-1020	12/02/21	5386	Α	STRAW AND JUTE NETTING
00280.14E	MATTING - TYPE D SLOPE	COCOFLEX ET-FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	03/12/09	3803	Α	EXTENDED TERM FLEXIBLE GROWTH MEDIUM. WOOD & COCONUT.
00280.14E	MATTING - TYPE D SLOPE	CURLEX NET FREE	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	11/13/08	3712	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	EARTHGUARD FIBER MATRIX/VERTEX	LSC ENVIRONMENTAL PRODUCTS 800/800-7671 HANES GEOCOMPONENTS 800/426-4976	08/13/09	2972	Α	SPRAY W/ WOOD CELLULOSE FIBER GUAR TACKIFIER, PAM STABILIZER & STARCH BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	EROSION CONTROL BLANKET SC 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/13/15	4846	A	BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	EROSION CONTROL BLANKET C 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	05/01/15	4848	Α	BIODEGRADABLE

STANDARD SPEC#	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE D SLOPE	EROSION CONTROL BLANKET S 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4845	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	EXCEL CS-3 ALL NATURAL	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3397	Α	70% WHEAT STRAW & 30% COCONUT. WITH JUTE SCRIM BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	FLEXTERRA HP-FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	02/10/11	4205	Α	FLEXIBLE GROWTH MEDIUM HYDRAULICALLY APPLIED. RECYCLED THERMALLY REFINED WOOD FIBERS BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	FUSION	LSC ENVIRONMENTAL PRODUCTS 800/800-7671 HANES GEOCOMPONENTS 800/426-4976	06/19/19	5199	Α	HYDRO. APPLIED, GAR, PAM STABILIZER SOIL BIO-AMENDMENTS BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	GEOJUTE PLUS	BELTON INDUSTRIES INC 800/225/4099 ACF WEST INC 503/771/5115	06/30/11	2490	Q	NOT FOR USE AS TYPE A & C
00280.14E	MATTING - TYPE D SLOPE	GROUNDCONTROL HY-C3 STRAW & COTTON	EAST COAST EROSION CONTROL 610/488-8496	05/03/13	4619	Α	HYDRAULICALLY APPLIED BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	GROUNDCONTROL HY-C4 STRAW & COTTON	EAST COAST EROSION CONTROL 610/488-8496	05/03/13	4620	Α	HYDRAULICALLY APPLIED BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	HYDRA CM STEEP SLOPE MATRIX	NORTH AMERICAN GREEN 800/772-2040	11/11/10	4265	Α	70% STRAW & 20% RECLAIMED COTTON FIBER. BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE	HYDRA CX2	NORTH AMERICAN GREEN 800/772-2040	05/14/09	3532	Α	BIODEGRADABLE

<sup>\*</sup>LIST 'A' = APPROVED. MAY BE USED WITHOUT SAMPLES, TESTING, OR QUALITY COMPLIANCE CERTIFICATIONS. MAY NEED A FIELD INSPECTION REPORT.

\*\*LIST 'Q' = QUALIFIED. USE WITH SAMPLING, TESTING, &/OR QUALITY COMPLIANCE CERTIFICATIONS AS NEEDED. NEEDS A FIELD INSPECTIONS REPORT. CHECK SPECS AND NFTMAG.
LIST PUBLISHED BY: ODOT MATERIALS LAB; 800 AIRPORT RD SE; SALEM, OR 97301-4798; (503) 986-3059. PLEASE REPORT ANY PROBLEMS USING THESE PRODUCTS.

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE D SLOPE	KANSAS EROSION KEP-C100 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5357	Α	BIODEGRADABLE COIR & JUTE NETTING
00280.14E	MATTING - TYPE D SLOPE	KANSAS EROSION KEP-S2 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5358	Α	BIODEGRADABLE WHEAT STRAW & JUTE NETTING
00280.14E	MATTING - TYPE D SLOPE	KANSAS EROSION KEP-SC2 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5359	Α	BIODEGRADABLE WHEAT STRAW & COIR, JUTE NETTING
00280.14E	MATTING - TYPE D SLOPE	SOIL GUARD	MAT, INC. 888/477-3028 (WAS WEYERHAEUSER UNTIL 12/99)	11/09/95	1403	Α	MADE OF FIR AND HEMLOCK. BONDED FIBER MATRIX. HYDRAULICALLY APPLIED. BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE HYDRAULICALLY APPLIED	BINDEX BFM	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	12/10/12	4563	Α	HYDRAULICALLY APPLIED WOOD FIBER BIODEGRADABLE
00280.14E	MATTING - TYPE D SLOPE HYDRAULICALLY APPLIED	FLEXTERRA FGM	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	01/08/09	3319	Α	HYDRAULICALLY APPLIED WOOD FIBER BIODEGRADABLE
00280.14E	MATTING - TYPE E FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET SC 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/13/15	4846	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE E FLEXIBLE CHANNEL LINER	EXCEL CS-3 ALL NATURAL	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3397	Α	70% WHEAT STRAW & 30% COCONUT. WITH JUTE SCRIM BIODEGRADABLE
00280.14E	MATTING - TYPE E FLEXIBLE CHANNEL LINER	KANSAS EROSION KEP-C100 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5357	Α	BIODEGRADABLE COIR & JUTE NETTING

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE E FLEXIBLE CHANNEL LINER	KANSAS EROSION KEP-S2 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5358	Α	BIODEGRADABLE WHEAT STRAW & JUTE NETTING
00280.14E	MATTING - TYPE E FLEXIBLE CHANNEL LINER	KANSAS EROSION KEP-SC2 NATURAL	KANSAS EROSION 919/480-5616 OBC NORTHWEST 503/266-2021	07/19/21	5359	Α	BIODEGRADABLE WHEAT STRAW & COIR, JUTE NETTING
00280.14E	MATTING - TYPE E FLEXIBLE CHANNEL LINER	KOIRMAT 700	NEDIA ENTERPRISES 888/725-6999	05/14/09	3718	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE E FLEXIBLE CHANNEL LINER	NORTH AMERICAN GREEN C125BN	NORTH AMERICAN GREEN 800/772-2040 ACF WEST 800/878-5115	11/08/07	3565	Α	BIODEGRADABLE JUTE COCONUT
00280.14E	MATTING - TYPE E SLOPE	EROSION CONTROL BLANKET C 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	05/01/15	4848	Α	BIODEGRADABLE
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	AEC PREMIER STRAW DOUBLE NET	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	01/09/12	4527	Α	STRAW
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	AEC PREMIER STRAW/COCONUT	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	01/09/12	3520	Α	70% WHEAT STRAW & 30% COCONUT.
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	CURLEX ENFORCER	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	11/14/02	2637	Α	ASPEN EXCELSIOR WITH POLY NETTING ON BOTH SIDES.
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	CURLEX III (STITCHED)	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	12/12/02	2621	Α	ASPEN EXCELSIOR WITH POLY NETTING ON BOTH SIDES.

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	ECP-2 POLYPROPYLENE TURF REINFORCEMENT MAT (TRM)	EAST COAST EROSION BLANKETS 610/488-8496 LAYFIELD COPORATION 800/796-6868	02/13/15	4852	Q	CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	ECP-3 POLYPROPYLENE TURF REINFORCEMENT MAT (TRM)	EAST COAST EROSION BLANKETS 610/488-8496 LAYFIELD COPORATION 800/796-6868	02/13/15	4853	Q	CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	ERONET P300	WESTERN GREEN 800/582-4005 CASCADE GEOS 971/339-1020	12/02/21	5387	Q	POLYPROPYLENE NET
							CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET SC 32 BD	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/13/15	4846	Α	
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET SC 32	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/13/15	4849	Α	
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET PC 42	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/20/15	4851	Α	
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET EX 32	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4841	Α	
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET C 32	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4847	Α	
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET P 42	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4850	Q	CONSTRUCTION MATERIAL CMO REQUIRED

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EXCEL CC-4	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3399	Α	COCONUT FIBER
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EXCEL PP5-10	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	12/14/06	3304	Α	POLYFIBER
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EXCEL PP5-12	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3401	Α	SYNTHETIC FIBERS
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EXCEL PP5-8	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3400	Α	POLY FIBERS
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	EXCEL SD-3	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3398	Α	ASPEN EXCELSIOR
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	GREEN ARMOR SYSTEM 7020	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	05/10/18	5124	Α	
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	KOIRMAT 700	NEDIA ENTERPRISES 888/725-6999	05/14/09	3718	Α	
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	LANDLOK 435	PROPEX OPERATING COMPANY, LLC 423/553-2463 ACF WEST INC 503/771-5115	10/29/12	4544	Q	TURF REINFORCEMENT MAT  CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE F	LANDLOK 450	PROPEX OPERATING COMPANY, LLC	10/29/12	4545	Q	TURF REINFORCEMENT MAT
·· ·· -	FLEXIBLE CHANNEL LINER		423/553-2463 ACF WEST INC 503/771-5115	<del>-</del>			CONSTRUCTION MATERIAL CMO REQUIRED

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	LANDLOK C2	PROPEX OPERATING COMPANY, LLC 423/553-2463 ACF WEST INC 503/771-5115	10/29/12	4543	Α	COCONUT FIBER
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	LANDLOK CS2	PROPEX OPERATING COMPANY, LLC 423/553-2463 ACF WEST INC 503/771-5115	10/29/12	4542	Α	70% WHEAT STRAW 30% COCONUT FIBER
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	LANDLOK S2	PROPEX OPERATING COMPANY, LLC 423/553-2463 ACF WEST INC 503/771-5115	10/29/12	4541	Α	WHEAT STRAW
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	NORTH AMERICAN GREEN C125BN	NORTH AMERICAN GREEN 800/772-2040 ACF WEST 800/878-5115	11/08/07	3565	Α	BIODEGRADABLE JUTE COCONUT
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	NORTH AMERICAN GREEN C350	NORTH AMERICAN GREEN 800/772-2040 ACF WEST 800/878-5115	07/10/97	1378	Α	COCONUT
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	NORTH AMERICAN GREEN S150 STRAW MATS	NORTH AMERICAN GREEN 800/772-2040 OR 812/687-6632 ACF WEST 800/878-5115	03/15/89	297	Α	WHEAT STRAW
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	RECYCLEX - TRM	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	11/09/06	2618	Q	ARTIFICAL FIBER (SODA BOTTLES)
			TIANED DEG COMIT ONENTO 300/033-1420				CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE F FLEXIBLE CHANNEL LINER	T-RECS HIGH PERFOMANCE TRM	EAST COAST EROSION CONTROL 610/488-8496	05/03/13	4617	Q	
							CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	CURLEX ENFORCER	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	11/14/02	2637	Α	ASPEN EXCELSIOR WITH POLY NETTING ON BOTH SIDES.

STANDARD SPEC#	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	ECP-2 POLYPROPYLENE TURF REINFORCEMENT MAT (TRM)	EAST COAST EROSION BLANKETS 610/488-8496 LAYFIELD COPORATION 800/796-6868	02/13/15	4852	Q	CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	ECP-3 POLYPROPYLENE TURF REINFORCEMENT MAT (TRM)	EAST COAST EROSION BLANKETS 610/488-8496 LAYFIELD COPORATION 800/796-6868	02/13/15	4853	Q	CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET EX 32	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4841	Α	
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET PC 42	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/20/15	4851	Α	
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET P 42	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4850	Q	CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	EXCEL PP5-10	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	12/14/06	3304	Α	POLYFIBER
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	EXCEL PP5-12	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3401	Α	SYNTHETIC FIBERS
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	EXCEL PP5-8	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3400	Α	POLY FIBERS
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	GREEN ARMOR SYSTEM 7020	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	05/10/18	5124	Α	MUST BE VEGETATED PER DATA SHEET TO MEET SHEAR STRENGTH SPECIFICATIONS

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	KOIRMAT 700	NEDIA ENTERPRISES 888/725-6999	05/14/09	3718	Α	
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	RECYCLEX - TRM	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	11/09/06	2618	Q	ARTIFICAL FIBER (SODA BOTTLES)  CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	RECYCLEX TRM-V	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	01/09/12	4528	Q	TURF REINFORCEMENT MAT PERMANENT 100% RECYCLED CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE G FLEXIBLE CHANNEL LINER	T-RES HIGH PERFORMANCE TRM	EAST COAST EROSION CONTROL 610/488-8496	02/13/15	4617	Q	
							CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	ARMORFLEX CLOSED CELL BLOCK	CONTECH ENGINEERED SOLUTIONS, LLC 503/258-3101	01/10/08	3590	Α	SUBJECT TO APPROVAL BY NATURAL RESOURCE AGENCIES AT DESIGN. CONCRETE BLOCKS
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	ARMORFLEX OPEN CELL BLOCK	CONTECH ENGINEERED SOLUTIONS, LLC 503/258-3101	02/14/08	3575	Α	
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	ARMORFLEX TAPERED CELL BLOCK	CONTECH ENGINEERED SOLUTIONS, LLC 503/258-3101	02/14/08	3591	Α	
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	ECP-2 POLYPROPYLENE TURF REINFORCEMENT MAT (TRM)	EAST COAST EROSION BLANKETS 610/488-8496 LAYFIELD COPORATION 800/796-6868	02/13/15	4852	Q	CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	ECP-3 POLYPROPYLENE TURF REINFORCEMENT MAT (TRM)	EAST COAST EROSION BLANKETS 610/488-8496 LAYFIELD COPORATION 800/796-6868	02/13/15	4853	Q	CONSTRUCTION MATERIAL CMO REQUIRED

STANDARD SPEC#	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET PC 42	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	02/20/15	4851	Α	
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET P 42	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC 503/771-5115	12/16/14	4850	Q	CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	EROSION CONTROL BLANKET P42 TRM	EROSION CONTROL BLANKET 866/317-3346 ACF WEST INC	11/13/08	3701	Q	
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	EXCEL PP5-10	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	12/14/06	3304	Α	POLYFIBER
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	EXCEL PP5-12	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3401	Α	SYNTHETIC FIBERS
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	EXCEL PP5-8	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955	02/08/07	3400	Α	POLY FIBERS
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	GREEN ARMOR SYSTEM 7020	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	05/10/18	5124	Α	MUST BE VEGETATED PER DATA SHEET TO MEET SHEAR STRENGTH SPECIFICATIONS
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	LANDLOK 1051	PROPEX OPERATING COMPANY, LLC 423/553-2463 ACF WEST INC 503/771-5115	10/29/12	4546	Q	TURF REINFORCEMENT MAT  CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE H	PYRAMAT	PROPEX OPERATING COMPANY, LLC	10/29/12	4547	Q	TURF REINFORCEMENT MAT
	FLEXIBLE CHANNEL LINER		423/553-2463 ACF WEST INC 503/771-5115			-	CONSTRUCTION MATERIAL CMO REQUIRED

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	RECYCLEX - TRM	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	11/09/06	2618	Q	ON THE TEXAS QPL. ARTIFICAL FIBER (SODA BOTTLES)
			THREE CEC COMM CHERT COCCOCC 1420				CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	RECYCLEX TRM-V	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	01/09/12	4528	Q	
							CONSTRUCTION MATERIAL CMO REQUIRED
00280.14E	MATTING - TYPE H FLEXIBLE CHANNEL LINER	T-RES HIGH PERFORMANCE TRM	EAST COAST EROSION CONTROL 610/488-8496	02/13/15	4617	Q	
							CONSTRUCTION MATERIAL CMO REQUIRED
00280.15A	CHECK DAM, TYPE 2	BMH-STRAW WATTLE W/NATURAL FIBER BIO- DEGRADABLE NETING 9", 12"	BLUE MOUNTAIN HAY, LLC 541/968-8565	11/09/20	5301	Α	BIODEGRADABLE NETTING (BURLAP OR TENCEL)
00280.15A	CHECK DAM, TYPE 2	WESTERN FIBER ROLL 9"	WESTERN FIBER COMPANY DON SUGARMAN 310/939-9254	06/17/21	5339	Α	BIODEGRADABLE NETTING (COTTON)
00280.15A	CHECK DAM, TYPE 3	BIO FILTER BAG	CITY OF ROSES DISPOSAL AND RECYCLING INC. 503/849-8881	11/12/09	2430	Α	NOT BIO-DEGRADEABLE SHORT TERM
							WAS NAMED GRABHORN BIO FILTER BAG
00280.15A	CHECK DAM, TYPE 3	CURLEX SEDIMENT LOG	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	05/08/08	2624	Α	NOT BIO-DEGRADEABLE
			HANES GEO COMPONENTS 300/099-1420				
00280.15A	CHECK DAM, TYPE 3	CURLEX SFW WATTLES	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	02/13/15	4863	Α	NOT BIO-DEGRADEABLE
00280.15A	CHECK DAM, TYPE 3	FILTREXX FILTERSOXX DITCHCHEXX	FILTREXX INTERNATIONAL 440/926-2607	12/08/05	3257	Α	NOT BIO-DEGRADEABLE

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.15A	CHECK DAM, TYPE 3	RICE STRAW FIBER ROLL	KRISTAR ENTERPRISES 800/579-8819	11/09/06	2634	Α	AVAILABLE,PHOTO OR BIODEGRADABLE NETTING
00280.15A	CHECK DAM, TYPE 3	SILTRAP CHECK BAG	HIGHWAY FUEL 503/363-6444	10/13/20	5260	Α	
00280.15A	CHECK DAM, TYPE 4	WOVEN POLYPROPYLENE SANDBAG MODEL: PPB1426T1600	SACRAMENTO BAG CO 800/287-2247 BUSSARD EROSION CONTROL 800/252-2692	07/11/02	2429	Α	NOT BIODEGRADEABLE
00280.15A	CHECK DAM, TYPE 5	GEOBALE	GEOHAY 864/472-7000	12/13/07	3579	Α	NOT BIO-DEGRADEABLE
00280.15A	CHECK DAM, TYPE 5	GEOFILTER	GEOHAY 864/472-7000	12/13/07	3580	Α	NOT BIO-DEGRADEABLE
00280.15A	CHECK DAM, TYPE 5	GEO-RIDGE	NILEX 303/766-2000 ACF WEST 800/878-5115	04/14/05	2357	Α	OK FOR REDUCING VELOCITITES, BUT NOT AS A CHECK DAM ALONE. USE WITH A MATTING NOT BIO-DEGRADEABLE
00280.15A	CHECK DAM, TYPE 5	TRIANGULAR SILT DIKE	TRIANGULAR SILT DIKE CO, INC. REP: JASON ROACH 405/741-7406 CSI GEOSYNTHETICS 800/426-7976	09/13/01	1592	Α	GEOTEXTILE FABRIC AND URETHANE FOAM. NOT BIO-DEGRADEABLE
00280.15A	CHECK DAM, TYPE: OTHER	EARTHSAVER RICE STRAW WATTLES	RH DYCK 530/662-7700 BUSSARD EROSION 541/926-7747	11/09/06	2431	Α	NOT BIO-DEGRADEABLE
00280.15A	CHECK DAM, TYPE: OTHER STRAW WATTLE	PERMALOK/PERMEATEX STRAW WATTL	NORTHWEST LININGS & GEOTEXTILE 253/867-5366	10/14/10	4194	Α	NOT BIO-DEGRADEABLE

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.15D	SLOPE DRAIN, TEMPORARY	TRIANGULAR SILT DIKE	TRIANGULAR SILT DIKE CO, INC. REP: JASON ROACH 405/741-7406 CSI GEOSYNTHETICS 800/426-7976	09/13/01	1592	Α	APPEARS TO BE A SUITABLE SUBSTITUTE FOR STRAW BALES OR SAND BAGS.
00280.15F	COMPOST FILTER SOCK MATERIAL	E-TUBE FILTER SOCK FABRIC	SOIL-TEK ETUBE FILTER SOCK PRODUCTS 515/480-0873	08/13/14	4761	Α	FABRIC FOR RUNOFF CONTROL MATERIALS NOT FULLY BIODEGRADABLE PHOTO-DEGRADABLE
00280.15F	COMPOST FILTER SOCK MATERIAL	FILTREXX SILTSOXX BIOSOXX	FILTREXX 404/687-8393	10/24/19	5219	Α	FABRIC FOR RUNOFF CONTROL MATERIALS BIO-DEGRADABLE
00280.15F	COMPOST FILTER SOCK MATERIAL	FILTREXX SILTSOXX WITH NATURAL PLUS MESH BIODEGRADABLE	FILTREXX 404/687-8393	12/28/20	5330	Α	FABRIC FOR RUNOFF CONTROL MATERIALS BIO-DEGRADABLE
00280.15F	COMPOST FILTER SOCK MATERIAL	PAC-SOCK COMPOST FILTER SOCK	PACIFIC CONTRACTOR SUPPLY 541/936-2619	07/07/21	5352	Α	FABRIC FOR RUNOFF CONTROL MATERIALS PHOTO-DEGRADABLE
00280.16D	INLET PROTECTION TYPE 10	CURB INLET SEDIMENT DAM	AMERICAN ENVIRON. CARDWELL; 541/688-7609 FAMILIAN NW 800/456-8611	10/10/02	2203	Α	DESIGNED FOR CURBED INLET PROTECTION. NEED TO MONITOR.
00280.16D	INLET PROTECTION - TYPE 1	BASIN WORK'R ECO	MIKE'S PRODUCTS 503/256-5607	07/24/15	4885	Α	
00280.16D	INLET PROTECTION - TYPE 1	MIKE'S PROD POCKETD SILT FENCE	MIKE'S PRODUCTS 503/256-5607 RESPONSIVE SUPPLY 503/804-7860	04/08/10	3996	Α	
00280.16D	INLET PROTECTION - TYPE 1 CURB	DP DRAIN TOPPER CURB	DP 208/270-1225	09/30/20	5292	Α	CURB

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.16D	INLET PROTECTION - TYPE 3	BASIN WORK'R ECO NO FRAME	MIKE'S PRODUCTS 503/256-5607	07/24/15	4885	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL AND MONITOR PER MFG INSTRUCTIONS
00280.16D	INLET PROTECTION - TYPE 3	DANDY CURB BAG SURFACE AND CURB INLET	DANDY PRODUCTS, INC 800/591-2284 SPILL CONTROL, INC 800/300-1649	11/17/14	4814	Α	DESIGNED FOR 250 GPM/FTSQ VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL AND MONITOR PER MFG INSTRUCTIONS
00280.16D	INLET PROTECTION - TYPE 3	DANDY CURB SACK SURFACE AND CURB INLET	DANDY PRODUCTS, INC 800/591-2284 SPILL CONTROL, INC 800/300-1649	11/17/14	4810	A	DESIGNED FOR 250 GPWFTSQ VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL AND MONITOR PER MFG INSTRUCTIONS
00280.16D	INLET PROTECTION - TYPE 3	DANDY SACK NO FRAME	DANDY PRODUCTS, INC 800/591-2284 SPILL CONTROL, INC 800/300-1649	11/17/14	4812	A	DESIGNED FOR 250 GPM/FTSQ VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL AND MONITOR PER MFG INSTRUCTIONS
00280.16D	INLET PROTECTION - TYPE 3	DRAIN BAGS NO FRAME	SPILL CONTROL,INC 800/300-1649	10/24/12	4539	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	DRAIN WEB DW4000REC 36"X24" FRAMED	ENVIROMET 360/944-6100	12/20/17	5103	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	DREAM STREAM GCDOTFB-3624 NO FRAME 36"X36"	THE GATE COMPANY 360/273-5802 MANARK PRODUCTS 360/790-9271	10/14/10	4174	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	FLEXSTORM INLET FILTER FRAMED	INLET & PIPE PROTECTION 866/287-8655 ADVANCED DRAINAGE SYSTEMS 800/821-6710	04/08/10	3965	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	FRAME & FILTER ASSEMBLY-DOME POLYMER FRAME	SILT SAVER, INC 770/388-7818 FERGUSON 541/618-7418	12/20/17	5101	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED

STANDARD SPEC#	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.16D	INLET PROTECTION - TYPE 3	HI-FLOW SILTSACK	ACF ENVIRONMENTAL DAVID KELLY 800/448-3636 DIST.: ACF WEST, INC. MELISSA HURLEY 503/771-5115	09/13/01	1164	A	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL AND MONITOR PER MFG INSTRUCTIONS REBAR USED INPLACE OF FRAME
00280.16D	INLET PROTECTION - TYPE 3	INLET PRO UNIERSAL W/FRAME 16"X20" - 28"X36"	HANES GEO COMPONENTS 888/239-4539 360/831-3613	04/02/21	5317	Α	
00280.16D	INLET PROTECTION - TYPE 3	MIKE'S PRODUCTS BASIN WORK'R FRAMED	MIKE'S PRODUCTS 503/256-5607 RESPONSIVE SUPPLY 503/804-7860	04/08/10	3995	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	NON-WOVEN SILT SACK	ACF ENVIRONMENTAL DAVID KELLY 800/448-3636	02/10/05	2958	Α	VERIFY PRODUCT SIZE VS INLET SIZE INSTALL AND MONITOR PER MFG INSTRUCTIONS REBAR USED INPLACE OF FRAME
00280.16D	INLET PROTECTION - TYPE 3	REGULAR FLOW SILTSACK	ACF ENVIRONMENTAL 804/271/2363 ACF WEST 800/878/5115	08/01/11	4442	Α	VERIFY PRODUCT SIZE VS INLET SIZE INSTALL AND MONITOR PER MFG INSTRUCTIONS REBAR USED INPLACE OF FRAME
00280.16D	INLET PROTECTION - TYPE 3	STORM DRAIN DEFENDER DD300REC 16"X20 TO 24"X36 FRAMED	ENVIROMET 360/944-6100	12/20/17	5102	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	STORM SENTINEL MODEL 4320NO 48" X 36" NO FRAME	ENPAC CORPORATION 800/936-7229 PAT GOTHRO (ENPAC)253/288-9215 FNW- DOUG MYERS 253/437-5141 FNW- MIKE STEWART 503/240-6747	04/29/14	4745	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED NO OVERFLOW
00280.16D	INLET PROTECTION - TYPE 3	STORM SENTINEL MODEL 4326NO 60" X 60" NO FRAME	ENPAC CORPORATION 800/936-7229 PAT GOTHRO (ENPAC)253/288-9215 FNW- DOUG MYERS 253/437-5141 FNW- MIKE STEWART 503/240-6747	04/29/14	4746	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED NO OVERFLOW
00280.16D	INLET PROTECTION - TYPE 3	STORM SENTINEL MODEL 4341	ENPAC CORPORATION 800/936-7229 PAT GOTHRO (ENPAC)253/288-9215 FNW- DOUG MYERS 253/437-5141 FNW- MIKE STEWART 503/240-6747	11/09/06	2936	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED WAS MODEL 1341

<sup>\*</sup>LIST 'A' = APPROVED. MAY BE USED WITHOUT SAMPLES, TESTING, OR QUALITY COMPLIANCE CERTIFICATIONS. MAY NEED A FIELD INSPECTION REPORT.

\*\*LIST 'Q' = QUALIFIED. USE WITH SAMPLING, TESTING, &/OR QUALITY COMPLIANCE CERTIFICATIONS AS NEEDED. NEEDS A FIELD INSPECTIONS REPORT. CHECK SPECS AND NFTMAG.
LIST PUBLISHED BY: ODOT MATERIALS LAB; 800 AIRPORT RD SE; SALEM, OR 97301-4798; (503) 986-3059. PLEASE REPORT ANY PROBLEMS USING THESE PRODUCTS.

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.16D	INLET PROTECTION - TYPE 3	STORM SENTINEL MODEL 4341 NO 36" X 24" FRAMED	ENPAC CORPORATION 800/936-7229 PAT GOTHRO (ENPAC)253/288-9215 FNW- DOUG MYERS 253/437-5141 FNW- MIKE STEWART 503/240-6747	04/29/14	4747	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED NO OVERFLOW
00280.16D	INLET PROTECTION - TYPE 3	STORM SENTINEL MODEL 4348 16"X20" TO 28"X36" FRAMED	ENPAC CORPORATION 800/936-7229 PAT GOTHRO (ENPAC)253/288-9215 FNW- DOUG MYERS 253/437-5141 FNW- MIKE STEWART 503/240-6747	10/14/10	4119	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	STORMGUARD FRAMED	SPILL CONTROL,INC 800/300-1649	12/24/12	4538	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	STREAMGUARD NO FRAME	FOSS INTERNATIONAL AND INFRASTRUCTURE SERVICES CO. JOE SMITH 206/378-4101	10/11/01	1600	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	ULTRA-DRAIN GUARD ADJ. FRAME MOD. #8930	ULTRATECH INTERNATIONAL 800/353-1611 EXT 211	05/02/13	4611	Α	ADJUSTABLE FRAME INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	ULTRA-DRAIN GUARD RE-USABLE NO FRAME	ULTRATECH INTERNATIONAL 800/353-1611 EXT 211	11/09/06	3308	Α	VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED
00280.16D	INLET PROTECTION - TYPE 3	WIRELESS DRAIN WEB DD-W-100 (SERIES)	ENVIROMET 360/944-6100	04/02/18	5114	A	MODEL DD-100 HAS AN OVER FLOW MODEL DD-W100NO NO OVER FLOW
00280.16D	INLET PROTECTION - TYPE 3 24" X 36" MAX	ULTRA-DRAIN GUARD ECONOMY FRAME ADJ. FRAME MOD. #8936	ULTRATECH INTERNATIONAL 800/353-1611 EXT 211	11/21/19	5224	Α	ADJUSTABLE FRAME INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED OVERFLOW OPENINGS
00280.16D	INLET PROTECTION - TYPE 3 GAS & OIL	ULTRA-DRAIN GUARD OIL & SEDIME NO FRAME	ULTRATECH INTERNATIONAL 800/353-1611 EXT 211	01/10/08	3309	Α	FOR GAS & OIL. VERIFY PRODUCT SIZE VS INLET SIZE. INSTALL PER MFG INSTRUCTIONS. MONITOR & MAINTAIN AS REQUIRED

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.16D	INLET PROTECTION - TYPE 4	BIO FILTER BAG	CITY OF ROSES DISPOSAL AND RECYCLING INC. 503/849-8881	11/12/09	2430	Α	NOT BIO-DEGRADEABLE WAS NAMED GRABHORN BIO FILTER BAG
00280.16D	INLET PROTECTION - TYPE 4	SILTRAP BIO BAGS	HIGHWAY FUEL 503/363-6444	11/13/08	3697	Α	PRESIZED WOOD CHIPS IN POLY MESH BAG.
00280.16D	INLET PROTECTION - TYPE 4	SLOPEGARD 3	KRISTAR ENTERPRIS 800/579-8819	11/09/06	2633	Α	
00280.16D	INLET PROTECTION - TYPE 6 OTHER	GEOFILTER	GEOHAY 864/472-7000	12/13/07	3580	Α	
00280.16D	INLET PROTECTION - TYPE 7	CURLEX SEDIMENT LOG	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	05/08/08	2624	Α	
00280.16D	INLET PROTECTION - TYPE 7	CURLEX SFW WATTLES	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	02/13/15	4863	Α	
00280.16D	INLET PROTECTION - TYPE 7	DREAM STREAM GCDOTFB-3624	THE GATE COMPANY 360/273-5802 MANARK PRODUCTS 360/790-9271	10/14/10	4174	Α	NEED TO MONITOR.
00280.16D	INLET PROTECTION - TYPE 7	ENVIRO STRAW 9" STRAW WATTLE	ENVIRO-STRAW 208/270-1225	01/21/14	4703	Α	
00280.16D	INLET PROTECTION - TYPE 7	FILTREXX FILTERSOXX INLETSOXX	FILTREXX INTERNATIONAL 440/926-2607	12/08/05	3258	Α	

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.16D	INLET PROTECTION - TYPE 7	FILTREXX FILTERSOXX SILTSOXX	FILTREXX INTERNATIONAL 440/926-2607	06/11/09	3256	Α	USE MFG APPROVED COMPOST MEDIA & ADDITIVES & MEET ODOT SPECS.
00280.16D	INLET PROTECTION - TYPE 7	SS FIBER ROLLS (9X25) UV	EROSION CONTROL SERVICES MARK CLELLAND 208/337-4620	04/08/10	3928	Α	
00280.16E	SEDIMENT BARRIER, OTHER	DIRTBAG 55	ACF ENVIRONMENTAL DAVID KELLY 800/448-3636 DIST.: ACF WEST, INC. MELISSA HURLEY 503/771-5115	02/12/09	1886	Α	THIS BAG IS 180" BY 180". AND TESTED TO 100 LB/IN2. APPLICATION: DOWNSTREAM END OF PIPE.
00280.16E	SEDIMENT BARRIER, OTHER	FILTREXX FILTERSOXX SILTSOXX	FILTREXX INTERNATIONAL 440/926-2607	06/11/09	3256	Α	USE MFG APPROVED COMPOST MEDIA & ADDITIVES & MEET ODOT SPECS.
00280.16E	SEDIMENT BARRIER, TYPE 1	ENVIRO STRAW 9" STRAW WATTLE	ENVIRO-STRAW 208/270-1225	01/21/14	4703	Α	
00280.16E	SEDIMENT BARRIER, TYPE 3	AEC PREMIER STRAW WATTLES	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	11/09/06	3327	Α	
00280.16E	SEDIMENT BARRIER, TYPE 3	CAL VISTA RICE STRAW WATTLE 8 X 25	CAL VISTA EROSION CONTROL JERRY SHADINGER 530/476-0706	12/11/08	3526	Α	
00280.16E	SEDIMENT BARRIER, TYPE 3	EARTHSAVER 8.25x25 WHEAT STRAW WATTLE	EARTHSAVERS EROSION CONTROL 530/662-7700	05/31/12	4410	Α	PHOTODEGRADABLE
00280.16E	SEDIMENT BARRIER, TYPE 3	EARTHSAVER RICE STRAW WATTLES	RH DYCK 530/662-7700 BUSSARD EROSION 800/252-2692 CSI GEOSYNTHETICS 360/699-1426	07/11/02	2431	Α	

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.16E	SEDIMENT BARRIER, TYPE 3	IEC 9" STRAW WATTLE	IDAHO EROSION CONTROL 208/329-9120 PACIFIC GEOSOURCE 503/261-3515	10/14/10	4184	Α	
00280.16E	SEDIMENT BARRIER, TYPE 3	OSW-NATURAL NET STRAW WATTLE	OREGON STRAW WATTLE 503/519-0848	09/10/18	5151	Α	WHEAT/RYE STRAW BIODEGRADABLE
00280.16E	SEDIMENT BARRIER, TYPE 3	OSW-R9 STRAW WATTLE	OREGON STRAW WATTLE 503/519-0848	12/11/08	3722	Α	RYE STRAW
00280.16E	SEDIMENT BARRIER, TYPE 3	RICE STRAW FIBER ROLL	KRISTAR ENTERPRIS 800/579-8819	11/09/06	2634	Α	
00280.16E	SEDIMENT BARRIER, TYPE 3	SEDIMENTSTOP	NORTH AMERICAN GREEN 800/772-2040 ACF WEST 800/878-5115	07/13/06	3286	Α	
00280.16E	SEDIMENT BARRIER, TYPE 3	SLOPEGARD 1	KRISTAR ENTERPRIS 800/579-8819	11/09/06	2632	Α	APPEARS OK AS TYPE 3 SEDIMENT BARRIER.
00280.16E	SEDIMENT BARRIER, TYPE 3	SOIL STOPPERS RICE STRAW WATTL 9" WATTLE	SOIL STOPPERS 209/993-2109	03/08/07	3439	Α	
00280.16E	SEDIMENT BARRIER, TYPE 3	SS FIBER ROLLS (9X25) UV	EROSION CONTROL SERVICES MARK CLELLAND 208/337-4620	04/08/10	3928	Α	TYPE 3.
00280.16E	SEDIMENT BARRIER, TYPE 3	STRAW WATTLE 9"	KT MANUFACTURING 208/576-3301	09/26/18	5153	Α	PHOTODEGRADABLE 6-12 MONTHS OR 12-18 MONTHS AVAILABLE

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.16E	SEDIMENT BARRIER, TYPE 3	WESTERN FIBER 9" STRAW WATTLE	WESTERN FIBER CO. 661/854-5556 OR 310/939-9254	11/13/08	3710	Α	WHEAT STRAW, POLYETHYLENE NET PHOTODEGRADABLE
00280.16E	SEDIMENT BARRIER, TYPE 3 STRAW WATTLE	PERMALOK/PERMEATEX STRAW WATTL	NORTHWEST LININGS & GEOTEXTILE 253/867-5366	10/14/10	4194	Α	RICE STRAW
00280.16E	SEDIMENT BARRIER, TYPE 4	WOVEN POLYPROPYLENE SANDBAG MODEL: PPB1426T1600	SACRAMENTO BAG CO 800/287-2247 BUSSARD EROSION CONTROL 800/252-2692	07/11/02	2429	Α	
00280.16E	SEDIMENT BARRIER, TYPE 7	ENVIRONMENTAL BARRICADE	BONAR PLASTICS 360/887-2230 ENVIRONMENTAL BARRICADES RICHARD STRIEFEL 800/656-1296	06/14/01	2401	Α	
00280.16E	SEDIMENT BARRIER, TYPE 7	GEOBALE	GEOHAY 864/472-7000	12/13/07	3579	Α	
00280.16E	SEDIMENT BARRIER, TYPE 7	GEOFILTER	GEOHAY 864/472-7000	12/13/07	3580	Α	
00280.16E	SEDIMENT BARRIER, TYPE 7	HARD SURFACE GUARD	ERTEC ENVIRONMENTAL SYSTEMS 866/521-0724	11/05/18	5146	Α	
00280.16E	SEDIMENT BARRIER, TYPE 7	PROWATTLE	ERTEC ENVIRONMENTAL SYSTEMS 866/521-0724	11/05/18	5144	Α	
00280.16E	SEDIMENT BARRIER, TYPE 7	S-FENCE	ERTEC ENVIRONMENTAL SYSTEMS 866/521-0724	11/05/18	5145	Α	

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
00280.16E	SEDIMENT BARRIER, TYPE 7	TRIANGULAR SILT DIKE	TRIANGULAR SILT DIKE CO, INC. REP: JASON ROACH 405/741-7406 CSI GEOSYNTHETICS 800/426-7976	09/13/01	1592	Α	DO NOT USE IN WATER. RE-USEABLE. SUITABLE SUBSTITUTION FOR SAND BAGS.
00280.16E	SEDIMENT BARRIER, TYPE 8	SILTRAP BIOFILTER SOCK	HIGHWAY FUEL 503/363-6444	05/12/20	5259	Α	BIODEGRADABLE SWITCHGRASS NOT APPROVED NOT REUSABLE, NOT MOVABLE ONCE PLACED
00280.16F	SEDIMENT MAT	SEDIMAT	INDIAN VALLEY INDUSTRIES 800/659-5111 CSI GEOSYNTHETICS 800/426-7976	06/14/07	1924	Α	FOR USE ON DOWNSTREAM END OF OUTLET END OF PIPE.
00280.16K	SEDIMENT CONTROL MATERIAL FLOCCULANT	CHITOSAN LACTATE PASSIVE TREATMENT SOCK/GELFLOC SOCK	SOUND ENVIRONMENTAL CONCEPTS,LLC 206/730-5376	11/14/17	5082	Α	
00280.16K	SEDIMENT CONTROL MATERIAL FLOCCULANT	CHITOVAN LIQUID (ACETATE) 1%	DUNGENESS ENVIRONMENTAL 206/730-5370 ACF WEST 800/878-5115 CSI GEOSYNTHETICS 800/426-7976	09/11/10	3837	Α	
00280.16K	SEDIMENT CONTROL MATERIAL FLOCCULENT	CHITOVAN CHITOSAN LACTATE CARTRIDGE	DUNGENESS ENVIRONMENTAL SOLUTIONS, INC 425/481-0600 HANES GEO SOLUTIONS 360/831-3613	10/05/20	5293	Α	
00340.11A	CHEMICAL DUST CONTROL-DRY TYPE 2	AIRTROL GEOBINDER	USG CORPORATION 916/417-5048 HANES GEO COMP. 800/324-4594 HANES GEO COMPONENTS 800/324-4595	07/09/09	3905	Α	
00340.11A	CHEMICAL DUST CONTROL-DRY TYPE 2	DUST ARMOUR	USG CORPORATION 916/417-5048 HANES GEO COMP. 800/324-4594	07/09/09	3904	Α	
00340.11A	CHEMICAL DUST CONTROL-DRY TYPE 2	DUST STOP	CYPHER INTERNATIONAL LTD. 204/489-1214	01/10/08	3173	Α	MFG CLAIMS NATURAL POLYSACCHARIDES.

<sup>\*</sup>LIST 'A' = APPROVED. MAY BE USED WITHOUT SAMPLES, TESTING, OR QUALITY COMPLIANCE CERTIFICATIONS. MAY NEED A FIELD INSPECTION REPORT.

\*\*LIST 'Q' = QUALIFIED. USE WITH SAMPLING, TESTING, &/OR QUALITY COMPLIANCE CERTIFICATIONS AS NEEDED. NEEDS A FIELD INSPECTIONS REPORT. CHECK SPECS AND NFTMAG.
LIST PUBLISHED BY: ODOT MATERIALS LAB; 800 AIRPORT RD SE; SALEM, OR 97301-4798; (503) 986-3059. PLEASE REPORT ANY PROBLEMS USING THESE PRODUCTS.

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
01012.11	POROUS PAVERS LIGHT, MEDIUM, HEAVY DUTY	STORM WATER CONTROL WATER QUALITY BIOFILTRATION SWALE		01/01/22		Α	SEE SECTION 01011.11
01030.15A	MULCHES TEMPORARY	RAINIER FIBER	RAINIER VENEER INC FIBER MARKETING INT INC 206/459/4942	02/16/11	4346	Α	
01030.15A	MULCHES TEMPORARY W/TACK	RAINIER FIBER + TAC	RAINIER VENEER INC FIBER MARKETING INT INC 206/459/4942	02/16/11	4347	Α	
01030.15A	MULCHES, TEMPORARY	AIRTROL GEOBINDER	USG CORPORATION 916/417-5048 HANES GEO COMP. 800/324-4594	07/09/09	3905	Α	
01030.15A	MULCHES, TEMPORARY	BINDEX BLEND	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	12/10/12	4565	Α	60% WOOD FIBER 40% RECYCLED PAPER
01030.15A	MULCHES, TEMPORARY	BINDEX WOOD	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	12/10/12	4566	Α	WOOD FIBERS
01030.15A	MULCHES, TEMPORARY	EARTH BARRIER MBFM	AGRIVESTMENTS 253/383-5014	08/14/08	3670	Α	
01030.15A	MULCHES, TEMPORARY	ENVIRO-BLANKET MULCH W/AIRTROL WOOD FIBER HYDRAULIC MULCH	USG CORPORATION 916/417-5048 HANES GEO COMP. 800/324-4594	07/09/09	3907	Α	
01030.15A	MULCHES, TEMPORARY	ENVIRO-BLANKET WOOD FIBR MULCH HYDRAULIC MULCH	USG CORPORATION 916/417-5048 HANES GEO COMP. 800/324-4594	07/09/09	3906	Α	

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
01030.15A	MULCHES, TEMPORARY	ENVIROPAM L	INNOVATIVE TURF SOLUTIONS 513/317-8311	03/10/11	4318	Α	WAS NAMED HYDRAPAM
01030.15A	MULCHES, TEMPORARY	ENVIROPAM(L) LIQUID	INNOVATIVE TURF SOLUTIONS 513/317-8311	03/10/11	4318	Α	WAS NAMED HYDRAPAM (L)
01030.15A	MULCHES, TEMPORARY	ENVIRO-SHIELD BONDED FIBER MATRIX	USG CORPORATION 916/417-5048 HANES GEO COMP. 800/324-4594	12/11/08	3533	Α	HYDRAULICALLY APPLIED MULCH.
01030.15A	MULCHES, TEMPORARY	EXCEL FIBERMULCH II	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	11/14/02	2625	Α	ON TEXAS DOT QPL.
01030.15A	MULCHES, TEMPORARY	GEOSKIN	MULCH & SEED INNOVATION 205/540-5775	08/13/09	3897	Α	85% STRAW & 15% COTTON PLANT MATERIAL.
01030.15A	MULCHES, TEMPORARY	GRASS MULCH	GRASS FIBER INC. 520 E. 2ND ST JUNCTION CITY, OR 97448	05/01/88	2131	Α	MAIN COMPONENT:CELLULOSE FIBER ORGANIC. WITHOUT TACKIFIER.
01030.15A	MULCHES, TEMPORARY	GROUNDCONTROL HY-C1 STRAW & COTTON	EAST COAST EROSION CONTROL 610/488-8496	05/03/13	4618	Α	HYDRAULICALLY APPLIED
01030.15A	MULCHES, TEMPORARY	GROUNDCONTROL HY-C3 STRAW & COTTON	EAST COAST EROSION CONTROL 610/488-8496	05/03/13	4619	Α	HYDRAULICALLY APPLIED
01030.15A	MULCHES, TEMPORARY	HYDRA CM STEEP SLOPE MATRIX	NORTH AMERICAN GREEN 800/772-2040 OR 812/687-6632	11/11/10	4265	Α	70% STRAW & 20% RECLAIMED COTTON FIBER.

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
01030.15A	MULCHES, TEMPORARY	HYDROSPRAY	CELLULOSE FIBER 253/627-8008 EMERALD SEED & SUPPLY 541/504-0307	11/09/06	3063	Α	INSTALL PER 01030.48(A)3.
01030.15A	MULCHES, TEMPORARY	HYDROSTRAW ALL IN 1 BONDED FIBER MATRIX	HYDROSTRAW 800/545-1755 RON EDWARDS	07/09/15	4899	Α	
01030.15A	MULCHES, TEMPORARY	HYDROSTRAW BONDED FIBER MATRIX	HYDROSTRAW 800/545-1755 RON EDWARDS	11/11/10	4164	Α	
01030.15A	MULCHES, TEMPORARY	HYDROSTRAW GUAR PLUS FORMULA	HYDROSTRAW 800/545-1755 RON EDWARDS	11/11/10	4165	Α	3% GUAR
01030.15A	MULCHES, TEMPORARY	HYDROSTRAW HE CELLULOSE FIBER PLUS	PROFILE PRODUCTS, LLC 800/578-2354 ACF WEST 503/771-5115	09/24/21	5365	Α	WHEAT STRAW FIBERS HIGH VISCOSITY COLLOIDAL POLYSACCHARIDES
01030.15A	MULCHES, TEMPORARY	MAT-FIBER	MAT, INC. 888/477-3028 CSI GEOSYNTHETICS 800/426-7976	01/13/05	2981	Α	WOOD FIBER FOR HYDRO SEEDING
01030.15A	MULCHES, TEMPORARY	MAT-FIBER PLUS	MAT, INC. 888/477-3028 CSI GEOSYNTHETICS 800/426-7976	01/13/05	2982	Α	WOOD FIBER FOR HYDRO SEEDING W/3% GUAR GUM TACKIFER.
01030.15A	MULCHES, TEMPORARY	NATURE'S OWN MULCH W/O TAC	HAMILTON MANUFACTURING 208/733-9689	03/12/98	1727	Α	MAIN COMPONENT: CELLULOSE FIBER - PAPERWOOD. ORGANIC. W/O TACKIFIER. RECYCLED PAPERWOOD FIBER.
01030.15A	MULCHES, TEMPORARY	NATURESOWN MULCH W/TAC	HAMILTON MANUFACTURING 208/733-9689	02/27/12	4450	Α	

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
01030.15A	MULCHES, TEMPORARY	PAM 12	ENCAP 877/405-5050	12/11/08	3545	Α	PAPER/STRAW WITH TACKIFIER.
01030.15A	MULCHES, TEMPORARY	PERMAMATRIX BIOTIC SOIL AMENDM	SUNMARK ENVIRONMENTAL 503/241-7333	11/11/10	4218	Α	
01030.15A	MULCHES, TEMPORARY	PROFILE SB 50/50	PROFILE PRODUCTS, LL 808/312-7671 ACF WEST INC 503/849-0971	04/11/22	5425	Α	HYDRAULICALLY APPLIED
01030.15A	MULCHES, TEMPORARY	PROFILE WOOD	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	07/13/06	3316	Α	
01030.15A	MULCHES, TEMPORARY	PROFILE WOOD WITH TACK	PROFILE PRODUCTS 847/215-1144 DAMON SUMP 503/537-8462 ACF WEST 800/878-5115	03/13/08	3611	Α	WOOD FIBER W/3% GUAR GUM TACKIFIER
01030.15A	MULCHES, TEMPORARY	SSEC LEGACY BLEND	PROFILE PRODUCTS, LLC 800/578-2354 CASCADE GEOSYNTHETICS 971/339-1019	09/24/21	5366	Α	WHEAT STRAW FIBERS
01030.15A	MULCHES, TEMPORARY	TURBOMULCH 70% WOOD	WESTERN EXCELSIOR 800/967-4009 GEOTK 360/750-1955 DIST.: EMERALD SEED & SUPPLY	06/08/00	1804	Α	WOOD FIBER, ORGANIC. W/O TACKIFIER. BIODEGRADABLE. 70% WOOD, 30% PAPER W/DYE.
01030.15A	MULCHES, TEMPORARY	WOODSTRAW	FOREST CONCEPTS 877/838-4759	12/13/07	3587	Α	
01030.15A	MULCHES, TEMPORARY W/TACKIFIER	BINDEX BLEND WT	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	12/10/12	4564	Α	60% WOOD FIBER 40% RECYCLED PAPER

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
01030.15A	MULCHES, TEMPORARY W/TACKIFIER	BINDEX WOOD WT	AMERICAN EXCELSIOR 888/352-9582 OR 715/236-5643 HANES GEO COMPONENTS 360/699-1426	12/10/12	4567	Α	WOOD FIBERS
01030.15A	MULCHES, TEMPORARY W/O TACKIFIER	NATURESOWN EVOLUTION 70	HAMILTON MANUFACTURING 208/733-9689	02/10/11	4202	Α	AGRICULTURAL FIBERS AND WOOD CELLULOSE FIBERS. HYDR APPLIED
01030.15A	MULCHES, TEMPORARY W/TACKIFIER	NATURESOWN EVOLUTION	HAMILTON MANUFACTURING 208/733-9689	02/10/11	4203	Α	AGRICULTURAL FIBERS AND WOOD CELLULOSE FIBERS. HYDR APPLIED GUAR BASED TAC
01030.15A	MULCHES, TEMPORARY W/TACKIFIER	NATURESOWN X9000	HAMILTON MANUFACTURING 208/733-9689	02/10/11	204	Α	AGRICULTURAL FIBERS AND WOOD CELLULOSE FIBERS. HYDR APPLIED POLYMER BASED TAC
01030.15A	MULCHING TEMPORARY	NATURESOWN EVOLUTION 70	HAMILTON MANUFACTURING INC 208/733/9689	08/04/11	4202	Α	
01040.17	SOIL BIO-AMENDMENT	BACTIFEED SOIL TREATMENT	TERRA SANA, LLC 801/556-3727 SPOIL YOUR SOIL, LLC 541/761-6958	06/12/18	5140	Α	
01040.17	SOIL BIO-AMENDMENT	MYCOAPPLY ENDO	MYCORRHIZAL APPLICATIONS 866/476-7800 OR 541/476-3985	02/11/10	3938	Α	
01040.17	SOIL BIO-AMENDMENT	MYCOAPPLY ENDO PLUS	MYCORRHIZAL APPLICATIONS 866/476-7800 OR 541/476-3985	02/11/10	3939	Α	
01040.17	SOIL BIO-AMENDMENT	MYCOAPPLY ENDO/ECTO PLUS	MYCORRHIZAL APPLICATIONS 866/476-7800 OR 541/476-3985	02/11/10	3940	Α	

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
01040.17	SOIL BIO-AMENDMENT	MYCOAPPLY ENDONET	MYCORRHIZAL APPLICATIONS 866/476-7800 OR 541/476-3985	02/11/10	3944	Α	
01040.17	SOIL BIO-AMENDMENT	MYCOAPPLY MICRONIZED ENDO	MYCORRHIZAL APPLICATIONS 866/476-7800 OR 541/476-3985	02/11/10	3941	Α	
01040.17	SOIL BIO-AMENDMENT	MYCOAPPLY MICRONIZED ENDO/ECTO	MYCORRHIZAL APPLICATIONS 866/476-7800 OR 541/476-3985	02/11/10	3942	Α	
01040.17	SOIL BIO-AMENDMENT	MYCOAPPLY SOLUBLE MAXX	MYCORRHIZAL APPLICATIONS 866/476-7800 OR 541/476-3985	02/11/10	3943	Α	
01040.17	SOIL BIO-AMENDMENT	NATURE'S OWN LIVING HUMUS	NATURE'S NEEDS 503/647-9489	04/14/05	2947	Α	
01040.17	SOIL BIO-AMENDMENT	PERMAMATRIX BIOTIC SOIL AMENDM	SUNMARK ENVIRONMENTAL 503/241-7333	11/11/10	4218	Α	
01040.17E	SOIL BIO-AMENDMENT MYCORRHIZAL	BIOTIC EARTH BLACK	VERDYOL PLANT REASEARCH 320/910-4800 ACF WEST 503/771-5115	05/30/13	4663	Α	
01040.17E	SOIL BIO-AMENDMENT MYCORRHIZAL	FUSION	LSC ENVIRONMENTAL PRODUCTS 800/800-7671 HANES GEOCOMPONENTS 800/426-4976	06/19/19	5199		HYDRO. APPLIED, GAR, PAM STABILIZER SOIL BIO-AMENDMENTS
01040.17E	SOIL BIO-AMENDMENT MYCORRHIZAL	PROGANICS BIOTIC SOIL MEDIA (BSM)	PROFILE PRODUCTS LLC 800/508-8681  ACF WEST 503/771-5115	08/04/15	4897	Α	

STANDARD SPEC #	CATEGORY	PRODUCT NAME	LOCAL REPRESENTATIVE AND/OR MANUFACTURER	EFFECTIVE DATE	PRODUCT NUMBER	LIST	REMARKS
01040.17F	SOIL BIO-AMENDMENT MICROBES	AG-1000	TERAGANIX 866/396-8976 EMERGE DNA 458/215-9922	12/04/20	5314	Α	
01040.22	MOISTURE RETENTION CHEMICAL - FOR SOIL	SOIL MOIST - POLYMER	JRM CHEMICAL 800/962-4010 1675 MARYLHURST DR WEST LINN, OR 97068 503/636-8849	11/09/06	446	Q	ACRYLIC POLYMER REDUCE WATERINGS BY 50%. INTENDED FOR PLANTING IN LOW MOISTURE AREAS. CONSTRUCTION MATERIAL CMO REQUIRED
01070.00	MAILBOX SUPPORTS	T&T MAILBOX SUPPORT MODELS 15001 & 15002	TRAFFIC SAFETY/TAPCO 800/547-8518	07/14/05	3166	Α	SLIGHT MODIFICATION OF TAPCO SUPPORT BY TRAFFIC SAFETY TO MEET OUR REQUIREMENTS - RD100. INCLUDES V-WING ANCHOR (20VR3)
01090.11	WEED CONTROL GEOTEXTILE	MIRAFI MSCAPE E	TENCATE GEOSYNTHETICS 480/489-0601 CASCADE GEOSYNTHETICS 971/339-1020	03/24/22	5398	Q	
							CONSTRUCTION MATERIAL CMO REQUIRED
02010.10	CEMENT, TYPE I, II	ASIA CEMENT COMPANY TAIWAN	ASHGROVE CEMENT CO. DAVE BURG 503/207-2109	12/09/20	5306	Α	ASIA CEMENT COMPANY TAIWAN AASHTO TYPE I, II
02010.10	CEMENT, TYPE I, II	CAL PORTLAND - MOJAVE CEMENT	CALPORTLAND COMPANY DAVE GERMER 971/235-2540	12/11/08	3724	Α	
02010.10	CEMENT, TYPE I, II	CAL PORTLAND - NANJING	CALPORTLAND COMPANY DAVE GERMER 971/235-2540	05/14/09	1619	Α	SOURCE: ONODA (NANJING).
02010.10	CEMENT, TYPE I, II	NEVADA CEMENT	NEVADA CEMENT 775/575-2281 LAKEVIEW REDIMIX 541/947-2212	01/12/06	3229	Α	SUBSTANCIALLY MET AASHTO M85 TYPE I, DID NOT MEET TYPE II REQUIREMENTS.
02010.10	CEMENT, TYPE III	ASH GROVE CEMENT - MONTANA CITY	ASHGROVE CEMENT CO. DAVE BURG 503/207-2109	04/03/19	5189	Α	MONTANA CITY AASHTO TYPE III

## **INSERT TAB**

## **NTMAG**

# OREGON DEPARTMENT OF TRANSPORTATION CONSTRUCTION SECTION

## NONFIELD-TESTED MATERIALS ACCEPTANCE GUIDE

## 2024 STANDARD SPECIFICATIONS

January 2024 UPDATE



Updated versions of this guide are available by printing from the web address listed below. This document is to be used as a guide for documentation required for acceptance of Materials on ODOT Construction projects and does not relieve the user of requirements specified in the Construction Project Documents. Please notify the Contract Administration Unit, in the Construction Section at the ODOT Materials Laboratory, of any changes in Standard Drawings, Special Provisions, or Standard Specifications, etc., which would require additions to, deletions from, or changes to this listing.

Internet Address: https://www.oregon.gov/ODOT/Construction/Pages/Structure-Services.aspx

Contact 541-784-7721 to have correction made to this guide. A summary of changes since last publication is found at the end of this document.

\*Special Provisions, Contract Plans, and Standard Specifications take precedence over this guide per 00150.10(a). Refer to the Contract for documentation requirements.

## Oregon Department of Transportation Nonfield-Tested Materials Acceptance Guide 2024 Standard Specifications

					ACCEPTAN	ICE DOCUMENTS	5	
				FURNIS	SHED BY	FURNISHED	BY AGENCY	
SECTION	TYPE OF CONSTRUCTION	MATERIALS	SUBSECTION	CONTRA	CTOR TO	MATERIALS	FIELD	REMARKS
				LAB	ENGR.	LAB	PERSONNEL	
		Rock Gabion Baskets	Refer to 00596A in this guid	e.				
00245 <b>SP</b> (con't)	Temporary Water Management (continued)	Turbidity Monitoring	00245.60		R			"R" is Turbidity Monitoring Reports according to 00290.30(a)(8).
00250 Special Provision	Diversion Bridges  Refer to Special Provisions for any	Submittals	00250.03		E			"E" is submittal(s) according to 00250.03 and 00150.35, at least 14 days before preinstallation conference.
	additional Contract-specific	New Material	Refer to 00500 in this guide					
	requirements.	- Precast Prestressed Concrete Members	Refer to 00550 in this guide					
		Used Material	00250.10(c)					
		Structural Steel Members     Documented Steel     Undocumented Steel	00250.10(c)(2) 02530		T, Q, O		F	
		- Timber Members	Refer to 00570 in this guide					
		- Piling, Steel Piles	Refer to 00520 in this guide					Used timber piles not allowed.
00252 Special Provision	Temporary Work Bridges	Submittals	00252.40		Е			"E" is submittal(s) according to 00252.40 and 00150.35.
00253	Temporary Work Access and Containment	Submittals	00253.03		E			"E" is submittal(s) according to 00253.03 and 00150.35, a minimum of 21 Calendar Days before preconstruction conference.
00270	Temporary Fences	New Materials	Refer to 01050.10 in this gu	ide.	l .			Refer to Contract Documents for required Materials.
		Temporary Barrier	Refer to 00226.11(a) in this	guide.				Refer to Contract Documents for required Materials.
00280	Erosion and Sediment Control (ESC)  Engineer must ensure specified  Materials and measures for Erosion and Sediment Control are used and documentation provided as required in	Erosion and Sediment Control Plan - on Agency Controlled Lands - on Non-Agency Controlled Lands	00280.04 00280.05		E			"E" is submittal(s) according to 00280.04 and 00280.05 at least 10 Calendar Days before preconstruction conference.  Note on test summary the date plan was received. Plan does not need to be submitted with semi-final documentation for non-Doc Express Projects.
	this guide.	Erosion and Sediment Control Manager	00280.30		P			"P" is current ODOT ESCM certification or documentation of successful completion of alternative erosion control training accepted by Engineer submitted according to 00280.30 at least 10 Calendar Days before preconstruction conference.
	(continued on next page)	Erosion and Sediment Control Monitoring	00280.30 00280.62		R			"R" is Erosion and Sediment Control Monitoring Reports according to 00280.30 and 00280.62.

					ACCEPTAN	ICE DOCUMENT:	S	
				FURNIS	SHED BY	FURNISHED	BY AGENCY	g.  " is from manufacturer.  PL" is for hydromulch fiber.  " is seed lab test results for weed seed content.  " is "Oregon Certified Seed" field source, or Department Agriculture certified weed free.  " is for Construction Material CMO according to 160.20(d) for Channel Liner Matting Type F, G, and H Italled as permanent features.  " is seed lab test results for weed seed content.  " is "Oregon Certified Seed" field source, or Department Agriculture certified weed free.  Id fabricated systems are not acceptable.
SECTION	TYPE OF CONSTRUCTION	MATERIALS	SUBSECTION	CONTRA	ACTOR TO	MATERIALS	FIELD	REMARKS
				LAB	ENGR.	LAB	PERSONNEL	
00280	Erosion and Sediment Control (ESC)	Seed (Temporary)	01030.13		Т		F	"T" is germination and purity information from tag on seed bag.
(con't)	(continued)	Fertilizer	01030.14		Q		F	"Q" is from manufacturer.
	For temporary items under 00280,	Mulch, Hydromulch (temporary or permanent)	00280.14(d) 01030.15(a)		Q		F, QPL	"QPL" is for hydromulch fiber.
	Engineer must verify items are as required by Contract Documents and functioning as intended.	Mulch, Straw (temporary or permanent)	00280.14(d) 01030.15(b)		T or Q		F	"T" is seed lab test results for weed seed content. "Q" is "Oregon Certified Seed" field source, or Department of Agriculture certified weed free.
	For permanent items under 00280, Engineer must acquire and retain the required documentation.	Slope and Channel Liner Matting – Bonded Fiber Matrix, Polypropylene or Polymer	00280.14(e)		С		F, QPL	"C" is for Construction Material CMO according to 00160.20(d) for Channel Liner Matting Type F, G, and H installed as permanent features.
	required documentation.	Check Dams - Cereal Straw Based Products	00280.15(a) 01030.15(b)		T or Q		F	"T" is seed lab test results for weed seed content.
								"Q" is "Oregon Certified Seed" field source, or Department of Agriculture certified weed free.
		Check Dams, Type 5 - Prefabricated System	00280.15(a)				F, QPL	Field fabricated systems are not acceptable.
		Compost	00280.14(f) 00280.15(a) Type 6 00280.15(f) 00280.15(g) 00280.16(d) Type 7 00280.16(e) Type 8&9 03020.00		T, Q, P/R		F	"T" is STA lab analysis of compost.  "Q" is from Supplier according to 03020.10 and 00165.35.  "P/R" is copy of the DEQ permit or registration of compost Supplier.  Note: Tackifier required according to 00280.14(b)(2) for Compost Erosion Blanket and/or Compost Berm.
		Inlet Protection, Type 3 - Prefabricated Filter Inserts	00280.16(d)				F, QPL	
		Sediment Barrier – Cereal Straw Based Products	00280.16(e) 01030.15(b)		T or Q		F	"T" is seed lab test results for weed seed content.  "Q" is "Oregon Certified Seed" field source, or Department of Agriculture certified weed free.
		Sediment Barriers, Type 7 - Prefabricated Barrier System	00280.16(e)				F, QPL	
		Sediment Barriers, Sediment Mat	00280.16(f)				F, QPL	
		Straw Bales	00280.14(g) 01030.15(b)		Q		F	"Q" is "Oregon Certified Seed" field source, or Department of Agriculture certified weed free.
		Sediment Control - Geotextile	Refer to 00350 in this guide	·				
		Prefabricated Construction Entrance	00280.16(a)				F	"F" must document visual verification.

				ACCEPTANCE DOCUMENTS				
SECTION	TYPE OF CONSTRUCTION	MATERIALS	SUBSECTION		SHED BY	FURNISHED	BY AGENCY	REMARKS
SECTION	TIPE OF CONSTRUCTION	IVIATERIALS	SUBSECTION	CONTRA	CTOR TO	MATERIALS	FIELD	NEIWIANNO
				LAB	ENGR.	LAB	PERSONNEL	
00290	Environmental Protection	Environmental Protection	Refer to Contract Specificat	tions for restr	rictions and re	equired submitta	als.	
		Turbidity Monitoring	00290.30(a)(8)		R			"R" is Turbidity Monitoring Reports according to Special Provision 00290.30(a)(8).
		Pollution Control Plan	00290.30(b)		E			Note on test summary the date plan was received. Plan does not need to be submitted with semi-final documentation for non-Doc Express Projects.
			00300 - ROAD	WORK				
00305	Construction Survey Work	3D Engineered Models	00305.05		Е			
00310	Removal of Structures and Obstructions	Section does not contain any nonfield	d-tested materials.					
00320	Clearing and Grubbing	Section does not contain any nonfield	d-tested materials.					
00330	Earthwork	Selected Topsoil	Refer to 01040 in this guide	2.				
00331	Subgrade Stabilization	Subgrade Geotextile	Refer to 00350 in this guide	2.				
		Subgrade Reinforcement Geogrid	Refer to 00350 in this guide	2.				
00335	Blasting Methods and Protection of Excavation Backslopes	Blasting Plan	00335.40(d)		E			"E" is submittal(s) according to 00335.40(d) at least 21 Calendar Days before beginning drilling for excavations or when any perimeter controlled blasting is required.
		Blasting Reports	00335.40(h)		R			"R" is submittal(s) according to 00335.40(h) within 48 hours of making each blast.
00340	Watering	Additives	00340.11				F, QPL	"F" and "QPL" when called for by Special Provisions or ordered.


					ACCEPTAN	ICE DOCUMENTS	5		
CECTION.	TVDF OF CONSTRUCTION	*******	CURCECTION	FURNIS	SHED BY	FURNISHED	BY AGENCY	2514421/6	
SECTION	TYPE OF CONSTRUCTION	MATERIALS	SUBSECTION	CONTRA	CTOR TO	MATERIALS	FIELD	REMARKS	
				LAB	ENGR.	LAB	PERSONNEL		
00990 (con't)	Traffic Signals (continued)	Metal Illumination and Traffic Signal Supports	Refer to 00962 in this guide.						
		Illumination On and Associated Appurtenances On Traffic Signal Poles	Refer to 00970 of this guide.	•					
		Traffic Control Signs	00990.43 00940						
		Backer Rod and Loop Sealant	00990.10		С		F, QPL	"C" is for Construction Material CMO according to 00160.20(d)	
		01	000 - RIGHT OF WAY DEVELOR	MENT AND	CONTROL				
01030	Seeding	Submittals - Weed Control Work Plan	01030.42(a)		E			"E" is submittal(s) according to 01030.42(a) at the preconstruction conference when applicable to Project.	
		- Weed Control Coordinator	01030.30(a) 01030.42(b) 01030.42(c)(1)		P, R			"P" is submittal(s) according to 01030.30(a) at the preconstruction conference.  "R" is documentation according to 01030.42(c)(1) from an approved disposal facility.	
		Topsoil, Soil Conditioners, Amendments, and Bio-Amendments	Refer to 01040 in this guide.		<u> </u>				
		Seed	01030.13 01030.60 01030.61		Т, Q		F	"T" is test results showing purity/germination rates, seed percentages, and lot number for pure live seed according to Special Provisions.  "Q" is information on label (may be documented separately by cert) - must include verifiable lot number to	
								test results.  "F" at time of application shall include form 734-5180.  Additional "F" at end of Establishment Period must document that minimum ground coverage is achieved.	
		Fertilizers	01030.14		Q		F	"Q" is label on container.  "F" must document fertilizer proportions from label.	
	(continued on next page)	Hydromulch	01030.15(a)				F, QPL		
		Straw Mulch	01030.15(b)		T or Q		,	Submit "Q" or "T" according to 01030.15(b).	


					ACCEPTAN	ICE DOCUMENTS	5		
				FURNIS	HED BY	FURNISHED	BY AGENCY		
SECTION	TYPE OF CONSTRUCTION	MATERIALS	SUBSECTION	CONTRA	CTOR TO	MATERIALS	FIELD	REMARKS	
				LAB	ENGR.	LAB	PERSONNEL		
01030 (con't)	Seeding (continued)	Compost Mulch	01030.15(c) 03020		T, Q, P/R		F	"T" is particle size and media parameters results according to 03020.10.	
								"Q" is compost requirements according to 03020.10.	
								"P/R" is copy of DEQ permit or registration of compost producer.	
		Tackifier	01030.16		Q		F		
		Pesticides	01030.17 01030.30(b)		Q, P		F	"Q" is manufacturer's federal registered label, and MSDS (if requested). Must recieve approval prior to use.	
								"P" is for pesticide applicator according to 01030.30(b).	
01040	Planting	Submittals - Planting Work Plan	01040.04(a)		E			"E" is submittal(s) according to 01040.04(a) within 90 Calendar Days of Award of the Contract.	
		- Pesticide Applicators License and Chemical Registration	01040.03(b)		Р			"P" is submittal(s) according to 01040.03(b).	
		Soil Testing	01040.13		T		F	"T" is Soil fertility test and Soil amendment report.	
								"F" must document Soil sampling locations.	
		Selected Topsoil	00330.10 00330.11 01040.14(a)				F	"F" must document selected Topsoil appears to be plant and weed free, and is part of the Soil "A" horizon.	
								Submit 20 lb sample to Engineer for approval.	
		Imported Topsoil	01040.14(b)		Q	L	F	"L" is test results from ODOT Salem Central Materials Lab.	
								"Q" must confirm weed free.	
								Submit 20 lb sample to Engineer.	
		Wetland Topsoil	01040.14(c)		Q		F	"Q" must confirm wetland Topsoil is free from substances detrimental to plant growth.	
	(continued on next page)							Submit 20 lb sample to Engineer for approval.	


					ACCEPTAN	ICE DOCUMENTS	5		
				FURNIS	SHED BY	FURNISHED	BY AGENCY		
SECTION	TYPE OF CONSTRUCTION	MATERIALS	SUBSECTION	CONTRA	CTOR TO	MATERIALS	FIELD	REMARKS	
				LAB	ENGR.	LAB	PERSONNEL		
01040 (con't)	Planting (continued)	Soil Conditioners, Amendments, and Bio-Amendments	01040.15 01040.16 01040.17		T, Q, P/R		F	"T" and "P/R" are for commercially manufactured compost according to 03020.90.	
			03020					Submit 15 lb. sample of mushroom compost and Peat moss Soil conditioners to Engineer for approval.	
		Fertilizers	01030.14 01040.18		Q		F	"Q" is label on container.	
								"F" must document fertilizer proportions from label.	
		Plants	01040.19 01040.70-79		Q		F	"Q" is State inspection certificate and shipping certificate for each load or lot of plant material according to 01040.19(c). "Q" for sod lawn can be from turf farm according to 01040.19(h)(17).	
								"F" must document the condition of the plants at each inspection and Final Inspection.	
		Mulch - Bark - Cinder - Rock - Wood Chip	01040.20				F	"F" must document mulch appears to meet the applicable requirements of 01040.20(a),(b),(d),(e).	
		Straw Mulch	01030.15(b) 01040.20(c)		T or Q		F	Submit "T" or "Q" according to 01030.15(b).	
		Compost Mulch	01040.20(f) 03020		T, Q, P/R		F	"T" is particle size and media parameters results according to 03020.10.	
								"Q" is compost requirements according to 03020.10.	
								"P/R" is copy of DEQ permit or registration of compost producer.	
		Herbicides	01040.21		Q		F		
		Weed Control Geotextile	01040.23		Q, C		F	"C" is for Construction Material CMO according to 00160.20(d)	
		Water - Moisture Retention Chemicals	01040.22(b)				F, QPL		


## **INSERT TAB**

**Standard Drawings** 










## **WOODEN CURB RAMP SECTION D-D**

All materials shall be in accordance with the current Oregon Standard Specifications. The selection and use of this Standard Drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user and should not be used without first consulting a Registered Professional Engineer. CALC BOOK NO

**OREGON STANDARD DRAWINGS CONSTRUCTION ENTRANCES** 2024 REVISION DESCRIPTION 01–2021 REMOVED CALC BOOK NUMBERS

SDR DATE\_ 20-JAN-2021

**RD1000** 




NOTE

L = Spacing along swale or ditch so that Elevation "U" equals Elevation "D".

## TYPICAL PROFILE SECTION CHECK DAMS (SHOWN WITH AGGREGATE)


NOT TO SCALE



NOTE: Pt "A" must be a minimum of 6" higher than Pt "B"

## AGGREGATE CHECK DAM - TYPE 1

NOT TO SCALE





## **SANDBAG CHECK DAM - TYPE 4**


NOT TO SCALE

### NOTES

- 1. Type 3 stake biofilter bags with two 2"x2"x18" (minimum) wood stakes per bag. Drive stakes a minimum of 6" into the ground and flush with the top of the bags. Omit stakes if placed over paved surfaces. Overlap bags 12" minimum at each joint.
- 2. Type 4 Tightly abut or overlap ends of sandbags at each joint.
- 3. Spacing between check dams for all check dam types shall comply with the typical profile section shown above.







## **SECTION A-A**

## **BIOFILTER BAG CHECK DAM - TYPE 3**

NOT TO SCALE

The selection and use of this
Standard Drawing, while
designed in accordance with
generally accepted engineering
principles and practices, is the
sole responsibility of the user
and should not be used without
first consulting a Registered
Professional Engineer.

All materials shall be in accordance with the current Oregon Standard Specifications.

OREGON STANDARD DRAWINGS

CHECK DAMS
TYPE 1, 3 AND 4


2024


DATE REVISION DESCRIPTION
01-2021 REMOVED CALC BOOK NUMBERS

SDR DATE\_ 20-JAN-2021 **RD1005** 


Effective Date: June 1, 2024 - November 30, 2024

CALC BOOK NO






## Grate #5 Rebar #5 Rebar Flow Sewn 6" Sewn 6' overlap overlap Geotextile insert Filtered water





## GEOTEXTILE/WIRE MESH/AGGREGATE - TYPE 2

PREFABRICATED FILTER INSERT - TYPE 3 **NOT TO SCALE** 

### **SOD PROTECTION - TYPE 6** NOT TO SCALE







### **AREA DRAIN PLAN**

Compost filter sock or wattle. Use

sandbags to hold wattles in place.

Place a sandbag at each

3' OC to hold in place

end of wattle and

Sandbags are not necessary for

compost filter socks

Type 2 - Geotextile/wire mesh/aggregate Place the wire mesh over the grate. Place sediment fence geotextile over the wire mesh and perimeter area around structure. Install aggregate over the geotextile fabric.

Type 3 – Prefabricated filter inserts Install prefabricated filter inserts according to the plans, special provisions, and manufacturer recommendations. Prefabricated inserts with provisions for overflow are allowed only when accompanied by additional BMP's to prevent the potential of sediments entering project storm systems. Field fabricated inserts are not allowed.

Type 7 - Compost filter sock Drive 2"x2" wood stakes a minimum of 6" into ground and flush with the top of the sock.

Overlap ends of sock per manufacturers recommendations (12"min., 36" max.). Use 8" to 12" dia sock on curbside in traffic areas.

(Type 7 cont.) Use 12" to 18" dia sock in non-traffic areas or areas where the larger socks can be used safely. use synthetic mesh socks for temporary

installations.

**CURB INLET SEDIMENT DAM - TYPE 10** 

NOT TO SCALE

Type 10 - Curb inlet sediment dam Fit curb inlet sediment dam snugly into inlet mouth. Curb inlet sediment dam is required for use with inlet filter insert where at-grade inlet grate and curb inlet

Type 11 - Wattle barrier with filter insert Install prefabricated filter insert per Type 3 detail.

## **WATTLE BARRIER WITH FILTER INSERT - TYPE 11**

are combined at a catch basin.

Install wattles over opening and 36" to each

side of opening tight against curb. Adjust wattle to force storm water to flow through filter insert or wattle prior to leaving the

Adjust, replace or modify the inlet protection as needed to prevent sediment laden water from entering the catch basin.

The selection and use of this Standard Drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user and should not be used without first consulting a Registered Professional Engineer.

### All materials shall be in accordance with the current Oregon Standard Specifications. **OREGON STANDARD DRAWINGS**


**INLET PROTECTION** TYPE 2, 3, 6, 7, 10 AND 11


2024


DATE	REVISION DESCRIPTION				
01-2021	REMOVED CALC BOOK NUMBERS				
01-2021	MOVED NOTES UP FROM OVERLAPPING THE SHEET BORDER				
CALC.	N/A SDR 20-JAN-2021 <b>RD1010</b>				


## **CURB INLET PERSPECTIVE VIEW**

COMPOST FILTER SOCK OR WATTLE - TYPE 7 NOT TO SCALE









## **BIOFILTER BAGS - TYPE 4**

NOT TO SCALE

### NOTES

- 1. Stake biofilter bags with 2"x2"x36" wood stakes, and use a minimum 2 stakes per bag. Drive stakes a minimum of 6" into the ground and flush with the top of the bags.
- 2. Omit stakes when bags are placed on pavement surface.
- 3. Overlap all bag joints 6".

4. Biofilter bags used on active roadways are easily displaced and made ineffective if struck by vehicles. If struck by a cyclist, falls with injury could result. On active roadways alternative inlet protection should be considered.


The selection and use of this
Standard Drawing, while
designed in accordance with
generally accepted engineering
principles and practices, is the
sole responsibility of the user
and should not be used without
first consulting a Registered
Professional Engineer.


# OREGON STANDARD DRAWINGS INLET PROTECTION TYPE 4

All materials shall be in accordance with the current Oregon Standard Specifications.

2024

ATE	REVISION DESCRIPTION					
-2021	REMOVED CALC BOOK NUMBERS					
ALC. OK NO	N/A SDR 20-JAN-2021	RD1015				










### NOTES.

- 1. For Type 2 barrier, drive stakes flush with top of bag and into undisturbed ground a min. of 12". Omit stakes if bags are placed on paved surface.
- 2. For Type 2 and Type 4 barriers, space bags (L) so that the elevation of point "A" is less than or equal to the elevation of point "B".

*Type 2 – Biofilter bags Type 3 – Wattles Type 4 – Sand bags* 







## FIBER ROLL BARRIER - TYPE 3 NOT TO SCALE

The selection and use of this
Standard Drawing, while
designed in accordance with
generally accepted engineering
principles and practices, is the
sole responsibility of the user
and should not be used without
first consulting a Registered
Professional Engineer.

OREGON STANDARD DRAWINGS

SEDIMENT BARRIER
TYPE 2, 3 AND 4

2024

DATE REVISION DESCRIPTION
01-2021 REMOVED CALC BOOK NUMBERS


SDR DATE\_ 20-JAN-2021 RD1030

All materials shall be in accordance with

the current Oregon Standard Specifications.

Effective Date: June 1, 2024 - November 30, 2024

CALC BOOK NO



2' min.

AGGREGATE BARRIER - TYPE 6

NOT TO SCALE

BRUSH BARRIER - TYPE 5

NOT TO SCALE

### NOTES

- 1. Direct diverted flows from the outlet side of the rock filter berm/dams onto a stabilized area, such as vegetation and or rock, or into a sediment trapping facility.
- 2. Embed barrier a min. of 4" into the existing ground/embankments.
- 3. Use 1:3 or flatter side slope. Within the safety clear zone, use 1:6 or flatter side slopes.
- 4. Use 4"-1" clean aggregate.


The selection and use of this
Standard Drawing, while
designed in accordance with
generally accepted engineering
principles and practices, is the
sole responsibility of the user
and should not be used without
first consulting a Registered
Professional Engineer.


# OREGON STANDARD DRAWINGS SEDIMENT BARRIER TYPE 5 AND 6 2024 REVISION DESCRIPTION

All materials shall be in accordance with the current Oregon Standard Specifications.

01-2021 REMOVED CALC BOOK NUMBERS


CALC.
BOOK NO. \_\_\_\_N/A \_\_\_ SDR DATE\_ 20-JAN-2021 RD1031





C	COMPOST FILTER BERM DIMENSIONS							
	AND SPACING BASED ON SLOPE							
SI OPF	BERM SPACING	BERM DIMENSIONS						
SLOPE	BERM SPACING	HEIGHT	BOTTOM WIDTH	TOP WIDTH				
> 50:1	250 ft	1 ft	2 ft (min.)	1 ft				
50:1 - 10:1	125 ft	1 ft	2 ft (min.)	1 ft				
10:1 - 5:1	100 ft	1 ft	2 ft (min.)	1 ft				
3:1 - 2:1	50 ft	1.3 ft	2.6 ft (min.)	1 ft				
> 2:1		1.5 ft	3 ft (min.)	1 ft				

## COMPOST FILTER BERM - TYPE 9 NOT TO SCALE



**COMPOST FILTER BERM SERIES** 

NOT TO SCALE

NOTES:

- 1. Compost filter berm's are sediment control devices for areas where runoff occurs as sheet flow. See Section 00280, Oregon Standard Specifications.
- 2. The maximum drainage area for a continuous berm shall be 1/4 acre per 100 linear feet of filter berm.
- 3. Where possible, berm's should be placed away from the toe of slopes a minimum of 5 feet (10 feet preferred) to allow for energy dissipation and sediment storage.
- 4. Direct the outlet side of filter berm, located at base of slope, onto a stabilized area, such as vegetation and/or aggregate.
- 5. Place filter berm's along or on the ground contour with the ends of the filter berm turned up slope. Adequate area shall be provided behind berm for ponding.
- Compost filter berm's may be vegetated with temporary or permanent seeding after placement.
- 7. If placed in area with existing ground vegetation, cut vegetation to 2-4 inches above grade at berm footprint.

  Do not remove existing vegetation or cut back outside berm footprint unless directed by Agency.
- 8. If soils are exposed apply compost blanket per details and specifications.

The selection and use of this
Standard Drawing, while
designed in accordance with
generally accepted engineering
principles and practices, is the
sole responsibility of the user
and should not be used without
first consulting a Registered
Professional Engineer.

the current Oregon Standard Specifications.


OREGON STANDARD DRAWINGS

SEDIMENT BARRIER
TYPE 9

All materials shall be in accordance with


2024


TE	REVISI	ON DESCRIPTION	
021	REMOVED CALC BOOK NUM	MBERS	
LC. K NC	o <u>N/A</u>	SDR DATE_ <b>20-JAN-2021</b>	RD1033



## **SEDIMENT FENCE AND GEOTEXTILE BURY DETAIL - TYPE 1**

NOT TO SCALE





## **GEOTEXTILE END CONNECTIONS**

NOT TO SCALE

## Post (downslope of geotextile) Sediment fence geotextile Bury 1' flap of fence with 3/4" min. rock, mineral soil, or approved equal Exposed soil Sediment fence geotextile -1'-0" 1. Use must be approved by the engineer. 2. Not approved for use with sediment fencing with sewn-in post sleeves.

## **ALTERNATE SEDIMENT FENCE** WITHOUT TRENCHING - TYPE 2

NOT TO SCALE

### GENERAL NOTES:

NOTES:

- 1. Use 2"x2" wood fence posts.
- 2. Posts to be installed on downhill side of sediment fence geotextile. Position posts to prevent separation from geotextile.
- 3. Compact filter fabric trench backfill and soil on uphill side of fence.
- 4. Locate fence no closer than three feet to the toe of a slope.
- 5. Wing spacing shall comply with "Fence Spacing for General Application Table".

FENCE SPA GENERAL APPL	FENCE SPACING FOR GENERAL APPLICATION TABLE					
INSTALL PARALLEL ALONG	CONTOURS AS FOLLOWS					
GRADE MAXIMUM SPACING ON GRADE						
<i>Grade &lt; 10%</i>	300'					
<i>10% ≤ Grade &lt; 15%</i>	150'					
<i>15% ≤ Grade &lt; 20%</i>	100'					
<i>20% ≤ Grade &lt; 30%</i>	50'					
<i>30% <b>≤</b> Grade</i>	25'					

	POST SPACING TABLE
6'	Sediment Fence with Geotextile elongation less than 50%
4'	Sediment Fence with Geotextile elongation 50% or more


The selection and use of this Standard Drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user and should not be used without first consulting a Registered Professional Engineer.

**OREGON STANDARD DRAWINGS SEDIMENT FENCE** 2024 REVISION DESCRIPTION

All materials shall be in accordance with the current Oregon Standard Specifications.

01-2021 REMOVED CALC BOOK NUMBERS CALC BOOK NO SDR DATE\_ 20-JAN-2021 RD1040

## **PERSPECTIVE**




### **PROFILE**

## TEMPORARY SLOPE DRAIN NOT TO SCALE


### NOTE


- 1. Temporary slope drains shall be used at the top of fill slopes as the embankment is constructed to prevent erosion.
- 2. Temporary drainage curbs shall be used in conjunction with temporary slope drains to prevent erosion on completed slopes and to direct flow into end section.
- 3. All dimensions not indicated will be as directed.




TEMPORARY DRAIN AT GUARDRAIL


NOT TO SCALE






## CONNECTION DETAILS NOT TO SCALE





PIPE SIZE TABLE					
P	PIPE	CONTRIBUTING AREA			
Slope (min.)	D in. (min.)	TO SLOPE DRAIN (sq ft)			
3.8%	6	A < 200			
2.5%	8	200 ≤ A < 500			
1.9%	10	500 ≤A < 850			
1.5%	12	850 ≤A<1400			
-	special design reqd.	1400≤ A			



FRONT VILV

## INLET SECTION DETAILS NOT TO SCALE

The selection and use of this Standard Drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user and should not be used without first consulting a Registered Professional Engineer.

All materials shall be in accordance with the current Oregon Standard Specifications.

OREGON STANDARD DRAWINGS

## TEMPORARY SLOPE DRAIN WITH ENERGY DISSIPATOR

2024

DATE REVISION DESCRIPTION
01-2021 REMOVED CALC BOOK NUMBERS

CALC.
BOOK NO. \_\_\_\_N/A \_\_\_ SDR DATE\_ 20-JAN-2021 RD1045

PLAN

6D typ. 3D Ground Line 1:3 Typ. Dissipator 12" thick, Class 100 riprap sump floor

- 1. All dimensions not indicated will be as directed.
- 2. Install level spreader, sediment barrier(s), check dam(s) or other appropriate BMP(s) to address volume, velocity and turbidity of discharge water.

## TEMPORARY SCOUR BASIN / ENERGY DISSIPATOR

**SECTION A-A** 

The selection and use of this Standard Drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user and should not be used without first consulting a Registered Professional Engineer.

All materials shall be in accordance with the current Oregon Standard Specifications. OREGON STANDARD DRAWINGS

## TEMPORARY SCOUR BASIN / ENERGY DISSIPATOR

2024

	ON DESCRIPTION	REVISIO	DATE		
	REMOVED CALC BOOK NUMBERS				
RD1050	SDR DATE_ <b>20-JAN-2021</b> _	) <u>N/A</u>	CALC.		




FIGURE A1: TOP OF BANK ANCHOR TRENCH, H>3' AND TERMINAL SLOPE

NOT TO SCALE

**ANCHOR TRENCH. H<3'** 

FIGURE A2: **TOP OF BANK** 

NOT TO SCALE

Bank

Fill anchor trench




FIGURE A3: **CHANNEL CHECK SLOT** 






FIGURE A4: **CHANNEL CHECK SLOT WITH ROCK BACKFILL** 

NOT TO SCALE



## FIGURE A5: **INITIAL CHANNEL ANCHOR TRENCH**


NOT TO SCALE




Slope matting

SLOPE MATTING ISOMETRIC VIEW

- 1. Install matting on smooth soil surface after seeding is applied (where applicable).
- 2. Install matting vertically down slope.
- 3. Install matting so edge overlaps are shingled away from prevailing winds.
- 4. Place fastener at 12" OC on matting edges
- 5. Overlap upper mat over lower mat, and fasten.
- 6. Stagger alternate rows of fasteners placed at 24" OC
- 7. Extend mat 24" beyond toe of slope; fold mat back under 4" and fasten.
- 8. Matting Types A through E: Furnish fully biodegradable product. Matting with plastic or photodegradable components will not be accepted.



- 1. Install matting on smooth soil surface after seeding is applied (where applicable).
- 2. Install channel liner matting, in the direction of water flow. Anchor upstream end of mat with check slot for culvert outfalls, place mat under pipe 12" minimum upstream from pipe outlet.
- 3. Construct check slots across channel bottom at 25' spacing and at the end of each mat (Fig. A3 or A4).
- 4. Overlap side channel liner matting edges 6" over the center channel liner matting and fasten edges 12" OC Continue overlap and stapling pattern for each additional side channel
- 5. Lap upstream matting end 12" over beginning edge of downstream matting. Fasten 12" OC
- 6. Anchor top edge of side channel matting in trench and fasten 12" OC (Fig. A2).
- 7. Fasten matting interior at 24" OC with staggered spacing.
- 8. Construct initial anchor trench at downstream end of matting and terminal slope anchor at upstream end.
- 9. Matting Types A through E: Furnish fully biodegradable product. Matting with plastic or photodegradable components will not be accepted.



### **CHANNEL MATTING ISOMETRIC VIEW** NOT TO SCALE


The selection and use of this Standard Drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user and should not be used without first consulting a Registered Professional Engineer.


All materials shall be in accordance with the current Oregon Standard Specifications. **OREGON STANDARD DRAWINGS** 


## **SLOPE AND CHANNEL** MATTING


2024

DATE REVISION DESCRIPTION 01-2021 REMOVED CALC BOOK NUMBERS CALC BOOK NO SDR DATE\_ 20-JAN-2021 RD1055









The selection and use of this Standard Drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user and should not be used without first consulting a Registered Professional Engineer.

OREGON STANDARD DRAWINGS

CONCRETE TRUCK WASH OUT

2024

All materials shall be in accordance with the current Oregon Standard Specifications.

DATE REVISION DESCRIPTION

CALC. BOOK NO. \_ \_ N/A \_ \_ SDR DATE 20-JAN-2021 RD1070