

# *Oregon Highway Bridge Maintenance*

## *A Pilot Training Course /Workshop*



# Bridge Scour

Doug McLain  
Clackamas County

A decorative graphic consisting of several parallel white lines of varying lengths, slanted diagonally from the bottom right towards the top right, located in the lower right quadrant of the slide.

# Bridge Scour


Scour is the number 1 cause  
of bridge failure in the  
United States





DEC • 64





Above: Common Bridge Foundation Types

# Aggradation





# Degradation



# Lateral Stream Migration






# Angle Of Attack



# High Water Events

When and how often to monitor?



# What are we looking for?

- Overtopping of the bridge deck or approach roadway
- Pressure flow at the bridge (the low chord mostly or fully submerged)
- Vertical or lateral displacement of the superstructure
- Excessive horizontal or vertical separation at bridge deck joints
- Visible damage to the bridge deck, low chord, or substructure
- Sinkholes in the roadway behind the abutments
- Massive debris buildup, especially if near the low chord



Rt. #	Drainage	Sub Drainage	Br. #	Br. Alias	SCR	Affected Areas (Piers, Beams, Abutments, Approaches)	Foundation Type	High Water Mark	Date / Time / Comments	Inspectors
	Clackamas Rv.	Eagle Creek	03060A	Eagle Creek / Old State Hwy.	3	Btm of PW steel encasement is 3' above crk. btm. expsg 4 piles (channel side of PW). US rock bar directs flows on to bnt 2 steel encasement.	Spread ftng col. bnts except bnt 2. Bnt 2 is PW on piles.			
	Clackamas Rv.	Eagle Creek	05244	Kitzmilller Rd. / Bear Cr.	4	US NE bank scoured & undercut. N BW: Top of ftng xpsd & covered w/ lrg rocks. SE WW ftng xpsd. No undermining present.	Spread footings			
	Clackamas Rv.	Eagle Creek	05246	Kitzmilller Rd. / N. Fk. Eagle Cr.	4	N. Abutment: Ftng & 20"-30" of vert. face are expsd. S. Abutment: Ftng & 1' of vert face (on the US & DS corners) are expsd. Ftng undermined @ BW- WW jct. (small area 4"-6" deep undermined). SE WW undermined (4"	Spread footings poured on rock			
	Clackamas Rv.	Eagle Creek	05295	Heiple Road West			Spread footings			
	Clackamas Rv.	Eagle Creek	05296	Heiple Road East			Spread footings			
	Clackamas Rv.	Rock Creek	06040	Foster Road						
	Clackamas Rv.	Rock Creek	06287	172nd	3	Footings are exposed on both abutments with 4" of vertical footing face exposed on NE WW. Up to 8" of vert. ftng face xpsd on S. abut. @ mid pt. (no undermining present). US & DS banks eroding especially behind wingwalls.	Spread Footing			
	Clackamas Rv.	Deep Creek	06299	Deep Cr.		US & DS S. bank scour. Shear vert. bank wall w/in feet of S. abutment. Bnt 2 col. undermined ftngs filled w/ lrg rock counter measures	End bents on piles. Int column bnts; spread ftngs			
	Clackamas Rv.		06364	Sailing Rd.		Channel scour holes @ NW and SE wingwalls. No footings are expsd. Creek flows against US NW wingwall.	Spread ftngs			
	Clackamas Rv.	Eagle Creek	06424	North Fork Eagle Cr.	8	US & DS bank scour. Hvy abrasion on int. bnts. S. int bnt: PW is undermined 1" deep full length on bank side & 6" deep @ US end on creek side. Bridge over topped with lrg debris, 2008.	Spread ftngs; End & int. bents pour on rock.	Deck overtopped. Apprch GR backfill eroded. (09)		
	Clackamas Rv.	Eagle Creek	06466	Snuffin Rd.	8	S. abutment: US half of the BW ftng & 6"- 8" of vert ftng face expsd. N. abutment: Ftng & 4"- 2' of ftng face expsd from US WW- BW jct to end of DS WW. A 6' L x 1' D x 9" H section of the DS WW is undermin-ed, 4' DS from the BW-WW	Spread footings			
	Clackamas Rv.	Clear Creek	06505	Fishers Mill	8	Bnt 2: DS col; overpour undermined back to col. Bnt 3: US col overpour expsd & undermined. Channel & bank scour (scour hole 3'-5' deep 2' out from US col. in bnt 3). No ftngs expsd on either int bnt. (ftngs 1.5' vert.)	End bents on piles. Int bnts; spread ftngs			
	Clackamas Rv.	Clear Creek	06508	Viola	3	Channel scour holes @ bnt 2 col (no ftngs expsd). Bent 3 col. ftngs & 3.5"-24" of ftng faces exposed. Some ftng bttms expsd but, not undermined. Spn 4: Hvy S. bank erosion @ bnt	Spread footings end and int. bents.			

Drainage	Sub Drainage	Br. #	Br. Alias	SCR	Affected Areas (Piers,Beams,Abutments,Approaches)	Foundation Type
Clackamas Rv.	Rock Creek	06287	172nd	3	Footings are exposed on both abutments with 4"of vertical footing face exposed on NE WW. Up to 8" of vert. ftng face xpsd on S. abut. @ mid pt. (no undermining present). US & DS banks eroding especially behind wingwalls.	Spread Footing











Bridge ID: 19951


### Zigzag River Bridge - Upstream

Lolo Pass Road

⊕ Bent 1

⊕ Bent 2


1420











X - REMOVE RED ALDER  
 OHWL - ORDINARY HIGH WATER LINE  
 TCE - TEMPORARY CONSTRUCTION EASEMENT

EXCAVATE & REGRADE SLOPE AND CHANNEL. ADD RIVER-RUN MATERIAL


RICHARD W. COGGIN &  
 BRENDA L. COGGIN  
 TAXID 00500 01500

WALTER R BENTON & JOYCE M BENTON

WALTER R BENTON &

















NOTE-SOUTH SIDE RESTORATION

- WILLOW STAKES (*SALIX LUCIDA*) (20)
- RED OSIER DOGWOOD STAKES (*CORNUS SERICIA*) (20)



RICHARD W. COGGIN &  
BRENDA L. COGGIN  
TAXMAP 62E08 01000  
DOC# 1994-35694

WALTER R BENTON  
JOYCE M BENTON  
TAXMAP 62E08 01100  
DOC# 2005-129443

WALTER R BENTON  
JOYCE M BENTON  
TAXMAP 62E08 01  
DOC# 2005-12944

NOTE-UPSTREAM NORTH SIDE RESTORATION

- 6' WILLOW BUNDLES (10)
- X WILLOW STAKES (*SALIX LUCIDA*) (45)
- RED OSIER DOGWOOD STAKES (*CORNUS SERICIA*) (55)
- BIG LEAF MAPLE (*ACER MACROPHYLLUM*) (2)
- OREGON ASH (*FRAXINUS LATIFOLIA*) (6)
- WHITE ALDER (*ALNUS RHOMBIFOLIA*) (11)
- SWORD FERN (*POLYSTICHUM MUNITUM*) (20)

NOTE-UPSTREAM SOUTH SIDE RESTORATION


- BIG LEAF MAPLE (*ACER MACROPHYLLUM*) (2)
















60' ROAD  
RIGHT OF WAY






















































CONSTRUCT  
ENGINEERED  
RIFFLES AND POOLS  
FULL SPANNING  
POROUS ROCK WEIR

FULL SPANNING  
POROUS ROCK WEIR  
REMOVE EXISTING  
WATERLINE

















































*Place coir rolls parallel to the streambank along a horizontal contour.*

16-30 in.  
(47-70 cm)

*Double stakes required for offshore installation.*

*Place branches crisscross and dipping at different angles before backfilling behind coir roll.*







# Meadowbrook Bridge Over Milk Creek

Undermining found 2006

Temporary Mitigation installed 2007

Permit Application process started June, 2007

Work started July, 2008

# Underwater Inspection Report

UNDERWATER INSPECTION REPORT					
BRIDGE NAME:	Milk Creek Beaver Creek Road	REGION:		BRIDGE NUMBER:	06198
RIVER NAME:	Milk Creek	OWNER:	County	DISTRICT:	2C
STATE HWY #:		ROUTE NUMBER:		INSPECTION DATE:	6/2/2006
COUNTY:	Clackamas	ROAD NAME:	Beaver Creek Road	MILE POINT:	0.17
FOUNDATION TYPE:		ACCESS:	3	CURRENT:	Low
DIVERS:	Shorb, James, Nelson	INS. INTERVAL:	1	VISIBILITY (Ft.):	1.5
Water Elevation:	Bent #2 from bottom of steel girder down 8.4-ft.	WATER TEMP:	55	MAXIMUM DEPTH:	5
		Constructed in:	1959		

UNDERWATER ELEMENT CONDITION STATES:		CONDITION STATES								
Elem.	Description:	Environment	Qty	Units	1	2	3	4	5	Temp
215	Concrete Abutment	Moderate	2	LF	0%	100%	0%	0%	0%	N
361	Scour Smart Flag	Moderate	1	each	0	1	0	0	0	N

#### NBI Ratings

Item	Description:	Condition Rating
60	Substructure Condition Assessment	4
61	Channel and Channel Protection Condition Assessment	4
113	Scour	3

#### GENERAL NOTES:

This is a single-span structure, supported with concrete abutments.

#### ELEMENT REMARKS:


Elem. Description:

- 215 **Bent #1:** Concrete Abutment has some heavy abrasion and is in Condition State 2. The upstream end of the abutment is in the dry. The downstream corner is in 5.1-ft. of water. The downstream corner is undermined 0.8-ft. vertical and 2.5-ft. horizontal for a distance along the abutment of 16.5-ft. See sketch. The streambed consists of silty/gravel.
- 215 **Bent #2:** Concrete Abutment has some heavy abrasion and is in Condition State 2. The downstream end of the abutment is in the dry. The upstream corner is in 4.6-ft. of water. The upstream corner is undermined 0.5-ft. vertical and 2.5-ft. horizontal for a distance along the abutment of 8.5-ft. See sketch. The streambed consists of silty/gravel.

#### Maintenance Recommendations:


Elem. Description:

- 215 **Bent #1 & Bent #2** repair undermined abutment walls.


  
 Rick Shorb, P.E.  
 Underwater Operations Engineer  
 (503) 986-2979


cc: Clackamas County Public Works  
 Bridge Operations

06-22-06P12:33 RCVD














# Engineering Required?





1. FILL VOID BELOW EXISTING FOOTING COMPLETELY WITH CONCRETE.
2. PLACE CONCRETE AGAINST UNDISTURBED GROUND.
3. PLACE CONCRETE TO EXISTING GROUND OR 1'-0" MIN, WHICHEVER IS GREATER.





# Critical Path Document

Task	Sub-Task	Start Date	Materials	MRI Status	Special Tools	Tool Stat	Equipment	Eqp Status	Manpower
Install Dam(s)			14 Large Sandbags	CCBM	3" x 16' Slings	CCBM	Excavators	CCBM	
			200 Small Sandbags	CCBM	Pallet Forks	CCBM	461	CCBM	
			plastic sheeting						
Install Fish Nets			2 - Nets	Devin	T Post Driver	CCBM			
			16 - T Posts	CCBM					
Install Pump System									
		Place 3" minus for Pump Pads	6yds 3" minus	CCBM					
			Pump System, Hauled to site by Xylem		2-Electric 2" Pumps	CCBM			
			2 - Containment Tubs with Brackets	CCBM	200' - 2" Hose	CCBM			
			100' roll Plastic Sheeting						
			Sediment Bag	Xylem					
			Pump Screen	CCBM					
			100 Large Zip Ties	CCBM					
			6 Bio Bags	CCBM					
			1 bag Oil Containment Booms	CCBM					
			1 Box Oil Diapers	CCBM					
			6 Waddles	CCBM					
			6 Hay Bales	CCBM					






































































































































































# Salmon River Bridge Brightwood Loop Road

Undermining found SEP, 2018

*Emergency* Permit Application  
process started SEP, 2018

Work started FEB, 2019








SALMON RIVER BRIDGE, # 01438  
 SCOUR MITIGATION PROJECT, BM2018.17


- EXISTING Boulders
- Boulders to be added



- \* PLACE 6-10 YD<sup>3</sup> Boulders
- \* COVER W/ 5 YD<sup>3</sup> RIVER RUN (COBBLES/SAND/NATIVE SOIL)

DWMCLAIN  
 CCBM  
 04 OCT 18























### RAM100N Multi-Use Anchor

#### Performance:


Static tensile strength: 10,000-lbf  
(44kN) minimum.  
Working Load Limit: 2000-lbs

#### Dimensions:

Weight: 0.5-lbs (.22kg)  
Length: 13.75" (349mm)  
Diameter: 1" (25.4mm)

#### Component Materials:

Main Cable: Aircraft Cable. End Termination: Stainless Steel Spoons:  
Stainless Steel. Stop Sleeve: Stainless Steel. Trigger: Aluminum. Spring: Zinc  
Plated Steel. Swage: Zinc Plated Copper. Return Wire: Aircraft Cable. Anchor  
Thimble: Zinc Plated Steel.


















Questions?

Comments?

A decorative graphic consisting of several parallel white lines of varying lengths, slanted diagonally from the bottom-left towards the top-right, located in the lower right quadrant of the slide.

# *Oregon Highway Bridge Maintenance*

## *A Pilot Training Course /Workshop*

