DRAFT 100% 2024-2027 STIP Projects, ODOT Region 1

July 1, 2022

The following projects constitute a draft "100%" list for the 2024-27 Statewide Transportation Improvement Plan (STIP). The list does not currently include projects from the Local Bridge program or the Urban Mobility Office. Many of the fund categories are managed at the statewide level. For further information on the 150% lists and the STIP programs, www.odotregion1stip.org

This list will remain draft until the Oregon Transportation Commission adopts the final 2024-27 STIP in Summer 2023.

ID	Fund Category	Program	Project Name/Location	Description	Applicant	Hwy Name/Local Road	City	County
30	Enhance Highway	Enhance Highway	I-5: Capitol Highway - OR217 Northbound	Install electronic signs to provide advance warning of traffic up ahead on the highway to improve congestion, queuing and potential collisions.	ODOT	I-5: Pacific Freeway	Lake Oswego, Portland,	Clackamas, Washington
393	Enhance Highway	Enhance Highway	I-5: Capitol Highway - OR217 Southbound	Install electronic signs to provide advance warning of traffic up ahead on the highway to improve congestion, queuing and potential collisions.	ODOT	I-5: Pacific Freeway	Tigard, Portland	Washington, Multnomah
123	Fix-It	Bridge	US26: Cedar Creek Bridge	Replace the existing aging structure with a new single span bridge to provide improved fish passage and earthquake resilience.	ODOT	US26: Mt. Hood Highway		Clackamas
124	Fix-It	Bridge	OR99E: Clackamas River (McLoughlin) Bridge	Repaint the bridge to prevent corrosion of the steel structure.	ODOT	OR99E: Pacific Hwy East	Gladstone, Oregon City	Clackamas
126	Fix-It	Bridge	I-5: Northbound Interstate Bridge	Pavement resurfacing and joint repair to prevent damage to the existing structure. Extensive repairs are not planned due to the proposed future replacement of this structure.	ODOT	I-5: Pacific Freeway	Portland	Multnomah
127	Fix-It	Bridge	I-84 (Westbound): Union Pacific Railroad bridge	Replace the existing bridge in need of major repairs with a new structure that has wider shoulders and improved earthquake resilience.	ODOT	I-84: Columbia River Freeway	Hood River	Hood River
128	Fix-It	Bridge	I-405: Fremont Bridge (Willamette River) West Ramps	Repaint the west bridge ramps to prevent corrosion of the steel structures.	ODOT	I-405: Stadium Freeway	Portland	Multnomah
130	Fix-It	Bridge	OR35: US26 overcrossing bridge	Pavement resurfacing to prevent damage to the structure and replacent of the sub-standard bridge rail to improve safety.	ODOT	OR35: Mt Hood Hwy		Clackamas
439	Fix-It	Bridge	OR120: Columbia Slough Bridge	Replace the existing obsolete timber bridge structure, in need of constant repair and unable to support heavier loads. The new bridge will be planned to include a cycle track.	ODOT	OR120: Swift Highway	Portland	Multnomah
28	Fix-It	Culverts	I-84: Wyeth - East Hood River Interchange	Repair culverts to improve drainage along this section of highway and prevent roadway damage.	ODOT	I-84: Columbia River Freeway	Cascade Locks, Hood River	Hood River, Multnomah
241	Fix-It	Culverts	Evans Creek Culvert	Replace the existing culvert with a larger structure to restore fish access to upstream locations.	ODOT	Evans Creek Dr		Hood River
47	Fix-It	Interstate Maintenance	I-84: NE Martin Luther King Jr Blvd - I-205	Design for a project to resurface the pavement over this section to repair cracking, rutting and potholes.	ODOT	I-84: Columbia River Freeway	Portland	Multnomah
31	Fix-It	Operations	OR8: SE10th Ave at SE Walnut St	Replace the existing traffic signal to reduce maintenance costs and improve safety at this location. Install curb ramps to current standards.	ODOT	OR8: Tualatin Valley Hwy	Hillsboro	Washington

DRAFT

DRAFT 100% 2024-2027 STIP Projects, ODOT Region 1

July 1, 2022

32	Fix-It	Operations	OR99E: McLoughlin Blvd at W Arlington St and River Rd	Replace the existing traffic signal to reduce maintenance costs and improve safety at this location. Install curb ramps to current standards.	ODOT	OR99E: Pacific Hwy East	Milwaukie	Clackamas
34	Fix-It	Operations	OR99E Canemah Rockfall Phase 2	Reduce rockfall hazard by repairing mesh; scaling and rock dowel installation as necessary, remove vegetation, and clear catchment.	ODOT	OR99E: Pacific Hwy East	Oregon City	Clackamas
394	Fix-It	Operations	I-84 Active Traffic Management	Design for a project to Install variable advisory speed, variable message , queue warning and advanced directional signage to help maintain more consistent travel speeds, improve travel time reliability, reduce crashes and improve operations.	ODOT	I-84: Columbia River Freeway	Gresham, Portland, Troutdale	Multnomah
395	Fix-It	Operations	US26 Active Traffic Management	Design for a project to Install variable advisory speed, variable message , queue warning and advanced directional signage to help maintain more consistent travel speeds, improve travel time reliability, reduce crashes and improve operations.	ODOT	US26: Sunset Highway	Beaverton, Hillsboro, Portland	Multnomah, Washington
7	Fix-It	Preservation	OR224: SE 17th - Rusk Rd	Resurface the pavement to repair cracking, rutting and wear to improve the surface and extend the life of the roadway. Improve or install curb ramps to current standards.	ODOT	OR224: Clackamas Hwy	Milwaukie	Clackamas
13	Fix-It	Preservation	OR213: S Spangler Rd - Mulino	Design for a project to resurface pavement to repair cracking and rutting. This will improve the travel surface, reduce the risk of water pooling and improve safety.	ODOT	OR213: Cascade Hwy South		Clackamas
380	Public & Active Transportation	Ped/Bike Strategic	OR8: Tualatin Valley Hwy at SW142nd Ave	Install pedestrian crosswalks with a flashing beacons and lighting. Improve the rail crossing at SW 142nd Ave This project improves safety for pedestrians and transit riders.	ODOT	OR8: Tualatin Valley Hwy	Beaverton	Washington
383	Public & Active Transportation	Ped/Bike Strategic	OR99E: SE Mcloughlin Blvd Pedestrian Safety (Risley - Gloucester)	Install sidewalks to fill gaps in this section to improve pedestrian safety and access.	ODOT	OR99E: Pacific Hwy East	Gladstone	Clackamas
390	Public & Active Transportation	Ped/Bike Strategic	OR99E: SE Mcloughlin Blvd Pedestrian Safety (Meldrum/Mildred)	Install a crosswalk with flashing beacons and a center median. Close off the SE Mildred St approach. This project improves safety for pedestrians and other vulnerable road users.	ODOT	OR99E: Pacific Hwy East		Clackamas
426	Public & Active Transportation	Ped/Bike Strategic	OR8: Tualatin Valley Hwy at 214th Ave	Install pedestrian crosswalks with flashing beacons and lighting. This project improves safety for pedestrians and transit riders.	ODOT	OR8: Tualatin Valley Hwy	Hillsboro	Washington
427	Public & Active Transportation	Ped/Bike Strategic	OR99W: (Barbur Blvd) SW 26th Way - SW 26th Ave	Design for a project to Install a crosswalk with rapid flashing beacons and sidewalk infill as required to improve safety for pedestrians and other vulnerable road users.	ODOT	OR99W: Pacific Hwy West	Portland	Multnomah
45	Public & Active Transportation	Safe Routes to School	US26: E Salmon River Rd - E Lolo Pass Rd	Construct a multi-use path to enable safe pedestrian access to this area.	ODOT	US26: Mt. Hood Highway		Clackamas
435	Public & Active Transportation	Safe Routes to School	OR141: Hall Blvd at SW Hemlock St	Install an enhanced pedestrian crosswalk with flashing beacons, median island, curb ramps, signage, striping and lighting. Install sidewalk on the West side of Hall Blvd from the bus stop north of Hemlock to the new crosswalk.	ODOT	OR141: Beaverton-Tualatin	Tigard	Washington
15.2	Safety	ARTS	OR99E: SE McLoughlin Blvd Pedestrian Safety (Risley)	Install a crosswalk with flashing beacons, median island, curb ramps, improve lighting and install signing upgrades to improve safety.	ODOT	OR99E: Pacific Hwy East		Clackamas
15.4	Safety	ARTS	US30B: (N Lombard St) at Peninsula Crossing Trail	Install a crosswalk with advance pedestrian warming signs, flashing beacons, curb ramps, evaluate lighting improvements and install signing, install bike lanes across the railroad to improve safety.	ODOT	US30B: Northeast Portland Bypass Hwy	Portland	Multnomah

DRAFT

DRAFT 100% 2024-2027 STIP Projects, ODOT Region 1

July 1, 2022

16	Safety	ARTS	OR224 at OR211 and SE Burnett Rd	Design and right-of-way for a roundabout, including lighting, sidewalks and signing to improve safety at this intersection.	ODOT	OR224: Clackamas Hwy		Clackamas
19	Safety	ARTS	I-205: Columbia River - SE 82nd Drive	Install improved lighting, crosswalks, signals and signing at ramp terminal intersections to improve safety.	ODOT	I-205: East Portland Freeway	Gladstone, Happy Valley, Oregon City, Portland, West Linn	Clackamas, Multnomah
20	Safety	ARTS	I-84: I-5 - Hood River	Install improved lighting, crosswalks, signals and signing at ramp terminal intersections to improve safety.	ODOT	I-84: Columbia River Freeway	Cascade Locks, Fairview, Gresham, Hood River, Portland, Troutdale	Hood River, Multnomah
132	Safety	ARTS	SE Cesar Chavez Blvd: Lafayette Ct - Shiller St (Portland)	Reduce this section from 4 to 3 lanes (one in each direction and a center turn lane). Add north-south left-turn lanes on SE Chavez at SE Raymond St. Rebuild the signal at SE Holgate to protect left turns. Relocate the bus stop at SE Holgate St closer to the crosswalk.	City Of Portland	SE Cesar Chavez Blvd	Portland	Multnomah
133	Safety	ARTS	NE Cornell Rd at 17th Ave and 21st Ave	Restrict the 17th Ave intersection to right in right out only and Install a signal at the 21st Ave intersection. Install streetlights at both locations	Washington County	NE Cornell Rd	Hillsboro	Washington
136	Safety	ARTS	SE Sunnyside Rd: 132nd Ave - 172nd Ave (Clackamas)	Install an adaptive signal system to coordinate signals on this section of the corridor to improve traffic flow at SE 92nd Ave and SE Division St, E Burnside St and 122nd Ave, E Burnside St and 148th Ave, N Basin Ave and Emerson St.	Clackamas County	SE Sunnyside Rd	Happy Valley	Clackamas
138	Safety	ARTS	Lake Oswego Signals Visibility Upgrades	Signal upgrades to improve visibility and safety. Install leading pedestrian intervals and changes from permissive-only green left turn signals to flashing yellow arrows.	City Of Lake Oswego	Various	Lake Oswego	Clackamas
139	Safety	ARTS	N Basin Ave: N Leverman St - N Emerson St (Portland)	Install a raised median, improved street lighting, signage and markings to reduce the potential for vehicle crashes.	City Of Portland	N Basin Ave	Portland	Multnomah
140	Safety	ARTS	SE Foster Rd: 101st Ave - 136th Ave	Install speed feedback signs, additional lighting and raised pavement markers to improve safety.	City Of Portland	SE Foster Rd	Portland	Multnomah
141	Safety	ARTS	Gresham Pedestrian Improvements	Install crosswalks with flashing beacons, stop bars and signs to improve safety at various locations. Install curb ramps to meet current standards.	City Of Gresham	Various	Gresham	Multnomah
322	Safety	Rail Safety	US30B: (NE Lombard St) NE Lombard Pl - NE 11th Ave	Design and right-of-way to improve the rail crossing on NE 11th Ave and close the crossing at NE Lombard Place while retaining business access. Install new railroad signals and gates and improve the signalized intersection at NE Lombard St and 11th Ave. Construct sidewalk infill west from NE 11th Ave to existing sidewalk . This project aims to improve safety at this location.	ODOT	Northeast Portland	Portland	Multnomah

DRAFT