

STATE PARKS & RECREATION BRANCH
525 TRADE STREET SE
SALEM, OREGON 97310



**Statewide Inventory
of
Historic Sites and Buildings**

Wasco County

**Oregon State Historic Preservation Office
Parks and Recreation Branch
Department of Transportation**

1976





Department of Transportation
STATE HISTORIC PRESERVATION OFFICE
Parks and Recreation Branch
525 TRADE STREET S.E., SALEM, OREGON 97310

July 28, 1977

TO ALL LOCAL GOVERNMENTS, PLANNING BODIES AND PUBLIC LIBRARIES

Ladies and Gentlemen:

Enclosed herewith is a copy of the appropriate section of the Statewide Inventory of Historic Properties as expanded under special contract by Stephen Dow Beckham in 1976.

We hope and trust that the Inventory will assist you in the development of your comprehensive plans and other matters. It should be remembered that the Inventory is not complete in this form. It will be revised and enlarged continually. Moreover, archeological sites are not included for purposes of site protection. In many cases, properties which have been entered into the National Register of Historic Places are not included. We are including as an addendum a listing of properties in your area which were included in the Inventory prior to 1976.

If questions regarding the Inventory arise, please contact us at 378-5001.

Sincerely,

Paul B. Hartwig
Historic Preservation Coordinator

EWP:ko

Enc.

HISTORIC PRESERVATION FACT SHEET

OREGON STATE HISTORIC PRESERVATION OFFICE (SHPO):

Mr. David G. Talbot, State Parks Superintendent
State Historic Preservation Officer
Department of Transportation
Parks and Recreation Branch
525 Trade Street SE
Salem, OR 97310
503/378-6305

For operating questions, call Mr. Paul B. Hartwig (503/378-6118)

STATE ADVISORY COMMITTEE ON HISTORIC PRESERVATION (Advisory to SHPO):

Dr. Edwin Bingham
Dept. of History - U of O
Eugene, OR 97403
686-4802

Mr. Lewis L. McArthur
4154 SW Tualatin Ave.
Portland, OR 97201
288-5341

Prof. David L. Cole
Museum of Natural History
University of Oregon
Eugene, OR 97403
686-3034

Mr. George McMath, AIA
1030 SW Second Avenue
Portland, OR 97204
228-5154

Mr. Robertson Collins
PO Box 1309
Medford, OR 97501
664-3313

Mr. Thomas Vaughan, Director
Oregon Historical Society
1230 SW Park Avenue
Portland, OR 97205
222-1741

Prof. Philip Dole
Dept. of Architecture-U of O
School of Arch., Allied Arts
Eugene, OR 97403
686-3664

NATIONAL REGISTER OF HISTORIC PLACES:

The National Register of Historic Places is the official list of the nation's cultural resources worthy of preservation. It is maintained by the National Park Service under authority of the National Historic Preservation Act of 1966. The list contains districts, sites, archeological sites, buildings, structures and objects of national, state or local significance. National Historic Landmarks are automatically included. A cumulative listing of all National Register properties is published annually in the February issue of the Federal Register, the regular Congressional publication. Under certain circumstances, National Register properties are eligible for federal preservation assistance.

Dr. William J. Murtagh
Keeper of the National Register
US Department of the Interior
National Park Service
Washington, DC 20240

THE ADVISORY COUNCIL ON HISTORIC PRESERVATION:

In the National Historic Preservation Act of 1966, Congress established the Advisory Council on Historic Preservation to advise Congress and the President and to assist federal departments and agencies in discharging their historic preservation responsibilities under Section 106 of the Act.

Advisory Council on Historic Preservation
Suite 430, 1522 K Street NW
Washington, DC 20006

THE NATIONAL TRUST FOR HISTORIC PRESERVATION:

The National Trust for Historic Preservation is a national, non-profit organization chartered by Congress to encourage public participation in the preservation of sites, buildings and objects significant in American history and culture.

Chairman, Board of Trustees: Mr. Carlisle Humelsine
President, Colonial Williamsburg
Williamsburg, VA 23185

President: Mr. James Biddle
740-748 Jackson Place NW
Washington, DC 20006
202/638-5300

Director, Western Regional Office: Mr. John L. Frisbee III
802 Montgomery St.
San Francisco, CA 94133

OTHER ORGANIZATIONS:

American Association for State and Local History
1400 8th Avenue S.
Nashville, TN 37203
William Alderson, Director

Society of Architectural Historians
1700 Walnut Street
Philadelphia, PA 19103
Rosann Berry, Executive Secretary

Northern Pacific Coast Chapter
Society of Architectural Historians
Earl D. Layman, Preservation Officer
City of Seattle Office of Urban
Conservation, Arctic Building
Seattle, WA 98104

American Institute of Architects
Alfred M. Staehli, Preservation Officer
317 SE 62nd Avenue
Portland, OR 97215

The Victorian Society in America
The Athenaeum
East Washington Square
Philadelphia, PA 19106
Joan Thill, Executive Director

Friends of Cast Iron Architecture
44 W. 9th Street
New York, NY 10011
Margot Gayle, Director

Portland Friends of Cast Iron Architecture
1030 SW Second Avenue
Portland, OR 97204

Association for Preservation Technology
Box CP 2487 -- Station D
Ottawa, Ontario
CANADA K1P 5W6

DEFINITIONS OF PRESERVATION TERMS AS USED BY THE NATIONAL PARK SERVICE:

Preservation is the process of sustaining the form and extent of a structure essentially as it now exists. Preservation aims at halting further deterioration and providing structural stability but does not contemplate significant rebuilding.

Restoration is the process of accurately recovering the form and details of a property as it appeared at a particular period of time by means of removal of later work and the replacement of missing original work.

Reconstruction is the process of reproducing by new construction the exact form and detail of a vanished structure, or part of it, as it appeared at a specific period of time. Reconstruction should be undertaken only when the property to be reconstructed is essential for understanding and interpreting the value of a historical district and sufficient historical documentation exists to insure an exact reproduction of the original.

Rehabilitation is the process of returning a property to a state of utility, through repair or alteration, which makes possible an efficient contemporary use. In rehabilitation, those portions of the property which are important in illustrating historic and cultural values are preserved or restored.

- - - - -

National Parks - Outstanding, relatively spacious land and water areas under federal ownership. They usually contain a diversity of scenic, scientific and other values and support a broad range of visitor-use programs.

National Monuments - Outstanding land and water areas, usually under federal ownership. They generally contain lesser acreage than National Parks and support a narrower range of visitor-use programs. Their purpose is to preserve resources of special scientific significance.

National Historic Sites - Properties of outstanding historical value to the nation as a whole. They may be under federal, state or local ownership. In the latter cases, the National Park Service acts in an advisory capacity.

National Memorials - Properties commemorating historic events and/or personages of exceptional significance to the nation. Usually they are under National Park Service jurisdiction, but ownership may be mixed.

National Historic Landmarks - Outstanding examples of the nation's historical and/or cultural patrimony. They are evaluated and recommended for designation by the Advisory Board on National Parks, Historic Sites, Buildings, and Monuments. Federal ownership is not implied. Ownership may be public or private, but owner must agree to maintain property in accord with accepted preservation precepts if he accepts designation. Landmark status offers higher priority in the distribution of grants-in-aid under the National Historic Preservation Act of 1966 and is acknowledged by a bronze plaque and a certificate from the Secretary of the Interior.

National Survey of Historic Sites and Buildings - Conducted by the National Park Service under authority of the Historic Sites Act of 1935 for purposes of identifying historic and prehistoric places of national significance. The Survey forms the basis of National Historic Landmark designations.

HABS - Historic American Buildings Survey - Initiated by the National Park Service in 1933 for purposes of assembling a national collection of detailed records of historically and architecturally significant buildings. Conducted in cooperation with the American Institute of Architects and the Library of Congress.

HAER - Historic American Engineering Record - Established by the National Park Service in 1969 for purposes of documenting historic engineering, industrial and technological works. Conducted in cooperation with the American Society of Civil Engineers and the Library of Congress.

NATIONAL PARK SERVICE LANDMARK DESIGNATIONS IN OREGON

NATIONAL HISTORIC SITES

McLoughlin House, Oregon City, Clackamas County

NATIONAL MEMORIALS

Fort Clatsop, Clatsop County

NATIONAL MONUMENTS

Oregon Caves, Josephine County

John Day Fossil Beds, Grant and Wheeler Counties

NATIONAL PARK

Crater Lake, Klamath County

NATIONAL NATURAL LANDMARKS

Crown Point, Multnomah County

Fort Rock State Monument, Lake County

Horse Ridge Natural Area, Deschutes County

Newberry Crater, Deschutes County

NATIONAL HISTORIC LANDMARKS

Deady Hall, Eugene, Lane County

Elmore (Samuel) Cannery, Astoria, Clatsop County

Fort Astoria, Astoria, Clatsop County

Fort Rock Cave, Lake County

Jacksonville Historic District, Jackson County

Lower Klamath National Wildlife Refuge, Klamath County (also in Siskiyou County, California)

Pioneer Courthouse, Portland, Multnomah County

Portland Skidmore/Old Town Historic District, Portland, Multnomah County

Villard Hall, Eugene, Lane County

PROPERTIES IN THE NATIONAL REGISTER OF HISTORIC PLACES

As of February 1, 1977 (see attached)

NOTICES

OREGON

oklahoma county

Edmond. **OLD NORTH TOWER, CENTRAL STATE COLLEGE**, 400 E. Hurd St., Central State College campus, (6-21-71)
 Jones vicinity. **"RINGING THE WILD HORSE" SITE**, (1-25-71)
 Oklahoma City. **CAPITOL-LINCOLN TERRACE HISTORIC DISTRICT**, Irregular pattern roughly bounded by 13th, 23rd, Lincoln Blvd. and Kelley Ave., (9-30-76)
 Oklahoma City. **CENTRAL HIGH SCHOOL**, 700 block of N. Robinson, (11-7-76)
 Oklahoma City. **COLCORD BUILDING**, Robinson and Sheridan, (11-7-76)
 Oklahoma City. **FAIRCHILD WINERY**, 1600 NE. 81st St., (3-13-75)
 Oklahoma City. **HARN HOUSE**, NE 17th and Stiles Sts., (4-13-73) G.
 Oklahoma City. **OKLAHOMA STATE CAPITOL**, 22nd St. and Lincoln Blvd., (10-8-76)
 Oklahoma City. **OVERHOLSER HOUSE**, 405 N.W. 15th St., (6-22-70)
 Oklahoma City. **POST OFFICE, COURTHOUSE, AND FEDERAL OFFICE BUILDING**, Robinson at 3rd St., (8-30-74)

okmulgee county

Beggs vicinity. **ISPARHECHER HOUSE AND GRAVE**, 4 mi. W of Beggs off OK 16, (7-12-76)
 Okmulgee. **CREEK NATIONAL CAPITOL**, (10-15-66) NHL.
 Okmulgee vicinity. **NUYAKA MISSION**, 9 mi. W of Okmulgee, (4-13-72)

osage county

Pawhuska. **CITY HALL (OSAGE COUNCIL HOUSE)**, Main and Grandview Ave., (1-1-76)
 Pawhuska. **OSAGE AGENCY**, Agency Hill, (5-17-74)

pawnee county

Pawnee. **PAWNEE INDIAN AGENCY**, E edge of Pawnee, (4-11-73)
 Pawnee vicinity. **BLUE HAWK PEAK RANCH**, W of Pawnee on U.S. 64, (10-10-75)

payne county

Stillwater. **OLD CENTRAL, OKLAHOMA STATE UNIVERSITY**, Oklahoma State University campus, (7-27-71)
 Yale. **THORPE, JIM, HOUSE**, 704 E. Boston St., (3-24-71)

pittsburg county

McAlester vicinity. **PERRYVILLE**, SW of McAlester on U.S. 69, (5-5-72)
 Pittsburg vicinity. **BLACKBURN'S STATION SITE**, 9 mi. SE of Pittsburg, (3-7-73)

pottawatomie county

Shawnee. **SANTA FE DEPOT**, Main St. and Minnesota Ave., (6-5-74)
 Shawnee. **ST. GREGORY'S ABBEY AND COLLEGE**, 1900 W. MacArthur Dr., (8-15-75)
 Shawnee vicinity. **SHAWNEE FRIENDS MISSION**, 2 mi. S of Shawnee, (3-7-73)

pushmataha county

Tuskahoma vicinity. **TUSKAHOMA (CHOCTAW COUNCIL HOUSE)**, 2 mi. N of Tuskahoma, (7-28-70)

roger mills county

Cheyenne vicinity. **WASHITA BATTLEFIELD**, NW of Cheyenne on U.S. 283, (10-15-66) NHL.

rogers county

Oologah vicinity. **ROGERS, WILL, BIRTHPLACE**, About 4 mi. NE of Oologah, (9-29-70)

seminole county

Seminole. **CRISSO, W. E., MANSION**, 612 Hwy. 9 East, (1-27-75)
 Seminole vicinity. **MEKASUKEY ACADEMY**, SW of Seminole, (3-28-74)

sequoyah county

Akins vicinity. **SEQUOYAH'S CABIN**, OK 101, in Sequoyah's Cabin State Park, (10-15-66) NHL.
 Marble City vicinity. **DWIGHT MISSION**, 3 mi. SW of Marble City, (3-20-73)
 Sallisaw vicinity. **PARRIS MOUND**, NE of Sallisaw, (1-31-76)

texas county

Hardesty vicinity. **OLD HARDESTY**, NE of Hardesty, (6-20-74)
 Optima vicinity. **STAMPER SITE**, 2.5 mi. S of Optima on the S bank of the North Canadian River, (10-15-66) NHL.

tulsa county

Tulsa. **CREEK COUNCIL TREE SITE**, 18th and Cheyenne Sts., (9-29-76)
 Tulsa. **MCBIRNEY, JAMES H., HOUSE**, 1414 S. Galveston, (11-13-76)
 Tulsa. **TULSA MUNICIPAL BUILDING**, 124 E. 4th St., (7-18-75)
 Tulsa. **WESTHOPE**, 3704 S. Birmingham St., (4-10-75)

wagoner county

Cowetah vicinity. **KOWETA MISSION SITE**, 1 mi. S of Cowetah off OK 58B, (6-19-73)
 Tullahassee. **TULLAHASSEE MISSION SITE**, NE of Tullahassee, (9-10-71)

washington county

Bartlesville. **NELLIE JOHNSTONE NO. 1**, Johnstone Park, (4-11-72)
 Bartlesville. **PHILLIPS, FRANK, HOUSE**, 1107 Cherokee Ave., (3-13-75) G.
 Bartlesville. **PRICE TOWER**, 6th St. and Dewey Ave., (9-13-74)
 Dewey. **DEWEY HOTEL**, Delaware and Don Tyler Ave., (4-4-75)

washita county

Carnegie vicinity. **CEDAR CREEK DISTRICT**, N of Carnegie off OK 58, (5-29-75)
 Colony vicinity. **MCLEMORE SITE**, 4 mi. SE of Colony on OK 69, (10-15-66) NHL.

woods county

Waynoka. **SANTE FE DEPOT AND READING ROOM**, Sante Fe Tracks, (6-20-74)

woodward county

Fort Supply. **FORT SUPPLY HISTORIC DISTRICT**, Western State Hospital grounds, (6-21-71)

OREGON

baker county

Sumpter. **SUMPTER VALLEY GOLD DREDGE**, SW of Sumpter near Cracker Creek, (10-26-71)

benton county

Corvallis. **CORVALLIS ARTS CENTER (EPISCOPAL CHURCH OF THE GOOD SAMARITAN)**, 700 S.W. Madison Ave., (9-10-71)
 Kings Valley vicinity. **FORT HOSKINS SITE**, SW of Kings Valley, (5-1-74) G.
 Philomath. **PHILOMATH COLLEGE**, Main St., (12-11-72)

Philomath vicinity. **KING, ISAAC, HOUSE AND BARN**, N of Philomath off OR 223, (10-29-75)

clackamas county

Brightwood vicinity. **ROCK CORRAL ON THE BARLOW ROAD**, W of Brightwood off U.S. 26 near Sandy River, (12-19-74)
 Carver vicinity. **BAKER, HORACE, LOG CABIN**, S of Carver off OR 224, (12-12-76)
 Government Camp vicinity. **TIMBERLINE LODGE**, 6 mi. N of Government Camp in Mount Hood National Forest, (11-12-73)
 Lake Oswego. **OREGON IRON COMPANY FURNACE**, George Rogers Park, (2-12-74)
 Molalla. **DIBBLE, HORACE L., HOUSE**, 616 S. Molalla Ave., (12-19-74) HABS.
 Molalla. **VONDER AHE, FRED, HOUSE AND SUMMER KITCHEN**, 625 Metzler Ave., (3-26-76)

Molalla vicinity. **ROCK CREEK METHODIST CHURCH**, W of Molalla off OR 211, (10-29-75)

Oregon City. **BARCLAY, DR. FORBES, HOUSE**, 719 Center St., (11-5-74)

Oregon City. **McCARVER, MORTON MATTHEW, HOUSE**, 554 Warner-Parrot Rd., (1-21-74) HABS.

Oregon City. **MCLOUGHLIN HOUSE NATIONAL HISTORIC SITE**, McLoughlin Park, between 7th and 8th Sts., (10-15-66) HABS.

Oregon City. **ROSE FARM**, 534 Holmes Lane, (12-2-74) HABS.

Oregon City vicinity. **AINSWORTH, CAPT. JOHN C., HOUSE**, 19195 S. Leland Rd., (3-26-73)

Wemme vicinity. **OREGON TRAIL, BARLOW ROAD SEGMENT**, NW of Wemme, (11-20-74)

West Linn. **WILLAMETTE FALLS LOCKS**, W bank of Willamette River, (2-5-74)

clatsop county

Astoria. **ASTORIA COLUMN**; Coxcomb Hill, (5-2-74) G.

Astoria. **ELMORE, SAMUEL, CANNERY**, On the waterfront at the foot of Flavel St., (11-13-66) NHL.

Astoria. **FORT ASTORIA**, 15th and Exchange Sts., (10-15-66) NHL.

Astoria vicinity. **FORT CLATSOP NATIONAL MEMORIAL**, 4.5 mi. S of Astoria, (10-15-66)

Hammond. **FORT STEVENS**, Fort Stevens State Park, (9-22-71)

coos county

Bandon. **COQUILLE RIVER LIGHT**, Bullard's Beach State Park, (3-22-74)

Coos Bay. **MARSHFIELD SUN PRINTING PLANT**, 1049 N. Front St., (3-21-73) G.

curry county

Agness vicinity. **ROGUE RIVER RANCH**, E of Agness near confluence of Mule Creek and Rogue River, (12-29-75)

Douglas county

Glide vicinity. **SUSAN CREEK INDIAN MOUNDS SITE**, (11-20-74)

Roseburg. **FLOED, CREED, HOUSE (JOSEPH LANE HOUSE)**, 544 S.E. Douglas St., (12-31-74)

Roseburg. **WILLIS, JUDGE WILLIAM R., HOUSE**, 744 SE. Rose St., (6-5-75)

Yoncalla vicinity. **APPLEGATE, CHARLES, HOUSE**, NE of Yoncalla on Halo Trail, (3-17-75) HABS.

OREGON

NOTICES

grant county

Canyon City. **ST. THOMAS' EPISCOPAL CHURCH**, 135 Washington St., (11-21-74) g.

John Day. **KAM WAH CHUNG COMPANY BUILDING**, Canton St., John Day City Park, (3-20-73) g.

harney county

Burns vicinity. **FRENCH ROUND BARN**, Diamond Station, (9-10-71)

hood river county

Cascade Locks. **CASCADE LOCKS MARINE PARK**, On the Columbia River, (5-15-74) g.
Mt. Hood. **CLOUD CAP INN**, NE flank of Mt. Hood in Mt. Hood National Forest, (10-18-74)

jackson county

Eagle Point. **SNOWY BUTTE FLOUR MILL**, Off OR 62, (9-1-76)

Jacksonville. **JACKSONVILLE HISTORIC DISTRICT**, (4-11-72) NHL.

Jacksonville. **ORTH, JOHN, HOUSE**, Main and 3rd Sts., (4-11-72) g.

Rogue River vicinity. **BIRDSEYE, DAVID N., HOUSE**, U.S. 99, S of Rogue River, (5-1-74) HABS.

josephine county

Wolf Creek. **WOLF CREEK TAVERN**, About 22 mi. N of Grants Pass, (9-22-72) HABS; g.
Wolf Creek vicinity. **WHISKY CREEK CABIN**, 10 mi. W of Wolf Creek at Rogue River, (9-5-75)

klamath county

LOWER KLAMATH NATIONAL WILDLIFE REFUGE, Reference—see Siskiyou County, CA

Fort Klamath vicinity. **FORT KLAMATH SITE**, (10-7-71)

Klamath Falls. **BALDWIN HOTEL**, 31 Main St., (10-2-73)

lake county

ABERT LAKE PETROGLYPH SITE, (11-20-74)

GREASER PETROGLYPH SITE, (11-20-74)

Fort Rock vicinity. **FORT ROCK CAVE**, (10-15-66) NHL.

Plush vicinity. **STONE BRIDGE AND THE OREGON CENTRAL MILITARY WAGON ROAD**, The Narrows S of Plush, (11-8-74)

Silver Lake vicinity. **PICTURE ROCK PASS PETROGLYPHS SITE**, SE of Silver Lake, (8-28-75)

lane county

Cottage Grove. **FIRST PRESBYTERIAN CHURCH**, 216 S. 3rd St., (12-31-74)

Eugene. **DEADY HALL**, University of Oregon campus, (4-11-72) HABS.

Eugene. **SMEEDE HOTEL**, 767 Willamette St., (1-17-74)

Eugene. **VILLARD HALL**, University of Oregon, (4-11-72) HABS.

lincoln county

Newport. **OLD YAQUINA BAY LIGHTHOUSE**, Yaquina Bay State Park, (5-1-74)

Siletz. **SILETZ AGENCY SITE (GOVERNMENT HILL)**, Siletz-Logsdon Rd., (1-1-76)

linn county

Albany. **MONTEITH, THOMAS AND WALTER, HOUSE**, 518 W. 2nd Ave., (5-21-75) g.

Albany. **ST. MARY'S ROMAN CATHOLIC CHURCH**, 822 S. Ellsworth St., (6-5-75)

Albany vicinity. **BABER, GRANVILLE H., HOUSE**, NE of Albany off U.S. 99, (10-29-75) HABS.

Brownsville. **MOYER, JOHN M., HOUSE**, 204 Main St., (1-21-74)

Stayton vicinity. **MT. PLEASANT PRESBYTERIAN CHURCH (CHRISTIAN CHURCH AT MOUNT PLEASANT)**, S of Stayton on Stayton-Jordan Rd., (1-24-74)

malheur county

Arook vicinity. **SHEEP RANCH FORTIFIED HOUSE**, W of Arook, (11-1-74)

Danner vicinity. **CHARBONNEAU, JEAN BAPTISTE, MEMORIAL AND INSKIP STATION RUINS**, (3-14-73)

Jordan Valley. **PELOTA FRONTON**, Bassett St. (U.S. 95), (5-19-72)

Vale. **OLD STONE HOUSE (STONE HOUSE HOTEL)**, 283 S. Main St., (5-19-72) g.

Vale vicinity. **OREGON TRAIL HISTORIC DISTRICT (LYTLE PASS AREA)**, 5 mi. SE of Vale at Lytle Blvd., (10-29-75)

marion county

Aurora. **AURORA COLONY HISTORIC DISTRICT**, (4-16-74)

Champoeg vicinity. **CASE, WILLIAM, HOUSE**, SE of Champoeg off Arbor Rd., (3-21-73)

Gervais vicinity. **BROWN, SAM, HOUSE**, E of Gervais, (11-5-74) HABS.

Hubbard vicinity. **STAUFFER, JOHN, HOUSE AND BARN**, NE of Hubbard, (5-1-74)

Jefferson. **CONSER, JACOB, HOUSE**, 114 Main St., (1-21-74) HABS.

Mount Angel. **ST. MARY'S ROMAN CATHOLIC CHURCH**, Off OR 214, (10-22-76)

Salem. **BOON BRICK STORE**, 888 Liberty St., NE., (11-20-75)

Salem. **BOON, JOHN D., HOUSE**, 260 12th St. NE., (1-17-75)

Salem. **BUSH, ASAH, HOUSE**, 600 Mission St., SE., (1-21-74)

Salem. **KAY, THOMAS, WOOLEN MILL**, 260 12th St. SE., (5-8-73) g.

Salem. **LEE, JASON, HOUSE**, 260 12th St. SE., (4-23-73)

Salem. **METHODIST MISSION PARSONAGE**, 260 12th St. NE., (12-31-74)

Salem. **PORT, DR. LUKE A., HOUSE (DEEPWOOD)**, 1116 Mission St., SE., (10-2-73) g.

Salem. **WALLER HALL, WILLAMETTE UNIVERSITY**, 900 State St., (11-20-75)

Silverton vicinity. **MCCORKLE, GEORGE F., HOUSE**, W of Silverton, (12-24-74) HABS.

West Stayton vicinity. **PLEASANT GROVE PRESBYTERIAN CHURCH**, NW of West Stayton, (8-7-74)

Woodburn. **SETTLEMIER, JESSE H., HOUSE**, 355 N. Settlemier Ave., (12-19-74)

multnomah county

Crown Point. **VISTA HOUSE**, Columbia River Scenic Hwy., (12-5-74)

Portland. **BISHOP'S HOUSE**, 219-223 S.W. Stark St., (10-18-74) g.

Portland. **COMMONWEALTH BUILDING**, 421 SW. 6th Ave., (3-30-76)

Portland. **FIRST CONGREGATIONAL CHURCH**, 1126 SW. Park St., (5-2-75)

Portland. **FIRST NATIONAL BANK (OREGON PIONEER SAVINGS LAND-MARK BUILDING)**, 401 S.W. 5th Ave., (10-15-74)

Portland. **FIRST PRESBYTERIAN CHURCH OF PORTLAND**, 1200 S.W. Alder St., (12-19-74)

Portland. **KAMM, JACOB, HOUSE**, 1425 S.W. 20th Ave., (11-5-74)

Portland. **MARKS, MORRIS, HOUSE**, 1501 S.W. Harrison St., (12-30-75)

Portland. **OLD CHURCH (CALVARY PRESBYTERIAN CHURCH)**, 1422 S.W. 11th Ave., (3-29-72) g.

Portland. **PARAMOUNT THEATRE**, 1037 SW. Broadway, (4-22-76)

Portland. **PIONEER COURTHOUSE (U.S. COURTHOUSE AND CUSTOMHOUSE)**, 520 S.W. Morrison St., (3-20-73)

Portland. **PITTOCK MANSION**, 3229 N.W. Pittock Dr., (11-21-74)

Portland. **PORTLAND ART MUSEUM**, 1219 S.W. Park Ave., (12-31-74)

Portland. **PORTLAND CITY HALL**, 1220 S.W. 5th Ave., (11-21-74)

Portland. **PORTLAND YAMHILL HISTORIC DISTRICT**, Roughly bounded by Taylor, Morrison, 2nd Ave. (includes both sides), and Willamette River, (7-30-76)

Portland. **ST. JAMES LUTHERAN CHURCH**, 1315 SW. Park Ave., (5-21-75)

Portland. **ST. JOHN'S EPISCOPAL CHURCH**, Foot of S.E. Spokane St., (12-27-74)

Portland. **ST. PATRICK'S ROMAN CATHOLIC CHURCH AND RECTORY**, 1635 N.W. 19th Ave., (5-1-74)

Portland. **U.S. CUSTOMHOUSE**, 220 N.W. 8th Ave., (5-2-74)

Portland. **WATZEK, AUBREY R., HOUSE**, 1061 S.W. Skyline Blvd., (11-1-74)

Sauvie Island. **BYBEE-HOWELL HOUSE**, Off Sauvie Island Rd., (11-5-74) HABS.

multnomah county

Portland. **PORTLAND SKIDMORE/OLD TOWN HISTORIC DISTRICT**, Roughly bounded by Harbor Dr., Everett, 3rd, and Oak Sts., (12-6-75)

polk county

Salem. **BRUNK, HARRISON, HOUSE**, Brunk Corner and OR 22, (5-6-75)

Salem vicinity. **PHILLIPS, JOHN, HOUSE**, NW of Salem on Spring Valley Rd., (3-15-76)

Willamina vicinity. **FORT YAMHILL SITE**, (7-27-71) g.

Zena. **SPRING VALLEY PRESBYTERIAN CHURCH**, SE of McCoy, (5-15-74)

sherman county

Grass Valley vicinity. **MACK CANYON ARCHEOLOGICAL SITE**, 5-mi. NW of Grass Valley, (8-22-75)

tillamook county

Manzanita vicinity. **WENTZ, HARRY F., STUDIO/BUNGALOW**, N of Manzanita off U.S. 101, (4-22-76)

umatilla county

Weston. **SAILING, ISHAM, HOUSE**, Off OR 204, (1-1-76) g.

union county

Cove. **ASCENSION EPISCOPAL CHURCH AND RECTORY**, Church St., (12-3-74)

wasco county

The Dalles. **FORT DALLES SURGEON'S QUARTERS**, 15th and Garrison Sts., (9-10-71) g.

The Dalles. **ST. PETER'S ROMAN CATHOLIC CHURCH**, 3rd and Lincoln Sts., (6-20-74)

The Dalles vicinity. **FIVEMILE RAPIDS SITE**, (12-19-74)

NOTICES

PENNSYLVANIA

washington county

- Forest Grove. SMITH, ALVIN T., HOUSE, S. Elm St., (11-8-74) HABS.
 Forest Grove. TUALATIN ACADEMY (OLD COLLEGE HALL), Pacific University campus, (2-12-74) HABS.
 Hillsboro. OLD SCOTCH CHURCH, Scotch Church Rd., (11-5-74)
 Tualatin. SWEET, JOHN, HOUSE, 18815 S.W. Boones Ferry Rd., (11-8-74)
 West Union. WEST UNION BAPTIST CHURCH, W. Union Rd., (7-10-74) HABS.

yamhill county

- Dayton. SMITH, ANDREW, HOUSE, 306 5th St., (6-23-76)
 Dayton vicinity. COOK, AMOS, HOUSE, NW of Dayton on OR 233, (12-31-74) HABS.
 Dayton vicinity. FLETCHER, FRANCIS, HOUSE, W of Dayton off OR 18, (10-29-75) HABS.
 Dundee. HAGEY, LEVI, HOUSE, Off U.S. 99, (12-19-74) HABS.
 Newberg. MINTHORN, DR. HENRY J., HOUSE (HERBERT HOOVER HOUSE), 115 S. River St., (10-29-75)

PENNSYLVANIA

adams county

- Fairfield. FAIRFIELD INN, Main St., (4-2-73) HABS.
 Gettysburg. ADAMS COUNTY COURTHOUSE, Baltimore and W. Middle Sts., (10-1-74)
 Gettysburg. DOBBIN HOUSE, 89 Steinwehr Ave., (3-26-73)
 Gettysburg. GETTYSBURG NATIONAL MILITARY PARK, (10-15-66) HABS.
 Gettysburg. LUTHERAN THEOLOGICAL SEMINARY-OLD DORM, Seminary Ridge, Lutheran Theological Seminary campus, (5-3-74) HABS.
 Gettysburg. PENNSYLVANIA HALL, GETTYSBURG COLLEGE, Gettysburg College campus, (3-16-72) HABS.
 Gettysburg. SHEADS HOUSE, 331 Buford Ave., (12-8-76)
 Gettysburg and vicinity. GETTYSBURG BATTLEFIELD HISTORIC DISTRICT, Town of Gettysburg and its environs, (3-19-75)
 Gettysburg vicinity. EISENHOWER NATIONAL HISTORIC SITE, SW edge of Gettysburg National Military Park, (11-27-67)
 Hanover vicinity. CONEWAGO CHAPEL, 3 mi. NW of Hanover, (1-29-75)
 Hunterstown. GREAT CONEWAGO PRESBYTERIAN CHURCH, Church Rd., (12-27-74)
 New Oxford. JOHN'S BURNT MILL BRIDGE, SW of New Oxford, over South Branch of Conewago Creek, (12-16-74)

allegheny county

- Bethel vicinity. MILLER, JAMES, HOUSE, E of Bethel on Manse Dr., (1-17-75)
 Braddock. CARNEGIE FREE LIBRARY OF BRADDOCK, 419 Library St., (6-19-73)
 Churchill. BEULAH PRESBYTERIAN CHURCH, Beulah and McCready Rds., (11-3-75)
 Edgeworth. SHIELDS, DAVID, HOUSE (NEWINGTON), Shields Lane, (10-29-75)
 Heidelberg vicinity. NEVILLE HOUSE, S of Heidelberg on PA 50, (2-5-74) g.
 Natrona Heights vicinity. BURTNER STONE HOUSE, NW of Natrona Heights on Burtner Rd., (1-13-72)
 Oakdale vicinity. WALKER-EWING LOG HOUSE, NE of Oakdale on Noblestown Rd., (1-30-76)

- Pittsburgh. ALLEGHENY COUNTY COURTHOUSE AND JAIL, 436 Grant St., (3-7-73) NHL; HABS.
 Pittsburgh. ALLEGHENY POST OFFICE (OLD NORTH POST OFFICE), Allegheny Center, (7-27-71) HABS; g.
 Pittsburgh. BUTLER STREET GATEHOUSE, 4734 Butler St., (7-30-74)
 Pittsburgh. BYERS-LYONS HOUSE, 901 Ridge Ave., (11-19-74)
 Pittsburgh. CARNEGIE FREE LIBRARY OF ALLEGHENY, Allegheny Center, (11-1-74)
 Pittsburgh. CATHEDRAL OF LEARNING, Forbes Ave. and Bigelow Blvd., (11-3-75)
 Pittsburgh. DOLLAR SAVINGS BANK, 4th Ave. and Smithfield St., (7-14-76)
 Pittsburgh. DUQUESNE INCLINE, 1220 Grandview Ave., (3-4-75)
 Pittsburgh. EMMANUEL EPISCOPAL CHURCH, North and Allegheny Aves., (5-3-74)
 Pittsburgh. EVERGREEN HAMLET, Evergreen Hamlet Rd., (9-17-74)
 Pittsburgh. FORKS OF THE OHIO, Point Park, (10-15-66) NHL.
 Pittsburgh. GARDNER-BAILEY HOUSE, 124 W. Swissvale Ave., (10-1-74)
 Pittsburgh. HEATHSIDE COTTAGE, 416 Catoma St., (12-30-74)
 Pittsburgh. HIGHLAND TOWERS APARTMENTS, 340 S. Highland Ave., (9-28-76)
 Pittsburgh. MAIN BUILDING, U.S. BUREAU OF MINES, 4800 Forbes Ave., (5-24-74)
 Pittsburgh. MANCHESTER HISTORIC DISTRICT, Irregular pattern contained with Fausley, Chateau, Franklin, and Bidwell Sts., (9-18-75)
 Pittsburgh. MEXICAN WAR STREETS HISTORIC DISTRICT, Irregular pattern between Brighton and Arch Sts. and between O'Hern and West Park, (5-28-75)
 Pittsburgh. OLD HEIDELBERG APARTMENTS, Braddock Ave. at Waverly St., (5-4-76)
 Pittsburgh. PENNSYLVANIA RAILROAD STATION, 1101 Liberty Ave., (4-22-76)
 Pittsburgh. PHIPPS CONSERVATORY, Schenley Park, (11-13-76)
 Pittsburgh. PITTSBURGH & LAKE ERIE RAILROAD STATION, Smithfield St. at Carson St., (1-11-74) HABS.
 Pittsburgh. ROTUNDA OF THE PENNSYLVANIA RAILROAD STATION, 1100 Liberty Ave. at Grant St., (4-11-73) HABS.
 Pittsburgh. SHADYSIDE PRESBYTERIAN CHURCH, Amberson Ave. and Westminster Pl., (4-3-75)
 Pittsburgh. SINGER, JOHN F., HOUSE, 1318 Singer Pl., (11-13-74)
 Pittsburgh. SMITHFIELD STREET BRIDGE, Smithfield St. at the Monongahela River, (3-21-74) NHL.
 Pittsburgh. SNYDER, WILLIAM PENN, HOUSE, 852 Ridge Ave., (5-3-76)
 Pittsburgh. SOLDIERS AND SAILORS MEMORIAL HALL, 5th Ave. at Bigelow Blvd., (12-30-74)
 Pittsburgh. SOUTH SIDE MARKET BUILDING, 12th and Bingham Sts., (10-14-76)
 Pittsburgh. ST. JOHN BAPTIST'S UKRANIAN CATHOLIC CHURCH, 109 S. Carson St., (10-29-74)
 Pittsburgh. ST. STANISLAUS KOSTKA ROMAN CATHOLIC CHURCH, 21st and Smallman Sts., (9-14-72)
 Pittsburgh. UNION TRUST BUILDING, 435 Grant St., (1-21-74)
 Pittsburgh (Mount Washington). MONONGAHELA INCLINE, Grandview Ave. at Wyoming Ave., (6-25-74)

- Pittsburgh vicinity. FULTON LOG HOUSE, NW of Pittsburgh on Clifton-Bridgeville Rd off PA 65, (12-6-75)
 Springdale. CARSON, RACHEL, HOUSE, 613 Marion Ave., (10-22-76)

armstrong county

- Dayton. MARSHALL, THOMAS, HOUSE, State St., (4-22-76)

beaver county

- BEGINNING POINT OF THE U.S. PUBLIC LAND SURVEY, Reference—see Columbia County, OH
 Ambridge vicinity. OLD ECONOMY, NE of Pittsburgh on PA 65, (10-15-66) NHL.
 Beaver. FORT MCINTOSH SITE, River Rd., (4-24-75)
 Beaver. QUAY, MATTHEW S., HOUSE, (5-15-75) NHL.
 Darlington. GREERSBURG ACADEMY, Market St., (2-24-75)
 Freedom. VICARY, CAPT. WILLIAM, HOUSE, 1251 4th St., (11-8-74)
 Harmony. LEGIONVILLE, Between Duss Ave. and PA 65, (3-27-75)

bedford county

- Bedford. ESPY HOUSE, 123 Pitt St., (11-19-74)

berks county

- Bally vicinity. CHRISTMAN, PHILIP, HOUSE, 1 mi. SE of Bally at the Berks/Montgomery County line, (3-7-73)
 Birdsboro vicinity. BOONE, DANIEL, HOMESTEAD SITE AND BERTOLET CABIN, 2 mi. N of Birdsboro, (3-24-72)
 Centerport vicinity. BELLMAN'S UNION CHURCH, SW of Centerport off Rte. 726, (12-4-73)
 Douglassville. OLD SWEDE'S HOUSE, Old Philadelphia Pike, (1-21-74) HABS.
 Douglassville. WHITE HORSE TAVERN, 509 Old Philadelphia Pike, (4-21-75)
 Kutztown vicinity. HOTTENSTEIN MANSION, 2 mi. E of Kutztown on U.S. 222, (6-22-72)
 Lobachsville vicinity. KEIM HOMESTEAD, W of Lobachsville, (5-1-74) HABS.
 Morgantown vicinity. HOPEWELL VILLAGE NATIONAL HISTORIC SITE, 10 mi. NE of Morgantown off Pennsylvania Tpke., (10-15-66) HABS.
 Pleasant Valley. GRUBER WAGON WORKS, SE of Mount Pleasant on PA 183, (6-2-72) HAER.
 Reading. ASKEW BRIDGE, N. 6th St. near Woodward St., (3-1-73) HABS.
 Reading. PAGODA, Mount Penn, at jct. of Duryea Dr. and Skyline Blvd., (11-7-72) g.
 Reading. TRINITY LUTHERAN CHURCH, 6th and Washington Sts., (6-7-76)
 Topton vicinity. SALLY ANN FURNACE COMPLEX, SW of Topton, (8-17-76)
 Womelsdorf vicinity. WEISER, CONRAD, HOUSE, 2 mi. E of Womelsdorf, (10-15-66) NHL.
 Yellow House vicinity. FISHER, HENRY, HOUSE, About 1.25 mi. N of Yellow House on PA 662, (6-4-73)

blair county

- Altoona. BAKER MANSION, 3500 Baker Blvd., (6-5-75)
 Altoona. DUDLEY, CHARLES B., HOUSE, 802 Lexington Ave., (5-11-76) NHL.
 Altoona. MISHLER THEATRE, 1208 12th Ave., (4-11-73)
 Altoona vicinity. HORSESHOE CURVE, 5 mi. W of Altoona on PA 193, (11-13-66) NHL.

Staten Island, U.S. Coast Guard Base, St. George.

Saratoga County

Saratoga Springs, *Saratoga Springs Historic District.*

Saratoga Springs, *Yaddo House and Gardens, Saratoga Springs Historic District.*

Schuylerville, *Archeological Site, Schuylerville Water Pollution Control Facility.*

Schoharie County

Breakabeen, *Breakabeen Historic District*, between village of North Blenheim and Breakabeen.

Staten Island

Tottenville, *Ward's Point, Oakwood Beach Project*

Suffolk County

Janesport vicinity, *East End Site.*

Janesport vicinity, *Hallock's Pond Site.*

New York, *Fire Island Light Station, U.S. Coast Guard Station.*

New York, *Little Gull Island Light Station*, off North Point of Orient Point, Long Island.

New York, *Plum Island Light Station*, off Orient Point, Long Island.

New York, *Race Rock Light Station*, S. of Fishers Island, 10 mi. N. of Orient Point.

Northville *Historic District*, houses along Sound Ave.

Ulster County

Kingston vicinity, *Esopus Meadows Light Station*, middle of Hudson River.

New York, *Rondout North Dike Light*, center of Hudson River at Jct. of Rondout Creek and Hudson River.

New York, *Saugerties Light Station*, Hudson River.

Washington County

Greenwich, *Palmer Mill (Old Mill)*, Mill St.

Westchester County

Port Washington vicinity, *Execution Rocks Light Station*, lower SW portion of Long Island Sound.

Yonkers, *Women's Institute Building.*

Yorktown, *Yorktown Railroad Station.*

NORTH CAROLINA

Alamance County

Burlington, *Clapp's Mill and Dam Site* (also in Guilford County).

Burlington, *Faust Mill* (also in Guilford County).

Burlington, *Low House* (also in Guilford County).

Burlington, *Southern Railway Passenger Depot*, NE corner Main and Webb Sts.

Brunswick County

Southport, *Fort Johnston*, Moore St.

Caswell County

Archeological Sites OS-12, County Line Creek Watershed Project (also in Rockingham County).

Womack's Mill, in County Creek Watershed Project (also in Rockingham County).

Cleveland County

Archeological Resources in Second Broad River Watershed Project (also in Rutherford County).

Cumberland County

Fayetteville, *Veterans Administration Hospital Confederate Breastworks*, 23 Ramsey St.

Dare County

Buxton, *Cape Hatteras Light*, Cape Hatteras National Seashore.

Hyde County

Ocracoke, *Ocracoke Lighthouse.*

NORTH DAKOTA

Burleigh County

Bismarck, *Fort Lincoln Site.*

OHIO

Adams County

Wrightsville vicinity, *Grimes Site (33 AD 39)*, Killen Electric Generating Station.

Wrightsville vicinity, *Killen Bridge Site, (33 AD 36)*, Killen Electric Generating Station.

Ashtabula County

Astabula, *West Fifth Street Bridge*, over Astabula River.

Clermont County

Neville vicinity, *Maynard House*, 2 mi. E of Neville off U.S. 52.

Crawford County

Calvary Reformed Church, *First United Methodist Church, Crestline Shunk Museum.*

Darke County

DAR-S.R.-571-0.00.

Montgomery County

Columbia Bridge Works.

Lower Cratis Road Bridge.

Pickaway County

Williamsport vicinity, *The Shack (Daugherty, Harry, House)*, 5.5 mi. NW of Williamsport.

Richland County

Mansfield, *Ritter, William, House*, 181 S. Main.

Seneca County

Tiffin, *Old U.S. Post Office*, 215 S. Washington St.

Summit County

United Way Building, Perkins St.

Warren County

Corwin, *Shaffer Mound*, S of New Burlington Rd.

Harveysburg, *E. L. Anderlee Mound*, S of New Burlington Rd. in Caesar Creek Lake Project.

Wayne County

Wooster, *Thorne House*, 1576 Beal Ave.

OKLAHOMA

Atoka County

Estep Shelter, Lower Clear Boggy Watershed.

Graham Site, Lower Clear Boggy Watershed.

Comanche County

Fort Sill, *Blockhouse on Signal Mountain* off Mackenzie Hill Rd.

Fort Sill, *Camp Comanche Site*, E range on Cache Creek.

Fort Sill, *Chiefs Knoll, Post Cemetery*, N of

Haskell County

Keota vicinity, *Otter Creek Archeological Site*, SW of Keota.

Kay County

Newkirk vicinity, *Bryson Archeological Site*, NE of Newkirk.

OREGON

Baker County

Baker vicinity, *Virtue Flat Mining District*, 10 mi. E of Baker off Hwy. 86.

Columbia County

Scappose vicinity, *Portland and Southwestern Railroad Tunnel*, 13 mi. NW of Scappose.

Coos County

Charleston, *Cape Arago Light Station.*

Curry County

Port Orford, *Cape Blanco Light Station.*

Douglas County

Winchester Bay, *Umpqua River Lighthouse.*

Gilliam County

Arlington vicinity, *Four Mile Canyon Area (Oregon Trail)*, 10 mi. SE of Arlington. *Crum Gristmill*, Ghost Camp Reservoir area. *Old Wagon Road*, Ghost Camp Reservoir area. *Olex School*, Ghost Camp Reservoir Area. *Steel Truss Bridge*, Ghost Camp Reservoir area.

Klamath County

Crater Lake National Park, *Crater Lake Lodge.*

Lane County

Roosevelt Beach, *Heceta Head Lighthouse.* Roosevelt Beach, *Heceta Head Light Station.*

Lincoln County

Agate Beach, *Yakuina Head Lighthouse.*

Tillamook County

Tillamook, *Cape Meares Lighthouse.*

Wasco County

Memaloose Island, River Mile 177.5 in Columbia River.

Wheeler County

Antone, *Antone Mining Town*, Barlie 1901-1906.

PENNSYLVANIA

Adams County

Gettysburg, *Barlow's Knoll*, adjacent to Gettysburg National Military Park. *Kuhn's Forging Bridge*, spans Conewago Creek.

Allegheny County

Bruceton, *Experimental Mine*, U.S. Bureau of Mines, off Cochran Mill Rd. *McJunkin Site*, New Texas Rd.

Berks County

Mt. Pleasant, *Berger-Stout Log House*, near jct. of Church Rd. and Tulephocken Creek. Mt. Pleasant, *Conrad's Warehouse*, near jct. of Rte. 183 and Powder Mill Rd. Mt. Pleasant, *Heck-Stamm-Unger Farmstead*, Gruber Rd.

Mt. Pleasant, *Miller's House*, jct. of Rte. 183 and Powder Mill Rd.

Mt. Pleasant, *O'Bolds-Billman Hotel and Store*, Gruber Rd. and Rte. 183.

Mt. Pleasant, *Pleasant Valley Roller Mill*, Gruber Rd.

Mt. Pleasant, *Reber's Residence and Barn*, on Tulephocken Creek.

Mt. Pleasant, *Union Canal*, Blue Marsh Lake Project area.

Butler County

Butler, *Bonnie Brook Archeological Site.*

Chester County

Charlestown, *Nesspor House (Thomas Davis House)*, State Rd.

Charlestown, *Pickering Creek Ice Dam*, State Rd.

Lock Aerie.

Nature Center of Charleston, State Rd. Charleston township.

Cultural Resources In Oregon

To date, some 70% of the State of Oregon has been surveyed by historians to identify historic sites and buildings important to Oregon's past. At the same time, only some three percent of the state has been surveyed by archeologists. The results of these cultural resource surveys indicate that Oregon contains some 2,500 historic sites worthy of placement on the Statewide Inventory and perhaps some 120,000 archeological sites, for a density of about 1.3 cultural sites per square mile.

The large difference between numbers of historic and archeologic sites is merely a reflection of the fact that Indians have lived here for some 20,000 years while Euro-Americans have been in Oregon only about 173 years. The large gap between seventy percent and three percent in completeness of surveys is due to several factors: 1) archeological sites are "buried" to a greater degree and therefore more difficult to locate 2) historians have written records to utilize, often telling them where to look 3) the Indian societies were pre-literate and most of their oral traditions telling of old village site locations were never recorded by early settlers.

Since the year of 1906 the federal government has passed several laws and executive orders in order to try and preserve the cultural remains of both Indian and early Euro-American history. The government realized that the native cultures had been largely destroyed and their cultural remains were likewise disappearing under the shovel of "pot-hunters", the construction of towns, and the activities of road builders, loggers, miners and others.


Each archeologic site is like a book of which only one copy exists. Properly excavated and analyzed, a site can tell who lived there, when they lived there, how large the group was, what the people ate, the climate at the time, the type of social organization the group practiced, average life spans, religious practices and even some of the diseases they suffered from. If this site is destroyed, either through the purposeful digging of relic hunters or through the accidental activities of house, road, sewer line, water line, or other developers, then the book, which is public property has been burned.

Archeological Site Density



high density



medium density



largely
unsurveyed



Abiqua Trail, Marion, Clackamas, Umatilla, Morrow, Gilliam and Sherman Counties,

Prehistory-Anthropology.

Wasco

Alder Creek Indian Campsite, City of the Dalles. Watershed , (T. 15, R., 11 E., NW $\frac{1}{4}$ NW $\frac{1}{4}$,

Sec. 30), The Dalles vicinity, Prehistory: Anthropology.

Wasco

Antelope, 1860s, Transportation and Communication.

Wasco

Balch Hotel, Dufur, 1907, Architecture: Commercial; Commerce and Industry

Wasco

Barlow Road, Mt. Hood vicinity, Clackamas and Hood River Counties, 1846, Oregon

Trail Migration.

Wasco

Barlow Road Junction (The Dalles), S3, T1N, R13E, (3rd and Washington Sts.),

The Dalles, 1845 and later. Oregon Trail.

Barlow Toll Gate (Eastern), S35, T4S, R11E, 11 miles west of Tygh Valley,
1846-1852. Oregon Trail.

Wasco

Bennett (Judge A.S.) House, West 8th Street, The Dalles, 1899, Architecture: Queen Anne

Wasco

Celilo Canal, Celilo vicinity, 1915, Transportation and Communication.

Wasco

Celilo Converter Station, The Dalles vicinity, 1970, Commerce and Industry; Transportation
and Communication

Wasco

Celilo Falls, The Dalles vicinity, Prehistory: Anthropology.

Wasco

Celilo Portage Railroad Site, The Dalles vicinity, 1863, Transportation and Communication.

Wasco

Chenoweth Creek (mouth), S28, T2N, R13E, The Dalles vicinity, 1850 and later.
Oregon Trail.

Commercial Building (Bonney Saddles), Union Street, The Dalles, 1876, Architecture:

Wasco

Crow Creek Indian Camp Site, City of the Dalles Watershed (T. 15, R. 11 E., NW $\frac{1}{4}$ NW $\frac{1}{4}$,
Section 24), The Dalles vicinity, Prehistory; Anthropology.

Wasco

Deschutes River Bridge, State Highway 216, 7.7 miles east of Tygh Valley, 1915.
Transportation.

Wasco

Dufur, ca. 1872, Agriculture, Transportation and Communication.

Wasco

"End of Oregon Trail" Monument, 8th and Union Sts., S3, T1N, R13E, The
Dalles, 1906. Oregon Trail.

Wasco

Female Seminary Building, The Dalles, ca. 1864, Architecture: Italianate; Education

Wasco

First Wasco County Courthouse, Lewis and Clark Plaza, The Dalles, 1858, Political and
Military Affairs after 1864

Wasco

Fivemile Rapids Site, The Dalles, 9,000 B.C. to AD 1820, Prehistory-Anthropology

Wasco

Fort Dalles Surgeon's Quarters, The Dalles, 1857, Military and Indian Affairs,

Wasco

Fort Rock Campsite, The Dalles, 1806, Lewis and Clark Expedition

Wasco

Granada Theatre, Second Street, The Dalles, Architecture: Traditional; Travel and Recreation.

Wasco

Indian Shaker Church, The Dalles Vicinity, 1896, Religious Movement

Wasco

Johnstone Building, Main Street, Dufur, ca. 1900, Architecture: Commercial;

Commerce and Industry.

Wasco

Klinger's Camp, S3, T4S, R9E, 4 miles east of Barlow Pass, 1845-1846.

Oregon Trail; Transportation and Communication.

Wasco

Lolo Pass Trail, The Dalles to Sandy vicinity, Hood River and Clackamas Counties,

Transportation and Communication, Prehistory-Anthropology.

Wasco

Masonic Building, (A.F. and A.M.) Main Street, Dufur, 1908, Architecture: Commercial

Wasco

Meek Cutoff, Malheur, Harney, Deschutes, Lake, Jefferson, Crook Counties, 1845,

Transportation and Communication.

Wasco

Memaloose Island, Mosier vicinity, Prehistory-Anthropology.

Wasco

Moody (Zenas Ferry, Gov.) House, 10th Street, The Dalles, 1860s, Political and
Military Affairs after 1864.

Wasco

Nathan Olney's Store Site, Union St. at E. 1st, S3, T1N, R13E, The Dalles,
1847-1850. Oregon Trail.

Wasco

Old Columbia River Highway Bridge, 5.5 miles south of Mosier on old U.S.
Highway 30, 1921. Transportation.

Wasco

Oregon Trail, Malheur, Baker, Umatilla, Morrow, Sherman, Clackamas, Multnomah, *William*
^R
Hood^Rriver Counties, 1843-1857, Oregon Trail Migration.

Wasco

Oregon Trunk Railroad, Jefferson, Deschutes and Klamath Counties, ¹⁹⁰⁰ Transportation and

Wasco

Ortley, 10 miles N.W. of ~~the~~ Dalles near Rowena, off Interstate 80N, 1908-1922.
Agriculture.

Wasco

Petroglyph, The Dalles vicinity (T. 15, R. 11 E., NW ¼, NW ¼, Section 5) City of the

Dalles Watershed, Prehistory: Anthropology.

Wasco

Pulpit Rock, The Dalles, 1834, Missionary Frontier.

Wasco

St. Peter's Roman Catholic Church, S.W. corner of Third and Lincoln, The Dalles, 1898,

Architecture: Gothic Revival.

Wasco

Second Wasco County Courthouse, 103 W. 3rd Street, The Dalles, 1884, Political and Military

Affairs after 1864; Architecture: Renaissance Revival

Wasco

Seufert Cannery, The Dalles, 1886, Commerce and Industry

Wasco

Shaniko, ca. 1870, Transportation and Communication; Commerce and Industry

Wasco

Shaniko Hotel, Shaniko, ca. 1900, Architecture: Commercial; Commerce and Industry

Wasco

Sherar's Bridge, Tygh Valley vicinity, 1868, Prehistory: Anthropology; Transportation and Communication; Travel and Recreation;

Wasco

The Dalles - Canyon City Wagon Road, 1864, Transportation and Communication

Wasco

The Dalles City Hall, 313 Court Street, The Dalles, 1909, Architecture: Traditional; Political and Military Affairs

Wasco

The Dalles-Sandy River Trail, South bank Columbia River, ~~Hood River~~ and

~~Multnomah Counties~~, 1800's, Transportation and Communication.

Wasco

Tygh Valley, 1892, Agriculture, Transportation and Communication.

Tygh Valley Grade, S9, T4S, R13E, Tygh Valley vicinity, n.d. Oregon Trail.

Wasco

"Tygh Valley Rock Bridge", off State Highway 216, 1.7 miles east of Tygh Valley,
1915. Transportation.

Wasco

U.S. Mint, E. 3rd Street, The Dalles, 1868, Political and Military affairs after 1864.

Wasco

Waldron Store, 1st Street, The Dalles, 1857, Commerce and Industry; Architecture:

Commercial

Wasco

Warm Springs Indian Reservation, Jefferson County, 1855, Military and Indian Affairs.

Wasco

"Wascopam," Methodist Mission Site, (Fort Lee), The Dalles, 1838-1847, Military and

Indian Affairs; Missionary Frontier.

Wasco


WS-1 Big Eddy, WS-1 lies ca. 5 miles east of The Dalles on the south bank of the Columbia River and at the west end of Fivemile Rapids, excavated in 1952, 1953, and 1956. Aboriginal Prehistory.

Wasco

White River Power Plant, S12, T3S, R13E, Four Miles East of Tygh Valley, 1901,

Development of Conservation and Natural Resources.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 7-3, 10-1
Name
(Common) Anderson (Lewis) Granary
(Historic) (same)
Address W. 16th at Garrison streets
The Dalles, Oregon
Present Owner City of The Dalles
(Address) The Dalles, Oregon
Original Use granary
Date of Construction c. 1890's

nd statement of historical significance:

The Lewis Anderson granary is a rectangular, wood building constructed of hewn logs which are notched and joined on the corners. It has a gable roof and a small diamond window above the door for lighting. The building was resited in The Dalles in 1973-74. The structure originally stood on the Anderson farm at Pleasant Ridge in Wasco County.


Lewis Anderson was born in Sweden on February 13, 1859. He settled in Wasco County about 1885 and later erected a complex of buildings on his farm at Pleasant Ridge. For additional biographical information see file sheet on the Lewis Anderson house.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office Anderson, Dale. The History and Preservation of the Lewis Anderson Homestead. Oxon Hill, Md.: [The Author], 1974.
Please enclose map Township 1 S Range 13 W Section 4
(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem 97310



County Wasco
Theme _____
Name (Common) A.O.U.W. Lodge Hall
(Historic) (same)
Address Main Street
Antelope, Oregon
Present Owner _____
Address _____
Original Use Lodge Hall; Commercial
Date of Construction 1893

Physical description of property and statement of historical significance:

The A.O.U.W. Lodge Hall stands on the west side of Highway 218 in Antelope, Oregon. This two story, wood frame building has a gable roof, false front, shiplap exterior, and has one-over-one, double hung sash windows. The front bears the date "1893" and the letters "A.O.U.W." and the symbol of this lodge. The main entry is in the center of the front elevation and is flanked by display windows. The building is in good condition and is used as an antique shop.

Antelope Lodge No. 44 of the A.O.U.W. was one of six fraternal lodges in this town in 1905. The building is the last standing in the community that is associated with such activity.

This may likely be the only A.O.U.W. Hall standing in Oregon.


continue on back if necessary

Recorded by Stephen Dow Beckham Date 1 Sept. 1976

For Oregon State Historic Preservation Office Sources Consulted:

Please enclose map Township 8 ^N _S 17 ^E W Section 5 An Illustrated History of Central Oregon.
Spokane, Wash.: Western Historical Publishing Co., 1905, p. 169.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 9-5, 10-A
Name
(Common) Anderson (Lewis) House
(Historic) (same)
Address W. 16th at Garrison streets
The Dalles, Oregon
Present Owner City of The Dalles Museum Comple
(Address) The Dalles, Oregon
Original Use House
Date of Construction 1895

statement of historical significance:

The Lewis Anderson house originally stood at Pleasant Ridge and was resited in 1975 to its present location in The Dalles. The building is a one and one-half story, wood structure made of hewn logs which are notched and joined at the corners. The house has a shingle, gable roof and a half-round window for attic lighting in the gable ends. The windows are four-over-four, double hung sash.

This house was built in 1895. The longer logs were hauled about four miles to the farm site. Construction was carried out by Abe Pearson, Pearson's son, and Lewis Anderson. Dale Anderson wrote: "Logs were hewn to rough shape and pulled up skids via block and tackle. A log would be placed in position and a gage was used on each side to mark the upper log. It would be turned and hewed down to the mark. They matched both corners of the log in a wedge form and drilled holes with hand augers into which pegs were hammered with a wooden maul. Corners were pegged and fir pegs were spaced along the walls." Anderson continued: "When the gable ends were finished big logs were placed lengthwise to support the roof. Rafter of fir poles were added and slab sheeting. The roof was made of 22 inch split shakes, lapped 8 inches to provide four layers and also ship lapped so that in effect 7 to 8 thicknesses were provided when done. These were nailed down with square nails."

Lewis Anderson was born in Sweden on February 13, 1859. At the age of 14 Anderson was sent to sea. Returning to Sweden in 1879 he found that a sister was going to emigrate to the United States. Anderson joined the party. In 1878 he married Carrie Jacobson. (over)

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:


For Oregon State Historic Preservation Office Anderson, Dale L. The History and Preservation of the Lewis Anderson Homestead. Oxon Hill, Md.: The Author, 1974.
Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 4

(over)

Sources:

Davis, C. Gilman. "The Lewis Anderson Homestead." Thomas Vaughan and Virginia G. Ferriday, eds. Space, Style, and Structure. Portland, Ore.: Oregon Historical Society, 1974, vol. 1, 255-60, photos.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem 97310



County Wasco
Theme _____
Name
(Common) Antelope Community Church
(Historic) Methodist Episcopal Church
Address n.e. corner Union & College
Antelope, Oregon
Present Owner Antelope Community Church
Address Antelope, Oregon
Original Use Chruuch
Date of Construction 1897

Physical description of property and statement of historical significance:

The Antelope Methodist Episcopal Church is a "T"-shape, wood frame building with a gable roof. The structure, set on a stone foundation, has shiplap siding and lancet window bays. The windows are four-over-four, double hung sash and have pediments on the wood surrounds. A round window is located in the gable end of the building. The main entry is through the base of a low bell tower with an open belfry surmounted by a steep, four-sided, hip roof. The date "1897" appears above the entry. This building is in excellent condition and has been recently repainted.

The Methodist Episcopal Church erected this building in 1897. It is in a design or style used by several similar fellowships of this denomination in Oregon in the late 19th century. Three other examples of this church are located in Elkton, Drain, and near Oakland in Douglas County. The Episcopal Church also once had a congregation in this community.

continue on back if necessary

Recorded by Stephen Dow Beckham Date 1 Sept. 1976

For Oregon State Historic Preservation Office

Sources Consulted:

Please enclose map Township 8 ^N 17 ^E Section 5

An Illustrated History of Central Oregon.
Spokane, Wash.: Western Historical Publishing Co., 1905, p. 169.


About 1885 the Andersons came to the Pacific Northwest and at The Dalles Lewis Anderson found employment with the O. R. and N. railroad. Carrie Anderson died July 18, 1922; Lewis Anderson died November 8, 1933.

The Anderson farm included a complex of buildings. Of these structures the house and granary (see file sheet) have been resided in The Dalles.

Sources:

Davis, C. Gilman. "The Lewis Anderson Homestead." Thomas Vaughan and Virginia Guest Ferriday, eds. Space, Style and Structure. Portland, Ore.: Oregon Historical Society, 1974, vol. 1, 255-60, photos.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme _____

Name
(Common) Balch (Charles) Hotel

(Historic) Balch (Charles) Hotel

Address 210 Main Street
Dufur, Oregon

Present Owner _____
(Address) _____

Original Use hotel

Date of Construction 1907

Statement of historical significance:

The Balch Hotel is a three story brick building with rectangular shape. The windows are one-over-one double hung sash set in segmental arches with brick voussiors. The voussiors on the first and second story of the west (front) elevation project from the face of the building. The front porch and balcony of the second floor are supported by square wood columns.

Charles L. Balch was born in Wisconsin on April 21, 1860, a son of John A. and Caroline (Stevenson) Balch. Educated in Oshkosh, Wisconsin, Balch emigrated overland to Oregon in 1883 and settled in Wasco County. After farming, he became a druggist in Dufur and a partner with A. J. Dufur in stock raising. Balch married in 1889 to Lois Dufur, a daughter of Andrew J. Dufur. Balch's sister, Elizabeth E., married A. K. Dufur.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 8 July 1976 Sources Consulted:


For Oregon State Historic Preservation Office

Friedman, Ralph. "Let's Go", Oregon Journal, May 18, 1973.

Please enclose map Township 1 ^N _(S) Range 13 ^{(E) _(W) Section 25}

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme
Name
(Common) Assembly of God Church
(Historic) Christian Church
Address 805 Union Street
The Dalles, Oregon
Present Owner Assembly of God Church
(Address) The Dalles, Oregon
Original Use Church
Date of Construction

211

statement of historical significance:

The former Christian Church in The Dalles is located at the southwest corner of West 7th and Union streets. It is a one story, wood frame building in the shape of a Greek Cross with a steep gable roof. The building has boxed eaves with decorative brackets. The square bell tower has louvers in the belfry and possesses a four-sided, bellcast roof. The exterior of the building is shiplap. The windows are one-over-one, double hung sash. The window bay in the east (front) elevation is made of stained glass. The building is shingled on the gable ends. It is set on a basement and stone foundation covered with stucco or concrete.


The Illustrated History of Central Oregon, which reviews the history of the foundation of churches in The Dalles, does not mention the early background of this fellowship. However, the volume does note: "The Ladies' Aid Society of the First Christian Church of The Dalles was organized October 1, 1892, under the name of the Christian Church Ladies. It began with eight members and has steadily increased in numerical strength."

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office Illustrated History of Central Oregon. Spokane, Wash.: Western Historical Publishing
Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3 Co., 1905, p. 154.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 1.1, 1.2, 1.3
Name (Common) Bear Springs Camp Shelter
Historic) Bear Springs Camp Shelter
Address Highway 216, Mt. Hood National Forest
Present Owner U.S. Forest Service, Dept. of Agriculture
Address) Washington, D.C.
Original Use Picnic Shelter
Date of Construction _____

Historical significance:

This rectangular shelter, constructed of peeled logs, has a shingled gable roof. Vertical logs fully enclose the south elevation and serve as pillars to support the roof on the other three elevations. Logs set in a diagonal decorate the gable ends. A large fireplace of dressed stone flanked by two ovens is located in the south (rear) elevation. An owl, carved of wood, decorates the mantel of the fireplace.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office


Please enclose map Township 5 ^N _S Range 10 ^E _W Section 22

Sources: (Cont'd)

"Charles P. Balch." Illustrated History of Central Oregon. Spokane, Wash.: Western Historical Publishing Co., 1905, pp. 233-234.

McNeal, Wm. H. History of Wasco County, Oregon. [The Dalles, Ore.: Mimeo, c. 1953]; copy at Oregon Historical Society, Portland, Ore., p. 329.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 320-A
Name
(Common) Bekins-Ralph's Transfer & Storage Co
(Historic) U.S. Mint
Address 710 East Second Street
The Dalles, Oregon
Present Owner _____
(Address) _____
Original Use Mint
Date of Construction 1864-ff.

9277

historical significance:

The former U.S. Mint building in The Dalles is a one story, stone building with a flat roof. A large brick section completes the wall on the south elevation. The windows are sixteen-over-?, the bottom part of each window being covered with a wood panel. The windows are set in semi-elliptical arches with stone voisseurs. The building has a basement and a large, one story concrete block addition on the north elevation.


The dates for the construction of this building vary considerably between 1864 and 1868. Joe.D. Thomison wrote in 1940 that the mint was completed in 1868 at a cost of \$110,000. He stated that in 1889 the building was purchased by the Diamond Milling Company.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office Thomison, Joe D. "Old U.S. Mint at The Dalles,"
Please enclose map Township 1 S Range 13 W Section 3 Oregon Historical Quarterly, vol. 41,
72-73.
(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme _____
Name
(Common) Beer () House
(Historic) Ball () House
Address 526 West Third Place
The Dalles, Oregon
Present Owner Charles McCarthy
(Address) 526 W. 3rd Place, The Dalles, Ore.
Original Use Residence
Date of Construction _____

Statement of historical significance:

The Ball house is a two story, wood frame dwelling in an "L" shape. The building has shiplap siding and a gable roof with a small hip on the north (front) elevation. The south (rear) elevation has four-over-four, double hung sash windows; the fenestration in the rest of the house is primarily two-over-two, double hung sash windows with entablatures and shutters. The building has two brick chimneys; one is old with a decorative band on the top. A small porch is located on the one story "L" on the north (front) elevation.



Mr. Jim Beer of The Dalles is the grandson of the Beer family and the great grandson of the Ball family which once owned this house.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office McCarthy, Mrs. Charles. Interview with Stephen Dow Beckham, 2 July 1976, The Dalles, Oregon.
Please enclose map Township 1 ^N S Range 13 ^E W Section 4

STATE OF OREGON INVENTORY
 HISTORIC SITES AND BUILDINGS
 State Historic Preservation Office
 Oregon State Parks, Salem, 97310



County Wasco

Theme _____

Name
 (Common) Bonney Saddle Shop

(Historic) _____

Address 205 Court Street
The Dalles, Oregon

Present Owner Garth Bonney
 (Address) 1008 East 10th Street
The Dalles, Oregon

Original Use Probably Medical-Drug Store

Date of Construction 1876

2117

historical significance:

The Bonney Saddle Shop is located in a brick building which faces First Street at the southwest corner of First and Court in The Dalles. The structure has a cast iron facade on First Street on its north elevation. All of the window and door bays in this elevation have been enclosed or filled-in and covered with stucco. The cast iron work was made by the "Golden State Iron Works, San Francisco" and the date 1876 appears on the facade. The medical symbol appears at the top of each iron pilaster and would indicate that this building was probably a doctor's office or drug store at the time of its construction.


Three window bays and a doorway now open on the east (side) elevation of the building on Court Street. The exterior of the building has been covered with stucco. The structure has a brick basement.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmark List," MS Typescript,
 Planning Office, City of The Dalles,
 Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3 The Dalles, Oregon.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme 6-D

Name Bohn's Printing
(Common) Hudson's Insurance

(Historic) Gates (Col. N. H.) Hotel

Address n.e. corner E. 3rd & Union Streets
The Dalles, Oregon

Present Owner John Hudson

(Address) The Dalles, Oregon

Original Use Commercial

Date of Construction 1870

statement of historical significance:

The former Gates Hotel is a rectangular, two story brick building which faces south on East Third Street in The Dalles. The building, which has a flat roof, has one-over-one, double hung sash windows set in semi-elliptical arches with metal keystone decorations on the second floor. The first story has been altered but possibly once had a cast iron facade.

In 1976 this building houses Bohn's Printing and Hudson's Insurance.

Col. N. H. Gates was a prominent businessman and politician living in The Dalles in the nineteenth century. Gates was Speaker of the House of Representatives in 1859. In 1871 and 1877-78 he served as mayor of The Dalles.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office Krier, Malcolm and Jean. Interview with Stephen
Dow Beckham, 2 July 1976, The Dalles, Ore.

Please enclose map Township 1 S Range 13 W Section 3 (over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco

Theme CA

Name Burlington-Northern/Union Pacific
(Common) Railroad Depot

(Historic) Oregon Trunk Railroad Depot

Address Maupin, Oregon

Present Owner Burlington-Northern Railroad

(Address) _____

Original Use train depot

Date of Construction Prior to 1916

statement of historical significance:

The Burlington-Northern/Union Pacific Depot is a one story, rectangular wood frame building with hip roof. The exterior is shiplap siding, except for a band of vertical milled boards around the base of the building. The eaves are enclosed. The windows are irregular and include four-over-four double hung sash, one-over-four double hung sash and casement windows. There are two brick chimneys. The depot includes a freight area and quarters for the agent.

This depot was constructed by James J. Hill of the Great Northern Railroad who in 1909 began construction of the Oregon Trunk Railway through the canyon of the Deschutes River. The depot at Maupin was probably erected about 1910. For a time Edward H. Harriman's Deschutes Railroad also had a depot in Maupin.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Culp, Edwin. Stations West: The Story of Oregon Railways. Caldwell, Idaho: Caxton Printers, 1972, pp. 123-127, photos.

Please enclose map Township 4 ^N _(S) Range 14 ^(E) _(W) Section 32

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme 10-A

Name
(Common) Brookhouse (John) House

(Historic) _____

Address 216 W. Fourth St.

The Dalles, Ore.

Present Owner _____

(Address) _____

Original Use residence

Date of Construction c. 1880

statement of historical significance:

The Brookhouse house is a one story wood frame building with elements of Classical Revival style. It has low gable roof with frieze boards at the eaves. The exterior is clapboard siding. The windows are six-over-six double hung sash.

John Brookhouse was a son of Richard and Ann (Clark) Brookhouse. Both of his parents were born in Ireland. His father came to Oregon in 1860 and married at The Dalles. The Brookhouse family lived for some years at Tygh Ridge and later on Tenmile Creek. John Brookhouse, a farmer, and his wife Mamie, resided in this house in 1938 when they were quite aged.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 6 July 1976 Sources Consulted:


For Oregon State Historic Preservation Office

Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3

Lundell, Gary. Interview with Stephen Dow Beckham, 3 July 1976, The Dalles, Oregon.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 9-3, 10-A
Name
(Common) "Chinese Building"
(Historic) _____
Address 210 First Street
The Dalles, Oregon
Present Owner John McCloskey
(Address) The Dalles, Oregon
Original Use Store & Residence
Date of Construction _____

statement of historical significance:


The "Chinese Building" on First Street in The Dalles is a nineteenth century structure which was used as a store and residence by its proprietors. This two story, brick building faces north on First Street and faces the railroad tracks. The building has three arch bays on its front elevation and a small false front. The first floor (or basement level since filling along First Street) is surrounded by parking lot in 1976. The building opens onto what was probably the original second floor.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office Krier, Malcom and Jean. Interview with Stephen Dow Beckham, 2 July 1976, The Dalles, Ore.
Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco

Theme 2-7-1B

Name
(Common) Celilo Falls Landmark

(Historic) (same)

Address Celilo Falls Park
near The Dalles, Oregon

Present Owner U.S. Army Corps of Engineers
(Address) Washington, D.C.

Original Use Landmark

Date of Construction _____

Physical description of property and statement of historical significance:

The Celilo Falls Landmark is a bronze plaque mounted on a boulder which stands in the Celilo Falls Park on the north side of Interstate 80N east of The Dalles, Oregon. The plaque has a bas-relief of an Indian fisherman on its upper half and bears the following inscription:

"In commemoration of the Celilo Falls Fishing Grounds. Historic fishing, trading, and gathering place for Indians of many tribes from time immemorial until inundated by the rising waters of Lake Celilo in March 1957."


Continue back if necessary

Recorded by Stephen Dow Beckham Date 25 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 2 ^(N) ^(E) S Range 15 W Section 21

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



92 101

County Wasco
Theme 7-D, G
Name
(Common) Civic Auditorium and Veterans Memorial
(Historic) same
Address East Fourth St.
The Dalles, Oregon
Present Owner City of The Dalles
(Address) _____
Original Use civic auditorium
Date of Construction 1921

Statement of historical significance:

The Civic Auditorium is a 2-1/2 story concrete building with a buff colored brick exterior. The windows are six-over-one double hung sash. Two story brick columns decorate the south (front) elevation.

According to William H. McNeal this building was completed in 1922 at a cost of \$100,000.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

McNeal, Wm. H. History of Wasco County, Oregon.

The Dalles, Ore.: Mimeo, c. 1953; copy at Oregon Historical Society, Portland, Ore., p. 40.

Please enclose map Township 1 S Range 13 W Section 3

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme Religion

Name
(Common) Church of God of Prophecy

(Historic) _____

Address s.e. corner of West 7th & Union
The Dalles, Oregon

Present Owner Church of God of Prophecy
(Address) The Dalles, Oregon

Original Use Church

Date of Construction _____

Statement of historical significance:

The Church of God of Prophecy occupies a building of unknown history. The structure is a one story, wood frame building with a square bell tower which rises on the center of the west (front) elevation. It has a louvered belfry and a bellcast cone roof. The bell tower is decorated with a round window. The church has a gable roof and a stone foundation and basement enclosed with ashlar siding. The exterior of the main part of the building is shiplap. The sanctuary has five bays of double hung, sash windows containing stained glass on the north and south elevations.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 S Range 13 W Section 3

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 6-5
Name
(Common) Craig Office Supply Building
(Historic) Vogt Opera House
Address 308 Washington
The Dalles, Oregon
Present Owner Vogt Estate (U.S. National Bank
(Address) Trustee)
Original Use Opera House & Commercial
Date of Construction 1889

92 117

Statement of historical significance:

The former Vogt Opera House is a two story, brick building with a rectangular shape which faces west on Wasington Street. The structure has one-over-one, double hung sash windows on the second floor of its front elevation. The windows have "eyebrow" decorations of projecting bricks located above semi-elliptical archvoussoirs. The first floor of the front elevation has been altered and has black and yellow tiles at the base of the store windows.

In 1976 this building housed the Craig Office Supply Company.


Following a fire on September 2, 1888, in The Dalles, Max Vogt erected several new, brick, commercial buildings. On January 1, 1889 the Times-Mountaineer noted that Vogt had two buildings, two stores, and two brick buildings under construction. According to William H. McNal, who wrote in the early 1950's, Vogt erected in 1890 the Vogt Block at Second and Federal and an elegant theater at Third and Washington. This latter structure burned in 1891 and was rebuilt. Maximillian and Frank Vogt, brothers, settled in The Dalles in the 1860's. Both were born in Germany. Max Vogt was a general merchant and operated his major retail outlet with his sister, Phillipine (Vogt) Chapman.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmarks List," MS Typescript,
Please enclose map Township 1 S Range 13 W Section 3 The Dalles, Oregon.
(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme _____
Name
(Common) Columbia Brewery Building
(Historic) (same)
Address e. side of East 3rd near Taylor St.
The Dalles, Oregon
Present Owner Mrs. Henry Meier
(Address) The Dalles, Oregon
Original Use Brewery
Date of Construction 1869

211

statement of historical significance:

The Columbia Brewery Building is a three story, stone building with brick window bays. The building has brick lugsills and semi-elliptical brick surrounds. The structure once had several large, wood sections; the wood parts of the building have all been removed.

The Columbia Brewery was established in 1867 by Emil Schanno. A painted marker on this building reads: "Columbia Brewery. Est. 1867, Charles Schanno, owner."

In April, 1877, August Buchler purchased the Columbia Brewery from Emil Schanno its founder. Buchler was born in Appenzell, Switzerland on August 8, 1841. He immigrated to the United States in 1864 and worked for seven years as a miner in Montana. In November, 1871, he located in Portland, Oregon, where he worked in the Weinhardt Brewery. Buchler continued to operate the Columbia Brewery in 1905 at the time a biographical sketch was written about him. He married in 1875 to Sarah Buckhalter.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "August Buchler." Illustrated History of Central Oregon. Spokane, Wash.: Western Historical Publishing Co., 1905, pp. 295-296.

Please enclose map Township 1 ^(N) _(E) Range 13 W Section 3

(over)



JUL 76

County Wasco
Theme W.A.A.
Name (Common) Dalles Indian Mission Landmark
(Historic) (same)
Address Traffic Island at junction of W. 3rd Place, Trevitt St., & W. 6th, The Dalles, Ore
Present Owner City of The Dalles
(Address) The Dalles, Oregon
Original Use Landmark
Date of Construction _____

statement of historical significance:

The Dalles Indian Mission Landmark is a granite marker set on a stone base. The granite is engraved to read:

"The Dalles Indian Mission of the Methodist Episcopal Church
Established in 1838 by Daniel Lee Marked by Willamette
University."

A bronze plaque with the scene of the "Oregon Trail Memorial" is mounted on this landmark. The plaque was designed by J.E. and L.G. Fraser, sculptors.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 6 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 S Range 13 W Section 4

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco

Theme 7-5 1-1

Name
(Common) Dalles Bridge Landmark

(Historic) same

Address State Highway 30 near its inter-
section with Interstate 80-N

Present Owner State of Oregon

(Address) Salem

Original Use Landmark

Date of Construction Dec. 18, 1953

211

statement of historical significance:

The Dalles Bridge landmark consists of three pieces of stone to which are attached bronze plaques. The largest plaque reads:

"This shaft of native stone commemorates the completion of the Dalles Bridge. This is a monument to many things. to the dreams of yesterday, to the dreams of today, to the visions of tomorrow. It is also a monument to the faith, the courage, the persistent industry of Wallace S. Nelson who, in the face of obstacles seemingly insurmountable forced a dream to come true. This bridge was dedicated by Honorable Paul Patterson, the Governor of Oregon and Honorable Arthur B. Langlie, Governor of Washington on December 18, 1953."

The plaques list the engineers, contractors and cooperating agencies.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township (N) S Range (E) 13 W Section 1

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 9-E, 12-A
Name
(Common) Elks Temple
(Historic) (same)
Address 200 East 3rd Street
The Dalles, Oregon
Present Owner BPOE Lodge
(Address) The Dalles, Oregon
Original Use Lodge Hall & Residential
Date of Construction 1910

statement of historical significance:

The Elks Temple in The Dalles was erected in 1910. This three story brick building is in the Colonial Style. It has four columns with a terra cotta exterior in a buff or beige color on the north (front) elevation which support a pediment and balcony. The second and thrid stories have one-over-one, double hung sash windows; some of the windows on the second floor have transom panes. Pilasters on the north and south elevations provide major decorative elements as does a balcony on the west side of the first floor elevation onto which open five sets of French doors. The building has a concrete foundation and a basement. As originally constructed the third floor has several rooms for resident members.

The BPOE of The Dalles was organized in Cascade Locks on July 11, 1895, as Cascade Lodge No. 303. In March, 1896, the lodge moved to The Dalles.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmarks List," City of The Dalles,
Planning Office, The Dalles, Oregon.

Please enclose map Township 1 S Range 13 W Section 3 (over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76



County Wasco
Theme 10-A
Name
(Common) The Dufur Historical Society
Museum
(Historic) Schreiber (Joseph) House
Address Main Street
Dufur, Oregon
Present Owner Dufur Historical Society
(Address) _____
Original Use residence
Date of Construction c. 1901

historical significance:

The Joseph Schreiber house is a 1½ story rectangular log building with gable roof. The gable ends are covered with vertical planks. The windows are one-over-one double hung sash. The peeled logs are notched and joined at the corners. A veranda reaches along the west (front) elevation. The roof is broken by a small dormer on the east and west sides.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 8 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 ^N _S Range 13 ^E _W Section 25

Douglas, Winifred. Interview with
Stephen Dow Beckham 3 July 1976,
Dufur, Oregon.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme 2-A

Name
(Common) First Christian Church

(Historic) _____

Address S.E. Corner of 3rd and Washington S
Mosier, Oregon 97040

Present Owner First Christian Church

(Address) same as above

Original Use church

Date of Construction 1909

atement of historical significance:

The First Christian Church is a one story wood frame building set on a foundation of stone and with a gable roof. The roof is presently covered with corrugated sheet metal. The exterior is narrow lapped siding. The windows are one-over-one double hung sash in simple surrounds with entablatures. A square bell tower with imbricated shingles on the belfry is located on the north (front) elevation. There is one brick chimney. The gable end is covered with imbricated shingling.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Gholston, Willis. Interview with Stephen Dow Beckham, 2 July 1976, Mosier, Ore.

Please enclose map Township 2 ^(N) _(S) Range 11 ^(E) _(W) Section 1

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 2.5 A
Name
(Common) End of Oregon Trail Landmark
(Historic) (same)
Address The Dalles City Park
The Dalles, Oregon
Present Owner City of The Dalles
(Address) The Dalles, Oregon
Original Use Landmark
Date of Construction 1906

statement of historical significance:

The End of the Oregon Trail Landmark is a stone shaft which stands in The Dalles City Park at West 6th and Union streets in The Dalles. Dedicated in 1906 at the time Ezra Meeker was attempting to draw popular attention to the Oregon Trail, the landmark reads:

"End of the Old Oregon Trail, 1843-1906."

This marker was dedicated on March 11, 1906.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976

For Oregon State Historic Preservation Office

Please enclose map Township 1 S Range 13 W Section 3

Sources Consulted:

McNeal, Wm. H. History of Wasco County, Oregon.
The Dalles, Ore.: Mimeo, c. 1953; copy at
Oregon Historical Society, Portland, Ore.,
p. 151.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme T-F
Name
(Common) Fort Dalles Landmark
(Historic) same
Address S.W. Corner of W. 15th and Garrison
Streets
Fort Dalles, The Dalles, Oregon
Present Owner Ft. Dalles Historical Society
(Address) The Dalles, Oregon
Original Use landmark
Date of Construction 1933

274

statement of historical significance:

A bronze plaque on stone, the Fort Dalles landmark reads:

"This marks the site of the Commanding Officer's house of Fort Dalles established 1850. Given by Quinett Chapter, D.A.R. and the American Legion, August 31, 1933."


Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 4

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



92 777

County Wasco

Theme _____

Name
(Common) "Fish House"

(Historic) E.O.B. Co. Building

Address s. side of E. 3rd at Taylor Street
The Dalles, Oregon

Present Owner _____

(Address) _____

Original Use _____

Date of Construction 1905

historical significance:

The "Fish House" bears the inscription above its door "E.O.B. Co., 1905." This structure stands on the hillside near the Columbia Brewery and may possibly have at one time been part of that building complex. The building is a one story, stone structure with a lean-to type roof (of one pitch). The building has brick, semi-elliptical window arches with four panes of casement windows per bay.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmarks List," MS Typescript,
Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3 The Dalles, Oregon
Planning Office, City of The Dalles,

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 10-A
Name
(Common) _____
(Historic) Gray (Capt. W. P.) House
Address 210 West Fourth
The Dalles, Ore.
Present Owner Jack Patrick
(Address) 210 W. Fourth St., The Dalles
Original Use residence
Date of Construction unknown

statement of historical significance:

The Capt. W. P. Gray house is a 2½ story wood frame building in the Queen Anne style. Set upon a foundation of stone blocks and possessing a basement, this building has shiplad siding, a gable roof and shingling on the gable ends. There are three large brick chimneys and a front porch and small balcony on the north (front) elevation. The windows are mostly one-over-one double hung sash.

Captain William Polk Gray was a son of Dr. William Henry Gray who was born in Utica, New York, in 1810. In 1836 Gray emigrated to Oregon with Marcus Whitman. In 1837 he returned to the United States, married Mary A. Dix, and brought her overland to Oregon that year. William Polk Gray was born in 1845 in Oregon City. In 1860 he began his career on the steamboats of the Columbia River. Capt. Gray married Ocia Falkland Bush who was born at sea on her father's vessel when it was near the Falkland Islands. The Grays later lived in Pasco, Washington.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 S Range 13 W Section 3

"The Gray Family." Lockley, Fred. History of the Columbia River Valley from The Dalles to the Sea. Chicago: S.J. Clarke Publishing Co., 1928, vol. 2, p. 50-65.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 10-I, 10-G
Name (Common) Granada Theatre
(Historic) (same)
Address 221 East 2nd Street
The Dalles, Oregon
Present Owner _____
(Address) _____
Original Use Theatre
Date of Construction 1920's

Statement of historical significance:

The Granada Theatre, erected in the 1920's in The Dalles, is a building in the Mission Style with specific affinities to Moorish elements in Spain. The three story building has vertical bands of brick on its south (front) elevation which are topped by small domes which are painted silver. A section of terra cotta tiles is located at the roof level on the center of the front elevation. The windows are six-over-six, double hung sash. The building is used as a theatre and for commercial purposes.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 N Range 13 W Section 3 E

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco

Theme 10-A

Name
(Common) _____

(Historic) Heisler (William) House

Address S.W. Corner of 4th and Main Sts.

Present Owner _____

(Address) _____

Original Use residence

Date of Construction c. 1882

Statement of historical significance:

The Heisler house is a 2 story wood frame building with a gable roof and a major cross gable on the east (front) elevation. The exterior is clapboard siding. The windows are two-over-two double hung sash with entablatures. The fenestration on the first floor of the front elevation has been altered. The original front porch and balcony have been removed. The eaves are boxed and are decorated by a wide frieze board. The house has 2 large brick chimneys. All of the gables are decorated with porthole windows at the attic level.

William Heisler was born on April 13, 1828, in Schuylkill County, Pennsylvania. He was the son of John and Catherine (Yost) Heisler. In 1847 Heisler became a cigar maker in Pittsburg and soon thereafter enlisted in the U.S. Army to serve in the war against Mexico. Heisler served at Fort Leavenworth. In 1849 he emigrated overland to California; he returned east, married, and emigrated to Oregon in 1852. Heisler first lived in Marion and Lane counties. In 1870 he moved to Prineville and in September, 1882, Heisler opened a store in Dufur. He eventually entered the cattle business with his sons. In 1897 he purchased a grist mill in Dufur which he operated until 1903.

A biographer noted in 1905: "At the present time Mr. Heisler is dwelling in Dufur and has a comfortable cottage in the center of town, which is situated in a block well set to trees and ornamental shrubs."

Continue back if necessary


Recorded by Stephen Dow Beckham Date 8 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 N Range 13 E Section 25

"William Heisler." An Illustrated History of Central Oregon. Spokane, Wash.: Western Historical Publishing Co., 1905, pp. 255-256.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 10-A
Name
(Common) Hebring (Henry) House
(Historic) Hebring (Henry) House
Address 313 W. Fourth St.
The Dalles, Oregon
Present Owner _____
(Address) _____
Original Use residence
Date of Construction 1860

historical significance:

The Henry Hebring house is a two story brick building erected in 1860. There is a two story wood frame addition attached on the east elevation in the 19th century. The building, which appears to be a commercial structure, has an iron facade with two finials on its north elevation. The windows are one-over-one double hung sash and are decorated by brick voussoirs with keystones. The wood frame part of the house, which faces on West Fourth street, has two projecting window bays with one-over-one double hung sash windows joined by a simple front porch. The exterior is shiplap siding.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976

For Oregon State Historic Preservation Office

Please enclose map Township 1 S Range 13 W Section 3

Sources Consulted:


Hudson, Thomas. Interview with
Stephen Dow Beckham, 3 July 1976,
The Dalles, Oregon

Sources:

Illustrated History of Central Oregon. Spokane, Wash.: Western Historical Publishing Co., 1905, p. 137.

Huntington, Wallace Kay. "Victorian Architecture." Space, Style and Structure. Thomas Vaughan and Virginia Guest Ferriday, eds. Portland, Ore.: Oregon Historical Society, 1974. vol. 1, p. 297.

McNeal, Wm. H. History of Wasco County, Oregon. [The Dalles, Ore.: Mimeo, c. 1953]; Oregon Historical Society, Portland, Oregon, p. 64.



County Wasco

Theme 6-0

Name
(Common) House of Chen Restaurant

(Historic) Schanno (Emil) Building

Address 310 East Second Street
The Dalles, Oregon

Present Owner Delaney Schanno

(Address) The Dalles, Oregon

Original Use Commercial

Date of Construction c. 1890

statement of historical significance:

The Schanno Building on East Second Street in The Dalles is a two story, brick building erected for commercial use. This rectangular structure faces north on Second Street and has four bays of one-over-one, double hung sash windows on its second story. Parts of the case iron facade remain on the east side for the first floor of the front elevation. A tile and glass section on the first floor elevation probably dates from alterations made in the 1920's or 1930's.

The building may have possibly been erected by Emile Schanno. The fire of June 18, 1880, which swept through the city destroyed a building owned by Schanno which was valued at \$2,500.

A photograph and article on the Emil Schanno house, erected in The Dalles, circa 1895, appears on p. 297, Space, Style and Structure. (vol. 1). Amel or Emil Schanno was born in Alsace-Lorraine, the son of Francis Schanno. He emigrated to The Dalles in 1860 with his brothers and father. The Schannos established the Columbia Brewery (see file sheet) which they loater sold to August Buchler. Schanno developed orchards, especially cherry production. He married Eliza Schuster and was deceased by 1910.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

"The Dalles Landmark List," MS Typescript, Planning Office, City of The Dalles, The Dalles, Ore.
(over)

Please enclose map Township 1 S Range 13 W Section 3

HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 22
Name
(Common) _____
(Historic) Hunt's Ferry Warehouse Co.
Flour, Feed, Salt, Grain, Storage
Address Bakeoven Road
Maupin, Oregon
Present Owner _____
(Address) _____
Original Use Grain Elevator
Date of Construction c. 1920

statement of historical significance:

The Hunt's Ferry Warehouse Company elevator is a wood frame building with shiplap exterior and center elevator sections. It stands near the banks of the Deschutes River in Maupin, Oregon. The roof, which was originally shingle, has been subsequently covered with tar paper, and more recently with corrugated sheet metal. The building is in fair condition.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 4 ^N _(S) Range 14 ^(E) _(W) Section 33

Stovall, Bertha. Interview with Stephen Dow Beckham, 3 July 1976, Maupin, Ore. (Mrs. Stovall, age 90, has resided in Maupin since 1916.)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 10-A
Name
(Common) _____
(Historic) Hudson (Thomas A.) House
Address 419 W. Third St.
The Dalles, Oregon
Present Owner _____
(Address) _____
Original Use residence
Date of Construction c. 1879-80

statement of historical significance:

This house, occupied in the 1880's by the Thomas A. Hudson family, is a one story wood frame building with gable roof. The exterior is shiplap siding. A simple front porch with chamfered posts stands on the south (front) elevation. The main entry door has a transom. The building is set on a stone foundation.

Thomas A. Hudson was the son-in-law of Caleb N. Thornbury (see file sheet for Thornbury house). Hudson was born in Belfast, Ireland, in 1853. At the age of thirteen he enlisted in the U.S. Navy and served in the American Civil War. He came to Oregon in 1878 and settled in The Dalles in 1879. He married Amanda Edith Thronbury in 1880.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:


For Oregon State Historic Preservation Office

Please enclose map Township 1 S Range 13 W Section 4

Hudson, Thomas. Interview with Stephen Dow Beckham, 3 July 1976, The Dalles, Oregon.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme
Name
(Common) I.O.O.F. Lodge #209 Hall
(Historic) same
Address Maupin, Oregon

Present Owner
(Address)
Original Use lodge hall
Date of Construction c. 1921

Statement of historical significance:

The Odd Fellows Lodge Hall is a two story wood frame building with a gable roof and shiplap exterior. The structure has one-over-one double hung sash windows in three bays on the first and second story on the north and south elevations. The east (front) elevation has two double entry doors with transoms and a pediment on the gable end of the roof.

I.O.O.F. Lodge No. 209 was established on August 1, 1908, at Wapinitia. The lodge moved to Maupin on January 1, 1916. A major fire swept through much of the Maupin business district on September 10, 1921; consequently this building may have been erected after that fire.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 4 ^N _(S) Range 14 ^(E) _(W) Section 32

Stovall, Bertha. Interview with Stephen Dow Beckham, 3 July 1976, Maupin, Oregon. Mrs. Stovall, age 90, has resided in Maupin since 1916.)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



9/11/76

County Wasco

Theme

Name
(Common) Indian Shaker Church

(Historic) Indian Shaker Church

Address Near the Portage Inn on Inter-
state 80 overlooking the Columbia
River
The Dalles, Oregon

Present Owner

(Address)

Original Use Indian Shaker Church

Date of Construction c. 1904

historical significance:

The Indian Shaker Church stands on a lava outcrop on the south bank of the Columbia River near Interstate 80. The building is a rectangular, wood frame structure with gable roof and vertical board and batten exterior. A small altar bay projects on the south (rear) elevation. The building once had a shingle roof, but most has vanished. This small building, a visible reminder of a unique Indian religious faith, is in very poor condition. Recently the small cross which was once mounted on the roof has vanished.

This building was constructed on Lone Pine Island, or Cumsuuk Island as known to the Indians, by Henry Gulick, a Scotchman. Gulick operated two fish wheels on the island and erected the church for his Indian wife. The church originated at Toledo, Washington, and was chartered in 1904. The church has twice been resited. For a history of its construction and resiting see Ray Harmon article in references.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 5 July 1976

For Oregon State Historic Preservation Office

Please enclose map Township 2 ^(N) S Range 13 ^(E) W Section 36

Sources Consulted:
Graydon, Charlotte. "Garden Clubs Gather Data on
Historic Trees in Oregon," Oregonian, Sept.
29, 1975, photo.
(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 6-10
Name
(Common) _____
(Historic) Johnston Bros. Bank
Address Main Street
Dufur, Oregon
Present Owner Wayne Tienhaara
(Address) Dufur, Oregon
Original Use bank
Date of Construction c. 1907

statement of historical significance:

The Johnston Bank is a square brick building facing east on Main Street. The principle ornamentation on the front elevation is a delicate metal facade of brackets interspersed by garlands of flowers at the roof level. The main entryway, which has a wood pediment and Colonial style, is probably a later addition.

The Johnston Brothers Bank of Dufur was organized in 1904 by George W., T. H., and J. C. Johnston, sons of James and Anna (Cogswell) Johnston of Centerville, New Brunswick, Canada. George W. Johnston, president of the bank, was born in 1859 and settled in 1884 in Dufur. Johnston and his brothers were, initially, merchants. In 1889-90, Johnston represented Wasco and Sherman counties in the Oregon legislature and later served as mayor of Dufur. George W. Johnston owned two thousand acres of orchards near Dufur and was yet living in the town in 1922.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 8 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Douglas, Winifred. Interview with Stephen Dow Beckham, 3 July 1976, Dufur, Ore.

Please enclose map Township 1 ^N _(E) Range 13 W Section 25

(over)

STATE OF OREGON INVENTORY
 HISTORIC SITES AND BUILDINGS
 State Historic Preservation Office
 Oregon State Parks, Salem, 97310

County Wasco
 Theme 7-10-B
 Name
 (Common) I.O.O.F. Lodge Hall
 (Historic) (same)
 Address 421 East 2nd Street
The Dalles, Oregon
 Present Owner I00F Lodge
 (Address) The Dalles, Oregon
 Original Use Lodge Hall; Commercial
 Date of Construction 1904; 1915

statement of historical significance:

The I.O.O.F. Lodge Hall in The Dalles is a two story, rectangular, brick building which faces south on East Second Street. The building has one-over-one, double hung sash windows with transom panes above on the second floor. The base of the building on the first floor is decorative stone. Brickwork quoins are located on the corners of the building.

This structure has a cornerstone dated "1904" on the southeast corner of the front elevation. The building burned and was rebuilt, however, in 1915. The first floor presently houses Pioneer Electric and Docherty Furniture Company.


The Oddfellows Lodge was the first white fraternal society organized in The Dalles. The organization commenced on November 1, 1856 when H. W. Davis organized Columbia Lodge No. 5. The fire of 1891 destroyed the records of this lodge.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmark List," MS Typescript,
 Planning Office, City of The Dalles,
 Please enclose map Township 1 S Range 13 W Section 3 The Dalles, Ore.

(over)



JUL 76

County Wasco
Theme 11 - 1
Name
(Common) Knowles (P.T.) House
(Historic) Knowles (P.T.) House
Address N.W. corner of 2nd and Harrison Sts
Dufur, Ore.
Present Owner _____
(Address) _____
Original Use residence
Date of Construction c. 1896-98

Statement of historical significance:

The P.T. Knowles house is a 1½ story building of wood frame construction. The building has a steep gable roof with cross gables on the east and west sides. The windows are one-over-one double hung sash. The window bays project on the south (front) elevation and are joined by a veranda. The gable end on the front elevation is decorated and supported by brackets with pendants. The exterior of the house is asbestos shingles. The house has one brick chimney.

P. T. Knowles was the father of P.W. Knowles, a Dufur merchant. P. T. Knowles was born in Delaware. A veteran of the Civil War, he came to The Dalles in 1899 and with his son, P. W. Knowles, established the 15 Mile House in Dufur. In 1901 he established a store with Eli Hinman. Knowles served in the state legislature from 1906 to 1910 and was a mayor of Dufur for four terms.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 8 July 1976 Sources Consulted:


For Oregon State Historic Preservation Office

Please enclose map Township 1 ^N _E Range 13 W Section 25

Douglas, Winifred. Interview with
Stephen Dow Beckham, 3 July 1976,
Dufur, Oregon.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme 10-A

Name
(Common) Kileen (Vincent) House

(Historic) Knowles (P.W.) House

Address 803 Second St.

Dufur, Ore.

Present Owner Vincent Killeen

(Address) 803 Second St., Dufur

Original Use residence

Date of Construction c. 1896-98

Statement of historical significance:

The Knowles house is a one and one-half story wood frame building in the Queen Anne style. Initially the house was a simple rectangular structure. It has since received additions on its north and south elevations. A veranda reaches across the south (front) elevation and is decorated by cut scroll work and carved posts. The exterior of the house is shiplap except on the first floor (front) elevation where it is diagonal boards. The windows are one-over-one double hung sash. The roof is hip on gable.

P. W. Knowles was a partner with Hinman in a general store in Dufur. He was the son of P. T. Knowles. (See file sheet on the P. T. Knowles house).

Continue back if necessary

Recorded by Stephen Dow Beckham Date 8 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Douglas, Winifred. Interview with Stephen Dow Beckham, 3 July 1976, Dufur, Ore.

Please enclose map Township 1 (S) Range 13 W Section 25

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 6-D
Name
(Common) Maier () Building
(Historic) (same)
Address 308 Second St.
The Dalles, Oregon
Present Owner Maier Family Heirs
(Address) The Dalles, Oregon
Original Use Commercial
Date of Construction 1890

Statement of historical significance:

The Maier Building is a three story brick structure which faces north on Second Street in The Dalles. Erected in 1890, this building has four bays of one-over-one, double hung sash windows on its second and third stories on the front elevation. The first floor has been significantly altered. Decorative metal panels are located on the east and west sides of the front elevation on the first and second stories.


This building presently in 1976 houses Monahans Jewelry.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmark List," MS Typescript,
Planning Office. City of The Dalles,
Please enclose map Township 1 S Range 13 W Section 3 The Dalles, Oregon.

STATE OF OREGON INVENTORY
 HISTORIC SITES AND BUILDINGS
 State Historic Preservation Office
 Oregon State Parks, Salem, 97310



JUL 76

County Wasco
 Theme _____
 Name
 (Common) Kramer Building
 (Historic) Johnston Bros. Store
 Address N.W. Corner of First and Main
Streets
Dufur, Oregon
 Present Owner Van Kramer
 (Address) Dufur, Ore.
 Original Use commercial
 Date of Construction _____

atement of historical significance:

This building is a 2 story brick building in a square shape. The east (front) elevation contains two store fronts with cast iron columns flanking the central entry doors. On the second floor the windows are one-over-one double hung sash with what was apparently a transom now filled in with wood. The brick work on the corners of the building simulates quoins. At the attic level there is a rather elaborate decorative brick facade which includes inverted pyramids, bands of brick and small rectangles. There are several brick chimneys. The name "Johnstons'" appears in a metal plate above the second story of the front elevation. This building presently houses Kramer's Grocery.

The Johnston Store was established in 1884 by T.H., J.C., and George William Johnston. In 1904 the bothers incorporated this store under the name "Johnstons' Inc." That same year the brothers established the Johnston Brothers Bank (see file sheet). Writing in 1905, one historian noted: "In the fall of 1904, our subject (Thomas H. Johnston), with his brother, George, and his brother John, and W. A. Johnston of The Dalles, organized a company, incorporating under the laws of the state, the name being "Johnston," with a capital of \$50,000. They have erected a handsome, two story edifice of brick, eighty by ninety-four feet, with electric elevator, the only one in the town, and electric lights, with other modern conveniences."

Continue back if necessary


Recorded by Stephen Dow Beckham Date 7 July 1976

For Oregon State Historic Preservation Office

Please enclose map Township N 1 S Range 13 E Section 25

Sources Consulted:

"George William Johnston." Lockley, Fred.
History of the Columbia River Valley
from The Dalles to the Sea. Chicago:
 S. J. Clarke Publishing Co., 1928,
 vol. 2, 116-118



JUL 76

County Wasco
Theme 10-A, 7-C
Name Masonic Lodge Hall
(Common) Smith-Callaway Chapel
(Historic) Wasco County Courthouse #2
Address n.w. corner of Union & West 3rd St.
The Dalles, Oregon
Present Owner Masonic Lodge
(Address) The Dalles, Oregon
Original Use Courthouse
Date of Construction 1881

tatement of historical significance:

The second Wasco County Courthouse, erected in 1881, is a two story, brick building in the Italianate Style. The building has a low, hip roof which is covered with sheets of metal. It has boxed eaves and decorative brackets. The building has one-over-one windows in arched bays with brick voussoirs with keystones. An octagonal clock tower with a four-sided roof rises on the south end of the building. The first floor of this structure has been altered for use as a funeral home. The second floor is the Masonic Lodge Hall.

This courthouse, replacing an earlier wood frame building (restored in 1976), was erected in 1881 by N.J. Blagen, contractor. The building cost \$23,000. In 1914 it was purchased by the Knights of Pythias as a lodge hall and in 1929 was purchased by the Masons.

The Masonic Lodge, Wasco Lodge No. 15, was organized March 28, 1857. Its charter was issued on June 8, 1857. The lodge first met in the second story of H. P. Isaacs stone building. Later the lodge occupied the second story of Gates' hall at Second and Court streets. Eventually the Masons moved to the second story of the H. J. Waldron Druge Store (see file sheet) on First Street. In 1880 the lodge met in a room at the corner of Third and Court.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office Krier, Malcom and Jean. Interview with Stephen
Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3 Oregon.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme 9-K, 10 E

Name
(Common) Masonic Lodge Hall

(Historic) Hinman and Knowles Building

Address N.E. corner of First & Main Sts.
Dufur, Oregon

Present Owner Masonic Lodge

(Address) _____

Original Use general store and lodge
hall

Date of Construction 1906

statement of historical significance:

The Masonic Lodge Hall is a two story rectangular brick building set on a stone foundation. The windows are one-over-one double hung sash and several are enclosed with iron shutters. Each window bay has a segmental brick voussior and "eyebrow" decoration. A rather elaborate flaired brick facade decorates the attic level. The building has several chimneys. The west (front) elevation has been covered with stucco. The building bears the inscription "A.F. & A.M. 1906."

This building was erected by P. W. Knowles and his partner, Hinman. The second floor has always been the Masonic Lodge. Eli T. Hinman, a contractor and builder of Dufur, Oregon, was born at Augusta, New York on January 23, 1834. He was a son of Eli and Ann (Foote) Hinman. In 1881 Hinman emigrated to Oregon and was first employed as a sheep farmer. In 1887 he located at Dufur where he joined Monroe Heisler to build the Methodist and United Brethren churches, the school, several residences, and some business structures.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:


For Oregon State Historic Preservation Office

Please enclose map Township 1 ^N _(S) Range 13 ^E _(E) Section 25

Douglas, Winifred. Interview with
Stephen Dow Beckham, 3 July 1976,
Dufur, Ore.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 1-12
Name
(Common) Mosier Fruit Growers Building
(Historic) same
Address The North end of Center Street at
First
Mosier, Oregon
Present Owner Mosier Fruit Growers
(Address) Mosier, Oregon
Original Use industrial
Date of Construction c. 1915

statement of historical significance:

The Mosier Fruit Growers building is a one story building of terra cotta blocks in the Mission Style. It has a basement. Possessing a low gable roof, the building has open eaves and decorative support brackets at the gable ends. Two square louvre cupolas and large rectangular section extend through the middle section of the building. Most of the windows are six-over-six double hung sash. The building has several freight portals and stands adjacent to the railroad tracks.

Until 1975 this building contained all of its original sorting and processing machinery. It is now used primarily as a fruit warehouse.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976

Sources Consulted:

For Oregon State Historic Preservation Office

Gholston, Willis. Interview with Stephen Dow Beckham, 2 July 1976, Mosier, Ore.

Please enclose map Township 2 ^(N) Range 11 ^(E) Section 1

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310

County Wasco

Theme

Name
(Common) McDaniel () Building

(Historic) (same)


Address s.e. corner 3rd & Washington
The Dalles, Oregon

Present Owner McDaniel Estate

(Address) The Dalles, Oregon

Original Use Commercial

Date of Construction 1890's



JUL 76

statement of historical significance:


The McDaniel Building is a one story, brick building with vague elements of Second Empire Style in the mansard-like facade at the roof level. The exterior of the building is stucco, probably over brick. The exterior is decorated by a metal facade with metal bands and pilasters. The commercial areas on the front elevation have been altered and presently house several businesses among which are Kelly's Barber Shop and The Travel Bureau.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmarks List," MS Typescript,
Planning Office, City of The Dalles,
Please enclose map Township 1 S Range 13 W Section 3 The Dalles, Oregon.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 10-A
Name
(Common) Mosier (Jefferson) House
(Historic) Mosier (Jefferson) House
Address S.E. corner of 3rd and Idaho Sts.
Mosier, Oregon
Present Owner Ethel Kerr
(Address) Mosier, Oregon
Original Use residence
Date of Construction c. 1894-98

92111

Statement of historical significance:

The Jefferson Mosier house is a 1½ story wood frame building in the Queen Anne style. It has a veranda on its north (front) elevation which is decorated with spools and is supported by turned posts. The upper story is covered with imbricated shingles while the first floor has a narrow shiplap exterior. The windows are mostly one-over-one double hung sash. A square tower with a bell-cast roof rises on the northwest corner of the building.

Jefferson N. Mosier was born on September 28, 1860, a son of Jonah H. and Jane (Rollins) Mosier. His father, founder of Mosier, Oregon, hired George J. Ryan, an Irish tutor, to educate Jefferson and his other children. In 1876 Jefferson Mosier went to Walla Walla where he worked in a furniture store and as a butcher. After several other jobs, he returned to Mosier to farm property given him by his father. At the turn of the 20th Century, Jefferson Mosier purchased the interests of other heirs in his father's estate and laid out the town of Mosier, Oregon.

A biographer of Jefferson Mosier noted in 1904: "Mr. Mosier has recently erected an ornate Queen Anne cottage near the old Mosier home and is taking steps to beautify and make popular the town of Mosier."

Jefferson Mosier married on 1889 to Mary A. Sivener.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:


For Oregon State Historic Preservation Office

Gholston, Willis. Interview with Stephen Dow Beckham, 1 July, 1976, Mosier, Ore.

Please enclose map Township 2 ^(N) ^(E) S Range 11 W Section 1

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco

Theme 7-A

Name
(Common) Mosier Grange Hall

(Historic) Baptist Church

Address South end of Oregon St.
Mosier, Oregon

Present Owner Mosier Grange Hall #234

(Address) Mosier, Oregon

Original Use Church

Date of Construction c. 1894-96

9/11

Statement of historical significance:

The Mosier Baptist Church, now owned by the Mosier Grange, is a one story wood frame building with gable roof. The building has four bays of four-over-four double hung sash windows in its east and west elevations. The exterior is shiplap siding. Recent alterations to the building include a wing on the west elevation and a porch on the north (front) elevation. The roof is now corrugated sheet metal. It has a stone foundation.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Gholston, Willis. Interview with Stephen Dow Beckham, 2 July 1976, Mosier, Ore.

Please enclose map Township 2 ^(N) S Range 11 ^(E) W Section 1

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 7. E
Name
(Common) Mosier School
(Historic) same
Address _____
Mosier, Oregon
Present Owner _____
(Address) _____
Original Use school
Date of Construction _____

211
Description of property and statement of historical significance:

The Mosier school is a two story wood frame building with shiplap exterior and a partial hip roof. A band of vertical milled boards encircles the building between the first and second story. The windows are four-over-four double hung sash and are set in four bays on the east and west elevations, and in three bays on the north (front) elevation. The foundation is constructed of stone. The eaves are boxed with a partial eave return on the front elevation. The main entryway has sidelights and a transom. The school had four rooms.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Gholston, Willis. Interview with Stephen Dow Beckham, 2 July 1976. Mosier, Ore.

Please enclose map Township 2 ^(N) _(S) Range 11 ^(E) _(W) Section 1

STATE OF OREGON INVENTORY
 HISTORIC SITES AND BUILDINGS
 State Historic Preservation Office
 Oregon State Parks, Salem, 97310



County Wasco
 Theme _____
 Name
 (Common) Mosier (Jonah H.) Sawmill Site
 (Historic) Mosier (Jonah H.) Sawmill Site
 Address Mosier Creek
1/4 mile southeast of Mosier, Ore.
 Present Owner _____
 (Address) _____
 Original Use industrial site
 Date of Construction 1854

historical significance:

Two water falls on Mosier Creek powered the Mosier sawmill which cut the lumber to build much of The Dalles, Oregon. Commencing operation in 1854, this mill cut lumber that was shipped by sailing a barge up the Columbia to The Dalles. The sawmill was the precipitating factor in the establishment of Mosier, Oregon.

Jonah H. Mosier was born March 10, 1821, in Maryland. Mosier's father moved several times during the ensuing years and by 1839 the family had settled in Platte County, Missouri, where Jonah Mosier was apprenticed as a cabinet maker. Mosier also worked as a carpenter and clerk. In 1846 he married Jane Rollins. In 1849 Mosier joined a company of men to travel to the California gold fields. After several months in the mines, Mosier returned to Missouri and in 1853 emigrated to Oregon with his family.

Arriving at The Dalles with \$1.75 and one head of oxen, Mosier began work as a carpenter and erected stores and buildings. Seeing a shortage of materials, Mosier sought a mill site and located sixteen miles down the Columbia on what is now known as Mosier Creek. There in 1855 he filed on a Donation Land Claim and with Thomas Davis erected a sawmill. Noah Mull was also a partner in the sawmill enterprise but eventually Mosier purchased all interests. Mosier died on October 5, 1894.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July
1976
 For Oregon State Historic Preservation Office


Sources Consulted:

Gholston, Willis. Interview with Stephen Dow Beckham, Mosier, Ore., July 1, 1976.

Please enclose map Township 2 S Range 11 W Section 1

"Hon. Jonah H. Mosier." Illustrated

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 10-A, 6-D
Name
(Common) New Life Coffee House
(Historic) Waldron (H. J.) Drug Store
Address 1st & Washington streets
The Dalles, Oregon
Present Owner Dr. Ted Hyde
(Address) 1215 E. 18th St., The Dalles, Ore.
Original Use Drug Store
Date of Construction 1867

9/11

statement of historical significance:

The New Life Coffee House, formerly H. J. Waldron's Drug Store, is possibly the oldest commercial building in The Dalles, Oregon. Erected in 1867 this structure is a two story, stone building which faces south toward the railroad tracks on First Street. The rectangular building has an arch on its roof which creates the feeling of a low, false front. The windows are one-over-one, double hung sash and are set in three bays on the second floor of the front elevation. The building has stone quoins on the corners of the front elevation. The flush voussoirs have keystones on the second floor window bays. A cast iron facade remains on the first floor of the front elevation. Filling of First Street has raised the street level about four feet above the original entrance to this building. A stairway leads down to the main entry.

H. J. Waldron was an early druggist in The Dalles. Waldron died as a result of injuries he sustained in the fire of October 27, 1878, which burned several buildings on Second Street, Federal Street, and Washington Street. One history of The Dalles, published in 1905, noted:

"Mr. Waldron was a pioneer and at the time of the conflagration was proprietor of a drug store in the old stone building adjoining the Cosmopolitan Hotel."

(over)

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Illustrated History of Central Oregon. Spokane, Wash.: Western Historical Publishing Co., 1905, p. 136, 152.

Please enclose map Township 1 S Range 13 W Section 3

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme B-D

Name
(Common) Mosier Valley Post Office

(Historic) Mosier Valley Bank

Address N.W. Corner of 3rd and Main Sts.
Mosier, Oregon 97040

Present Owner _____

(Address) _____

Original Use bank

Date of Construction 1914

Statement of historical significance:

The former Mosier Valley Bank is a one story brick building with a flat roof. The main entryway is located on the southeast corner of the structure. The building is set on a concrete foundation and has as its principle ornamentation brick diamonds and brick rectangles at the roof level. The window bays contain six casement windows.

The Mosier Valley Bank was founded in 1914 and closed in bankruptcy in 1929. The Scarce Brothers and V.R. Brooks were the major backers of this bank.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Gholston, Willis. Interview with Stephen Dow Beckham, 2 July 1976, Mosier, Oregon.

Please enclose map Township 2 S Range 11 W Section 1

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco

Theme _____

Name
(Common) Nichols Museum

(Historic) St. Paul's Episcopal Church

Address Union Street at West 5th
The Dalles, Oregon

Present Owner _____

(Address) _____

Original Use Church

Date of Construction 1875

if historical significance:

St. Paul's Episcopal Church stands at the west end of West Fifth Street on Union in The Dalles. The building is a one story, wood frame building with a stucco exterior and a dressed, stone foundation. A lancet bay of stained glass is the principal feature of the east (front) elevation. A square bell tower rises on the northeast corner of the front elevation; the tower has a louvered belfry. The building has a gable roof and simulated buttresses on its north and south elevations.

According to a plaque on this building it was erected in 1875 and was nearly duplicate to the Ascension Episcopal Church of Cove, Oregon, which was erected about 1873. About 1900 this Gothic building in The Dalles was remodeled. Its wood exterior was removed and covered with stucco. The tower was then built on the front elevation. For a picture of the Cove church see Space, Style and Structure, Volume I, Figure III-218 (p. 305).

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

"The Dalles Landmark List," MS Typescript,
Planning Office, City of The Dalles,
The Dalles, Ore.

Please enclose map Township 1 S Range 13 W Section 3

(over)

Sources:


"The Dalles Landmark List," MS Typescript, Planning Office, City of The Dalles, The Dalles, Oregon.

McNeal, Wm. H. History of Wasco County, Oregon. [The Dalles, Ore.: mimeo, c. 1953], copy at Oregon Historical Society, Portland, Ore., p. 17.

In the 1870's the second story of this building was used as a lodge hall for Wasco Lodge No. 15 of the A.F. and A.M. (Masons).

About 1953 William H. McNeal, in the mimeographed History of Wasco County, stated that this building was erected in 1859 by Henry J. and George W. Waldron. He noted that a drug store occupied the first floor and that offices and the Masonic lodge were on the second floor. In 1880 the street to the south of the building was raised twelve feet.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 6-D, 10-A
Name
(Common) Odd Fellow Lodge Hall
(Historic) Lamb (Larkin) General Store
Address S.W. Corner of 2nd and Oregon Sts.
Mosier, Oregon
Present Owner _____
(Address) _____
Original Use store (hall)
Date of Construction 1900

211

historical significance:

The Odd Fellow Lodge Hall at Mosier, Oregon is a 2 story wood frame building overlooking the Columbia River. The building has an elegant false front with three pediments. The roof is gable. The commercial section on the first floor possesses its original glass windows and double entry doors. A veranda protects the front entranceway. The doors are one-over-one double hung sash. The building has a stone foundation and contains its original store fixtures. There is a louvered cupola on the roof and one brick chimney with corbelled top.

In 1905 the Odd Fellows purchased this building and owned it until about 1968 at the time of the dissolution of the lodge. From its construction in 1900 this building was used by many civic groups and lodges in Mosier.

Larkin Lamb was born in Iowa on September 30, 1841. He was a son of William and Fanny (Gaar) Lamb. Lamb located in The Dalles in 1864 where he became a farmer. Lamb married Mary Marsh in 1869 and in 1879 homesteaded property. The Lambs were later divorced and he settled in Mosier. Lamb was also a carpenter.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 2 S Range 11 W Section 1

Gholston, Willis. Interview with
Stephen Dow Beckham, 1 July 1976
Mosier, Oregon.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco

Theme 6-D

Name
(Common) Petticoat Junction

(Historic) _____

Address 208 Washington St.
The Dalles, Oregon

Present Owner M. Williams Co.

(Address) The Dalles, Oregon

Original Use Commercial

Date of Construction 1880's

211

Statement of historical significance:


The building which presently houses the commercial firm Petticoat Junction is of stone block construction with a brick facade at the roof level. The building has stone arch radiating voussoirs with keystones in three bays on the west (front) elevation. Each bay is closed by double doors.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 6 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmark List," MS Typescript,
Please enclose map Township 1 S Range 13 W Section 3 The Dalles, Ore.
Planning Office. City of The Dalles,

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JM 76

County Wasco

Theme _____

Name
(Common) Phil's Home Furniture

(Historic) Skibbe Hotel

Address 624 East Second St.
The Dalles, Oregon

Present Owner _____

(Address) _____

Original Use Hotel

Date of Construction 1870's

Statement of historical significance:


The former Skibbe Hotel is a two story, brick building with a rectangular shape. The main entrance to the structure is located on the northeast corner of the building. The windows are one-over-one, double hung sash set in semi-elliptical bays. Each of the windows has an "eyebrow" decoration of projecting bricks. The building has been painted green and is altered on the first floor on the north (front) elevation. A two story, wood frame lean-to is attached on the south (rear) elevation.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmark List," MS Typescript,
Planning Office, City of The Dalles,
Please enclose map Township 1 S Range 13 W Section 3 The Dalles, Oregon.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme -D

Name
(Common) Pioneer Building

(Historic) _____

Address n.e. corner of E. 2nd & Washington
The Dalles, Oregon

Present Owner Gary Kortge
338 West 21st Street
(Address) The Dalles, Oregon

Original Use Commercial

Date of Construction 1860-65; 1880's

atement of historical significance:

The Pioneer Building, extensively reconstructed in the 1880's, is a two story, brick building with a stucco exterior. The building has one-over-one, double hung sash windows in the second story. Used brick has been added as a new exterior on the first floor and a split shake awning has been attached between the first and second stories. A photograph of this building c. 1900 shows it in its 19th century condition and being used as a grocery store. The photo is on file at the Surgeon's Quarters, Fort Dalles Historical Museum.


In 1976 this building housed The Shoe Tree and other shops.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmarks List," MS Typescript,
Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3 The Dalles, Oregon, Planning Office, City of The Dalles,
The Dalles, Oregon.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme (1-19 (i r))

Name
(Common) Pulpit Rock Landmark

(Historic) Pulpit Rock Landmark

Address Intersection of Court and East
Twelfth Streets
The Dalles, Oregon

Present Owner City of The Dalles

(Address) _____

Original Use landmark

Date of Construction 22 March 1908

Statement of historical significance:

The bronze plaque on the Pulpit Rock Landmark reads:

"Pulpit Rock. Rev. Jason Lee with Rev. Daniel Lee and Rev. H. K. W. Perkins
Founded Methodist Indian Mission, March 22, 1838."


Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 4

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 6-A
Name
(Common) Riverside Hotel
(Historic) _____
Address U.S. Highway 197
Maupin, Oregon
Present Owner Mrs. Mickey Snodgrass
(Address) Maupin, Oregon
Original Use hotel
Date of Construction c. 1920

statement of historical significance:

The Riverside Hotel is a two story wood frame building overlooking the Deschutes River in Maupin, Oregon. It has a hip roof, shiplap siding, and one-over-one double hung sash windows. A veranda extends along the west (front) and north elevations and is supported by Chamfered square posts entablatures. The building has a concrete foundation and its veranda footings are enclosed by a lattice.

The Riverside Hotel was built by Lester Kelley.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 5 ^N _S Range 14 ^E _W Section 5

Stovall, Bertha. Interview with Stephen Dow Beckham, 3 July 1976, Maupin, Ore. (Mrs. Stovall, age 90, has resided in Maupin since 1916.)

STATE OF OREGON INVENTORY
 HISTORIC SITES AND BUILDINGS
 State Historic Preservation Office
 Oregon State Parks, Salem 97310



County Wasco
 Theme _____
 Name (Common) Shaniko Auxiliary Water Tower
 (Historic) (same)
 Address Shaniko, Oregon
 Present Owner _____
 Address _____
 Original Use Water Tower
 Date of Construction prior to 1902

Physical description of property and statement of historical significance:

The Shaniko Auxiliary Water Tower is the tallest structure in this town in southern Wasco County. Erected prior to January, 1902, when photographed in the Shaniko Leader, this structure has a rectangular shape and is of wood frame construction. The water tower has a rectangular section with a hip roof and a small cupola atop a rectangular, tower base. The exterior of the structure is shiplap. The building has small casement windows in each elevation. The structure is in fair condition.

In 1905 Shaniko was the fifth largest town in Wasco County. In 1899 Shaniko became the terminus of the Columbia Southern Railway. In that year the townsite was platted and in 1900 the first building was erected in the community. The first train arrived in the spring of 1900. Writing in 1905 an historian remarked:

"The water which supplies Shaniko is obtained from springs, pure and clear as crystal, gushing forth from the hillsides. These were cleaned out, cemented up and piped to a large receiving reservoir holding 120,000 gallons, and from that the water is pumped into the the auxiliary reservoir which stands high above all the buildings and holds 60,000 gallons. The water system was completed and the mains laid over the city... in July, 1900." continue on back if necessary

Recorded by Stephen Dow Beckham Date 1 Sept. 1976

For Oregon State Historic Preservation Office

Sources Consulted:

Please enclose map Township 6 ^N 11 ^E Section 36

An Illustrated History of Central Oregon.
 Spokane, Wash.: Western Historical Publishing Co., 1905, pp. 170-171.

Shaniko Leader, Jan. 2, 1902, photo, p. 116.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



211

County Wasco

Theme 6-3

Name
(Common) Schmidt (Charles L.) Grist Mill Site

(Historic) Schmidt (Charles L.) Grist Mill Site

Address West Third St. at Mill Creek
The Dalles, Oregon

Present Owner _____

(Address) _____

Original Use grist mill site

Date of Construction _____

Statement of historical significance:

In the 1870's Charles L. Schmidt operated a grist mill on the banks of Mill Creek, The Dalles, Oregon. His house, erected in the 1870's, stands at 415 West Third Street (see file sheet).

Continue back if necessary


Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Hudson, Thomas. Interview with Stephen Dow Beckham, 3 July 1976, The Dallas, Oregon.

Please enclose map Township 1 S Range 13 W Section 4

STATE OF OREGON INVENTORY
 HISTORIC SITES AND BUILDINGS
 State Historic Preservation Office
 Oregon State Parks, Salem 97310



County Wasco
 Theme _____
 Name
 (Common) Shaniko City Hall
 (Historic) (same)
 Address Shaniko, Oregon
 Present Owner _____
 Address _____
 Original Use City Hall
 Date of Construction Prior to Jan., 1902

Physical description of property and statement of historical significance:

The Shaniko City Hall is a narrow, two story, wood frame building with a rectangular shape which stands in Shaniko across the street from the Columbia Southern (Shaniko Hotel) Hotel. This building has a gable roof and a false front. The exterior is shiplap. The windows are one-over-one, double hung sash. The first floor has double barn-like doors and an entry door with a transom window. The building has vertical boards on its false front and has a short flagpole.

Erected prior to January, 1902, when a photograph of the building was published in the Shaniko Leader, this structure served as a fire department and city offices. The fire department occupied the first floor and the city offices were on the second story. The city government was established in Shaniko on February 9, 1901. F. T. Hurlbert was elected the first mayor. Demolition of this building commenced in the fall of 1962 but was terminated after a campaign by Joe Morelli and other local residents.

continue on back if necessary


Recorded by Stephen Dow Beckham Date 7 Sept. 1976

For Oregon State Historic Preservation Office Sources Consulted:

Please enclose map Township 6 ^N 10 ^E Section 36 An Illustrated History of Central Oregon.
 Spokane, Wash.: Western Historical Publishing Co., 1905, p. 171.

Shaniko Leader, Jan. 2, 1902, p. 116, photo.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem 97310



County Wasco
Theme 1.3
Name
(Common) Shaniko Hotel
(Historic) Columbia Southern Hotel
Address Shaniko, Oregon
Present Owner Sue Morelli
Address Shaniko, Oregon
Original Use Hotel
Date of Construction prior to Jan., 1902

Physical description of property and statement of historical significance:

The Columbia Southern Hotel is a large, two story, brick building in the center of Shaniko, Oregon. The structure has one-over-one, double hung sash windows set in semi-elliptical surrounds of brick. The building has a decorative, brick facade at the roof level and has several brick chimneys. A verandah with balcony runs along part of the south and west elevations. The main entry is at the southwest corner of the building and has a transom window. The first floor elevation has large windows with half-round window panes above.

The Columbia Southern Hotel was erected prior to January, 1902, when a photograph of the building appeared in the Shaniko Leader. This hotel was one of the largest of the structures erected in Shaniko after it became the terminus of the Columbia Southern Railroad in 1899-1900. The hotel is yet operating in 1976.

continue on back if necessary

Recorded by Stephen Dow Beckham Date 1 Sept. 1976

For Oregon State Historic Preservation Office

Sources Consulted:

Please enclose map Township 6 ^N ^E 16 W Section 36

Shaniko Leader, Jan. 2, 1902, p. 134, photo.


Guernsey, John. "Want a Colorful Hotel? Try Shaniko," Oregonian, Nov. 17, 1975, photo, p. A14.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem 97310

County Wasco
Theme _____
Name
(Common) Shaniko School
(Historic) Public School
Address Shaniko, Oregon

Present Owner _____
Address _____
Original Use School
Date of Construction Prior to January, 1902



Physical description of property and statement of historical significance:

The Public School of Shaniko, Oregon, is a square, wood frame building with a truncated hip roof. This building has a shiplap exterior. The appearance of the structure indicates that at one time it was probably of a rectangular shape, but that in later years an addition was attached to the rear elevation to give the building a square shape. The building is dominated by a five-sided tower at the front entrance. This tower becomes an octagonal belfry with an octagonal cone roof covered with shingles. The belfry is enclosed with louvers. The building has one-over-one, double hung sash windows.

According to Lambert Florin this school was erected in 1902. A photograph of it appeared, however, in January, 1902, in the Shaniko Leader. This much photographed building served as the public school in this town which boomed with the construction of the Columbia Southern Railroad line in 1899-1900. For a brief time between 1900 and 1904 Shaniko was the largest shipping point for wool in the United States. The building and most of the town are deserted in the 1970's.

continue on back if necessary


Recorded by Stephen Dow Beckham Date 1 Sept. 1976

For Oregon State Historic Preservation Office Sources Consulted:

Please enclose map Township 6 ^N (S) 16 ^E W Section 36 Florin, Lambert. Ghost Towns of the West.
[n.p.]: Promontory Press, 1971, p. 767.
photo.

Shaniko Leader, January 2, 1902, photo, p. 119.

STATE OF OREGON INVENTORY
 HISTORIC SITES AND BUILDINGS
 State Historic Preservation Office
 Oregon State Parks, Salem, 97310



County Wasco
 Theme 10-A
 Name
 (Common) Sigman's Flowers
 (Historic) _____
 Address 200 East 2nd Street
The Dalles, Oregon
 Present Owner Bud Sigman
 (Address) The Dalles, Oregon
 Original Use Commerical
 Date of Construction c. 1890's

% 111

ement of historical significance:

The two story brick building occupied by Sigman's Flowers has an unknown history. The structure exhibits elements of the Italianate Style with a flat roof and decorative brackets set at the roof level. The building has one-over-one, double hung sash windows set in semi-elliptical bays with radiating voussoirs with keystones. Decorative metal sections are placed on the north (front) elevation.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Krier, Malcolm and Jean. Interview with Stephen Dow Beckham, 2 July 1976, The Dalles, Oregon.

Please enclose map Township 1 S Range 13 W Section 3

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 10-A
Name
(Common) _____
(Historic) Sinnott (Col. N.B.) House
Address 316 W. Fourth St.
The Dalles, Ore.
Present Owner Dick Pearson
(Address) 316 W. Fourth, The Dalles
Original Use residence
Date of Construction 1868

statement of historical significance:

The Col. N.B. Sinnott house is a 1½ story wood frame building set on a stone foundation. The building faces north on West Fourth Street and overlooks the Columbia River. The exterior is clapboard siding. The windows are presently one-over-one double hung sash. The main entry door has sidelights and a transom. The house, which is in a "T" shape, has a gable roof with boxed eaves and wide frieze boards. The front yard is terraced with a stone wall and concrete wall.

Co. N. B. Sinnott was the brother of P. B. and Bridget (Morrin) Sinnott. His brother was born in Wexford, Ireland, and in 1858 emigrated to Oregon where from 1860 to 1872 he operated the Columbia Hotel in Portland. From 1872-85 Sinnott was agent at the Grand Ronde Indian Agency. N. B. Sinnott was an early settler at The Dalles and was the father of N. J. Sinnott, longtime U.S. Senator from Oregon, and Robert Sinnott of Portland, Oregon.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 S Range 13 W Section 4

"William P. Sinnott." Lockley, Fred.
History of the Columbia Valley from
The Dalles to the Sea. Chicago:
S. J. Clarke Publishing Co., 1928,
vol. 2, 772-773.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 10-A
Name
(Common) Smith (Leonard) Rental
(Historic) _____
Address 217 West Fourth St.
The Dalles, Oregon
Present Owner Leonard Smith
(Address) The Dalles, Oregon
Original Use residence
Date of Construction unknown

statement of historical significance:

This small wood frame house of unknown history stands across the street from the Ben Snipes house and faces south on West Fourth. The structure exhibits several elements of Classical Revival Style, including a low gable roof and a veranda on the front elevation supported by square posts with entablatures and with pilasters. The exterior is clapboard siding. The windows and door on the front elevation are of Twentieth Century construction.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 S Range 13 W Section 3

Lundell, Gary. Interview with Stephen Dow Beckham, 3 July 1976, The Dalles, Oregon.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 5-7
Name
(Common) Ben Snipes Barn
(Historic) Ben Snipes Barn
Address behind 218 West Fourth St.
The Dalles, Oregon
Present Owner Lundell & Sons Plumbing
(Address) 218 West Fourth
Original Use barn
Date of Construction prior to 1875

historical significance:

The Ben Snipes barn is a rectangular wood frame building with gable roof and board and batten siding. It has irregular fenestration. The building is sitting upon a stone foundation.

The title record for this property indicates that Ben Snipes owned this barn in 1875.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976


For Oregon State Historic Preservation Office

Please enclose map Township 1 S Range 13 W Section 3

Sources Consulted:

Lundell, Gary. Interview with Stephen Dow Beckham, 3 July 1976, The Dalles, Oregon.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme (C-A)
Name
(Common) Snipes (Ben) House
(Historic) Snipes (Ben) House
Address 218 West Fourth
The Dalles, Oregon
Present Owner John Lundell
(Address) 218 W. Fourth St., The Dalles
Original Use residence
Date of Construction c. 1866:c. 1872

historical significance:

The Ben Snipes house is a 1½ story wood frame building which faces north on West Fourth Street. This structure has clapboard siding, a gable roof and six-over-six double hung sash windows on its second floor. On the first floor projecting window bays are located on the east and west elevation, and were constructed about 1895. The house has a stone foundation. A veranda with four turned columns reaches across the front elevation; a door from a cross gable on the second floor opens on to the veranda roof. The front entry has side-lights and a transom.

This house was first built c. 1866. The fireplace chimney survived a fire which destroyed part of this house c. 1895. The initials "B. S." appear on the mantel.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office
Please enclose map Township 1 S Range 13 W Section 3

Lundell, Gary. Interview with Stephen Dow Beckham, 3 July 1976, The Dalles, Oregon.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme ED
Name
(Common) Stadelman Building
(Historic) French & Company Bank
Address s.e. corner of Second & Washington
The Dalles, Oregon
Present Owner Stadleman
(Address) _____
Original Use Commercial
Date of Construction 1879

Statement of historical significance:

The Joshua W. French Bank was erected in 1870 and refaced with a new facade early in the twentieth century. This structure is a two story, brick building which has a terra cotta (buff colored) facade or exterior. The main entrance is located diagonally on the northwest corner of the building. The fenestration is irregular.

Joshua W. French was born September 13, 1830, in Holland, Vermont. In 1852 he journeyed via Panama to California and there with his brothers Daniel and Joseph he operated a ferry on the Stanislaus River. In 1864 French came to The Dalles to join his brother Daniel. Daniel and Joshua W. French established the first bank in The Dalles. After Daniel's death, Joshua French assumed full management of the bank. French married Ellen Burke.

According to Charles Carey the French brothers were cousins of William S. Ladd of Portland. Ladd encouraged them to establish the bank in The Dalles which they initially did under the name of Gilman, French & Company. The French & Company Bank was established in 1867. Carey wrote: "In 1876 they removed to their building on the north side of Second street and three years later completed a building at the corner of Second and Washington streets, which has been occupied and known as the French & Company Bank from that time until the present, the business being still carried on under the firm name. Daniel French died in 1902 and Joshua French died on December 23, 1907.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

"Joshua W. French." Illustrated History of Central Oregon. Spokane, Wash.: Western Historical Publishing Co., 1905, pp. 278-475.

Please enclose map Township 1 S Range 13 W Section 3

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco

Theme 10-B

Name
(Common) "The Stone House"

(Historic) _____

Address 1015 Court Street

The Dalles, Oregon

Present Owner Frank Hammel

(Address) _____

Original Use residence

Date of Construction _____

statement of historical significance:

The building is a two story stone house covered with a stucco exterior in the Mansard Mansion Style. The windows are one-over-one double hung sash set in segmental bays. The mansard roof is metal. A simple front porch stands on the east (front) elevation with cut scroll work. A door opens from the second story over the front porch. There is a simple back porch on the south elevation. The eaves are decorated with wood brackets.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3

Krier, Jean. Interview with Stephen Dow Beckham, 2 July 1976, The Dalles, Oregon.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 6-B, 10-A
Name
(Common) Sunshine Biscuit Co. Building
(Historic) Wasco Warehouse Milling Co. Building
Address 901 East 2nd Street
The Dalles, Oregon
Present Owner Continental Grain Co.
(Address) The Dalles, Oregon
Original Use Warehouse & Offices
Date of Construction 1869

Historical significance:

The Wasco Warehouse Milling Company Building is a large, two story brick building which extends over one block along the railroad tracks on the east end of The Dalles, Oregon. The building consists of two major sections, each possessing a dome roof surmounted with a series of louvered cupolas. Port hole windows are located in the south (side) elevation. The windows on the west (front) elevation are mostly four-over-four, double hung sash. All of the windows, including the port hole windows, have decorative, brick "eyebrows."

A biography of banker Joshua W. French, born in 1830, noted that he was a director of the Wasco Warehouse Milling Company. At the turn of the twentieth century this company was one of the largest flour mills in Oregon. On January 2, 1902 the Times-Mountaineer noted: "The Wasco Warehouse & Milling Company's plant at White River, just completed, is the most modern and complete on the coast. . . ."

Writing about 1953, William H. McNeal noted that the Wasco Warehouse was incorporated in 1883 by J. W. French, S. L. Brooks, and E. B. McFarland. Wentworth Lord served as manager. The firm handled wool, hides, pelts, hay, and grain.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office Illustrated History of Central Oregon. Spokane, Wash.: Western Historical Publishing Co.,
Please enclose map Township 1 S Range 13 W Section 3 1905, p. 147.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 7-2, 1-B
Name
(Common) The Dalles City Hall
(Historic) (same)
Address 313 Court Street
The Dalles, Oregon
Present Owner City of The Dalles
(Address) The Dalles, Oregon
Original Use City Hall
Date of Construction 1908

statement of historical significance:

The Dalles City Hall, erected in 1908, is a two story building which exhibits elements of the Colonial Style. The building has an exterior of stucco with brick trim for decoration; the trim includes brick quoins and flat arch brick voussoirs as well as bands of brick between the first and second stories and at the roof level. The one-over-one, double hung sash windows have concrete lugsills. The building houses city offices and a fire department with bays for fire trucks located on the south elevation. The building faces east on Court Street. The front elevation is covered with ivy. The structure is set on a stone foundation and has a basement.

City government was constituted in The Dalles in 1855 with the election of a council. In 1863 the charter was amended to replace the City President with a Mayor.

According to William H. McNeal, who wrote about 1953, this building was erected in 1910 at a cost of \$30,000.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office


Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3 The Dalles, Oregon.

"The Dalles Landmark List," MS Typescript,
Planning Office, The Dalles City Hall,

The Dalles, Oregon.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme Industrial
Name
(Common) The Dalles Iron Works Building
(Historic) #1 (same)
Address 720 East Second Street
The Dalles, Oregon
Present Owner Loyal Kirk
(Address) 1906 West Scenic Drive
The Dalles, Oregon
Original Use Foundry
Date of Construction c. 1870's

historical significance:

Building #1 of The Dalles Iron Works is a two story, brick structure with a rectangular shape. The building has two store fronts on its north (front) elevation with double entry doors flanked by pairs of narrow, iron columns and display windows. The second story has one-over-one, double hung sash windows with "eyebrow" semi-elliptical voussoirs. The building has a brick facade at the roof level.

A wood frame building (The Dalles Iron Works Building #2--see file sheet) stands on the west and is attached to this building by a lean-to roof.


The Dalles Iron Foundry was operated in 1882 by Tom Lewis and made castings for boats and the railroad. It was later owned by F. W. L. Skibbe.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmarks List," MS Typescript,
Please enclose map Township 1 N Range 13 E Section 3 The Dalles, Oregon.
(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme _____
Name
(Common) The Dalles Iron Works Building #2
(Historic) (same)
Address 720 East Second
The Dalles, Oregon
Present Owner Loyal Kirk
(Address) 1906 West Scenic Drive
The Dalles, Oregon
Original Use Foundry
Date of Construction c. 1870's

statement of historical significance:

The Dalles Iron Works Building #2 is a one story, wood frame building with double entry doors and display windows on its north (front) elevation. The wood false front has small decorative brackets at its top and is covered with horizontal shiplap. The interior of this building is plaster and lath. The roof is a lean-to against the brick building on the east (see file sheet for The Dalles Iron Works Building #1). The exterior on the west elevation of the building is covered with corrugated sheet metal as is the roof.

The Dalles Iron Foundry was operated in 1882 by Tom Lewis and made castings for boats and the railroad. It was later operated by F. W. L. Skibbe.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmarks List," MS Typescript,
City of The Dalles, Planning Office,
Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3 The Dalles, Oregon.

(Over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme Historic
Name
(Common) Thompson (Robert R.) House
(Historic) (same)
Address 215 West Third Street
The Dalles, Oregon
Present Owner _____
(Address) _____
Original Use Residence
Date of Construction 1868

Statement of historical significance:

The Robert R. Thompson house is a one and one-half story, wood frame building with clapboard siding and a gable roof. The structure has one-over-one, double hung sash windows with a pair of French doors over the porch on the second story of the south (front) elevation. A verandah extends across the front elevation. A decorative panel with garlands is attached on the front elevation above the French doors. The main entry has leaded glass sidelights and a transom. The building has a wood lattice under the front porch and has one brick chimney.

According to the Landmarks Committee in The Dalles this house was erected by transportation magnate Robert R. Thompson. Thompson was born in Pennsylvania in 1820 and emigrated overland to Oregon in 1846. After working in Oregon City and spending some time in the California gold mines, Thompson invested in the first steamboat on the upper Columbia River. In 1858 Thompson moved to Portland where he continued investing in land and in transportation systems.

Because of the assertion that Thompson moved to Portland in 1858 one needs to check the title records on this property to ascertain if this is indeed the Thompson residence.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:


For Oregon State Historic Preservation Office

"The Dalles Landmark List," MS Typescript,
Planning Office, City of The Dalles,
The Dalles, Oregon.

Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3

(over)

STATE OF OREGON INVENTORY
 HISTORIC SITES AND BUILDINGS
 State Historic Preservation Office
 Oregon State Parks, Salem, 97310



JUL 76



County Wasco
 Theme 10-A
 Name
 (Common) Thornbury (Caleb N.) House
 Historic) Thornbury (Caleb N.) House
 Address W. Second Place
The Dalles, Oregon
 Present Owner Mrs. Phyllis Baker
 Address) The Dalles, Ore.
 Original Use residence
 Date of Construction 1878

Historical significance:

The Caleb N. Thornbury house is a 2 story wood frame building in the Italianate style. It has a low hip roof, boxed eaves and decorative brackets with pendants. The exterior is shiplap. The windows are four-over-four and two-over-two double hung sash with decorative surrounds and entablatures. A 2 story projecting window bay is located on the north (front) elevation and has segmental window opening on the second story. There is a simple front porch on the east elevation.

Caleb N. Thornbury was in the general mercantile and sheep and cattle business in Wheeler County, Oregon. He moved to The Dalles in the 1870's and was named fees receiver of The Dallas Land Office. In the 1880's he established a real estate and insurance business and in 1892 was elected Judge of Wasco County. Thornbury's daughter married Thomas A. Hudson (1853-1926) (see file sheet for the Hudson house).

Continue back if necessary


Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 ^(N) Range 13 ^(E) W Section 3

Hudson, Thomas. Interview with Stephen Dow Beckham on 3 July 1976, The Dallas, Ore.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 10-A
Name
(Common) Trevitt (Victor) House
(Historic) (same)
Address 209 West Third Street
The Dalles, Oregon
Present Owner _____
(Address) _____
Original Use Residence
Date of Construction _____

statement of historical significance:

The Victor Trevitt house is a two story, wood frame building in the Queen Anne Style. The building has a hip-on-gable roof with a square tower on the southeast corner of the south (front) elevation. The building is set on a stone foundation. The house has imbricated shingling on its gable ends and possesses one-over-one, double hung sash windows. Several of the windows on the first floor have leaded glass sections as well as stained glass. The two brick chimneys have corbelled tops.

Victor Trevitt, proprietor of the Mount Hood Saloon in The Dalles, served in the Oregon Territorial legislature in 1858 and in the State Senate in 1868. Born in Virginia in 1827, Trevitt emigrated to Oregon in 1851 and settled on his Donation Land Claim in Wasco County in 1855. Trevitt is buried on Memaloose Island in the Columbia River.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3

Krier, Jean and Malcolm. Interview with
Stephen Dow Beckham, July 2, 1976,
The Dalles, Oregon.
(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



JUL 76

County Wasco
Theme 9-2 1-18
Name
(Common) U.S. Post Office
(Historic) (same)
Address 100 West 2nd Street
The Dalles, Oregon
Present Owner U.S. Government
(Address) _____
Original Use Post Office
Date of Construction 1915

statement of historical significance:

The U. S. Post Office in The Dalles is a two story, dressed stone building in the Colonial Style. Erected in 1915 this building has a metal-covered gable roof which is mostly concealed by a stone facade at the roof level. Stone quoins decorate the corners of the building. The windows are eight-over-eight, double hung sash on the second floor and twelve-over-twelve double hung sash on the first floor. The main entry is recessed and is flanked by pairs of stone columns, each two stories high. A one story wing is attached on the south (rear) elevation. The building's interior lobby is unaltered and is done in white oak. A pair of cast iron lamp bases stand on either side of the main entry.

A previous post office burned in August, 1914. In February, 1915, George Isackson of Portland was awarded the contract to erect this building at a cost of \$73,978. The building is made of Tenino sandstone.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmark List," MS Typescript,
Please enclose map Township 1 S Range 13 W Section 3 The Dalles, Ore.
Planning Office, City of The Dalles,

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem 97310



County Wasco
Theme _____
Name
(Common) Unknown House
(Historic) (same)
Address w. side of Highway 218
Antelope, Oregon
Present Owner _____
Address _____
Original Use Residence
Date of Construction c. 1870's

Physical description of property and statement of historical significance:

This one and one-half story, wood frame house of unknown history stands on the west side of Highway 218 in Antelope, Oregon. According to local residents the building is the oldest residence in the community. A simple building, it has a gable roof and an exterior which is now covered with tar paper shingles or shakes. A verandah reaches along the east and south elevations. The windows are one-over-one, double hung sash.

According to an article published in the Oregonian in 1960, an account based on interviews with John Silvertooth, long-time resident of Antelope, this structure was erected in the year 1862. While the building may be old, accounts of the history of Antelope state that the community was not established until 1873.

continue on back if necessary


Recorded by Stephen Dow Beckham Date 1 Sept. 1976

For Oregon State Historic Preservation Office Sources Consulted:

Please enclose map Township 8 ^N ^E 17 _W Section 5 "Unfruitful Years Take Toll of Ancient Town of Antelope," Oregonian, Sept. 15, 1960.

An Illustrated History of Central Oregon. Spokane, Wash.: Western Historical Publishing Co., 1905, p. 167.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



92 W

County Wasco
Theme 10-A
Name
(Common) Walter (Raymond) House
(Historic) Schmidt (Charles L.)*
Address 415 West 3rd Street
The Dalles, Oregon
Present Owner Raymond B. Walter
(Address) 415 West Third, The Dalles
Original Use residence
Date of Construction c. 1878

historical significance:

The Walter house is a 1½ story wood frame building with a steep gable roof and small cross gable on the south (front) elevation. It has shiplap siding and a projecting window bay on the first floor (east) elevation. The windows are four-over-four double hung sash with decorated wurrounds and pediment entablatures. The second story has a lancet door bay above the simple front porch and lancet double hung sash windows in the east and west gable ends. There is a transom above the front entry door. The verge boards have cut woodwork designs. There is a porch on the east rear elevation.

Charles L. Schmidt was a miller who erected a grist mill on Mill Creek near this house. In later years Schmidt and his wife operated a rooming house in this building.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:


For Oregon State Historic Preservation Office

Please enclose map Township 1 S Range 13 W Section 3

Walter, Mrs. Raymond B. Interview with
Stephen Dow Beckham, 3 July 1976,
The Dalles, Oregon.

Hudson, Thomas. Interview with Stephen
Dow Beckham. 3 July 1976. The Dalles

STATE OF OREGON INVENTORY
 HISTORIC SITES AND BUILDINGS
 State Historic Preservation Office
 Oregon State Parks, Salem, 97310



County Wasco

Theme ED

Name
 (Common) Wapanitia School

(Historic) Wapanitia School

Address Wapanitia, Oregon

Present Owner _____

(Address) _____

Original Use school

Date of Construction _____

Statement of historical significance:

The Wapanitia school is a one story wood frame building in a "T" shape with a gable roof and shiplap exterior. The windows are two-over-two double hung sash. A square bell tower with open belfrey is situated at the north (front) entrance. The tower has a bellcast hip roof. The eaves are open. There is one brick chimney covered with stucco. The building is in very poor condition.

A post office was established at Wapanitia on March 21, 1878, when the site was the southern terminus of the Wapinitia-The Dalles stage line. William H. McNeal noted about 1953: "The Wapinitia school is almost as old as the post office and Callie Bigbee and her husband G. F. Bigbee were teachers as far back as 1889." It is unclear whether the reference is to the building or the school as an institution.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Please enclose map Township 5 ^N _S Range 12 ^E _W Section 25

McNeal, William H. History of Wasco County, Oregon. The Dalles, Ore.: Mimeo, c. 1953; copy at Oregon Historical Society, Portland, Ore., pp. 249-251.

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 7
Name
(Common) Wasco County Library, Mosier
(Historic) Mosier Commercial Club
Address Third Avenue
Mosier, Oregon
Present Owner Wasco County
(Address) _____
Original Use Club Hall
Date of Construction c. 1909

217

Statement of historical significance:

The Mosier Commercial Club building is a small one story wood frame structure with a gable roof and open eaves. The eaves are decorated by scalloped beams and open brackets. The exterior is shingle with decorative vertical boards. The windows are one-over-one double hung sash.

The Mosier Commercial Club was a business promotion for orchards in the Mosier area. Two brothers named Devon from Hood River were major backers of the Mosier Commercial Club.

Continue back if necessary


Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

Gholston, Willis. Interview with Stephen Dow Beckham, 2 July 1976, Mosier, Ore.

Please enclose map Township 2 S Range 11 W Section 1

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme 6-D
Name
(Common) Weigelt (Gus) Bookstore
(Historic) Nickelsen (I.C.) Book Store
Address 315 Second Street
The Dalles, Oregon
Present Owner Gus Weigelt
(Address) 500 West 7th Street
The Dalles, Oregon
Original Use Commercial
Date of Construction c. 1870-80

2111

historical significance:

The Weigelt Bookstore is a one, story brick building which faces south on East Second Street. The building once had semi-elliptical bays on its west elevation; those window bays have been bricked-in. The front elevation has been entirely altered and is now covered with stucco. Large iron doors and shutters remain on the north (rear) elevation of this building.

This business was founded in the 1880's by I. C. Nickelson. In 1883 his store was located at 315 East Second Street. Nickelson was born in Germany in 1842 and was the son of Peter and Christina (Peterson) Nickelson. He settled in New York in 1859 and came to The Dalles in 1867. He rebuilt his store after the fire of 1891. The Weigelts purchased the store in 1927. Nickelson married in 1872 to Josine Fredden.



Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "The Dalles Landmarks List," MS Typescript,
Please enclose map Township 1 ^(N) _(S) Range 13 ^(E) _(W) Section 3 The Dalles, Oregon.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco
Theme _____
Name
(Common) Williams (Don) House
(Historic) Bennett (Alfred S.) House
Address 608 Trevitt Street
The Dalles, Oregon
Present Owner Edward D. Williams
(Address) 608 Tevitt St., The Dalles, Ora
Original Use Residence
Date of Construction 1899

of historical significance:

The Judge Alfred S. Bennett house is a two and one-half story, wood frame building which stands on the east bank of Mill Creek in The Dalles. This building, in the Queen Anne Style, has an exterior of shiplap siding and imbricated shingling. The windows are one-over-one, double hung sash. A verandah, with a circular bay, extends along the north and east elevations. The hip roof has major gables on the east, north, and west elevations and is broken by a cupola and a tower. The house is surrounded by many of its original plantings and the property is enclosed by a low, stone wall and wrought iron fence.

Alfred S. Bennett was born at Dubuque, Iowa, on June 10, 1854, and emigrated overland to Oregon with his parents in 1865. From 1870 to 1873 Bennett was a farmer, but then he began teaching and studying law. He was admitted to the bar in 1880 and settled in The Dalles. Bennett served as school superintendent of Wasco County in 1878 and in 1882 represented the county in the legislature. He was also county judge and was candidate for the supreme court in 1894 and for Congress in 1896 but was defeated. In 1890 and 1912 Bennett was a delegate to the Democratic National conventions. Bennett married in 1887 to Mary McCauley of Dayton, Washington.

Don Williams, present owner of this house, is a fourth generation resident of The Dalles and is a major owner of "Williams--1870," his family's 106-year-old department store.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 5 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office

"Alfred S. Bennett." Gaston, Joseph. Centennial History of Oregon. Chicago: S. J. Clarke Publishing Co., 1912, vol. 4, 1054.

Please enclose map Township 1 S Range 13 W Section 4

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



County Wasco

Theme _____

Name
(Common) Williams 1870 Building

(Historic) Wingate & Williams (Griffith E.)
Building

Address 306 Second Street

The Dalles, Oregon

Present Owner M. Williams Company

(Address) The Dalles, Oregon

Original Use Commercial

Date of Construction 1869-70

9/11

statement of historical significance:

Williams 1870, a major retail firm in The Dalles, was founded in 1870 by Wingate and Griffith E. Williams. This building, which has housed the firm since its founding, is a two story, brick building which faces north on Second Street. The front elevation has been altered significantly. The first floor of the front elevation is now covered with Travertine marble.

Griffith E. Williams was born in Wales about 1835. He was a son of Evan and Phoebe (Roberts) Williams. After the death of his parents when he was about nine-years-old, Williams emigrated to the United States with his brothers and sisters. In 1852 Williams traveled overland to Oregon and after working in several sawmills settled in 1862 in The Dalles where he built cars for the Oregon Railroad & Navigation Company. He joined Edward Wingate in the hardware business. After Wingate's death, Williams continued to expand the firm into general merchandising until his death on March 6, 1886. Williams was a member of The Dalles city council. He married Anna M. Marshall in 1860.


Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historic Preservation Office "Griffith E. Williams." Illustrated History of
Central Oregon. Spokane, Wash.: Western
Historical Publishing Co., 1905, pp. 222-
223.

(over)

STATE OF OREGON INVENTORY
HISTORIC SITES AND BUILDINGS
State Historic Preservation Office
Oregon State Parks, Salem, 97310



92 111

County Wasco

Theme 10-A

Name
(Common) Zimmerman (Jacob) House

(Historic) Zimmerman (Jacob) House

Address 406 W. Second Place
The Dalles, Oregon

Present Owner _____

(Address) _____

Original Use residence

Date of Construction c. 1879-80

Statement of historical significance:

The Jacob Zimmerman house is a small one story wood frame building with a gable roof. This structure has two-over-two double hung sash windows, ship-lap siding, boxed eaves and a veranda on its north (front) elevation. There is a transom above the front entry door. The building has two brick chimneys.

Jacob Zimmerman, a Swiss immigrant, was a carpenter in The Dalles in the 19th century.

Continue back if necessary

Recorded by Stephen Dow Beckham Date 7 July 1976 Sources Consulted:

For Oregon State Historical Preservation Office

Please enclose map Township 1 ^(N) S Range 13 ^(E) W Section 3

Hudson, Thomas. Interview with Stephen Dow Beckham, 3 July 1976, The Dalles, Oregon.

